

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Due to exigencies/emergency of work (certificate attached) the sealed item rate tender on PWD Form 6 & 8 are hereby invited (without press notice) by the Executive Engineer, Shimla Rural Division, H.P.P.W.D. Dharni on behalf of Governor of Himachal Pradesh by using the overall ceiling power of 25.00 lakh for works costing above 1.00 lakh to 5.00 lakh for the following work from the eligible contractors enlisted in H.P.P.W.D. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on before **03-09-2021 up to 11:00 AM** and the same shall be opened on the same day at **11:30 AM** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **02-09-2021 up to 4:00 PM** and the application for issue of tender form shall be received on **01-09-2021 up to 4:00 PM**.

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer, Shimla Rural Division, HPPWD Dharni must be accompanied with the application for tender documents. Please note no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 90 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	A/R & M/O Judicial Academy at Ghandhal Shimla (SH:-P/F Toughened glass in VVIP bhats, Cup boards, floor tiles, painting, Unistone and W.S. & S.I., granite stone, repair of gutter etc.)	Rs. 4,99,302/-	Rs. 10,000/-	Two Months	Rs. 350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their **PAN** No., **GST** No., copy of **enlistment** renewed letter and **EPF** certificate alongwith **FDR** against earnest money.
- (ii) The contractor is requested to submit an **undertaking for not having more than two works in hand** for execution.
- (iii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhama

On behalf of Governor of Himachal Pradesh

No: PW-SRDD-CB-CTR / 2020-21-

7022-31

Dated:- 16/8/2021

Copy forwarded for the following for information and necessary action to:-

1. The Superintending Engineer, 4th Circle, HPPWD, Shimla-3.
2. The Executive Engineer (IT) for information and upload the same on the departmental website.
3. All the Assistant Engineer, working under this division.
4. All the heads of the branches in this office.
5. Notice Board.

Executive Engineer,
Shimla Rural Division,
H.P.P.W.D.Dhama.

Certificate

Certified that the tender for work "A/R & M/O Judicial Academy at Ghandhal Shimla (SH:-P/F Toughened glass in VVIP bhats, Cup boards, floor tiles, painting, Unistone and W.S. & S.I., granite stone, repair of gutter etc.)" is hereby invited without press notice due to exigencies/emergency of work in the public interest/*in the interest of academy.*

Executive Engineer,
Shimla Rural Division,
H.P.P.W.D.Dhama.

SCHEDULE OF QUANTITY

Name of work:- Annual Repair & Maintenance of Judicial Academy at Chandhal Shimla (SH:- P/F Toughened glass in VIP baths, cup Boards, floor tiles, Painting, Unistone and W.S. & S.I., granite stone, repair of gutter etc.)

Estimated Cost :- Rs 4,99,298/- only

Earnest Money :- Rs.10,000/-only

Deposit work

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	In words		
			4	5	6	7
1	2 Providing and fixing toughened glass (twelve millimetre thick) in partitions including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	3 7.00 Rmt.			Per Running Metre	
2	Providing and fixing on wall face PVC (D-Plast) rain water pipes of working pressure not less than 4.5 kg/sqm including filling the joints with approved adhesive complete. 150mm dia pipes including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	40.00 Rmt.			Per Running Metre	
3	Providing and fixing on wall faces PVC (D-Plast) accessories for rain water pipes including filling the joints with approved adhesive complete PVC. Plain bend 150mm dia including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	10.00 Nos.			Each	
4	Providing and laying heavy duty precast cement concrete inter locking paver blocks vibro compacted upto M- 50 grade i/c border or kub block grey or coloured over sub-base of concrete with 25mm thick average thickness of cement mortar 1:4 (1 cement : 4 sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks i/c curing rubbing & polishing complete (Sub base concrete floor to be paid for 60mm thick inter locking blocks including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	72.00 Sqm			Per Square Metre	
5	Providing and fixing 10mm thick anti skid water proof stain and impet resistant heavy duty vetrified tiles Nitco or equivalent 600x600mmx10mm manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (1 cement : 3 sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required Complete including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	3.50 Sqm			Per Square Metre	
6	Providing eaves board 200mmx25mm thick including fixing in position 2nd class deodar wood including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	10.00 Rmt.			Per Running Metre	
7	Providing and laying granite stone in flooring 20mm(average)thickness base of cement mortar 1:3(1cement: 3 sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of granite stone i/c rubbing and polishing complete. 20mm.thick including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	3.20 Sqm			Per Square Metre	
8	Providing gola in lime concrete with 25 mm nominal size stone/ brick aggregate and 50%of lime mortar 1:2 (1 lime puty :2 surkhi) underthe drip course and finished with lime plaster 1:2 (1 lime puty:2 surkhi) complete.	162.00 Rmt.			Per Running Metre	

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	In words		
1	2	3	4	5	6	7
9	Providing and fixing M.S. BP Sheet 1.66mm to 2mm thick in eaves board/facia/sofits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately)	48.60 Sqm			Per Square Metre	
10	Providing and fixing PGI Sheet 0.63mm thick in expansion joint with overall width 45 cm fixed to beam /slab with wooden plugs and screws i/c bending to slope and fixed in bitumen mix filler in proportion of 80 kg bitumen 1 kg of cement & 0.25 cum of sand hot mixed complete.	20.00 Rmt			Per Running Metre	
11	Providing and fixing 15 cm. Providing and fixing 15 cm. wide 45 cm. overall semicircular plain G.I. sheetgutter with iron brackets 40x3mm size bolts and nuts and washers etc. including making necessary connections with rain water pipe complete as per design. 0.63mm thick sheet including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	81.00 Rmt			Per Running Metre	
12	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. Cement Mortar 1:6 (1 Cement:6 Sand) including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	50.00 Sqm			Per Square Metre	
13	Repairs to plaster in patches of 2.50 Sq.M. and under and 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 metres with:- Cement Mortar 1:6 (1 Cement: 6 Sand) including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	60.00 Sqm			Per Square Metre	
14	Supplying and fixing glass panes with putty and nails including removal of broken glass panes wherever necessary:- Plain Glass: 4mm thick including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	7.44 Sqm			Per Square Metre	
15	Providing and fixing M.S. handles with necessary screws complete including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	0.00 0.00			0	
15	125mm	10.00 Nos.			Each	
15	100 mm	10.00 Nos.			Each	
16	Providing and fixing C.P. brass angle valve 15mm without Nuts and pipe (ESS ESS or Equivalent) including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	10.00 Nos			Each	
17	Providing and fixing one hole basin mixing Faucet(ESS ESS or Equivalent) including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	10.00 Nos			Each	
18	Providing and fixing 65x35mm special quality chromium plated brass cup board lock with six leavers including necessary screws etc. complete (Indian make) including carriage of material upto all leads and lifts as per the directions of Engineer in Charge.	20.00 Nos			Each	

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	In words		
1	2	3	4	5	6	7
19	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint including carriage of materials up to all leads and lifts and as per the direction of the Engineer-in-Charge. (i) In gratings, framed guard bars, ladders, railing, brackets and similar works.	12.07 Qlt			Per Quintal	
20	Providing and fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-Charge.	15.02 Sqm			Per Square Metre	
21	P/F steel welded wire mesh (50x50)mm including cutting, hoisting, fixing in position and applying a priming coat of red lead paint including carriage of materials up to all leads and lifts and as per the direction of the Engineer	50.00 Sqm			Per Square Metre	
22	Providing and laying cement concrete 1:3:6 (1 cement :3 sand :6graded stone aggregate 40mm nominal size) and curing complete excluding cost of form work in foundation and plinth with pitlilte or Dr.fixit water proofing treatment as per the direction of the Engineer-in-Charge but including carriage of materials up to all leads and lifts.	20.00 Cum			Per Cubic Metre	
23	Providing and fixing Unistone 12mm thick cladding on RCC surface side as on faces of Arch Masonry walls etc. on 12mm thick cement plaster in CM 1:3 (one cement isto three sand)and jointed with cement slurry including scaffolding complete. including carriage of materials up to all leads and lifts and as per the direction of Engineer-in-Charge.	60.00 Sqm			Per Square Metre	

Note :- All the material will be procured by the contractor him self.

EXECUTIVE ENGINEER
SHIMLA RURAL DIVISION
HPPWD, DHAMI