

# HP.P.W.D.TENDER

Short terms sealed items rate tender on PWD form Number 6 & 8 are hereby invited by the Executive Engineer, Jawali Division H.P.P.W.D. Jawali on behalf of the Governor of H.P. for the following work from the approved and eligible contractors C&D enlisted in H.P.P.W.D, so as to reach in this office in the waxed sealed cover on or before **26.08.2021** up to 11:00 (AM) and will be opened on the same day at 11:30 (A.M.) in the presence of the intending contractors or their authorized representative who may like to be present. The application for purchase of tender will be received up to 4.00 P.M on dated **24.08.2021** The tender form can be obtained from this office against cash payment non-refundable during the working hrs on **25.08.2021** up to 4.00 PM and no tender form shall be issued by post. The amount of earnest money in shape of FDR of any nationalized Bank in HP pledged in the name of the Executive Engineer, Jawali Division H.P.P.W.D. Jawali

The Conditional tender and tender received without earnest money will be rejected and if holidays declared by the Govt.. on the above date due to any reason the tender shall be received and opened on the next working day. The undersigned reserved the right to reject tender without assigning any reasons

S. No	Name of Work	Estimated Cost Rs.	Earnest Money Rs.	Time Limit	Cost of Form Rs.
1	R/R of Rain damages on various roads under HPPWD Sub Divn. Jawali(SH:- C/O Unpaved surface drain and Maintenance of earthen shoulder under Section Jawali-I).	199920/-	4000/-	One month	350/-
2	R/R of Rain damages of various roads under HPPWD Sub Divn. Jawali(SH:- C/O Unlined drain and Maintenance of earthen shoulder under Sidhatha Section).	154017/-	3100/-	One month	350/-
3	Improvement of Black spot on Jawalamukhi Dehra Jawali Raja-Ka-Talab road Km. 52/300 to 67/0(SH:- Providing and fixing W-Metal Beam steel crash Barrier at RD. 64/850 to 65/030).	484351/-	9700/-	One month	350/-
4	R/R of Rain damages on various roads under Jawali Sub Divn.HPPWD Jawali(SH:- C/O unlined Drain and Maintenance of earthen shoulders under Bharmar Section).	308028/-	6200/-	One month	350/-
5	Annual Maintenance of Rural roads under Annual Maintenance plan 2021-22 for Rural roads(SH:- Providing and laying hot applied Thermoplastic compound 2.5mm thick on Dhan to Guglara Via Chawara road Km. 2/0 to 4/0 & Lab to Jounta road Km. 13/0 to 14/0).	285000/-	5700/-	One month	350/-
6	Special repair of GSSS Matlahar under Deposit(SH:- C/O Toilet Block and other minor repair).	451590/-	9100/-	Two months	350/-
1.	The contractors/firms should possess the following documents(Photocopy to be attached)				
(i)	Copy of Registration/latest renewal of enlistment.				
(ii)	PAN Number(Permanent Account No).				
(iii)	Registration under GST No & EPF.				
2.	Ambiguous/Telegraphic/conditional tenders or tender by Fax/E-Mail shall not be entertained /considered in any case.				
3.	The offer of the tender shall be remain valid upto 30 days after the opening.				

1. Certified that tender of above works are being called of an emergent nature in Exigency of public interest.

Executive Engineer  
Jawali Divn. HP PWD,  
Jawali.

For on behalf of Governor of H.P.

No.PWJ/CB/TA/Tender/2021-22

Dated:-

1. Copy to the F.C Cum Principal Secretary(PW) to the Govt. of Himachal Pradesh Shima-2 for favour of information please.
2. Copy to the Engineer-in-Chief HPPWD Shimla for information please.
3. Copy to the Chief Engineer(KZ)HPPWD Dharamshala for favour of information please.
4. Copy to the Superintending Engineer,9<sup>th</sup> Circle HP PWD Nurgur for favour of information please.
5. Notice Board.
6. The Computer Cell office of the Engineer-in-Chief HpPWD Shimla for uploading the NIT on the Departmental website.

Executive Engineer  
Jawali Divn. HP PWD,  
Jawali.



1

## SCHEDULE OF QUANTITY

**Name of work:-** R/R of Rain damages on various roads under Sub Division HP:PWD, Javali. (SH: - C/O Unpaved surface drain and maintenance of earthen shoulders under Section Javali-I)

Estimated Cost : Rs. 1,99,920/-  
 Earnest Money : Rs. 4000/-  
 Time Limit : One Month

S.No.	Description of items	Quantity		Rates (In Rupees)		Unit	Amount
				In Figures	In words		
1	2	3		4	5	6	7
1	Surface Drains in soil	3500.00	Running Metres			Per Running Metre	
	Construction of unlined surface drains of average cross section all area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment with a lift upto 3m and lead of 50m (average 25m) as per technical specification clause 307						
2	Maintenance of earthen shoulder (filling with fresh selected soil)	4200.00	Square Metre			Per Square Metre	
	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved, selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m (One thousand metres ) as per technical specification Clause 1903.						
						Total:	

  
**Executive Engineer,**  
 Javali Division,  
 Javali-176023  
**H.P. P.W.D.**



2

# **SCHEDULE OF QUANTITY**


**Name of work:-** R/R of Rain damages of various roads under Sub Division HP.P.W.D. Jawali. (SH: - C/O Un-lined drain and maintenance of earthen shoulders under Sidhatla section)

Estimated Cost : Rs. 1,54,017/-

Earnest Money : Rs. 3100/-

Time Limit : One Month

S.No.	Description of items	Quantity		Rates (In Rupees)		Unit	Amount
				In Figures	In words		
1	2	3		4	5	6	7
1	Surface Drains in soil	3840.00	Running Metres			Per Running Metre	
	Construction of unlined surface drains of average cross section all area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment with a lift upto 3m and lead of 50m (average 25m) as per technical specification clause 307						
2	Maintenance of earthen shoulder (filling with fresh selected soil)	1780.15	Square Metre			Per Square Metre	
	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m (One thousand metres ) as per technical specification Clause 1903.						
						Total:	

  
**Executive Engineer,**  
 Jawali Division,  
 Jawali-176023



(3)

# **SCHEDULE OF QUANTITY**

**Name of work:--**Improvement of Black Spot on Jawalamukhi Dehra Jawali Raja Ka Talab road km. 52/300 to 67/0 (SH: - Providing and fixing W-Metal Beam Steel Crash Barrier at RD. 64/850 to 65/030)

Estimated Cost : Rs. 4,84,351/-

Earnest Money : Rs. 9700/-

Time Limit : One month

S.No	Description of items	Quantity		Rates (In Rupees)		Unit	Amount
				In Figures	In words		
1	2	3	Running Metres	4	5	6	7
3	Providing and erecting a "W" metal beam crash Barrier comprising of 3mm (three milimetres) thick corrugated sheet metal beam rail 70cm (seventy centimeters) above road ground level fixed with plain cement concrete 1:3:6 (one cement : three sand : six graded) on ISMC series channels vertical post 150x75x5mm (one hundred fifty into seventy five into five milimetres) spaced 2 meter (two metres) centre to centre 1.80 Metre point eight metre) high 1.10 meter (One point one zero metre) below ground (road level) all steel parts and fitment to be galvanized by hot dip process all fittings to conform to IS: 1367 and IS 1364 metal beam rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm (one hundred fifty into seventy five into five milimetres) 330mm (Three hundred thirty milimetres) long complete as per clause 811 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, malakana, toll tax, sale tax or other taxes imposed by the Government.	180.00				Per Running Metre	
						<b>Total:</b>	

**Executive Engineer,**  
**Jawali Division, H.R. P.W.D.**  
 Jawali-176023



2

## SCHEDULE OF QUANTITY

**Name of work:-** R/R of rain damages on various roads under HP:PWD Sub Division Jawali. (Bhamar section) (S.I):-  
C/O Unlined drains and maintenance of earthen shoulders)

Estimated Cost : Rs. 3,08,028/-  
Earnest Money : Rs. 6200/-

Time Limit : One Month

S.No.	Description of items	Quantity		Rates (In Rupees)		Unit	Amount
				In figures	In words		
1	1	2	3	4	5	6	7
1	Surface Drains in soil		7680.00			Per Running Metre	
	Construction of unlined surface drains of average cross section all area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment with a lift upto 3m and lead of 50m (average 25m) as per technical specification clause 307		Running Metres				
2	Maintenance of earthen shoulder (filling with fresh selected soil)		3560.00			Per Square Metre	
	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m (One thousand metres ) as per technical specification Clause 1903.		Square Metre				
						Total:	

**Executive Engineer,**  
**Jawali Division,**  
**Jawali-176023**



# SCHEDULE OF QUANTITY

**Name of work:-** Annual Maintenance of Rural Roads under Annual Maintenance Plan 2021-22 for Rural roads (SH: - Providing and laying Hot applied Thermoplastic compound 2.5mm thick on Dhan to Guglara Via Chalwara road km. 2/0 to 4/0 and Lab to Jounia road km. 13/0 to 14/0)

Estimated Cost : Rs. 2,85,000/-  
Earnest Money : Rs. 5700/-  
Time Limit : One month

S.No.	Description of items	Quantity		Rates (In Rupees)		Unit	Amount
				In Figures	In worda		
1	Providing and laying of hot applied thermoplastic compound 2.5mm (two point five millimetres) thick and (0.19 (zero point one zero) metre wide strip in centre line and 0.30 metre (zero point three zero metre) wide strip in zebra crossing including reflectorising glass beads @ 250gms (two hundred fifty grames) per square metre area, thickness of 2.5mm (two point five millimetres) is exclusive of surface applied glass beads as per IRC:35 (thirty five) in accordance with ministry of road transport specification (Latest revision) and IRC Code the finished surface to be level, uniform and free from streaks and holes including carriage of labours, equipments and materials to various location all modes of transportation in all leads, lifts and all incidental charges.	600.00	Square Metres	4	5	6 Per Square Metres	7
						Total:	

Executive Engineer,  
Jawahar Division, P.W.D.  
Jawahar-176023



## 6

### SCHEDULE OF QUANTITY

**Name of work:-** Special Repair of Govt. Senior Secondary School Matlahar under Deposit. (SH:- Construction of Toilet Block and other Minor Repair).

Estimated Cost : Rs. 4,51,590/-  
 Earnest Money : Rs. 9100/-  
 Time Limit : Two Months

S.No.	Description of items	Quantity		Rates (In Rupees)		Unit	Amount
				In Figures	In words		
1	2	3		4	5	6	7
1	Demolishing brick work manually/ by Mechanical means including stacking of serviceable materials and disposal of unserviceable material within all leads, as directed by the Engineer-in-Charge, within all leads, and lifts disposed earth to be levelled and neatly dressed including carriage of materials within all leads and lifts and other incidental charges. The rate is includes, royalty charges, octroi, GST sale tax, malkana and all other taxes as imposed by the Government.	2.27	Cubic Metres			Per Cubic Metre	
2	Earth work in excavation by mechnical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five milimetres) in width or 10sqm (Ten squaremetre) on plan) including dressing of side and ramming of bottams, lift upto 1.5m (One point five metres) including getting out the excavated soil and disposal of surplus excavated soil as directed within all leads all kind of soil. including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST sale tax, malkana and all other taxes as imposed by the Government.	2.84	Cubic Metres			Per Cubic Metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering, all work upto plinth level 1:3:6 (One cement : three sand : six graded stone aggregate 20mm (Twenty milimetres) nominal size including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	0.57	Cubic Metres			Per Cubic Metre	



	Random rubble masonry wall hard stone in foundation and plinth including leveling up with cement concrete 1:6:12 (One cement : Six coarse sand : twelve graded stone aggregate 20 mm (Twenty millimetres) nominal size) upto plinth level with Cement mortar 1:6 (One cement : Six coarse sand), including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, Malkana and all other taxes as imposed by the Government.					Metre	
	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and canilevers, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, Malkana and all other taxes as imposed by the Government.	10.02	Square Metre			Per Square Metre	
5	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° (Fifteen degree) landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (One cement : and half coarse sand : three graded stone aggregate 20 mm (Twenty millimetres) nominal size) including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, Malkana and all other taxes as imposed by the Government.	1.76	Cubic Metres			Per Cubic Metre	
7	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (One cement : Six sand) With Modular bricks, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, Malkana and all other taxes as imposed by the Government.	4.86	Cubic Metres			Per Cubic Metres	
8	15 mm (Fifteen millimetres) cement plaster on the rough side of single or half brick wall of mix 1:6 (One cement: six sand) including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, Malkana and all other taxes as imposed by the Government.	38.61	Square Metre			Per Square Metre	



9	12 mm (Twelve milimetres) cement plaster of mix 1:6 (One cement: six sand), including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	38.61	Square Metre			Per Square Metre	
10	6 mm (six milimetres) cement plaster 1:3 (One cement : three sand) finished with a floating coat of neat cement and thick coat of lime wash on top of walls when dry for bearing of R.C.C. slabs and beams, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	49.46	Square Metre			Per Square Metre	
11	Providing and applying white cement based putty of average thickness 1 mm (One millimetre) of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	126.67	Square Metre			Per Square Metre	
12	Distemping with 1st quality acrylic distemper, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre (Fifty grams oblique litre) of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	126.67	Square Metre			Per Square Metre	
13	Cement concrete flooring 1:2:4 (One cement : two sand : four graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etcetera complete. 40 mm (Forty milimetres) thick with 20 mm (Twenty milimetres) nominal size stone aggregate, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	35.43	Square Metre			Per Square Metre	



14	Precast terrazo tiles 22 mm (Twenty two millimetres) thick with graded marble chips of size upto 12 mm (Twelve millimetres) laid in floors, and landings, jointed with neat cement slurry mixed with pigment to match the shade of the tiles, including rubbing and polishing complete, on 20 mm (Twenty millimetres) thick bed of cement mortar 1:4 (One cement:four sand) : Light shade pigment using white cement, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	14.95	Square Metre				Per Square Metre	
15	Precast terrazo tiles 22 mm (Twenty two millimetres) thick with graded marble chips of sizes upto 12 mm (Twelve millimetres) in skirting and risers of steps not exceeding 30 cm (Thirty centimetres) in height, on 12 mm (Twelve millimetres) thick cement plaster 1:3 (One cement : three sand), jointed with neat cement slurry mixed with pigment to match the shade of the tiles, including rubbing and polishing complete with tiles of : Light shade pigment using white cement, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	26.47	Square Metre				Per Square Metre	
16	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply (Three ply) veneering with vertical grains or cross bands and face veneers on both faces of shutters 35 mm (Thirty five millimetres) thick including ISI marked Stainless Steel butt hinges with necessary screws, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	6.48	Square Metre				Per Square Metre	
17	Providing and fixing glazed utters for doors, windows and clerestory windows using 4 mm (Four millimetres) thick float glass panes, including ISI marked M.S. (Mild steel) pressed butt inges bright finished of equied size with necessary screws. Kiln seasoned selected planks of Sheesham wood 35 mm (Thirty five millimetres) thick, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	3.78	Square Metre				Per Square Metre	



18	Providing and fixing 300x16 mm (Three hundred into sixteen millimetres) aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etcetera complete, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	4	Numbers				1 each	
19	providing and fixing 200x10 mm(Two hundred into ten millimetres) aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 (Ten) as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete , including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	24	Numbers				1 each	
20	Providing and fixing 100 mm (One hundred millimetres) aluminium angles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with ecessary screws etc. complete, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	24	Numbers				Each	
21	Providing and fixing water closet squatting pan (Indian type W.C. pan ) with 100 mm (One hundred millimetres) sand cast Iron P or S trap, 10 litre (Ten litre) low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	2	Numbers				Each	
22	Providing and Fixing PVC pipes. 110 mm (One hundred ten millimetres) diameter, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	5.60	Running Metre				Per Running Metre	



23	Providing and Fixing PVC plain bends 110 mm (One hundred ten millimetres) diameter, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	2	Numbers				Each	
24	Providing and fixing brass bib tap (Superior or heavy type) :- 15mm (Fifteen millimetres) diameter, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	2	Numbers				Each	
25	Providing and fixing to wall ceiling and floor galvanised mild steel tubes (Medium grade) tube fitting and clamps including making good the wall, ceiling and floor, as per direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	12.20	Running Metre				Per Running Metre	
26	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm (eight millimetres) diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of proved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of urlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm (Zero point six three millimetres) thick with zinc coating not less than 275 gm/ m <sup>2</sup> (Two hundred seventy five grams oblique square metre), including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	58.32	Square Metre				Per Square Metre	
27	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	1081.25	Kilogrammes				Per Kilogrammes	



28	Deployment of Excavator Cum Loader (JCB) FOR REMOVAL OF slips, trees and such like activities repair of berms earthen shoulder and katcha drain on hiring basis in all kind of classification of soil complete in all respect as per direction of Engineer-in-Charge. The cost of lubricants, diesel, Operator, maintenance cost etcetera will be borne by the contractor, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	10.00	Hour					Per Hour	
29	Providing and laying 60mm (Sixty millimetres) thick factory made cement concrete interlocking paver block of M-30 (M-Thirty) grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, GST, sale tax, malkana and all other taxes as imposed by the Government.	120.00	Square Metre					Per Square Metre	
								Total:	

Executive Engineer,  
Rajwadi Division, H.P.R.W.D.  
Rajwadi-176023