

CERTIFICATE

Certified that the tenders have been invited in exigencies/emergency of work.


Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed item rates tender are hereby invited by the Executive Engineer, Ghumarwin Division, HP-PWD. Ghumarwin for the following works from the registered contractors of appropriate class enlisted in HP-PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act. 1968. The important date of tender are as under:-


Date of application 14/10/2021
Date of sale of tender. 16/10/2021

The tender shall be received up to 11:00A.M. on 18/10/2021 and will be opened on the same day at 11:30 A.M in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on 16/10/2021.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Ghumarwin Division, HP-PWD, Ghumarwin must accompany with each application. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The XEN reserve the right to accept or reject the tenders without assigning any reason.

S No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit
1	C/o Boundary wall at HSC Mundkhar Teshil Ghumarwin Distt. Bilaspur HP	Rs.471227/-	Rs.9500/-	Rs.350/	Two Month
2	C/o link road Chehari Jahari Kasaru Babeli Km 0/0 to 4/0	Rs.416283/-	Rs.8400/-	Rs.350/	Two Month
3	C/o L/R from Dadhol, ladrou road Kothi to Kamli Samlah Bhat Bhatwara Paplah Malot i/c Bridge over Drug Khad (SH:-ROFD at RD 0/210 to 0/240, 0/525 to 0/705 and C/o R/wall at RD 0/263 to 0/271.0, 0/289 to 0/292, W/wall at RD 0/685 to 0/703 and abutment at RD 0/240 to 0/435)	Rs.430818/-	Rs.9000/-	Rs.350/	One Month
4	C/o L/R Bouni towards GPS Dhalyani	Rs.298063/-	Rs.6000/-	Rs.350/	One Month

- I. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- II. The contractors should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.
- III. The list of similar type of work executed & work done performance certificate issued by the concerned Executive Engineer/GST/EPF No should be accompanied with application.
- IV. Earnest money should be accompanied with application. Application without earnest money will not be entertained.


Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW/GHD/CB/Tender/2021-

756266

Dated:- 27/09/2021

Copy along with Notice Inviting Tender list is forwarded to:-

1. The Engineer-in-Chief HPPWD Shimla-2
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineer, 10th Circle, HPPWD Bilaspur
4. The Executive Engineer (IT) O/O Engineer-in-Chief HPPWD Shimla-2 eeict-pwd-shi[at]hp[dot]gov.in a/w schedule of quantity to download on the department portal.
5. Drawing Branch
6. Account Branch


Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

ESTIMATED COST:- Rs. 471227/-Only.

EARNEST MONETY:- Rs.9500/-only.

TIME ALLOWED:-TWO Month.

SCHEDULE OF QUANTITY

Name of work:-C/O Boundary Wall at HSC Mundkhar Tehsil Ghumarwin Distt. Bilaspur (HP) (SH:-C/O boundary wall)

Sr No	Description /items	Quantity	Rate		unit	Amount
			Rate	Words.		
1	Excavation in hilly soil by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto any lead and lift upto 20 metre as per technical specification clause 1603.1 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	60.80			Per cubic metre	
2	Excavation in foundation trenches etcetera in earth work in all kinds of soil such as pick work, jumper work, blasting work soft or hard rock by chiseling/wedging out of rock where blasting is prohibited or in conglomerate rock and saturated soil etcetera including pumping and bailing out water stacking the serviceable excavated material 3.00 Meter (Three meter) clear from the edge of excavation with in all leads and lifts and then returning the stacked soil in fifteen centimeter layers when required into plinths and sides of foundation etcetera consolidating each deposited layer by ramming, watering and then disposal of surplus excavated earth as directed by Engineer-in-charge up to all leads and lifts disposed earth to be leveled and of neatly dressed. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	84.49			Per Cubic Metre	
3	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size plain/reinforced concrete in open foundation complete as per drawing and HP.PWD., technical specification clause 802, 803, 1202 & 1203 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	153.15			Per cubic meter	
4	Random rubble masonry (Uncoursed/brought to courses) with hard stones of approved quality in foundation and plinth including levelling up with cement concrete 1:6:12 (One cement: six sand: Twelve graded stone aggregate 20mm (Twenty millimetre nominal size) at plinth level in cement mortar 1:6 (One cement: Six sand) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	10.21			Per cubic Metre	
5	Brick work using common burnt clay building bricks in foundation and plinth in : in cement mortar 1:5 (one cement: five sand) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	2.7			Per cubic Metre	
6	Half brick masonry in common burnt clay building bricks in cement Mortar 1:4 (1 cement: 4 sand) in super structure 2nd class brick including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	79.89			Per Square Metre	
7	Providing 15mm thick cement plaster in single coat on rough side brick/concrete/walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth in cement mortar 1:6 (1 cement: 6 sand) and curing complete including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	114.85			Per Square Metre.	

8	Steel work welded in built up section, trusses and framed work including cutting, hoisting fixing in position and applying a priming coat of red lead paint in beam joints channels, angles, tee, flats with connection plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	1.70			per qtl	
9	Providing weep holes in brickmasonry/stone masonry/plain reinforced and concrete abutment wing wall R/Wall B/Wall with 100mm dia (Hundred millimetre) PVC pipe and complete providing and technical specification clause 614,709,12043.7. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	50.00			Each	
	Total=					

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

SCHEDULE OF QUANTITY						
			ESTIMATED COST:- Rs .416283/-ONLY.			
			EARNEST MONELY:- Rs 8400 Only.			
			TIME ALLOWED:- TWO MONTH.			
NAME OF WORK:C/O link road Chehari Jahari Kasaru Babeli km 0/0 to 4/0 (SH:- ROFD in km 2/165 to 2/540) unconneted Panchayat)						
Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-charge at site according to the M.O.R.D. Technical specification clause 300,1603.1,1603.2 and sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of material for filling in road way, camber embankments for grade improvements and disposal of all useful/surplus materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its leveling fine dressing and carriage of machineries, materials tools equipments and execution shall be the absolute responsibility of all the contractor which shall have to be duly compensated by him in all cases as per direction of Engineer-in-charge including carriage of material with in all leads and lifts . The rate including octroi,rolyality,Makrana,toll tax, sale tax or other taxes imposed by the Government. A recovery of useful stone for 91.71 cubic metre at the rate of Rs. 170/-(Rupes one lhundred seventy) per cubic metre shall be done on pro-rae basis in ekach running bill for this item	1663.80			Per cubic Metre	
	Total=					


 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs .498812/-ONLY.


EARNEST MONEY:- Rs. 10000 Only.

TIME ALLOWED:- TWO MONTH.


NAME OF WORK:-C/O L/R From Dhadhol, Ladrour Road vill Kothi to kamli Samlah bhatwara paplah malot i/c Bridge over Drug khad (SH:-ROFD at RD. 0/210 to 0/240, 0/525 to 0/705 and C/O R/Wall at RD. 0/263 to 0/271.10, 0/289 to 0/292 , B/Wall at RD. 0/685 to 0/703 & embankment at RD. 0/240 to 0/435)

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-charge at site according to the M.O.R.D. Technical specification clause 300,1603.1,1603.2 and sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of material for filling in road way, camber embankments for grade improvements and disposal of all useful/surplus materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its leveling fine dressing and carriage of machineries, materials tools equipments and execution shall be the absolute responsibility of all the contractor which shall have to be duly compensated by him in all cases as per direction of Engineer-in-charge including carriage of material with in all leads and lifts . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. A recovery of useful stone for 155.98 cubic metre at the rate of Rs. 170/-(Rupes one hundred seventy) per cubic metre shall be done on pro-rae basis in ekach running bill for this item	935.88			Per Cubic Metre	
2	Construction of embankment with approved material abtained from barrow pits with a lift of 1.50 mtr. Transporting grading to required slopes and compacting as per requirement of table 300.1 and 300.2 as per specification clause 301.5 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	1058.74			Per cubic meter	
3	Earth work is excavation for structures as per drawings and technical specifications cloause305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50 metres dressing of sides and bottom and back filling in trenches with excavated suitable materials(i)upto 3 metredepth MORD specification page NO.126Sr.No.11.1 MORD specification 300including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	26.13			Per cubic metre	
4	Providing and cement concrete 1:5;10 (One cement:Five sand:Ten graded stone aggregate of form work for plain/reinforced concrete in retining walls, breast walls, as per drawing and H.P.P.W.D., specification including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	78.56			Per cubic metre	
5	Providing weep holes in brickmasonrly/stone masonry/plain reinforced and concrete abutment wing wall R/Wall B/Wall with 100mm dia (Hundred millimetre) PVC pipe and complete providing and technical specification clause 614,709,12043.7. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The ratre including octroi, royalty, Malkana toll tax, GST or other taxis imposed by the Government.	37.00			Each	

6	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	19.13			Per cubic metre	
	Total=					


 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

SCHEDULE OF QUANTITY						
			ESTIMATED COST:- Rs .298063/-ONLY.			
			EARNEST MONELY:- Rs 6000 Only.			
			TIME ALLOWED:- TWO MONTH.			
NAME OF WORK:-C/O link road Bouni to Govt. Primary School Dhalyan Tehsil Ghumarwin Distt. Bilaspur (SH:-F/C in km 0/0 to 0/195 & 0/285 to 1/021))						
Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-charge at site according to the M.O.R.D. Technical specification clause 300,1603.1,1603.2 and sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of material for filling in road way, camber embankments for grade improvements and disposal of all useful/surplus materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, along with its leveling fine dressing and carriage of machineries, materials tools equipments and execution shall be the absolute responsibility of all the contractor which shall have to be duly compensated by him in all cases as per direction of Engineer-in-charge including carriage of material with in all leads and lifts . The rate including octroi, rolyality, Makrana, toll tax, sale tax or other taxes imposed by the Government. A recovery of useful stone for 263.41 cubic metre at the rate of Rs. 170/-(Rupes one lhunder seventy) per cubic metre shall be done on pro-rae basis in ekach running bill for this item	2923.05			Per cubic Metre	
	Total=					


 Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin

CERTIFICATE

Certified that the tenders have been invited in exigencies/emergency of work.



Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed item rates tender are hereby invited by the Executive Engineer, Ghumarwin Division, HP-PWD. Ghumarwin for the following works from the registered contractors of appropriate class enlisted in HP-PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act. 1968. The important date of tender are as under:-

Date of application 14/10/2021
Date of sale of tender. 16/10/2021

The tender shall be received up to 11:00A.M. on 18/10/2021 and will be opened on the same day at 11:30 A.M in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on 16/10/2021.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Ghumarwin Division, HP-PWD, Ghumarwin must accompany with each application. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The XEN reserve the right to accept or reject the tenders without assigning any reason.

S No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit
1	C/o Missing pipe culvert on Ghumarwin Talai Bhakhra road km 0/0 to 5/0 (SH:-C/o Missing pipe culvert at RD. 0/024 and W/Wall)	Rs.258601/-	Rs.5200/-	Rs.350/-	Two Month
2	Restoration of approach of Vinay Kumar Village Vijaypur P.O. Auhar Tehsil Jhandutta Distt Bilaspur HP (SH:- C/o R/Wall at R/Wall at RD. 0/0 to 0/20)	Rs.153400/-	Rs.3100/-	Rs.350/-	Two Month
3	Construction of Record room in Judicial Court complex at Ghumarwin (SH:- P/L of interlocking paver block in parking, site development)	Rs.255274/-	Rs.5200/-	Rs.350/-	One Month
4	A/R & M/O type III quarter in HPPWD Colony at Ghumarwin	Rs.117510/-	Rs.2400/-	Rs.350/-	One Month

- The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- The contractors should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.
- The list of similar type of work executed & work done performance certificate issued by the concerned Executive Engineer/GST/EPF No should be accompanied with application.
- Earnest money should be accompanied with application. Application without earnest money will not be entertained.

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW/GHD/CB/Tender/2021-

756271

Dated:- 27/09/2021

Copy along with Notice Inviting Tender list is forwarded to:-

1. The Engineer-in-Chief HPPWD Shimla-2
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineer, 10th Circle, HPPWD Bilaspur
4. The Executive Engineer (IT) O/O Engineer-in-Chief HPPWD Shimla-2 eeict-pwd-shi[at]hp[dot]gov.in a/w schedule of quantity to download on the department portal.
5. Drawing Branch
6. Account Branch

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs .258601/-ONLY.

EARNEST MONELY:- Rs 5200/- Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK:-C/O Missing pipe culvert on Ghumarwin Talai Bhakhra road km 0/0 to 5/0 (SH:-C/O Missing pipe culvert at RD. 0/024 and W/Wall)

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Earth work is excavation for structures as per drawings and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50 metres dressing of sides and bottom and back filling in trenches with excavated suitable materials(i) upto 3 metre depth MORD specification page NO.126Sr.No.11.1 MORD specification 300 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	88.31			Per cubic metre	
2	Providing and laying concrete for plain/ reinforced cement concrete in open foundation complete as per drawing and technical specification clause 802, 803, 1202 and 1203 1:4:8 (One cement: four sand: eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	3.83			Per cubic metre	
3	Providing concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802, 803, 1202 & 1203 grade M-10 (1:3:6) including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	15.43			Per cubic metre	
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement: Two sand) but excluding excavation protection work, back filling concrete and masonry work to head walls and parapets clause 1108 @ 900mm dia including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	10.00			Per Running Metre	
5	Providing and laying dowel bar in foundation in hard rock including making holes for dowel bar and fixing 25mm dia for steel in cement slurry including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	34.00				
6	Providing and cement concrete 1:5:10 (One cement: Five sand: Ten graded stone aggregate of form work for plain/reinforced concrete in retaining walls, breast walls, as per drawing and H.P.P.W.D., specification including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	67.02			Per cubic metre	
7	Providing weep holes in brick masonry/stone masonry/plain reinforced and concrete abutment wing wall R/Wall B/Wall with 100mm dia (Hundred millimetre) PVC pipe and complete providing and technical specification clause 614, 709, 12043.7. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	20.00			Each	
8	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	8.28			Per cubic metre	
Total=						

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs .153400/-ONLY.

EARNEST MONEY - Rs 3100 Only.

TIME ALLOWED:- TWO MONTH.

NAME OF WORK:-Restoration of approach of Vinay Kumar village Vijaypur P.O. Auhar Tehsil Jhandutta Distt. Bilaspur (HP) (SH:- C/O R/Wall at R/Wall at RD. 0/0 to 0/020)

Sr.No.	Sub-Head and item of work.	Quantity	rates in		Unit	Amount.
			Figures	Words.		
1	Earth work is excavation for structures as per drawings and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50 metres dressing of sides and bottom and back filling in trenches with excavated suitable materials upto 3 metre depth MORD specification page NO.126Sr.No.11.1 MORD specification 300 including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	29.80			Per cubic metre	
2	Providing and cement concrete 1:5:10 (One cement:Five sand:Ten graded stone aggregate of form work for plain/reinforced concrete in retaining walls, breast walls, as per drawing and H.P.P.W.D., specification including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	63.00			Per cubic metre	
3	Providing weep holes in brickmasonry/stone masonry/plain reinforced and concrete abutment wing wall R/Wall B/Wall with 100mm dia (Hundred millimetre) PVC pipe and complete providing and technical specification clause 614,709,12043.7. including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	32.00			Each	
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204 3.8 granular material including carriage of material within all leads and lifts as directed by the Engineer-in-charge. The rate including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	23.20			Per cubic metre	
	Total=					


Executive Engineer
 Ghumarwin Division
 PWD Ghumarwin

Schedule of Quantity

Estimated Cost:- Rs. 2,55,274.00

Earnest Money:- Rs. 5,200.00

Time :- One Month

Name of Work:- Construction of Record room in Judicial Court complex at Ghumarwin (SH:- Providing and laying of interlocking paver block in parking, site development).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto all leads and lift. dressing of sides and bottom and back filling in trenches with excavated suitable material as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	78.00	Per cubic metre			
2	Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. For Grading I Material including carriage of material with in all leads and lifts as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	40.00	Per cubic metre			
3	Providing and Laying concrete 1:4:8 (one cement : four sand : eight crushed stone aggregate) (40mm forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.00	Per cubic metre			
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (eighty millimetre) as per drawings and Technical Specification Clause 1504 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	249.66	Per square metre			
5	Providing and laying cement concrete for plain / reinforced concrete in open foundations complete as per technical specifications clauses 802, 803, 1202 and 1203 1:2:4 (one cement : two sand : four crushed stone aggregate) PCC Grade M-20 (twenty) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.30	Per cubic metre			
Total:-						


Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin

Estimated Cost:- Rs. 1,17,510.00
 Earnest Money:- Rs. 2,400.00
 Time :- One Month

Schedule of Quantity

Name of Work:- A/R & M/O to Type III Quarter in HP.PWD Colony at Ghumarwin (SH:- Painting work in 5 No's Quarters).

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Wall painting(one coat)with plastic emulsion paint of approved brand and manufacture on decorated wall surface to give an even shade including thoroughly brushing the surface clean of all dirt grease,loose pieces of scale and sand papered smooth.as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1211.47	Per square metre			
2	Extra item for every sub sequent coat of wall painting with plastic emulsion paint of approved brand and manufacture.as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1211.47	Per square metre			
3	Painting one coat (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt,dust and other foreign matter With Enamel paint other than white as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	355.11	Per square metre			
4	Extra item or every subsequent coat of paint.With enamel paint other than white as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	355.11	Per square metre			
5	Painting one coat (excluding priming coat)on previously painted wood and wood based surfaces with readymixed paint brushing to give an even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping With readymixed paint other then white as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	297.52	Per square metre			
6	Extra item for every subsequent coat of paint With readymixed paint(white) including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	297.52	Per square metre			
7	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equarled on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete.as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	481.84	Per square metre			
Total:-						

Executive Engineer
 Ghumarwin Division
 HPPWD Ghumarwin