

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PW-MDI-E-Tender-NIT/2021-22-

9156-S8

Dated:-13/9/21

To

✓ The Executive Engineer (IT Cell),
Nigam Bhhar, Shimla-2.

Subject: -

Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD, Mandi.

Copy forwarded the Superintending Engineer, 1st Circle, HPPWD, Mandi for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell) Nigam Bihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. Mandi.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PW-MDI-E-Tender-NIT/2021-22-

9156-58

Dated:- 13/9/2021

To

The Executive Engineer (IT Cell),
Nigam Bhhar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,
Mandi Division No.I,
HP. PWD. Mandi.

Copy forwarded the Superintending Engineer, 1st Circle, HPPWD, Mandi for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell) Nigam Bihar, Shimla-2 for information and further necessary action please.

Executive Engineer,
Mandi Division No.I,
HP. PWD. Mandi.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., Mandi on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before **20.09.2021 up to 12:00 Noon** and the same shall be opened on the same day at **12:30 P.M.** in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on **18.09.2021 upto 01:00 P.M.**

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., Mandi reserves the right to accept or reject the tenders. The tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Annual repair and maintenance of Pandoh Shiva road Km 0/0 to 13/0. (SH:- Construction of Retaining wall at RD 12/960 to 12/972.50)	3,59,371/-	7,200/-	350/-	One month
2	Annual repair and maintenance of Pandoh Shiva road Km 0/0 to 13/0. (SH:- Construction of Retaining wall at RD 12/972.50 to 12/985)	3,59,372/-	7,200/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The intending Contractors are requested to see the site of the work before submitting the tender.
5. The offer of the tender shall remain valid upto 90 days after the opening of tender.
6. The tender will be awarded without negotiation if the tendered amount is within (-) 10% to (+) 5% of approved market rates otherwise the tender will be recalled and negotiation shall be done as per CPWD Manual or CVC Guidelines. The negotiations procedure shall be as per Para 5.1.8(2) and SOP No. 5/4 which are limited only in specific situation as mentioned in paras.
7. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

HIM SUCHANA AVAM JAN SAMPARK


Executive Engineer,
Mandi Division No. I,
HPPWD., Mandi Distt. Mandi (H.P.)

Schedule of Quantity

Estimated Cost:- Rs. 359371.00
 Earnest Money:- Rs. 7200.00
 Time:- One month

Name of work:- Annual repair and maintenance of Pandoh Shiva road Km. 0/00 to 13/00.
 Sub Head:- Construction of Retaining wall at RD 12/960 to 12/972.50

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation of foundation of structures for all kinds of soil as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and dressing of sides and bottoms, back filling the excavation earth to the extent required and utilising the remaining earth locally for road work complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	37.12 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification. Plain cement concrete nominal mix 1:6:12 (one cement : six sand : twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	4.25 Cum.			Per cubic metre	
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification. Random rubble masonry in cement mortar 1:6 (one cement : six sand) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	47.25 Cum.			Per cubic metre	
4	Back filling behind abutment wing wall and return wall/retaining wall in all heights and depths complete as per Drawing and technical specifications, Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	9.75 Cum.			Per cubic metre	
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.00 No.			Each	
					Total	


 Executive Engineer,
 Mandi Division No.1,
 HP.PWD, Mandi

Schedule of Quantity

Estimated Cost:- Rs. 359372.00
Earnest Money:- Rs. 7200.00
Time:- One month

Name of work:- Annual repair and maintenance of Pandoh Shiva road Km. 0/00 to 13/00.
Sub Head:- Construction of Retaining wall at RD 12/972.50 to 12/985.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation of foundation of structures for all kinds of soil as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and dressing of sides and bottoms, back filling the excavation earth to the extent required and utilising the remaining earth locally for road work complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	37.13 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification. Plain cement concrete nominal mix 1:6:12 (one cement : six sand : twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	4.25 Cum.			Per cubic metre	
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification. Random rubble masonry in cement mortar 1:6 (one cement : six sand) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	47.25 Cum.			Per cubic metre	
4	Back filling behind abutment wing wall and return wall/retaining wall in all heights and depths complete as per Drawing and technical specifications, Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	9.75 Cum.			Per cubic metre	
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.00 No.			Each	
					Total	


Executive Engineer,
Mandi Division No.1,
H.P.PWD, Mandi.