

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer National Highway Division HPPWD Theog.

Email: eenh-theog-hp@gov.in Phone/ Fax No.: - 01783-238900

NO.PW.TH.D/CB/TENDER/Tender Notice/2020-21-

3628-30

Dated:- 25/9/2021


To

The Executive Engineer,(IT)
Nigam Vihar Shimla 2

Subject:- Publication of tender Notice.


Enclose please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on department website as per Notification Pr. Secy. (PW)) to the Govt. of HP letter No PBW(B)A(3)1/2020 dated 19 June 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl:- Schedule of Quantity.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Copy forwarded to the Superintending Engineer NH Circle Shimla HP PWD for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer(IT) Cell), Nigam Vihar Shimla-2 for information and further necessary action please.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department
Notice Inviting Tender

Sealed item rate s tender form No 6 & 8 are hereby invited by the Executive Engineer NH Division HP PWD Theog for the following works on behalf of the Governor of Himachal Pradesh from the eligible contractors enlisted in HP PWD so as to reach in this office as per time schedule Given below:-

- | | | |
|---|---|--------------------------|
| 1 | Date of receipt of Applications for tender forms: | 04.10.2021 upto 12:00 PM |
| 2 | Date of issue/sale of Tender forms:- | 05.10.2021 upto 4:00 PM |
| 3 | Date of receipt of Tender:- | 06.10.2021 upto 10:30 AM |
| 4 | Date of opening of Tender | 06.10.2021 upto 11:00 AM |

Sr. No	Name of Works	Estimated Cost	Earnest Money	Cost of form	Time Period for completion	Form No	Eligibility of Contractors
1	Ordinary repair to Kalka Shimla Wangoo road on NH22(New NH 05) Km 153/180 to 165/0)(Supplying and installation of Porta Cabin at Chhabra at Km 159/860	321525	6450	350	One Month	6&8	Class C & D enlisted in HP PWD
2	R/R damages on Kalka Shimla Wangoo road on Nh 05(from Km 155/0 to 236/0(SH: Removal of slips at various RD's between Km 177/0 to 193/0)	388654	7800	350	One Month	6&8	Class C & D enlisted in HP PWD
3	Ordinary repair on Kalka Shimla Wangoo road NH 22(New NH 05)Km 155/0 to 236/0(SH: Construction of Gate for NH Circle HP PWD Chaura Maidan Shimla HP)	84800	1700	350	One Month	6&8	Class C & D enlisted in HP PWD

Terms & Conditions:- The tender documents shall be issued to those contractors/firms who fulfill the following documents with the application:

- 1 The valid enlistment/ registration of contractor in appropriate class.
- 2 Permanent Account Number(PAN)
- 3 GST Number and EPF No.
- 4 Earnest Money in the shape of National saving certificate/Time deposit account in any of the Post office in HP FDR from any Nationalized Bank duly pledged in favour of the executive Engineer.
- 5 The earnest Money & Cost of Tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & Cost tender form shall summarily be rejected.
- 6 Ambiguous/telegraphic/Conditional tender of tender by fax/ E-mail shall not be entertained/considered and will summarily be rejected.
- 7 Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.

- 8 The offer of the tender shall remain valid upto 120 days after the opening of tender.
- 9 If the date given above happens to be a holiday, the same shall be processed on next working days.
- 10 The Contractors/firm must quote their rates in words as well as in figures failing which Xen reserves the right to accept/reject any or all tenders.
- 11 The Tender form will not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed/completed the previous awarded works within the stipulated period of completion.
- 12 One Contractor should not have more than two works in hand at a time.
- 13 Works should be completed by the contractor within the stipulated period.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog
Dated 25/9/2021

No/PW/NH/CB/Tender/2021

3577-3627

Copy forwarded for information and necessary actions to:

- 1 The Engineer-in Chief HP PWD Nigam Vihar shimla
- 2 The Chief Engineer, NH HP PWD Shimla 2
- 3 The Deputy Commissioner, Shimla . It is requested to display the notice on Notice Board
- 4 The Superintending Engineer, NH Circle HP PWD Shimla . It is requested to display the notice on the Notice Board please.
- 5 All the Superintending Engineer/Executive Engineers in HP PWD.
- 6 The Tehsildar Theog. It is requested to display the notice on Notice Board.
- 7 The BDO Theog . It is requested to display the notice on Notice Board.
- 8 All the Assistant Engineer working under this Division . It is requested to display the notice on Notice Board.
- 9 Correspondence Branch/Drawing Branch/Account Branch /Notice Board.

Executive Engineer,
NH Division,
H.P.P.W.D., Theog

SCHEDULE OF QUANTITY


Name of Work:- Ordinary Repair to Kalka Shimla Wangtoo road on NH-22(New NH-05) Km. 153/180 to 165/00 (SH:-Supplying and installation of Porta Cabin at Chhabra at Km. 159/860)

Estimated Cost:-321525.00

Earnest Money :-
6450.00

Time :- One Month.

Sr. No	Description of Work / Item (S)	Qty.	Unit	Rate with GST		Rate without GST		Amount with GST	Amount Without GST
				In Figures	In words	In Figures	In words		
1	Wrought iron and mild steel welded work) (using angle, square bars, tees and channel grills, grating frames, gates and tree guards of any size and design etc. including cost of screen and welding rod or bolts and nuts complete fixed in position but without the cost of excavation and concrete for fixing which will be paid separately	23.20	Qtls						
2	Providing and fixing internal wall and ceiling paneling of 6mm pre-laminated board of approved quality of IS standard or equivalent with butt joining and nail complete with all respect as per drawing and entire satisfaction of Engineer-in-Charge	57.02	Sqm						
3	Providing and fixing of cement Fiber board of 18mm thick in flooring of approved quality of IS standard or equivalent with butt jointing and nail complete with all respect as per drawing and entire satisfaction of Engineer-in-Charge	14.78	Sqm						
4	Providing and fixing 2mm thick Vinyl flooring plain or colored curbed or mosaic /metalled finish laid with approved adhesive on sub floor complete with all respect as per drawing and entire satisfaction of Engineer-in-Charge.	14.78	Sqm.						
5	Providing and fixing of preparatory board over head cabin under the shelves with bwp phenol bonded exterior /interior grade both side 8mm thick complete with all respect as per drawing and entire satisfaction of Engineer-in-Charge.	6.61	Sqm.						
6	Applying priming coat over new steel and other metal surfaces after the including preparing the surface by thoroughly cleaning oil grease dirt and other foreign matter and scoured with wire brushes fine steel wool scrappers and sand paper complete in all respect and entire satisfaction of Engineer-in-Charge	165.89	Sqm.						
7	Painting on steel surface : Providing and applying two coats of ready mix paint of approved brand on steel surface after thorough cleaning of surface to give an even shade	165.89	Sqm.						
8	Providing and fixing of aluminum sliding window of size 0.9m x 0.9m with all hinges tower bolts handles and fixing with wire gauge (JALLI) Weight 15.10 Kg per sqm. Hence 2 Nos window weight= 15.10 x 2 = 30.20 Kg. complete in all respect and entire satisfaction of Engineer-in-Charge	2.00	Nos						
9	Providing and fixing of stainless steel sink approved standard ISI Marked 610mm x 510mm with bowl depth 200mm HPSR rates 2011 water supply and sanitary installation item No.3.132 complete in all respect and entire satisfaction of Engineer-in-Charge	1.00	No						
10	Providing and fixing of all Electrical items as per the drawing complete in all respect and entire satisfaction of Engineer-in-Charge	13.00	Nos						


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Schedule of Quantity

Name of Work:- R/R damages on Kalka Shimla-Wangtoo road NH-22(New NH-07) km 155/00 to 236/00 (SH: Removal of slips on various RD's in between Km. 177/00 to 193/00).


Estimated Cost:-388654.00

Earnest Money :-7800.00

One Months.

Time :-

Sr. No.	Description of Work / Item (S)	Qty.	Rate		Amount
			In figures	In words	
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within all lift and lead as per technical specification 302.3.5 and 1611 as per direction of Engineer-in-Charge.	1518.18	Cum		


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

SCHEDULE OF QUANTITY


Name of Work:- Ordinary repair on Kalka-Shimla-Wangtoo road NH-22 (New NH-05) KM 155/00 TO 236/00 (SH:- Construction of Gate for NH Circle HPPWD Chaura maidan Shimla HP).

Estimated Cost:- 84800.00

Earnest Money :- 1700.00


Time :- One Month.

Sr. No	Description of Work / Item (S)	Qty.		Rate		Amount
				In figures	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil within all leads and lifts as per direction of Engineer-in-Charge (ordinary rock)	5.76	Cum			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)	5.76	Cum			
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works as per direction of Engineer-in-Charge.	426.99	Kg			
4	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture.	25.99	Sqm			
5	Providing and fixing ISI marked, IS : 1341, M.S. heavy weight butt hinges with necessary screws etc. complete as per direction of Engineer-in-Charge. i) 125x90x4.00 mm	4.00	Nos.			
	ii) 100x75x3.50 mm	2.00	Nos.			
6	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete as per direction of Engineer-in-Charge. : 300x16 mm	2.00	Nos.			


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Certificate

Certified that the tenders of works as called vide this office NIT No/PW/NH/CB/Tender/2021-3577-3627 Dated 25.09.2021 are of urgent nature works.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog