



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer National Highway Division HPPWD Theog.

Email: ee-nh-theog-hp@gov.in Phone/ Fax No.: 01783-238900

NO.PW.TH.D/CB/TENDER/Tender Notice/2020-21-
To

Dated:- 7/9/2021

3051-53

The Executive Engineer,
Nigam Vihar Shimla 2

Subject:- Publication of tender Notice.


Enclose please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on department website as per Notification Pr. Secy. (PW)) to the Govt. of HP letter No PBW(B)A(3)1/2020 dated 19 June 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl:- Schedule of Quantity.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Copy forwarded to the Superintending Engineer NH Circle Shimla HP PWD for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer(IT) Cell), Nigam Vihar Shimla-2 for information and further necessary action please.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

**Himachal Pradesh
Public Works Department
Notice Inviting Tender**

Sealed item rate s tender form No 6 &8 are hereby invited by the Executive Engineer NH Division HP PWD Theog for the following works on behalf of the Governor of Himachal Pradesh from the eligible contractors enlisted in HP PWD so as to reach in this office as per time schedule Given below:-


- | | | |
|---|---|--------------------------|
| 1 | Date of receipt of Applications for tender forms: | 14.9.2021 upto 2:00 PM |
| 2 | Date of issue/sale of Tender forms:- | 15.9.2021 upto 4:00 PM |
| 3 | Date of receipt of Tender:- | 16.09.2021 upto 10:30 AM |
| 4 | Date of opening of Tender | 16.09.2021 upto 11:00 AM |

Sr. No	Name of Works	Estimated Cost	Earnest Money	Cost of form	Time Period for completion	Form No	Eligibility of Contractors
1	Restoration of rain damages on Kalka Shimla Wangtoo Road on NH 05 Km 155/0 to 236/0(SH: C/o R/wall from Km 204/380 to 204/395)	493126/-	9900/-	350/-	Two Months	6&8	Class C & D enlisted in HP PWD
2	R/R damages on Kalka Shimla Wangtoo road NH 22(New NH 05) Km 155/0 to 236/0(SH: Removal of slips/debris & stacked muck at various RD between Km 165/0 to 177/00 & 224/00 to 236/00)	198128/-	3970/-	350/-	Two Months	6&8	Class C & D enlisted in HP PWD
3	A/R & M/o on Theog Hatkoti Road On NH 705 from km 0/00 to 69/0(Clearance of bushes and removal of earth from choked drain between km 0/0 to 10/00)	441990	8850	350	One Month	6&8	Class C & D enlisted in HP PWD
4	Consultancy services for preparation of Re—revised estimate for the construction of Theog bye pass road from Km. 174/040 to 176/400(Devrighat to Premghat on NH 22(New NH 05) in the state of Himachal Pradesh)	185360	3700	350	One Month	6&8	Class C & D enlisted in HP PWD

Terms & Conditions:- The tender documents shall be issued to those contractors/firms who fulfill the following documents with the application:

- 1 The valid enlistment/ registration of contractor in appropriate class.
- 2 Permanent Account Number(PAN)
- 3 GST Number and EPF No.
- 4 Earnest Money in the shape of National saving certificate/Time deposit account in any of the Post office in HP FDR from any Nationalized Bank duly pledged in favour of the executive Engineer.

- 5 The earnest Money & Cost of Tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & Cost tender form shall summarily be rejected.
- 6 Ambiguous/telegraphic/Conditional tender of tender by fax/ E-mail shall not be entertained/considered and will summarily be rejected.
- 7 Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.
- 8 The offer of the tender shall remain valid upto 120 days after the opening of tender.
- 9 If the date given above happens to be a holiday, the same shall be processed on next working days.
- 10 The Contractors/firm must quote their rates in words as well as in figures failing which Xen reserves the right to accept/reject any or all tenders.
- 11 The Tender form will not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed/completed the previous awarded works within the stipulated period of completion.
- 12 One Contractor should not have more than two works in hand at a time.
- 13 Works should be completed by the contractor within the stipulated period.


 Executive Engineer,
 NH Division,
 H.P.P.W.D., Theog
 Dated 7/9/2021

No/PW/NH/CB/Tender/2021

3054-3105

Copy forwarded for information and necessary actions to:

- 1 The Engineer-in Chief HP PWD Nigam Vihar shimla
- 2 The Chief Engineer, NH HP PWD Shimla 2
- 3 The Deputy Commissioner, Shimla . It is requested to display the notice on Notice Board
- 4 The Superintending Engineer, NH Circle HP PWD Shimla . It is requested to display the notice on the Notice Board please.
- 5 All the Superintending Engineer/Executive Engineers in HP PWD.
- 6 The Tehsildar Theog. It is requested to display the notice on Notice Board.
- 7 The BDO Theog . It is requested to display the notice on Notice Board.
- 8 All the Assistant Engineer working under this Division . It is requested to display the notice on Notice Board.
- 9 Correspondence Branch/Drawing Branch/Account Branch /Notice Board.

Executive Engineer,
 NH Division,
 H.P.P.W.D., Theog

SCHEDULE OF QUANTITY					
Name of Work:-Restoration of rain damages on kalka-shimla-wangtoo-Road on NH-05 KM 155/00 TO 236/00.(SH:- C/o R/Wall from km 204/380 to 204/395).				Estimated Cost:-493126.00	Time :-
				Earnest Money :-9900.00	
				Two Months.	
Sr. No	Description of Work / Item (S)	Qty.		Rate	
				In figures	In words
1	Excavation in soil by Manual Mean Excavation ordinary soil using mechanically/ manual means including loading in truck and carrying out earth to embankment site as per drawings and technical specifications clause 304, with all lifts and leads , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials by all modes of transportation as per the direction by the Engineer-in-charge.	11.85	Cum		
2	Excavation for Structures Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	31.87	Cum		
3	Providing and laying Plain cement concrete M15 Grade with crushed stone aggregate mechanically mixed vibrated placed in position & curing complete including cost of form work as per the Drawing and MoRT&H specifications No. 1500, 1700 & 2100 with in all leads and lifts including all material, labour, machinery/ equipments and any other incidentals required to complete the job as per direction of Engineer-in-Charge.	75.36	Cum		
4	Providing and laying of Filter media with granular materials/stone crushed aggregates satisfying the requirements laid down in clause 2504.2.2. of MoRTH specifications to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind abutment, wing wall and return wall to the full height compacted to a firm condition complete as per drawing and Technical Specification.	3.80	Cum		
5	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.PVC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing face.complete as per drawing and Technical Specifications.	22.50	Rmt		
Total					

Condition


- 1 Rates Should be quoted for all heights includings all leads and lifts.
- 2 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.
- 3 Cement should be procured from HP State Civil Supply Corporation only.


 Executive Engineer,
 National Highway Division ,
 H.P. P.W.D. Theog .

Schedule of Quantity				Estimated Cost:-198128		Time :-
Name of Work:- R/R damages on Kalka-Shimla-Wangtoo road NH-22(New NH-05) Km. 155/00 to 236/00 (SH:- Removal of slips/debris & stacked muck at various RD between Km 165/00 to 177/00 & 224/00 to 236/00).				Earnest Money :-3970.00		
				Two months.		
Sr. No	Description of Work / Item (S)	Qty.		Rate		Amount
				In figures	In words	
1	Removal of land slide/debris in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within all lift and lead as per technical specification 302.3.5 and 1611 as per direction of Engineer-in-Charge. .	3277.55	cum			
Condition						
1 Rates Should be quoted for all heights including all						

Condition


- 1 Rates Should be quoted for all heights includings all leads and lifts.
- 2 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.


Executive Engineer,
National Highway Division ,
H.P. P.W.D. Theog .

SCHEDULE OF QUANTITY						
Name of Work:-A/R & M/O on Theog Hatkoti Road on NH-705 from Km 0/00 To 69/00.(Sh :-Clearance of bushes and removal of earth from choked drain between km 0/00 to 10/00)					Estimated Cost:-441990.00	
					Earnest Money :-8850.00	
Sr. No	Description of Work / Item (S)	Qty.		Rate		Amount
				In figures	In words	
1	Cleaning grass and removal of rubbish up to any distance outside the periphery of the area including all leads , lift and carriage of materials as per the direction of Engineer - in -charge.	19000.00	Sqm			
2	Removal of earth from the choked hill side drain and disposing it on the valley side manually including all leads, lift and carriage of materials as per the direction of Engineer - in - charge.	8500.00	Rmt			
Total						

Condition

- 1 Rates Should be quoted for all heights includings all leads and lifts.
- 2 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.


Executive Engineer,
National Highway Division ,
H.P. P.W.D. Theog .

SCHEDULE OF QUANTITY

Name of Work:-Consultancy services for preparation of Re-revised estimate for the construction of Theog Bye pass road from Km. 174/040 to 176/400 (Devrighat to Premghat on NH-22 (New NH-05) in the State of Himachal Pradesh.

Estimated Cost:-185360.00


Earnest Money :-3700.00

Time :- One Month.

Sr. No	Description of Work / Item (S)	Qty.		Rate		Amount
				In figures	In words	
1	Preparation of detail project report and drawing complete in all manuscript from and submission of the same to higher office for approval. If any correction/amendment will be dresed by the head office the same may be corrected as desired and directed by Engineer-in-Charge and complete in all respect. After approval the same from the head office should be submitted in five fair copies and soft copy alongwith three copies of technical sanction & four copies of working estimates & three copies of DNITs as per the requirement of this office.	2.317	Km			
Total						


Condition

- 1 Rates Should be quoted for all heights includings all leads and lifts.
- 2 The contractor shall procure all the materials conforming to the specifications of MORT&H at his own risk and cost.


Executive Engineer,
National Highway Division ,
H.P. P.W.D. Theog .

Certificate

Certified that the tenders of works as called vide this office NIT No/PW/NH/CB/Tender/2021-3054-3105 Dated 07-09.2021 are of urgent nature works.


Executive Engineer,
NH Division,
H.P.P.W.D., Theng