

H. P. P.W.D. TENDER

Short terms sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEULE:

1. Date and time of receipt of application for tender form: 13.09.2021 upto 4.00 PM
2. Date and time of issue of tender form: 14.09.2021 upto 5.00 PM
3. Date and time of receipt of tenders: 15.09.2021 upto 11.00 AM
4. Date and time of opening of tenders: 15.09.2021 at 11.30 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	Restoration of rain damages due to laying of sewerage line buy (I.P.H) by Jal Shakti Department on link road to old Bazar Dehra Km. 0/0 to 01/190(SH: P/L Interlocking paver blocks 80mm at RD 0/210 to 0/365)	Rs.4,87,860	Rs.9800/-	Two months	Rs.350/-
2	Restoration of rain damages due to laying of sewerage line buy (I.P.H) by Jal Shakti Department on link road to old Bazar Dehra Km. 0/0 to 01/190(SH: P/L Interlocking paver blocks 80mm at RD 0/365 to 0/520)	Rs.4,87,860	Rs.9800/-	Two months	Rs.350/-
1.	The contractors/firms should possess the following documents(Photocopy to be attached):				
(i)	Copy of Registration/Latest renewal of enlistment.				
(ii)	PAN (Permanent Account No.)				
(iii)	Registration under GST No.				
(iv)	EPF(Employee Provident Fund Account No.)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
4	The offer of the tender shall remain valid upto 30 days after the opening.				

1.Ceritifed that the above work is of an emergent nature in exigency of public interest .

Executive Engineer
HPPWD Division Dehra
Distt Kangra H.P

on behalf of Governor of Himachal Pradesh

4827-32

Dated :- 6/9/2021

Endst.No.PWD/DEH/CB/Tender/2020-21:-

Copy forwarded to the following:-

1. The F.C. Cum Principal Secretary(PW) to the Govt. of Himachal Pradesh Shimla-2 .
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, 9th Circle HP.PWD. Nurpur.
5. Notice Board.
6. The Computer Cell office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Dehra Division HP.PWD.,
Dehra

BILL OF QUANTITY

Estimate Cost :- Rs.487860.00
 Earnest Money :- Rs. 9800.00
 Time Limit :- Two Months.

Name of work:- Restoration of damages due to laying of Sewerage line by I.P.H. Department on link road to Old Bazar Dehra Km. 0/0 to 01/190) SH:- Providing and laying Interlocking Paver Block at RD.0/210 to 0/365).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	50.38 Cubic metre			Per Cubic metre	-
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	9.50 Cubic metre			Cubic metre	-

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 40mm (forty millimeter) nominal size) in or under water in open foundations and the like for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	13.95 Cubic metre			Per Cubic metre	-
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504.as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	503.70 Square metre			Per Square metre.	
	Total					-


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

BILL OF QUANTITY

Estimate Cost :- Rs.487860.00
 Earnest Money :- Rs. 9800.00
 Time Limit :- Two Months.

Name of work:- Restoration of damages due to laying of Sewerage line by I.P.H. Department on link road to Old Bazar Dehra Km. 0/0 to 01/190) SH:- Providing and laying Interlocking Paver Block at RD.0/365 to 0/520).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	50.38 Cubic metre			Per Cubic metre	-
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	9.50 Cubic metre			Cubic metre	-

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 40mm (forty millimeter) nominal size) in or under water in open foundations and the like for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	13.95 Cubic metre			Per Cubic metre	-
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504.as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	503.70 Square metre			Per Square metre.	
	Total					-


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra