

**HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT
NOTICE INVITING TENDER**

Sealed items rates tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD so as to reach in this office 08.10.2021 upto 10:30 AM and shall be opened on the same day at 11:00 AM in the presence of intending contractors or their authorised representative who may link to be present. The tender form be had from his office against cash payment (non refundable) during working hours.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Rajgarh Division HPPWD Rajgarh must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Tender Sechedule	
1.	Last date for tender receipt of application for tender form	06.10.2021 upto 4:00 PM
2.	Last date of sale of tender forms.	07.10.2021 upto 4:00 PM
3.	Date of receipt of tender forms	08.10.2021 upto 10:30AM
4.	Date of opening of tenders	08.10.2021 at 11:00AM

Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of form
1.	Restoration of rain damages on Halonipul Dahan road Km. 0/0 to 15/0 (SH:- C/O PCC B/wall at RD 10/250 to 10/260)	2,84,623/-	6,000/-	Two Month	350/-
2.	A/R & M/O to Banethi Bagthan Rajgarh Chandol road Km 48/0 to 87/0 (SH:- Providing and laying Interlocking paver block between km 86/167 to 86/196)	1,38,292/-	3,000/-	One month	350/-
3.	A/R & M/O to Halonipul Dahan road Km. 0/0 to 15/0 (SH:- Widening/Improvement of curve between Km 12/100 to 12/170)	3,56,988/-	7,500/-	One month	350/-
4.	Restoration rain damages on Churwadhar Dahan road Km. 0/0 to 5/465 (SH:- C/O B/wall in wire create between RD 3/820 to 3/835)	1,23,058/-	2,500/-	Two Month	350/-
5.	Restoration rain damages on Banethi Bagthan Rajgarh Chandol road Km. 87/0 to 127/300 (SH:- Maintenance of earthan shoulder between Km 87/0 to 92/0)	1,97,790/-	4,000/-	One month	350/-
6.	Restoration rain damages on Banethi Bagthan Rajgarh Chandol road Km. 87/0 to 127/300 (SH:- Maintenance of earthan shoulder between Km 102/0 to 107/0)	1,97,790/-	4,000/-	One month	350/-
7.	Restoration rain damages on Halonipul Dahan road Km. 0/0 to 15/0 (C/O B/wall in wire create between RD 10/805 to 10/825)	1,65,655/-	3,400	Two Month	350/-

Certificate :-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application
3. The contractor/bidder should quoted his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
5. Conditional and telegraphic tender shall be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
7. The tender document shall be issued to only those contractors who dose not have more than two works in hand in any HPPWD Circle/ Division worth Rs. 1.00 crore each.
8. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The above Job is on present market rates and tender will be processed as per instruction issued by the Add. Chief Secretary (PW) to the Govt. of H.P notification No. PBW)B)A(3)1/2020 dt. 22.07.2020. Regarding adoption of CPWD works manual 2019 & other publication of CWP in HPPWD shall also be applicable.

11. The Executive Engineer reserve the right any or all the tenders without assigning any reason.

Executive Engineer
HPPWD Division Rajgarh
Distt Sirmour HP

on behalf of Governor of Himachal Pradesh

Tel. No. 01799-221023


Mail. ee-raj-hp@nic.in

Dated:- 30-9-2021

No.PW/RGH/Estt-Tender/2021-22- 6233-83

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD.Shimla-1.
2. The Chief Engineer (South) HP.PWD.Shimla-1.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer,
Rajgarh Division,
HP.PWD, Rajgarh.

SCHEDULE OF QUANTITY

Name of work: Restoration of rain damages on Halonipul Dahan road km 0/0 to 15/0(SH: C/O PCC R/wall at Rd 10/250 to 10/260).

Job No.

Estimated cost: Rs. 2,84,623/-

Earnest money: - Rs. 6,000/-

Time Limit: - Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	51.40	Per Cubic Metre.			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	66.70	Per Cubic Meter.			
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	19.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	10.90	Per Cubic Meter.			
					Total:	


 Executive Engineer
 Rajgarh Division
 HPPWD Rajgarh
Job No.

Job No.

SCHEDULE OF QUANTITY

Estimated cost:-Rs.1,38,292/-
Earnest money:- Rs. 3,000/-
Time Limit:- One Month.

Name of work: A/R & M/O to Banethi Bagthan Rajgarh Chandol road Km 48/0 to 87/0 (SH:- Providing and laying Interlocking paver block between km 86/167 to 86/196)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 Metres dressing of sides and bottom and backing filling in trenches with excavate suitable material. Upto 3.0 metres depth as per drawing and technical specification 305.1 in all leads and lift to the entire satisfaction of Engineer-in-charge.	1.30	Per Cubic Metre			
2	P/L interlocking cement concrete block pavement having thickness 80mm thick as Per drawing and technical specifications clause 150 including carriage of all labour equipment and materials to various locations through all leads and lifts to the entire specifications and directions of Engineer in charge.	105.08	Per Square Metre			
3	Providing and Laying RCC 1:2:4 (one cement : two sand : four aggregate) 20mm (Twenty milimetre) nominal size concrete for reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of all labour equipment and materials to various locations through all leads and lifts to the entire specifications and directions of Engineer in charge.	2.60	Per Cubic Metre			
					Total:	


Executive Engineer
Rajgarh Division
HPPWd Rajgarh


Job No.

SCHEDULE OF QUANTITY

Name of work: A/R & M/O to Halonipul Dahan road Km. 0/0 to 15/0 (SH:- Widening/Improvement of curve between Km 12/100 to 12/170) .

Estimated cost:-Rs. 3,56,988/-
Earnest money:- Rs. 7,500/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 261.78 cum (Two hundred sixty one point seventy eight cubic metre) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1826.40	Per cubic metre.			
					Total:	


Executive Engineer
Rajgarh Division
HPPWd Rajgarh

SCHEDULE OF QUANTITY

Estimated Cost: -	1,23,058
Earnest Money: -	2500.00
Time: -	One Month.

Name of Work:- Restoration rain damages on Churwadhar Dahan road Km. 0/0 to 5/465 (SH:- C/O B/wall in wire create between RD 3/820 to 3/835)

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	32.810 m3	Per Cubic Meter	5		6
2	Wire crates made of G.I. wire filled with boulders with square cut faces against the wire (Boulder filling to be measured and paid for separately). including hauling of materials in all leads & lifts as per entire satisfaction and direction of Engineer in charge.	225.000 m2	Per Square Meter			
3	Wire crates made of G.I. wire filled with boulders with square cut faces against the wire (Wire crates to be measured and paid for separately). including hauling of materials in all leads & lifts as per entire satisfaction and direction of Engineer in charge.	46.88 m2	Per Cubic Meter			


Executive Engineer
Rajgarh Division,
UP.PWD. Rajgarh

Job No.

Estimated cost:-Rs.1,97,790/-
Earnest money:- Rs. 4,000/-
Time Limit:- One Month.

SCHEDULE OF QUANTITY

Name of work : Restoration rain damages on Banethi Bagthan Rajgarh Chandol road Km. 87/0 to 127/300 (SH:- Maintenance of earthen shoulder in Km 87/0 to 92/0)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 .	5700.00	Per Square Metre			
					Total:	


Executive Engineer
Rajgarh Division
HPPWD Rajgarh

Job No.

Estimated cost:-Rs.1,97,790/-
Earnest money: - Rs. 4,000/-
Time Limit: - One Month.

SCHEDULE OF QUANTITY

Name of work : Restoration rain damages on Banethi Bagthan Rajgarh Chandol road Km. 87/0 to 127/300 (SH:- Maintenance of earthen shoulder in Km 102/0 to 107/0)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 .	5700.00	Per Square Metre			
					Total:	


Executive Engineer
Rajgarh Division
HPPWd Rajgarh

Job No.

SCHEDULE OF QUANTITY

Estimated Cost: -	165655.00
Earnest Money: -	3400.00
Time: -	one Month.

Name of Work: Restoration rain damages on Halonipul Dahan road Km. 0/0 to 15/0 (C/O B/wall in wire create between RD 10/805 to 10/825)

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	52.60 m3	Per Cubic Meter			
2	Wire crates made of G.I. wire filled with boulders with square cut faces against the wire (Boulder filling to be measured and paid for separately). including hauling of materials in all leads & lifts as per entire satisfaction and direction of Engineer in charge.	300.000 m2	Per Square Meter			
3	Wire crates made of G.I. wire filled with boulders with square cut faces against the wire (Wire crates to be measured and paid for separately). including hauling of materials in all leads & lifts as per entire satisfaction and direction of Engineer in charge.	62.50 m2	Per Cubic Meter			


 Executive Engineer
 Rajgarh Division,
 H.P.P.W.D. Rajgarh