

**HIMACHAL PRADESH •
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed items rate tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD, so as to reach in this office on 30.11.2021 up to 11.30 AM and shall be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 10.30 AM on 30.11.2021.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Nahan Division HP.PWD Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form
1	A/R & M/o Jamta mahipur Bechar ka bag road Km.0/0 to 27/565. (SH:-R/O pot holes in Km.1/0 to 8/0)	4,99,380/-	10,000/-	02 Month	350/-
2	A/R & M/o NDH road Km.0/0 to 36/0 (SH:-R/O pot holes in Km.21/0 to 36/0)	4,99,248/-	10,000/-	02 Month	350/-
3	Improvement of black spots NDH road Km.0/0 to 36/0.(SH:-P/L thermoplastic compound & fixing of cautionary, mandatory & informatory sign boards at various location in Km.9/0 to 13/0).	4,99,010/-	10,000/-	01 Month	350/-
4	Improvement of Banog kheri road Km.0/0 to 39/0.(SH:-P/F plastic road studs/cat eyes at various location in Km.0/0 to 6/0).	4,98,970/-	10,000/-	01 Month	350/-
5	A/R & M/o Banog kheri road Km.0/0 to 39/0.(SH:-C/O B/wall at RD.17/330 to 17/350).	4,09,640/-	8,200/-	02 Month	350/-
6	C/O Make Shift Hospital for COVID-19 at Judda near Nahan, District Sirmaur (HP) (SH:- P/L CC flooring) under deposit.	4,99,582/-	10,000/-	02 Month	350/-

CERTIFICATE:- It is certified that the tenders of above works are exigency/emergent nature and in public interest.

Terms & Conditions:-

1. The Contractors/Bidders must submit their Permanent Income Tax Account Number/ GST number on the tender alongwith copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any HP PWD Circle/ Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.

9. The offer shall remain valid upto 75 days.
10. The provisions of guidelines issued vide the Principal Secretary (PW) to the Govt. of HP, Shimla vide notification No.PBW(B)A(3)1/2020 dated.Shimla-2 the 22nd July, 2020 regarding adoption of CPWD works manual 2019 & other publication of CPWD in HPPWD shall also be applicable.
11. The Executive Engineer reserve the right to reject any or all the tenders without assigning any reason.

Executive Engineer,
Nahan Division,
HPPWD Nahan.

For & on behalf of Governor of Himachal Pradesh.

No. PWN/CB/Tender/2020-21-

6918-27

Dated:- 23/11/2024

Copy forwarded to the following for information & further necessary action:-

1. The Engineer-in-Chief, HP.PWD., Shimla please.
2. The Chief Engineer(SZ), HP.PWD., Shimla-2 please.
3. The Deputy Commissioner, Sirmaur Distt. at Nahan please.
4. The Superintending Engineer, 12th Circle, HP.PWD., Nahan please.
5. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD., Shimla-2 for uploading of Notice Inviting Tenders on departmental website please.
6. The S.D.M. Nahan please.
7. The Distt. Panchayat Officer, Nahan please.
8. The Executive Officer, M.C., Nahan please..
9. All the Assistant Engineers under this division to display on their respective Notice Boards.
10. The Notice Board.

Executive Engineer,
Nahan Division,
HPPWD, Nahan.

①

SCHEDULE OF QUANTITY

Name of work:-A/R & M/O Jamta Mahipur Bechar Ka Bag road Km 0/0 to 27/585(SH:- Repair of pot holes in Km 1/0 to 8/0)

Estimated cost :- Rs.4,99,380/-only

Earnest Money:- Rs.10,000 /-only

Time:- Two Months

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 (twenty) mm thick premix carpet and seal coat type B specification clause 1904.2, 503 and 508.1including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1770.00	Per Square metre			
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-3(three) as per Technical Specification Clause 405 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	9.00	Per Cubic metre			
Total :-						

Opened By Me
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Nahan Dadahu Haripurdhar road Km 0/0 to 36/0 (SH:- Repair of pot holes in Km 21/0 to 36/0)

Estimated cost :- Rs.4,99,248/-only
Earnest Money:- Rs.10,000 /-only
Time:- Two Months

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 (twenty) mm thick premix carpet and seal coat type B specification clause 1904.2, 503 and 508.1including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1752.00	Per Square metre			
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-3(three) as per Technical Specification Clause 405 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	12.00	Per Cubic metre			
Total :-						

Opened By Me
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.

Estimated cost :- Rs. 4,99,010/- only
Earnest Money :- Rs. 10,000/- only.
Time allowed :- One month.

Opened By me
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.

4

SCHEDULE OF QUANTITY

Name of work :-Improvement of Banog Kheri road Km 0/0 to 39/0(SH :-Providing and fixing plastic road studs/ cat eyes at various location in Km 0/0 to 6/0)

Estimated cost :- Rs. 4,98,970/- only
Earnest Money :- Rs. 10,000/- only.
Time allowed :- One month.

S. No.	Sub-head & item of works	Quantity	Unit	Rate		Amount
				Words	Figure	
1	Providing and fixing plastic road studs/ cat eyes of 3 m series to 290/ art No. C 1210 in yellow/ wide /red colour(two way acrylic reflector/ micro prismatic lense) as per astm 4280 type H or equivalent fixed at site with suitable epoxy as per PWD Specification to including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	1217.00	Each			
	Total :-					

Checked By Me
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Banog Kheri road km 0/0 to 39/0(SH:-C/O B/Wall at RD 17/330 to17/350)

Estimated cost :- Rs.4,09,640-only
Earnest Money:- Rs.8,200/-only
Time:- Two Months.

Sr No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	33.20	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	105.75	Per Cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	13.20	Per Cubic metre			
4	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614,709,1204,3.7. including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	16.00	Each			
Total :-						

Ordered By Me
 Drawing
 Over Writing
 Erasing
 Condition

Executive Engineer,
HP.PWD., Division
Nahan.

SCHEDULE OF QUANTITY

Name of work:-Construction of Make Shift Hospital for COVID-19 at Judda Near Nahan Distt Sirmour H.P (SH:-P/L Cement concrete flooring) under deposit

Estimated Cost:- Rs.4,99,582/-only
Earnest money:- Rs. 10000/- only
Time:- Two Months

Sr. No	Sub Head and item of work	Qty	Unit	Rate		Amount
				Figure	Words	
1	2	3	4	5	6	7
1	Providing & laying cement concrete 1:6:12 (One cement isto six sand isto twelve graded crushed stone aggregate 40mm (forty milimeter) nominal size) and curing complete excluding cost of form work in as per HPPWD. Specification 1990 volume-I (One) including carriage of all labour equipments and materials to various location through all leads,lifts and other incidental charges complete as per the entire satisfaction of the Engineer-in-Charge.	71.75	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete as per drawings and technical specifications Clause 802, 803, 1202 and 1203 grade M- 20- nominal mix 1:2:4(one cement isto two sand isto four graded stone aggregate) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	52.50	Per Cubic metre			
	Total :-					

Checked By Me
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
Nahan Division,
HP,PWD, Nahan.