



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

No.-PW/OSDN/ Tender-NIT/2021-22
To

10755-65 dt, 25-11-2021

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:-

Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

**DA/ Notice inviting tender/Schedule of Quantity
And "A" Certificate**

Ramp
Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.

Ramp
Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in



Phone No.-01904-255140
Fax No. 01904-255740

Certificate

Certified that the tenders called vide this
Office letter No.-PW/OSDN/TA/Tender-NIT/2021-22- 10755-65 dated
25.11.2021 is very urgent nature. So may be uploaded on Departmental
website in public interest please.


Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand


on behalf of Governor of Himachal Pradesh



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740



NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD, for the following works, so as to reach this office on **06.12.2021** up to 10.30 A.M. and same will be opened on the same day at 11.00 a.m. in presence of the interested contractors or their authorized representative. The tender form can be had from the office of Executive Engineer Outer Seraj Division HP.PWD, Nirmand on cash payment (Non- refundable) on or before **04.12.2021** during office hours till 1.00 p.m. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued . The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected .The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF** failing which no tender form will be issued to him.

Sr. No.	Name of work	Estimated cost (in Rupees)	Earnest Money (in Rupees)	Time	Cost of tender form Rs.
1	A/R & M/O link road to Sports Stadium Nirmand km. 0/00 to 1/450. (SH:- Maintenance of berms, constructin of road side kutcha drain and clearance of grass in km. 0/00 to 1/450)	147784.00	3000	One month	350/-
2	A/R & M/O Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 34/00. (SH:- Maintenance of berms at RD 10/00 to 15/00)	349920.00	8000	One month	350/-
3	A/R & M/O various roads under Nirmand Sub-Division. (SH:- Hiring of JCB for construction of road side kutcha drain and removal of slips)	350000.00	7000	One month	350/-
4	A/R & M/O Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 34/00. (SH:- Maintenance of berms at RD 3/00 to 7/500)	262440.00	6000	One month	350/-

5	A/R & M/O LDCK km. 0/00 to 53/500. (Sub Head:- Construction of PCC R/Wall at RD.28/195 to 28/215)	452492.00	10000	One month	350/-
6	A/R & M/O LDCK km. 0/00 to 53/500. (Sub Head:- Construction of PCC R/Wall at RD.28/300 to 28/315)	192648.00	4000	One month	350/-
7	Restoration of Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 34/00 (SH:- C/O retaining wall at RD 0/630 to 0/650) under BASP	498221.00	10000	One month	350/-
8	Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCSP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/990 to 1/135)	479128.00	10000	One month	350/-
9	Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCSP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/705 to 0/990)	489324.00	10000	One month	350/-
10	A/R & M/O various roads under Anni Sub-Division (SH:- Hiring of Excavator cum loader for removal of slips and construction of road side kutchra drain)	350000.00	7000	One month	350/-
11	A/R & M/O various roads under Brow Sub-Division. (SH:- Hiring of Excavator cum loader for removal of slips and construction of road side kutchra drain) Post rain.	225000.00	5000	One month	350/-
12	A/R & M/O various roads under Dalash Sub-Division. (SH:- Hiring of Excavator cum loader for removal of slips and construction of road side kutchra drain) Post rain.	498750.00	10000	One month	350/-
13	Construction of ADA office cum residence building at Anni. (Sh: -Providing and fixing panelling works in ADA office)	485240.00	10000	One month	350/-
14	Construction of ADA office cum residence building at Anni. (Sh: -Providing and laying wooden flooring and providing and fixing panelling and polishing works in ADA office)	496810.00	10000	One month	350/-

HIM SUCHANA AVAM JAN SAMPARK

Schedule of quantity						
Name of Work: A/R & M/O link road to Soprts Stadium Nirmand km. 0/00 to 1/450. (SH:- Maintenance of berms, C/O un-lined drain and clearance of grass km 0/00 to 1/450)				Estimated cost:- Rs. 147784.00 Earnest Money:- Rs. 3000.00 Time:- One month		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	2610.00	Square Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material and disposing of excavated earth in all leads and lifts and as per directions of The Engineer-In-Charge complete.	118.39	Cubic Metre			
3	Clearing grass and removal of rubbish up to a distance of 30 m outside the periphery of the area as per Technical Specification including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	0.25	Hectare			
Total in Figures						


 Executive Engineer
 Outer Seraj Division
 PWD, Noida

Schedule of quantity						
Name of Work: A/R & M/O Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 34/00. (SH:- Maintenance of berms at RD 10/00 to 15/00)				Estimated cost:- Rs. 349920.00 Earnest Money:- Rs. 8000.00 Time:- One month		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	9600.00	Square Metre			
Total in Figures						


 Executive Engineer
 Outer Sarsai Division
 FPOWD, Nirmand

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O various roads under Nirmand Sub-Division. (SH:- Hiring of Excavator cum loader for removal of slips and construction of road side kutchha drain) Post rain.

Estimated Cost Rs. 350000/-
Earnest Money Rs. 7000/-

Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	280.00			Per Hour	
					Total	


Executive Engineer
Outer Seraj Division
HPPWD, Nirmand

Schedule of quantity						
Name of Work: A/R & M/O Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 34/00. (SH:- Maintenance of berms at RD 3/00 to 7/500)				Estimated cost:- Rs. 262440.00 Earnest Money:- Rs. 6000.00 Time:- One month		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	7200.00	Square Metre			
Total in Figures						


 Executive Engineer,
 Outer Seraj Division,
 H.P.W.D. Mirmand

Schedule of quantity

Name of Work:- A/R & M/O Luhri Dalash Chowai Khanag road km. 0/00 to 53/500. (SH:- C/O PCC retaining wall at RD. 28/195 to 28/215).						Estimated cost:- Earnest Money		452492.00
						Time		10000
						One month		AMOUNT
Sl. No.	Description of work	Qty.	Unit	Figures	RATE			
					Words			
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	14.00	Cubic Metre					
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	28.60	Cubic Metre					
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.40	Cubic Metre					
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	92.00	Cubic Metre					
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.50	Cubic Metre					
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20	Each					
Total in Figures								


 Executive Engineer
 Outer Seraj Division
 HPFD, Jalandhar

Schedule of quantity									
Name of Work:- A/R & M/O Luhri Dalash Chowai Khanag road km. 0/00 to 53/500. (SH:- C/O PCC retaining wall at RD. 28/300 to 38/315).				Qty.		Unit	Figures	Estimated cost:-	
								Earnest Money	192648.00
								Time	4000
								One month	AMOUNT
Sl. No.	Description of work	Unit	Figures	RATE		Words			
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	Cubic Metre	5.85						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	Cubic Metre	17.85						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	Cubic Metre	4.05						
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	Cubic Metre	35.25						
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	Cubic Metre	3.12						
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	Each	10						
Total in Figures									


Schedule of quantity									
Name of Work:-Restoration of Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 34/00 (SH:- C/O retaining wall at RD 0/630 to 0/650) under BASP					Estimated cost:-		498221.00		
					Earnest Money		10000		
					Time		Three		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT		
					Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	30.8	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	37.8	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	4.9	Cubic Metre						
4	Providing and Laying cement concrete 1:4:8 (one cement : four sand : eight graded stone aggregate 40 mm (forty millimetre) nominal size) and curing complete including the cost of farmwork for plain/reinforced concrete in retaining walls, breast walls as per drawing and HP_PWD technical specifications including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	87.07	Cubic Metre						
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20	Each						
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	19.40	Cubic Metre						
		Total in Figures							

Executive Engineer
 Quater Sarsai Division
 HP PWD Jalandhar

Schedule of quantity

Name of Work: Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCSP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/990 to 1/135)					Estimated cost:- 479128.00	
					Earnest Money 10000	
					Time One month	
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	
					Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract of achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 271.67 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2037.54	Cubic Metre			
Total in Figures						

Signature of Tenderer with seal


 Executive Engineer
 Outer Sarai Division
 HPPWD, Mirmand

Schedule of quantity										
Name of Work: Construction of link road to village Shalog to Dugha via Lahut km. 0/00 to 1/700 under SCSP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/705 to 0/990)					Estimated cost:-		489324.00			
					Earnest Money		10000			
					Time		One month			
					RATE		AMOUNT			
Description of work					Qty.	Unit	Figures	Words		
Sl. No.										
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract ot achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 174.94 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.					2074.02	Cubic Metre			
Total in Figures										


 Executive Engineer
 Outer Sarai Division
 HPPWD, Mirmand

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O various roads under ~~Naam~~ ^{Annu} Sub-Division. (SH:- Hiring of Excavator cum loader for removal of slips and construction of road side kutcha drain) Post rains.

Estimated Cost Rs. 350000/-
Earnest Money Rs. 7000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	280.00			Per Hour	
					Total	

Executive Engineer
Outer Seraj Division
HPPWD, Durgam
[Signature]

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O various roads under Brow Sub-Division. (SH:- Hiring of Excavator cum loader for removal of slips and construction of road side kutchra drain) Post rain.

Estimated Cost Rs. 225000/-
Earnest Money Rs. 5000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	180.00			Per Hour	
					Total	

Executive Engineer
Outer Seraj Division
HPPWD, Demand

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O various roads under Dalash Sub-Division. (SH:- Hiring of Excavator cum loader for removal of slips and construction of road side kutcha drain) Post rain.

Estimated Cost Rs. 498750/-
Earnest Money Rs. 10000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	399.00			Per Hour	
					Total	

Executive Engineer
Outer Serai Division
HPPWD, Nmand

Schedule of Quantity						
Name of work: - Construction of ADA office cum residence building at Anni. (Sh: -Providing and fixing panelling works in ADA office)				Estimated cost:- Rs. 485240.00 Earnest Money:- Rs. 10000.00 Time:- One month.		
Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
1	Providing and fixing 12 mm thick plain framed panelling of deodar wood battens with necessary screws on unexposed surface etc. complete with 2nd class deodar wood frames including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	140.46	Square Metre			
2	Polishing two coats with french polish on new wood and wood based surface to give an even surface including cleaning the surface of all dirt,dust and sand papered smooth and including a coat of wood filler including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete	140.46	Square Metre			
Total in Figures						

Executive Engineer,
Outer Serai Division,
HP.PWD: Narnand.

Schedule of Quantity						
Name of work:- Construction of ADA office cum residence building at Anni. (Sh: -Providing and laying wooden flooring and providing and fixing panelling and polishing works in ADA office)				Estimated cost:- Rs. 496810.00 Earnest Money:- Rs. 10000.00 Time:- One month.		
Sr. No.	Description of work	Qty.	Unit	Rate In Figures		AMOUNT
				Figures	Words	
1	Providing and fixing 12 mm thick plain framed panelling of deodar wood battens with necessary screws on unexposed surface etc. complete with 2nd class deodar wood frames including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	76.72	Square Metre			
2	Polishing two coats with french polish on new wood and wood based surface to give an even surface including cleaning the surface of all dirt,dust and sand papered smooth and including a coat of wood filler including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete	76.72	Square Metre			
	Providing & fixing in position Phenol bonded Bamboowood flooring with planks of sizes 14mm thick, 1800mm length (minimum) and 130 mm wide(minimum), in approved colour, texture and finish, having Performance Appraisal Certificate (PAC) issued by Building Materials & Technology Promotion Council BMTPC). The flooring shall be fixed with tongue and groove interlocking system, with underlayment of 4mm thick expanded polyethylene foam sheets having density 40kg/cum, over prepared surface with necessary quarter round planks of size 1900mm x 18mm and door reducer of size 1900mm x 44mm, wherever required. The bamboowood planks shall have minimum density of 1000 Kg/cum & minimum Hardness 1000 Kgf. with Eco friendly UV coating, all complete including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete	44.07	Square Metre			
Total in Figures						