

**Himachal Pradesh
Public Works Department**

No. PW-SKT-CB -Tender/2021-22

20684 - 86

Dated:-

18-12-2021

To,

✓ The Executive Engineer I.T. Cell,
Nigam Bihar Shimla -2

Subject:-

Publishing of Notice inviting tenders.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website before 29.12.2021 as per notification issued by Pr. Secy. (PW) to the Govt. of HP vide letter No PBW (B) A (3)1/2020 dated 16th July 2021. As the works mentioned in the Tender Notice are urgent nature.

DA:-As above (in triplicate)


Executive Engineer,
Sarkaghat Division
HP.PWD.Sarkaghat

1. Copy along with N.I.T. to the Chief Engineer Mandi Zone HP.PWD . Mandi for information please.
2. Copy along with N.I.T. to the Superintending Engineer 1st Circle, HP.PWD. Mandi for information please


Executive Engineer,
Sarkaghat Division
HP.PWD. Sarkaghat.

**Himachal Pradesh
Public Works Department**

"Notice Inviting Tender"

Sealed item rate tender are hereby invited in form No. 6&8 by the Executive Engineer B&R Division, HP.PWD, Sarkaghat HP. on behalf of the Governor of Himachal Pradesh for the following works from the instruction and are also registered contractor of appropriate class enlisted in HP.PWD whose registration stood renewed as per revised instruction and are also registered dealers under the Himachal Pradesh General sales Tax Act. 1968. The important dates of tender are as under:-

The last date and time of receipt of application for tender form 29.12.2021 up to 4.00 P.M.

The last date for sale of tender is up to 30.12.2021 at 4.00PM.

The tender shall be received up to 11:00 AM on 31.12.2021 to be opened on the same day at 11:30 AM in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non refundable) during the working hours on 31.12.2021. The earnest money in the shape of National saving certificate, time deposit account in any post office/bank in HP. duly pledged in favor of the Executive Engineer B&R Division HP.PWD. Sarkaghat must accompany with each tender Conditional & in complete tenders and the tender received without earnest money will be summarily rejected. The offer of tender shall be kept open for 90 days. The Executive Engineer, reserves the right to accept or reject, the tender without assigning any reason.

Sr. No.	Name of work	Estimated cost.	Earnest Money.	Cost of form.	Time allowed.
1.	Construction of Matyara Dhula Ukhala Baras Road Km. 0/0 to 1/700 (SH:- Construction of R/wall in PCC 1:5:10 at RD R/wall 0/530 to 0/540) MLA Deposit	378951	7600	350	One Month
2.	Construction of Matyara Dhula Ukhala Baras Road Km. 0/0 to 1/700 (SH:- Providing and laying cement concrete pavement between RD 0/630 to 0/820) MLA Deposit	460819	9200	350	One Month
3.	R/R Damages on Rakhoh Rasain Samlet Road Km. 0/0 to 0/800 (SH:- Construction of PCC R/wall in Km. 0/715 to 0/731)	482625	10000	350	One Month
4.	R/R Damages on Plassi Ukhala Baras Smaila Road Km. 0/0 to 4/0 (SH:- Construction of R/wall in PCC 1:5:10 at RD 0/948 to 0/963)	186358	3700	350	One Month

TERMS AND CONDITONS:-

Following documents should accompany with the application for tenders.

1. The contractor/firms should be registered as or/dealer under HP Sales Tax Act. 1968/GST
2. The intending contractors/firms shall have to produce the copy of latest enlistment in HPPWD.
3. The contractor is required to submit an affidavit for not having more than two works in hand in the shape of affidavit duly attested by the competent authority.

4. If any of the date mentioned above happened to be Gazette Holiday the same shall be processed on next working day.
5. The contractor should quoted the rate of all the items in the tender both in figures and in words failing which tender is likely to be rejected.
6. The copy of Employees Provident Funds (EPF Number) GST, Pan Number, should be attached with application.
7. Minimum one similar work done of amount not less than 40% (Forty percent) of the estimated cost (without liquidated Damage or cpmensation) in last five years)
8. The earnest money for the above works should be attached with application forms.
9. Cost of tender for the above works may be deposited in cash with application.
10. All the required documents should be submitted with the application others wise single application may be rejected.
11. The Executive Engineer reserves the right to accept / reject any tender / application or all tenders without assigning any reason.


Executive Engineer,
Sarkaghat Division
HP.PWD,Sarkaghat.

Schedule of Quantity

Name of Work:- Construction of Matiyara Dhula Ukhala Baras Road km. 0/0 to 1700 (SH:- Construction of R/wall in PCC 1:5:10 at RD 0/530 to 0/540). (MLA Deposit)					
Estimated cost :-			Rs. 378951.00		
Earnest Money:-			Rs. 7600.00		
Time Limit:-			One month		
Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
1 Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas exceeding 30 cm (thirty centimetre) in depth, 1.5 m (one point five metre) in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m, (one point five metre) as directed by Engineer-in-charge. All kinds of soil.	40.15			Per cubic metre	
2 Providing and laying non pressure NP-3 class (Medium duty) R.C.C pipes including collars /spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement : two fine sand) including testing of joints etcetra. complete 450 mm (four hundred fifty millimetre) dia RCC pipes as per drawing and HP.PWDD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.	8.00			Per running metre	
3 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -All work up to plinth level 1:5:10 (one cement :five fine sand :ten) graded stone aggregate 40 mm (forty millimetre) nominal size as per drawing and HP.PWDD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.	31.54			Per cubic metre	
4 Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC (Polyvinyl Chloride) pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	16.00			Each	
5 Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	6.90			Per cubic metre	
6 Providing, laying, spreading and compacting stone aggregates of specified size to WBM (G-I) water bound macadam specification in uniform thickness hand packing and rolling with 3 (three) wheeled roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening/ binding material to fill up interstices of coarse aggregate, watering and compacting to the required density 90 mm to 45 mm (ninety millimetre) to (forty millimetre)size stone aggregate (ninety millimetre)as per direction of Engineer-in-charge.	22.50			Per cubic metre	

Schedule of Quantity						
Name of Work:- Construction of Matiyara Dhula Ukhala Baras Road km. 0/0 to 1/700 (SH:-Providing and laying Cement Concrete Pavement between RD 0/630 to 0/820). (MLA Deposit)						
				Estimated cost :-	Rs. 460819.00	
				Earnest Money:-	Rs. 9200.00	
				Time Limit:-	One month	
	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Providing, laying, spreading and compacting stone aggregates of specified size to WBM (G-I) water bound macadam specification in uniform thickness hand packing and rolling with 3 (three wheeled roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening/ binding material to fill up interstices of coarse aggregate, watering and compacting to the required density 90 mm to 45 mm (ninety millimetre) to (forty millimetre)size stone aggregate (ninety millimetre)as per direction of Engineer-in-charge.	63.50			Per cubic metre	
2	Cement concrete 1:2:4 (one Cement :two coarse sand: four graded stone aggregate 40 mm (forty millimetre) nominal size, in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete as per drawing and HP,PWDD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.	52.50			Per cubic metre	
				Total:-		

Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Plassi,Ukhla, Baras,Samaila road km 0/0 to 4/00 (SH:- Construction of R/wall in PCC 1:5:10 at RD 0/948 to 0/963)		Estimated cost:-		1,86,358.00
		Earnest Money:-		Rs. 3700.00
		Time Limit:-		One month
		In Figure	In words	Unit Amount
Description of item/Sub Head		Quantity		
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas exceeding 30 cm (thirty centimetre) in depth, 1.5 m (one point five metre) in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m, (one point five metre) asdirected by Engineer- in-charge. All kinds of soil.	9.90		Per cubic metre
2	Centering and shuttering including strutting, propping etcetra and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and siring courses filets, kerbs and steps etcetra.Including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	37.50		Per square metre
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -All work up to plinth level 1:5:10 (1 cement :5 fine sand :10) graded stone aggregate 40 mm (forty millimetre) nominal size as per drawing and HP.PWDD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.	35.50		Per cubic metre
4	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC (Polyvinyl Chloride) pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	13.00		Each
				Total:-

Executive Engineer,
B&R Divison,
HP PWD, Sarkaghat.

Draft Schedule of Quantity					
Name of Work:- R/R Damages on Rakhoth Rasain Samlet Road km. 0/0 to 0/800 (SH: -Construction of PCC R/Wall in km 0/715 to 0/731).					
Estimated cost :-				Rs. 4,82,625.00	
Earnest Money:-				10000.00	
Time Limit:-				One month	
	Description of item/Sub Head	Quantity	Rates		Amount
			In Figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas exceeding 30 cm (thirty centimetre) in depth, 1.5 m (one point five metre) in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m, (one point five metre) as directed by Engineer- in-charge. All kinds of soil.	50.40			Per cubic metre
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -All work up to plinth level 1:5:10 (1 cement :5 fine sand :10) graded stone aggregate 40 mm (forty millimetre) nominal size as per drawing and HP.PWDD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.	73.92			Per cubic metre
3	Centering and shuttering including strutting, propping etcetra and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etcetra. Including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	68.80			Per square metre
4	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC (Polyvinyl Chloride) pipe extending through the full width of the structure With slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	48.00			Each
5	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	8.64			Per cubic metre
					Total:-

Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.