

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed items rate tender on form 6&8 are invited by the Executive Engineer HPPWD Kotla Behar Division Kotla Behar for the following works from the approved and eligible contractors enlisted with HPPWD Department so as to reach in this office on dated 04.03.2022 up to 10.30AM and the same will be opened on the same day at 11.30 AM in the presence of contractors /firms or their authorized representative. The application for purchase of tender forms will be received up to 2.00 PM on dated 03.03.2022 and tender forms can be obtained from this office against cash payment (nonrefundable) on 03.03.2022 (5.00) and no tender form shall be issued by the post. The amount of earnest money in shape of FDR of any nationalized bank in HP duly pledged in the Name of Executive Engineer HPPWD Kotla Behar Division Kotla Behar

The conditional tender and tender received without earnest money (FDR) will be rejected and if holiday declared by the Govt. on the above date due to any reasons the tender shall be received and opened on the next working day. The undersigned reserved the right to rejected tender without assigned any reasons, .

Sr No	Name of work	Estimated cost	Earnest money	Time Limit	Cost of tender form	Form No
1	A/R & M/O HPPWD Rest House Building at Ghuraldhar (SH:- Repair of Parapet wall)	340283	6810	Two Month	350	6&8

1) Certified that tender of above works are being called in Exigency of public interest ,

Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

NO.PWD/KB/CB/TENDER 2020-21

8351-55

DATED

24/2/2022

Copy to the F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla -2 for favour of information please.

Copy to the Engineer-in-Chief HPPWD Shimla for information please.

Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

please.

Copy to the Superintending Engineer 9th Circle HPPWD Nurpur for favour of information

Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar.

BILL OF QUANTITY


Estimate Cost :- Rs.340283/-
Earnest Money :-Rs. 6850/-

Time Limit :- Three Month

Name of work:- A/R & M/O HPPWD Rest House Kotla Behar (SH: Repair of Roof.)


Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel of TATA/SAIL as required in grillings, frames, guard bar, ladder, railings, brackets, gates and similar works complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1645.02 Kilogram			Per Kilogram	
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade-M25 (M-Twenty Five) design mix with minimum cement contents not less than 400 kgs. (four hundred kilograms) per cubic meter with 20mm (Twenty millimeter) nominal size graded crushed stone aggregate in foundation and plinth and the like up to all heights, including cost of form work and curing complete but excluding the cost of reinforcement for Reinforced concrete work as per drawing and MORD technical specification section 800, 900 and 1400 complete and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, toll tax, GST or any other taxes imposed by the Government.	1.93 Cubic metre			Per cubic metre	
3	Repairs to plaster of any thickness in patches with cement mortar 1:4 (1 cement : 4 fine sand) including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material with in all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkhana, toll tax, GST or any other taxes imposed by the Government.	28.8 Square metre			Per Square metre	
4	Distempering (two or more coats) with oil bound washable distemper of approved brand and manufacture (Nerolac/Asian or equivalent make) and of required shade on un-decorated wall surfaces to give an even shade over and including a priming coat with distemper, primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth and carriage of materials within all leads, lifts and other incidental. The rate inclusive of Malkhana, Royalty, Octroi, toll tax, Sale Tax, GST or any taxes imposed by the Government.	55.5 Square metre			Per Square meter	

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
5	Providing and fixing pre-painted (ISI marked -Z- 120) of tata Durashine /sail/ Reliance/zindal steel sheet roofing over all steel trusses Kolar metal pre-painted single skin trapazoidal profile sheeting 0.60mm (Zero point sixty millimetre) thick having (1060 mm coverwith overall width 1126 mm) 28 mm crest depth and 353mm (Three hundred fifty three millimetre) centre to centre crest distance there will be two ribs at the centre or stiffing having depth of 25mm (Twenty five millimeter) at the lower 81mm (Eighty one millimeter) base metal of cold rolled steel coil with zinc coating top coat of 5 (Five) micron over 5 (Five) micron primer approved shade and Balancing reverse coat with polyester paint. Fixing of sheet shall be with self drilling and self tapping screws, of size 5.5mm (Five point five millimeter) diameter 75.5mm (Seventy five point five millimeter) length with EDPM seal. The material supply will be accompanied by test certificate and per directions and entire satisfaction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or any other taxes imposed by the Government.	90.59 Square metre			Per Square meter	
6	Providing and fixing pre-painted (ISI marked -Z-120) of tata Durashine /sail/Reliance/ zindal steel sheet ridges or hips 60cm (Sixty centimetre) overall 0.60mm (Zero point sixty millimetre) thick kolar metal pre-painted single skin to metal of cold rolled steel coil with zinc coating top coat with regular modified polyester coating of 20 (Twenty) micron over 5 (Five) micron primer coating to back coat of polyester of 5 (Five) micron over 5 (Five) micron primer of approved shade 5.5mm (Five point five millimeter) diameter 75.5mm (Seventy five point five millimeter) length with EDPM seal. The material supply will be accompanied by test certificate against corrosion/ Fading of colour and manufacturing defects as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or any other taxes imposed by the Government.	64.25 Runnin g meter			Per Runnin g meter	
	TOTAL					


 Executive Engineer,
 Kolar Behar Division,
 HPPWD Kolar-Belgaum

CERTIFICATE

Certified that tenders called vide this office Notice No PWD/KB/CB/Tender /2021-
22 - 8351-55 dated 24.2.2022 for 1 No.s Job is hereby invited without press notice
due to exigencies / emergency of work in the public interest


Executive Engineer
Kotla Behar Division
HPPWD Kotla Behar
