

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Short terms tenders on form 6&8 are hereby invited by the Executive Engineer Bangana Division HP.PWD Bangana on behalf of the Governor of H.P. for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below The offer of the tender will be kept open for 120 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of applications for the tender  
Form a/w requisite documents: - 14.03.2022 upto 5.00 PM.
2. Date of issue /sale of tender forms against  
Cash payment (Non-refundable):- 15.03.2022 upto 4.00 PM.
3. Date of receipt of tenders: - 16.03.2022 upto 10.30 AM.
4. Date of opening of tenders: - 16.03.2022 at 11.00 AM.

Sr.No.	Name of Work	Estimated Cost	EMD	Time Limit	Cost of Tender	Eligible class of Contractor
1	C/o Stadium in GSSS Basal Tehsil Bangana Distt. Una (SH:- C/o sitting Tires and Boundary wall).	498914	10000	Two months	350/-	Class-D
2	A/R & M/O link road Teuri Badoli road km. 0/0 to 6/500(GP Badoli) <i>SH: C/O R/WALL at RD 0/0/500</i>	414736	8300	Two months	350/-	Class-D


*0/600, 4/090 to 4/110 & 5/105 to 5/110*  
The Earnest money in the shape of National Saving certificate/Time deposit/Saving account of any post office or FDR of Nationalised Bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No., Income Tax PAN No & EPF No. must be attached with application.

SPECIAL CONDITION:-

1. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their applications.(The proof of ownership of machinery/legal tie up arrangement).
2. The tender form will not be issued to those contractors who have already two works in hand.The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.
3. The conditional/ambiguous/telegraphic tenders or tender by fax shall not entertained/considered in any case.

  
Executive Engineer  
Bangana Division  
HPPWD Bangana.




No.PW/BGN/CB/T-1/2020-21- 14450 - 86

dated 02-03-2022

Cop forwarded to the following for information anmd necessary action:-

1. The Engineer-in-Chief HPPWD. Nirman Bhawan Shimla.
2. All the Chief Engineer in HPPWD.
3. The Superintending Engineer, 15th Circle, HPPWD., Una.
4. All the Assistant Engineer, working under this Division.
5. The B.D.O. Bangana
6. Accounts Branch.
7. Drawing Branch.
8. Various Contractors working under this Division
9. Notice Board.




Executive Engineer,  
Bangana Division,  
HPPWD Bangana.



## Certificate

Certified that the tenders called vide this office letter No. PW/BGN/CB/T-1/2020-21-14450-80 dated 02.03.2022 is emergent nature and in public interest.



Executive Engineer,  
HPPWD Division  
Bangalore.



**SCHEDULE OF QUANTITY**

**Name of work:- A/R & M/O on Link road Teuri Badoli road 0/000 to 6/500 (GP Badoli) (SH:- C/O R/wall at 4/630 to 4/640, 4/090 to 4/110 & 5/105 to 5/110)**

Sr. No.	Description of work	Quantity	Unit	Estimated Cost Rs		Time Limit:	
				Figures	Words		
				RATE			AMOUNT
				Rs.	P		
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In - Charge including setting out construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	84.40	Per cubic metre				414736.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth as per drawing and technical specification clause 800, & 1200 for nominal mix 1: 5: 10 ( one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths and the cost of form work in retaining walls, breast walls etcetera as per the direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	180.58	Per cubic metre				8300.00
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre) dia PVC pipe make of (D-plast) / Finolex, ) working pressure not less than 4.5 (four point five ) kg/cm <sup>2</sup> extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	120.00	Each				

Executive Engineer  
 Bangana Division  
 P.P.W.D. Bangana




**SCHEDULE OF QUANTITY**

**Name of work:- Construction of stadium in G.S.S.S. Basal Tehsil Bangana Distt. Una (HP).  
(S.H.- C/O Sitting Tiers and Boundary Wall).**

Sr. No.	Description of work	Quantity	Unit	RATE		Estimated Cost Rs	498914.00		
				Figures	Words			Earnest Money Rs	10000.00
				Time Limit:					
				AMOUNT	Rs.	P			
1	Excavation in foundation trenches etcetra in earth work, lift upto 1.50 mtrs. (One point Five zero meter) stacking the excavated soil not more than 3 mtrs (three meter) clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeter) layers when required in to plinths sides of foundations etcetra consolidating each deposited layer by ramming as watering andthen disposing of all surplus excavated earth as directed by the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.90	Per cubic meter						
2	Providing form work with steel plates 3.15mm (three point fifteen millimeters) thick welded with angle iron in frame 30×30×5mm (Thirty into thirty into five millimeters) so as to give a fair finish including centring, shuttering, strutting and propping etcetra with wooden battens and ballies, height of propping and centring below supporting floor to ceiling upto any height and removal of the same for insitu reinforced cement concrete and plain concrete work upto all floor Level in all heights in foundation footing of cloumns and mass concrete including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, Labour Cess or other taxes imposed by the Government.	121.77	Per Square metre.						
3	Providing and laying in position cement concrete 1:5:10 (one cement : five fine sand : ten graded/ crushed stone aggregate 40 mm (forty millimeter) nominal size mechanically mixed and curing complete excluding the cost of form work in walls including attached buttresses pilasters and their caps and bases and string course etc. upto all floor level as per the direction by the Engineer in charge including carriage of materials with in all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	136.92	Per Cubic metre.						
4	Brick work using second class common burnt clay building bricks in superstructure above plinth level upto all floor level /height in cement mortar 1:4(one cement: four sand ) including curing complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax GST,labour cess or other taxes imposed by the Government.	8.51	Per cubic meter						
5	15mm (fifteen millimetre) cement plaster in Cement mortar 1:4 (one cement : four sand) single coat on the rough side of brick/concrete/stone walls for interior plastering upto all floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (eighty millimeter) in girth and finished even and smooth including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	136.57	Per Square metre.						



Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT Rs. P
				Figures	Words	
6	Providing and fixing 85cm high rail having baluster of 19 mm x 19 mm size and 12 mm x 12 mm MS solid square bars in combination with MS flat of 40mm x 5 mm size with PVC hand rail baluster dully welded/jointing with electric gas welding with top MS flat (MS flat and balusters or railings shall be measured and paid separately including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge . The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	55.50	Per Running metre			
7	Steel work welded in built up sections, trusses and framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint In beams joists channels, angles, tee , flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like complete in all respect including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	13.24	Per Quintal			
8	Supplying and fixing wovenplains G.I. wire fencing of mesh 50mm to 150mm to any type of standard rails, straining bolts. etc. including provision of binding wire, staples etc. including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	55.50	P/Sqm.			
9	Providing and laying Cement concrete flooring 1:2:4 (1 cement : 2 sand:4 graded stone aggregate 20 mm nominal size) laid in one layer finished with a floating coat of neat Cement. 40mm Thick as per direction of Engineer in charge including carriage of material within all leads lifts and other incidentals the rate inclusive of octroi,royalty,malkana and all type of taxes imposed by the Govt.	111.00	Per square meter			
<b>Total Rs.</b>						

  
 Executive Engineer  
 Bangana Divn.H.P.P.W.D.  
 BANGANA