

Himachal Pradesh
Public works Department
NO-PW-JDT-EA-I Tender NIT/2021-22:- Dated:-

170-72

16/04/2022

To,

The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject:-

Publishing of Tender notice

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Pr. Sec.(PW)to the Govt.of HP letter No-PBW(B)A9(3)1/2020dated Shimla -2the 16th july 2021 as the work mentioned in the tender notice are urgent in nature and public interest

DA:- Notice Inviting Tender

Executive Engineer
Jhandutta Division
HP PWD Jhandutta

Copy forwarded the Superintending Engineer 10th Circle
Bilaspur HP PWD Bilaspur for information please

Copy forwarded to the Computer Cell O/O Executive Engineer
(IT Cell) Nigam Bihar Shimla -2 for information and further necessary action

Executive Engineer
Jhandutta Division
HP PWD Jhandutta

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Short terms tenders on form 6 & 8 are hereby invited by the Executive Engineer Jhanduta HPPWD Jhanduta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 120 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender
Form a/w requisite documents:-
2. Date of issue/sale of Tender forms against
Cash payment (Non-refundable):-

26/04/2022 up to 3:00 PM

27/04/2022 up to 4:00 PM

The tender shall be received up to **11:00A.M. on 28/04/2022** and will be opened on the same day at 11:30 A.M in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on **28/04/2022.**

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhanduta Division, HP-PWD, Jhanduta must accompany with each application. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The XEN reserve the right to accept or reject the tenders without assigning any reason.

| S.No. | Name of work | Estimate cost | Earnest Money | Cost of form | Time limit | D class |
|-------|---|---------------|---------------|--------------|------------|---------|
| 1. | Repair of pot holes in various roads under sub- Division Jhandutta i.e Jhandutta to NarlaGhat road KM 0/00 to 3/00 & Anand Ghat to Behran Road Km 0/00 to 3/00 | 498880/- | 10000/- | 350/- | one Month | D |
| 2. | Repair of pot holes in various road under Sub- Division Berthin i.e. Bhager Berthin road KM 7/00 to 9/480 Ghumarwin -Berthin shahtalai MDR 116 KM 5/00 to 7/00 11/00 to 14/00 Balhu to Balori KM 0/00 to 4/450 | 495560/- | 10000/- | 350/- | one | D |
| 3. | Repair of ,pot holes in various roads under Sub- Division Jhandutta i.e. Gallian to Balla Raod Km 0/00 to 3/ 00 , 4/00 to 5/00 & Jhandutta to Behna Brahmana road 0/00 3/00 | 498880/- | 10000/- | 350/- | ones Month | D |
| 4. | Repair of pot holes in various roads under Sub- Division Jhandutta i.e Samoh to Hirapur Km 0/00 to 1/00 &3/00 To 5/00 Auhar to Barsand road Km 0/00 to 4/280 | 498880/- | 10000/- | 350/- | one Month | D |
| 5. | Repair to pot holes in various roads under Sub- Division Kalol i.e Bharoli kalla Jejwin salwar marotan raoad Km 18/00 to 19/00,Bharoli kalla to Bharoli Khurad KM 2/00 To 3/00 & Marotan to Dhani KM 0/00 to 0/00 to 3/00 6/00 to 7/500 | 491520/- | 10000/- | 350/- | One month | D |
| 6. | Repaair to pot holes in various roads under Sub- Division Kalol i.e Dholag to Malroun road Km 0/00 to 3/00 ,Theh to Buhar road Km 14/00 to 20/00 | 498560 | 10000/- | 350/- | one month | D |
| 7. | Repiar of pot holes in various roads under Sub- Division Berthin i.e. Jol to Peeru via Peerthan pump house KM 0/0 1/00Ghumarwin Berthin Shahtalai MDR 116 Km 29/00 To 30/00 Lathani kohdra shahtalai road MDR 112KM 11/00 to 13/00 & Badgoun Galu to Koshrian KM 2/00 to 5/00 | 498880/- | 10000/- | 350/- | One month | D |

| | | | | | | |
|----|--|----------|---------|-------|--------------|---|
| 8. | Repair of pot holes in various roads under Sub- Division Berthin i.e Mallari kallar road Km 5/00 to 5/700 Kathiun to Kuthera road KM 2/00 to 3/500 link road to village Ghandeer KM 0/00 to 2/870, Jhabola to Goacher road Km 3/00 to 6/00 | 496960/- | 10000/- | 350/- | One month | D |
| 9. | Repair of pot holes in various roads under Sub- Division Kalol i.e Koshrian to Jaddsu via Brahmni Kallan Km 2/00 to 10/00 | 498240/- | 10000/- | 350/- | One month | D |
| 10 | C/O Ambulance road from Gulani Main road to Bardu Ram house 800 meter (for completion) G.P Behnajattan (S. ROFD in Km 0/105 0/270 (Deposit work) | 60387/- | 1200/- | 350/- | Two month | D |
| 11 | Repair of Govt. Degree college Jhandutta Distt. Bilaspur (H.P) (SH:- Repair & Maintenance of existing building) Deposit work) | 279565/- | 5600/- | 350/- | Three months | D |
| 12 | A/R & M/O Residential Building under Berthin Sub-Division (SH:- Construction of Toilet and ceiling Repair etc) | 160905/- | 3200/- | 350/- | Three month | D |
| 13 | Repair to the Building of Sub- centre Daslehra Teh. Jhandutta Distt. Bilaspur (Balance work) (Deposit work) | 315683/- | 6300/- | 350/- | Three month | D |
| 14 | R/R Damages on Talai Deotsidh road KM 0/0 to 2/615 Maintenance of pot holes at RD 0/0 to 2/00 D/Lane | 458266/- | 9200/- | 350/- | Two Month | D |
| 15 | R/R Damages on Talai Deotsidh road KM 0/0 to 2/615 (SH;- Maintenance of pot holes Patch and BM etc. | 168034/- | 3400/- | 350/- | Two month | D |
| 16 | Construction of link road to Harizan Basti Mekhwin Km 0/0 to 1/0 (SH:- P/L tarring at RD 0/200 to 0/600) (Under OTMNP) | 283047/- | 5700/- | 350/- | Three month | D |

TERMS & CONDITIONS:

1. The tender forms will not be issued to those contractors whose performance is not found Satisfactory.

2. The contractors should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.

3. GST, EPF No, Earnest Money, Tender form cost, copy of Enlistment should be accompanied with application.

4. Application without all documents will not be entertained.

5. Proxy Application will not be entertained.

Executive Engineer
Jhandutta Division
HPPWD Jhandutta.

No-PW-JDT-CB-Tender NIT/2021-22:-

477-87

Dated:- 16/04/2022


Copy forwarded to the following for information and necessary action Please:-

1. The Engineer -in-Chief HP PWD Nirman Bhawan Shimla
2. All the Chief Engineer in HP PWD
3. The Superintending Engineer 10th Circle HP PWD Bilaspur
4. All the Assistant Engineer Working under this Division
5. The B.D.O Jhandutta
6. A/B & D/B in this office
7. Various Contractors working under this office
8. Notice Board

Executive Engineer
Jhandutta Division
HPPWD Jhandutta.

Certificate


Certified that the tenders called vide this office letter
No. PW-JDT EA-I-Tender /2021-22- 477-87 dated
16/04/22 is emergent nature and in Public interest


Executive Engineer
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

NAME OF WORK:-Repair of pot holes in various roads under sub Division Jhandutta i.e. JHANDUTTA TO NARLACHAT ROAD KM 0/00 to 3/00 & ANAND GHAT TO BEHRAN ROAD KM 0/000 to 3/000.

| Sr. No. | Description of items | Quantity | Estimated cost:- ₹ | | Only |
|---------|---|----------|--------------------------|------------------|--------|
| | | | Earnest Money:- ₹ | | Only |
| | | | Time allowed:-one Months | | |
| | | | Rates in | Unit | Amount |
| | | | Figures | words | |
| 1 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1559.00 | | Per square metre | |
| Total:- | | | | | |


 Executive Engineer,
 Jhandutta Division,
 HPPWD. Jhandutta.

SCHEDULE OF QUANTITY

Name of Work:- Repair of pot holes in various roads under sub Division Berthin i.e. Bhager Berthin road KM 7/00 to 9/480, Ghumarwin-Barthin-Shahatalai MDR 116 KM 5/00 to 7/00 , 11/00 to 14/00, Balhu to Balori KM 0/00 to 4/450

| Sr. No. | Description of items | Quantity | Estimated cost:- ₹ | | Only |
|---------|---|----------|--------------------|------------------|------|
| | | | Figures | Rates in words | |
| 1 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1549.00 | | Per square metre | |
| Total:- | | | | | |

Executive Engineer,
Jhandutta Division,
HPPWD. Jhandutta.

SCHEDULE OF QUANTITY


NAME OF WORK:- Repair of pot holes in various roads under sub Division Jhandutta i.e. GALLIAN TO BALA ROAD KM 0/00 to 3/00 , 4/00 to 5/00 & JHANDUTTA TO BEHNA BRAHMANA KM 0/00 to 3/00

| Sr. No. | Description of items | Quantity | Time allowed:- one Months | | | |
|---------|---|----------|---------------------------|--|-----------|------|
| | | | Estimated cost:- ₹ | | 498880.00 | Only |
| | | | Earnest Money:- ₹ | | 10000.00 | Only |
| Figures | Rates in words | Unit | Amount | | | |
| | | | | | | |
| 1 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1559.00 | Per square metre | | | |
| Total:- | | | | | | |


 Executive Engineer,
 Jhandutta Division,
 HPPWD. Jhandutta.


SCHEDULE OF QUANTITY

| SCHEDULE OF QUANTITY | | | | | | |
|--|---|----------|------------------------------|-------|------------------|--------|
| NAME OF WORK:-Repair of pot holes in various roads under sub Division Jhandutta i.e. SAMOH TO HIRA-PUR KM 0/00 to 1/00 & 3/00 to 5/00, AUHAR TO BARSAND ROAD KM 0/00 to 4/280. | | | Estimated cost:- ₹ 498880.00 | | Only | |
| | | | Earnest Money:- ₹ 10000.00 | | Only | |
| | | | Time allowed:- one Months | | | |
| Sr. No. | Description of items | Quantity | Rates in | | Unit | Amount |
| | | | Figures | words | | |
| 1 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1559.00 | | | Per square metre | |
| Total:- | | | | | | |


 Executive Engineer,
 Jhandutta Division,
 HPPWD, Jhandutta.

SCHEDULE OF QUANTITY


| Name of Work:- Repair of pot holes in various roads under sub Division kalol i.e. Bharoli Kallan Jejiwin Salwar Marotan road. KM 18/00 to 19/00, Bharoli Kallan to Bharoli Khurad. KM 2/00 to 3/00 & Marotan to Dhani KM 0/00 to 3/00, 6/00 to 7/500 | | | | | | |
|--|--|----------|------------------------------|-------|------------------|--------|
| | | | Estimated cost:- ₹ 491520.00 | | Only | |
| | | | Earnest Money:- ₹ 10000.00 | | Only | |
| Time allowed:- one Months | | | | | | |
| Sr. No. | Description of items | Quantity | Rates in | | Unit | Amount |
| | | | Figures | words | | |
| 1 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1536.00 | | | Per square metre | |
| Total:- | | | | | | |


 Executive Engineer,
 Jhandutta Division,
 HPPWD, Jhandutta.

SCHEDULE OF QUANTITY

NAME OF WORK:-Repair of pot holes in various roads under sub Division Kalol i.e. Dholag to Malroun road. KM 0/000 to 3/000, Then to Bulhad road KM 14/00 to 20/00


| NAME OF WORK:-Repair of pot holes in various roads under sub Division Katol i.e. Dholag to Malroun road. KM 0/000 to 3/000, Theh to Buhad road KM 14/00 to 20/00 | | | | | Estimated cost:- ₹ 498560.00 | Only |
|--|---|----------|----------|-------|------------------------------|--------|
| | | | | | Earnest Money:- ₹ 100000.00 | Only |
| Time allowed:- one Months | | | | | | |
| Sr. No. | Description of items | Quantity | Rates in | | Unit | Amount |
| | | | Figures | words | | |
| 1 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1558.00 | | | Per square metre | |
| Total:- | | | | | | |


 Executive Engineer,
 Jhandutta Division,
 HPPWD. Jhandutta.

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair of pot holes in various roads under sub Division Berthin i.e. Jole to Peeru via Peerthan pump house KM 0/000 to 1/000, Ghumarwin-Barthin-Shahatalai MDR 116 KM 29/00 to 30/00, Lathani-Kohdra-Shahatalai road MDR 112 KM 11/00 to 13/00 & Badgoun Galu to Koshrian KM 2/00 to 5/00.


| NAME OF WORK:- Repair of pot holes in various roads under sub Division Bertin i.e. Jole to Peeru via Peerthan pump house KM 0/000 to 1/000, Ghumarwin-Barthin-Shahatai MDR 116 KM 29/00 to 30/00, Lathani-Kohdra-Shahatai road MDR 112 KM 11/00 to 13/00 & Badgoun Galu to Koshrian KM 2/00 to 5/00. | | | | | | |
|--|---|----------|----------|-------|------------------|--------|
| Sr. No. | Description of items | Quantity | Rates in | | Unit | Amount |
| | | | Figures | words | | |
| 1 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1559.00 | | | Per square metre | |
| Total:- | | | | | | |


 Executive Engineer,
 Jhandutta Division,
 HPPWD. Jhandutta.

SCHEDULE OF QUANTITY

NAME OF WORK:-Repair of pot holes in various roads under sub Division Berthin i.e.Mallari Kallar road KM 5/00 to 5/700, Kathian to Kuthera road KM 2/00 to 3/500, Link road village Ghandeer KM 0/00 to 2/870 , Jhabola to Goacher road KM 3/00 to 6/00

| NAME OF WORK:-Repair of pot holes in various roads under sub Division Berthi i.e.Mallari | | | | | | | Estimated cost:- ₹ | 496960.00 | Only |
|---|--|----------|----------|-------|------------------|--------|---------------------------|-----------|------|
| Kallar road KM 5/00 to 5/7/00, Kathiun to Kuthera road KM 2/00 to 3/5/00, Link road village | | | | | | | Earnest Money:- ₹ | 100000.00 | Only |
| Ghandeer KM 0/00 to 2/870 , Jhabola to Goacher road KM 3/00 to 6/00 | | | | | | | Time allowed:- one Months | | |
| Sr. No. | Description of items | Quantity | Rates in | | Unit | Amount | | | |
| | | | Figures | words | | | | | |
| 1 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1553.00 | | | Per square metre | | | | |
| Total:- | | | | | | | | | |


 Executive Engineer,
 Jhandutta Division,
 HPPWD. Jhandutta.

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair of pot holes in various roads under sub Division Katol i.e. Koshrian to Jaddu via Brahmi Kallan. KM 2/000 to 10/000,

| | | | | | | | |
|--|--|----------|----------|-------|------------------|------------------------------|------|
| NAME OF WORK:- Repair of pot holes in various roads under sub Division Kalol i.e. Koshrian to Jaddu via Brahmi Kallan. KM 2/000 to 10/000, | | | | | | | |
| | | | | | | Estimated cost:- ₹ 498240.00 | Only |
| | | | | | | Earnest Money:- ₹ 10000.00 | Only |
| | | | | | | Time allowed:-one Months | |
| Sr. No. | Description of items | Quantity | Rates in | | Unit | Amount | |
| | | | Figures | words | | | |
| 1 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1557.00 | | | Per square metre | | |
| Total:- | | | | | | | |

Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta.

SCHEDULE OF QUANTITY

| SCHEDULE OF QUANTITY | | | | | | |
|--|---|--------------------------|-----------------|----------|-------|--------|
| Name of Work :- C/o Ambulance road from Gulani main road to Bardu Ram house 800 meter (for completion) GP Behnajatattan (SH:- ROFD in Km 0/105 to 0/270). (Deposit Work) | | Estimated cost:- ₹ | | 60387.00 | | Only |
| | | Earnest Money:- ₹ | | 1200.00 | | Only |
| | | Time allowed:- Two Month | | | | |
| Sr. No. | Description of iteams | Quantity | Unit | Rate | | Amount |
| | | | | Figures | words | |
| 1 | Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 302,1603.1,1603.2, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber ,embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 22.43 Cubic metre @ Rs. 300/- per cubic metre shall be done on pro-rata basis from each running bill for this item. | 373.89 | Per Cubic Meter | | | |
| Total:- | | | | | | |


 Executive Engineer,
 Jhandaatta Division
 HPD, Jhandaatta

Schedule of Quantity

Name of work:- Repair of Govt. Degree College Jhandutta District Bilaspur HP. (SH:- Repair & Maintenance of existing building). Deposit work.

| Name of work:- Repair of Govt. Degree College Jhandutta District Bilaspur HP. (SH:- Repair & Maintenance of existing building). Deposit work. | | | | Estimated Cost:- 279565.00 | | /-Only | |
|---|---|------|-----------|------------------------------|------|--------|--|
| | | | | Earnest Money:- 5600.00 | | /-Only | |
| | | | | Time allowed :- Three months | | | |
| Sr. No. | Description of item | Qty. | In Figure | Rate In Words | Unit | Amount | |
| 1 | Providing and fixing 100 mm (one hundred millimeter) sand cast Iron grating for gully trap. including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 24 | | | Each | | |
| 2 | Providing and fixing Bolts and nuts (G.I.)16 mm (sixteen millimeter) dia 60 mm (sixty millimeter) long. including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 24 | | | Each | | |
| 3 | Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430 x 260 x 350 mm (four hundred thirty into two hundred sixty into three hundred fifty millimeter) or 340 x 410 x 265 mm (three hundred forty into four hundred ten into two hundred sixty five millimeter) sizes respectively. including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 6 | | | Each | | |


| Sr. No. | Description of item | Qty. | Rate | | Unit | Amount |
|---------|---|------|-----------|----------|------|--------|
| | | | In Figure | In Words | | |
| 4 | Providing and fixing uplasticised PVC connection pipe with brass unions 45 cm (forty centimetre) length 15 mm (fifteen millimeter) nominal bore including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 4 | | | Each | |
| 5 | Providing and fixing PTMT extension nipple for water tank pipe, fittings of approved quality and colour 15 mm (fifteen millimeter) nominal bore, weighing not less than 32 (thirty two) gms including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 20 | | | Each | |
| 6 | Providing and fixing 600x120x5 mm (six hundred into one hundred twenty into five millimeter) glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm (forty millimeter) long screws, rawl plugs etc., complete. including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2 | | | Each | |
| 7.1 | Providing and fixing G.I.FITTINGS: G.I. ELBOWS 15 mm (fifteen millimeter) dia including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 80 | | | Each | |

| Sr. No. | Description of item | Qty. | Rate | | | |
|---------|---|------|-----------|----------|------|--|
| | | | In Figure | In Words | | |
| 7.2 | Providing and fixing G.I. FITTINGS: G.I. ELBOWS 25 mm dia (twenty five millimeter) dia including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 8 | | | Each | |
| 8.1 | Providing and fixing G.I. TEES EQUAL 15mm (fifteen millimeter) dia including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 60 | | | Each | |
| 8.2 | Providing and fixing G.I. TEES EQUAL 25mm (twenty five millimeter) dia including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 8 | | | Each | |
| 9.1 | Providing and fixing G.I. / M.I. unions. 15 mm (fifteen millimeter) dia including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 10 | | | Each | |
| 9.2 | Providing and fixing G.I. / M.I. unions. 25mm (twenty five millimeter) dia including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 7 | | | Each | |

| Sr. No. | Description of item | Qty. | Rate | | Unit | Amount |
|---------|--|-------|-----------|----------|------|--------|
| | | | In Figure | In Words | | |
| 10.1 | Providing and fixing G.I.NIPPLES 15 mm (fifteen millimeter) dia including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 20 | | | Each | |
| 10.2 | Providing and fixing G.I.NIPPLES 25mm (twenty five millimeter) dia including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 27 | | | Each | |
| 11 | Providing and fixing G.I.SOCKETS 15 mm (fifteen millimeter) dia including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 10 | | | Each | |
| 12 | Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° (fifteen degree) landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (one cement into one point five coarse sand) into three graded stone aggregate 20 mm (twenty millimeter) nominal size). including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 12.77 | | | cum | |

| Sr. No. | Description of item | Qty. | In Figure | In words | sqm |
|---------|--|--------|-----------|----------|-----|
| 13 | Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 323.1 | | | |
| 14 | Repairs to plaster of thickness 12 mm (twelve millimeter) to 20 mm (twenty millimeter) in patches of area 2.5(two point five) sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in Charge With cement mortar 1: 4(one cement : four fine sand) including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 145.39 | | | sqm |
| 15 | Providing and laying Ceramic glazed floor tiles of size 300x300 mm (three hundred into three hundred millimeter) (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm (twenty millimeter) thick cement mortar 1:4 (one Cement : four Coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm (three point three kilogram per square meter) including pointing the joints with white cement and matching pigment etc., complete. including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana, Toll tax, Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 78 | | | sqm |

| Sr. No. | Description of item | Qty. | Rate | | Unit | Amount |
|---------|--|------|-----------|----------|------|--------|
| | | | In Figure | In Words | | |
| 16 | Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. The rate includes, octroi, Malkana, Toll tax, leads and lifts and other incidental. The rate includes, welfare cess royally Goods & Service Tax, building and other construction worker, cess payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 3.5 | | | qtls | |
| | | | | Total:- | | |


 Executive Engineer,
 Jhandutta Division,
 HPPWD, Jhandutta.

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/o Residential Building under Berthin Sub Division (SH:- Construction of Toilet and ceiling Repair etc.).

| NAME OF WORK:- A/R & M/o Residential Building under Bertin Sub Division (SH:- Construction of Toilet and ceiling Repair etc.). | | | | | | | SCHEDULE OF QUANTITIES | |
|---|--|----------------------|----------|------------------------------|------------------|--------|------------------------|--|
| Sr. No. | | Description of items | Quantity | Estimated cost:- ₹ 160905.00 | | | Only | |
| | | | | Earnest Money:- ₹ 3200.00 | | | Only | |
| | | | | Time allowed:- Three Months | | | | |
| | | | Figures | Rates in words | Unit | Amount | | |
| 1 | Excavation in foundation trenches etc. earth work in all classification of soil such as pick work, jumper work, blasting work, pick jumper work, pick jumper blasting work, blasting work in soft and hard rock, saturated soil, any other mixed variety of soil in dry or saturated conditions up to any depth and lifts up to any height, de-watering, including chiseling/ wedging out rocks where blasting is prohibited, de-watering including pumping or bailing out water where required and removal of slush which may arise during the execution including stacking the serviceable and unserviceable material separately as directed. Then returning the stacked soil in 15 cm (Fifteen centimeter) layer when required in to plinths and side of foundation etcetra consolidating each deposited layer by ramming and watering and then disposing of all surplus unserviceable/excavated earth with in all leads and lifts and carriage of material tools, machinery as per direction of Engineer-In-Charge As per HP.PWD specification 1990 vol-I clause 7.1 with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 4.56 | | | Per cubic metre | | | |
| 2 | Dismantling doors, windows and clerestory window ventilators etcetra (wood or steel) shutters upto 3.00 (three point zero zero) square metre in area including chowkhats architraves, hold fast and other attachments etc complete and stacking them including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2.00 | | | Each | | | |
| 3 | Providing and fixing 40mm (forty millimeter) thick second class deodar wood wire gauge shutters using galvanized MS wire gauge of IS gauge designation 85g (Eighty five) gauge with wire of diameter 0.56mm (zero point five six millimeter) for doors, windows and clerestory windows including bright finished black enamelled iron hinges with necessary screws including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.80 | | | Per square metre | | | |

| | | | | | | |
|---|--|-------|--|--|------------------|--|
| 4 | Providing and fixing 9mm thick water proof kit ply of standard quality ISI mark and approved shade and colour in paneling & wall lining i.e mitring at junctions, butt jointing and nails complete (Frame work for base to be measured & paid for separately) including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 17.92 | | | Per square metre | |
| 5 | Second class brick work using common burnt clay building bricks of approved kiln in super structure upto all height and depth in cement mortar 1:5 (one cement : five sand) including curing complete including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 5.61 | | | Per cubic metre | |
| 6 | Stone soling properly hand packed filling intersices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moonum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.50 | | | Per cubic metre | |
| 7 | Providing and laying cement concrete 1:2:4(1 cement:2 sand :4 graded stone aggregate 40mm nominal size)and curing complete excluding cost of form work in Foundation and plinth. including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.50 | | | Per cubic metre | |
| 8 | 15mm (Fifteen millimeter) cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering upto floor all level including arrises, internal rounded angles, chamfers and or rounded angles not exceeding 80mm (eighty millimeter) in girth and finished even and smooth in cement mortar 1:3 (one cement : three sand) including curing complete including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 59.96 | | | Per square metre | |

| | | | | | | | |
|----|---|--------|--|--|--|------------------|--|
| 9 | Providing and fixing 10mm (ten millimetre) thick antiskid water proof stain and impact resistant heavy duty vitrified tiles nico or equivalent 600x600x10mm (six hundred into six hundred into ten millimetre) manufactured of approved shade and colour in flooring reads of steps and landings laid over 12mm (twelve millimetre) thick cement mortar 1:3 (one cement : three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 16.74 | | | | Per square metre | |
| 10 | White glazed tiles 6mm (six millimetre) thick in skirting riser of steps and dado 12mm (twelve millimetre) thick cement mortar 1:3 (one cement : three sand) and jointed with cement slurry complete upto all floor level in all respect including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 18.90 | | | | Per square metre | |
| 11 | Providing and fixing anodised aluminium work for door, window, ventilator and glazed partition frames with extruded built up standard tubular and other sections of approved make conforming to IS:733 and IS:1285 anodised transparent or dyed to require shade accordingly to IS:1868 (minimum anodic coating of grade AC15) fixed with raw plugs and screws or with fixing clips, necessary filling up of gaps and junctions at top, bottom and sides with required with PVC/neoprene felt etcetra. Aluminium section shall be smooth rust free, straight, mitred and jointed mechanically wherever required including cleasts angle, aluminium, snap beeding for glazing/panelling C.P. brass/stainless steel screws for door, window, ventilator and glazed partition frames complete including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 123.06 | | | | Per kilogram | |
| 12 | Providing and fixing 3 mm thick board (ACP signica) ceiling of approved quality ISI mark i/c fixing for partition door and windows frams with screws and clamps etc. including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 5.27 | | | | Per square metre | |

| | | | | | | |
|----|---|------|--|--|------------------|--|
| 13 | Providing and fixing glazing with glass pans of 4mm (four millimetre) thickness (weight not less than 10.00 kg/sqm (ten point zero zero kilogramme per square metre)) in aluminium door, window, ventilator shutters and partition etcetra with PVC/neoprens gaskets etcetra (Cost of aluminium snap beading shall be paid in basic item) complete including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 3.60 | | | Per square metre | |
| 14 | Providing and fixing aluminium anodized powder coated pattern to existing window/ventilator with 80mm x 80mm (eighty millimetre into eighty millimetre) panles holes with 25x8mm (twenty five into eighty millimetre) thick aluminium flat in windows and ventilators including fixing with aluminium screws or bolts and nuts complete in aluminium channels base frames (aluminium channels base frames to be measured and paid for separately) complete including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 3.00 | | | Per square metre | |
| 15 | Providing and fixing anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | | | | |
| i | 250X16 mm (Two hundred fifty into sixteen millimetre). | 2.00 | | | Each | |
| 16 | Providing and fixing heavy duty aluminium tower bolts (Barrel type) anodized transparent or dyed to required shade and colour with screws etcetra as approved by the Engineer-In-Charge complete in all respect including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | | | | |
| i | 150x10mm (One hundred fifty into ten millimeter) | 4.00 | | | Each | |

| | | | | | | | |
|----|--|-------|--|--|--|------------------|--|
| ii | 100X10mm (One hundred into ten millimeter) | 16.00 | | | | Each | |
| 17 | Providing and fixing mat finish aluminum heavy duty handles anodized transparent or dyed to required shade and colour with necessary screws etcetra as approved by the Engineer-in-Charge including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | | | | | |
| i | 125mm (One hundred twenty five millimetre) | 18.00 | | | | Each | |
| 18 | Applying priming coat over new wood and wood based surface after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter, sand papering and knotting with ready mixed paint brushing with white lead for priming complete including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 21.52 | | | | Per square metre | |
| 19 | Painting two coats(excluding priming coat) on new wood and wood based surface with surfaces,with readymixed paint , brushing to give an even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping of dirt,dust and other foreign matter, ICI (Dulux Gloss), Nerolic, Berger (Luxol High Gloss), Asian Paints (Premium Apolite Gloss), Shalimar including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 21.52 | | | | Per square metre | |
| 20 | Disitemper (Two coats) with oil bound washable disitemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with disitemper primer of approved brand and manufacture after throughly brushing the surface free from mortar droopings and other foreign matter and also including preparing the surface even and sand paped smooth on walls including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 52.73 | | | | Per square metre | |

| | | | | | | |
|----|---|------|--|--|------|--|
| 21 | Providing and fixing Orissa pattern vitaceous China wash down water closet squatting pan (Indian type W.C. pan) size 580mm (five hundred eighty millimetre) (earth work, bed concrete, foot rest and trap to be measured and paid for separately) including carriage of materials within all leads and lifts complete in all respect. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | | | Each | |
| 22 | Providing and fixing PVC 110 mm size (One hundred ten millimetre) size "P" or "S" trap for water closet (squatting pan) ISI marked including jointing the trap with the pan and and PVC pipe with approved adhesive etcetra complete including carriage of materials with in all leads, lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | | | Each | |
| 23 | Providing and fixing 10 to 12.50 ltrs (ten to twelve point five liters) vertious china low level flushing cistern with a pair mild steel bracket compete with fitting such as lead valve less syphon, 15mm (fifteen millimeter) nominal size brass ball valve with polythine float, C.P. brass handles unions and coupling for connections with inlet outlet and over flow pipes 40mm (forty millimeter) diameter C.P. flush bend including cutting holes in walls and making good the same and connecting the flush bend with cistern and closet (over flow pipe to be measured and paid for separately) including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | | | Each | |
| 24 | Providing and fixing plastic seat (solid/hollow type) and cover for wash down water closet with CP brass hinges and rubber buffers solid type with white plastic seat and cover including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | | | Each | |

| | | | | | | | |
|----|--|-------|--|--|--|----------------------|--|
| 25 | Providing and fixing PTMT jet spray of approved quality and colour with 1.50 (one point five zero) metre tube complete in all respect including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | | | | Each | |
| 26 | Providing and fixing 15mm (fifteen millimetre) diameter C.P brass bib tap superior or heavy type including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 4.00 | | | | Each | |
| 27 | Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | | | | | | |
| i | 110 mm (one hundred millimetre) diamoninal size | 14.00 | | | | Per Running Meter | |
| 28 | Providing and fixing 110 mm (one hundred millimetre) diamoninal size PVC plain double "Y" junction ISI marked including fixing with approved adhesive etc. complete. including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2.00 | | | | Each | |
| 29 | Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc. complete. including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 4.00 | | | | Each | |
| i | 110 mm (one hundred ten millimetre) nominal size | | | | | | |
| 30 | Providing and fixing to wall, ceiling and floor galvanized mild steel tubes (medium grade) tube fitting and clamps including making good the walls, ceiling and floor complete in all respect including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 25.00 | | | | Per running metre | |
| i | 15mm (fifteen millimeter nominal size) | | | | | | |

| | | | | | | | |
|----|---|------|--|--|--|------|--|
| 31 | Providing and fixing flat back 630x450mm (six hundred thirty into four hundred fifty millimeter) vitreous china wash basin with single hole for pillar tap with CI or MS brackets painted white including cutting of holes and making good the same but excluding fittings complete in all respect including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | | | | Each | |
| 32 | Providing and fixing 32mm (thirty two millimeter) diameter CP brass waste heavy duty for wash basin or sink complete in all respect including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | | | | Each | |
| 33 | Providing and fixing 110mm x 90 mm (one hundred into ninety millimeter) diameter PVC floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etcetra complete in all respect including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 3.00 | | | | Each | |
| 34 | Providing and fixing 15 mm (fifteen millimeter) dia brass stop cock complete in all respect including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 2.00 | | | | Each | |

| | | | | | | | |
|----|---|------|--|--|--|------|--|
| 35 | Providing and fixing 15mm (fifteen millimetre) diameter C.P. brass pillars tap heavy duty capstan head including carriage of materials within all leads and lifts complete in all respect, including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | | | | Each | |
| 36 | Providing and fixing 600 x 450mm (six hundred into four hundred fifty millimetre) bavelled edge mirror of superior glass mounted on 6mm (six millimetre) thick AC sheet or ply wood sheet and fixed to wooden plugs with CP brass screws and washers complete in all respect including carriage of materials within all leads and lifts. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | | | | Each | |
| 37 | Providing and fixing 600 x 20 mm (six hundred into twenty millimetre) CP brass towel rail complete with CP Brass brackets fixed to wooden plugs with CP brass including carriage of materials within all leads and lifts complete in all respect. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | | | | Each | |
| 38 | Providing and fixing CP brass toilet paper holder complete in all respect including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | | | | Each | |
| 39 | Providing and fixing chromium plated brass soap dish with CP brass brackets fixed to wooden cleats with CP brass screws complete in all respect including carriage of materials within all leads and lifts including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. | 1.00 | | | | | |

Executive Engineer,
Jhanda Division,
H.P.W.D., Jhanda.

1

SCHEDULE OF QUANTITY

Name of Work :- Repair to the Building of Sub Centre Daslehra teh. Jhandutta
Distt. Bilaspur H.P. (Balance work.) *Report Work*

| Name of Work :- Repair to the Building of Sub Centre Daslehra teh. Jhandutta Dist. Bilsapur H.P. (Balance work.) | | Department Works | | Estimated cost:- ₹ 315683.00 | | Only | |
|---|---|----------------------------|---------|------------------------------|-----------------|--------|--|
| | | Earnest Money:- ₹ 6300.00 | | Only | | | |
| | | Time allowed:- Three Month | | | | | |
| Sr. No. | Description of items | Quantity | Rate | | Unit | Amount | |
| | | | Figures | words | | | |
| 1 | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 (fifty) metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 (one into three into six) or richer mix (i/e equivalent design mix) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 2.30 | | | Per Cubic Meter | | |
| 2 | Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m (one point five meter) in width or 10 sqm (ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five meter), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty meter) , Ordinary rock including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 48.65 | | | Per Cubic Meter | | |
| 3 | Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundation and plinth in Cement mortar 1:4 (one cement : four coarse sand) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 0.83 | | | Per Cubic Meter | | |
| 4 | Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level in Mild steel and Medium Tensile steel bars including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 228.50 | | | Per Kilo gram | | |

| | | | | | | |
|---|---|-------|--|--|------------------|--|
| 5 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (one cement : two coarse sand) : four graded stone aggregate 20 mm(twenty millimeter) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 20.98 | | | Per Cubic Meter | |
| 6 | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand): six graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 10.78 | | | Per Cubic Meter | |
| 7 | Providing and laying Ceramic glazed floor tiles of size 300x300 mm (three hundred into three hundred millimeter) (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm (twenty millimeter) thick cement mortar 1:4 (one Cement : four Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm (three point three Kilogram per square meter) including pointing the joints with white cement and matching pigment etc, complete, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 46.83 | | | Per square metre | |
| 8 | Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % (zero point zero eight percentage) and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm (twelve millimeter) thick bed of cement mortar 1:3 (one cement: three coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three point three kilogram per square meter) including grouting the joint with white cement & matching pigments etc. complete Size of Tile 500x500 mm (five hundred into five hundred millimeter) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 6.75 | | | Per square metre | |

| | | | | | | | |
|----|---|------|--|--|--|------|--|
| 9 | Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 (ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1.00 | | | | Each | |
| 10 | Providing and fixing wash basin with C.I. brackets, 15 mm (fifteen millimeter) C.P. brass pillar taps, 32 mm (thirty two millimeter) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm (six hundred thirty into four hundred fifty millimeter) with a pair of 15 mm (fifteen millimeter) C.P. brass pillar taps including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1.00 | | | | Each | |
| 11 | Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1.00 | | | | Each | |
| 12 | Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 32 mm (thirty two millimeter) dia including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1.00 | | | | Each | |
| 13 | Providing and fixing 100 mm (one hundred millimeter) sand cast iron grating for gully trap including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1.00 | | | | Each | |
| 14 | Providing and fixing brass bib cock of approved quality 15 mm (fifteen millimeter) nominal bore including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 2.00 | | | | Each | |

| | | | | | | |
|----|---|-------|--|--|-------------------|--|
| 15 | Providing and fixing brass stop cock of approved quality 15 mm (fifteen millimeter) nominal bore including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 7.00 | | | Each | |
| 16 | Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms (eight hundred ten grams) in 15 mm (fifteen millimeter) nominal bore including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 8.00 | | | Each | |
| 17 | Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, i/e making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall 15 mm (fifteen millimeter) dia nominal bore including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 12.00 | | | per running meter | |
| 18 | Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 15 mm (fifteen millimeter) nominal bore including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 2.00 | | | Each | |
| 19 | Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm (six millimeter) thick hard board backing Circular shape 450 mm (four hundred fifty millimeter) dia including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1.00 | | | Each | |
| 20 | Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS 8931 15mm (fifteen millimeter) nominal bore including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1.00 | | | Each | |

| | | | | | | |
|---------|--|--------|--|--|-----------------|--|
| 21 | Providing and fixing PTMT bib cock of approved quality and colour 15mm (fifteen millimeter) nominal bore, 86 mm (eighty six millimeter) long, weighing not less than 88 gms (eighty eight grams) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1.00 | | | Each | |
| 22 | Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3(three) wheeled road/vibratory roller 8-10 (eight-ten) tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 20.00 | | | Per Cubic Meter | |
| 23 | Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 245.00 | | | Per Kilo gram | |
| Total:- | | | | | | |

Executive Engineer,
Jhantutta Division
HPPWD, Jhantutta

SCHEDULE OF QUANTITY

Name of Work :- R/R damadge on Talai Deotsidh road Km 0/0 to 2/615 (SH:- Maintenance of pot holes at RD 0/0 to 2/00).

| Name of Work :- R/R damage on Talai Deotsidh road Km 0/0 to 2/615 (SH:- Maintenance of pot holes at RD 0/0 to 2/00). | | | | | | |
|--|--|----------|------------------------------|------------|------------------|--------|
| Sr. No. | Description of iteams | Quantity | Estimated cost:- ₹ 458266.00 | | Only | |
| | | | Earnest Money:- ₹ 9200.00 | | Only | |
| | | | Time allowed:- Two Month | | | |
| | | | Figures | Rate words | Unit | Amount |
| 1 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (Twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1.. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 2684.63 | | | Per square metre | |
| Total:- | | | | | | |

Executive Engineer,
Jhandutta Division
HPMD, Jhandutta

SCHEDULE OF QUANTITY

| SCHEDULE OF QUANTITY | | | | | | |
|---|---|--------------------------|---------|------------|------------------|--------|
| Name of Work :- R/R damage on Talai Deotidh road Km 0/0 to 2/615 (SH:- Maintenance of pot holes, Patches and BM etc). | | Estimated cost:- ₹ | | 168034.00 | Only | |
| | | Earnest Money:- ₹ | | 3400.00 | Only | |
| | | Time allowed:- Two Month | | | | |
| Sr. No. | Description of iteams | Quantity | Figures | Rate words | Unit | Amount |
| 1 | Repair to pot holes by removal of failed material, trimming the sides to vertical and levelling the bottom, cleaning the same with compressed air or any appropriate method filled with 75mm B.M, applying bitumen emulsion prime coat at the bottom and bitumen emulsion tack coat on sides and on bottom as per technical specifications Clauses 502, 503 and 504, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 10.99 | | | Per Cubic metre | |
| 2 | Patch repair on already filled pot holes with 75 mm BM with 20 mm premix carpet and seal coat Type B as per drawings and technical specification Clause 1904.2, 508 and 510 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 146.23 | | | Per square metre | |
| 3 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 382.38 | | | Per square metre | |
| Total:- | | | | | | |

Executive Engineer,
Jhanda Division
H.D. Jhanda

SCHEDULE OF QUANTITY

| Name of Work:- Construction of link road to Harizan Basti Mekhwin Km 0/0 to 1/0 (SH:- P/L starting at RD 0/200 to 0/600). Under OTMNP. | | Estimated cost:- ₹ 283047.00 | | Only |
|---|--|------------------------------|---------------|------------------|
| | | Earnest Money:- ₹ 5700.00 | | Only |
| | | Time allowed:- Three Month | | |
| Sr. No. | Description of items | Quantity | Rate | Amount |
| | | | Figures words | |
| 1 | Providing and applying primer coat with Bitumen emulsion (SS-1) (one) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.00 kg/sqm (zero point seventy to one point zero zero Kilogram per square meter) using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts complete in all respect. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1344.00 | | Per square meter |
| 2 | Providing and applying tack coat with Bitumen emulsion (RS-1) (one) using emulsion distributor at the rate of 0.25 to 0.30 kg per sqm (zero point twenty five to zero point three zero Kilogram per square meter) on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. including carriage of materials within all leads and lifts complete in all respect. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1344.00 | | Per square meter |
| 3 | Providing and laying 20 mm (Twenty millimeter) thick Open-Graded Premix Carpet using Bituminous (penetration grade/modifed bitumen) Binder Providing, laying and rolling of open-graded premix carpet of 20 mm (Twenty millimeter) thickness composed of 13.2 mm to 5.6 mm (thirteen point two to five point six millimeter) aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN (eighty - one hundred Kilonewtons) static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508. By Mechanical Means Bitumen (S-90) (ninety) including carriage of materials within all leads and lifts complete in all respect. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1344.00 | | Per square meter |
| 4 | Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510 using Type B Bitumen (S-90) (ninety) including carriage of materials within all leads and lifts complete in all respect. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. | 1344.00 | | Per square meter |
| Total:- | | | | |


 Executive Engineer,
 Jhanda Division
 HPPWD, Jhanda