

7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any HP PWD Circle/ Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The provisions of guidelines issued vide the Principal Secretary (PW) to the Govt. of HP, Shimla vide notification No.PBW(B)A(3)1/2020 dated.Shimla-2 the 22nd July, 2020 regarding adoption of CPWD works manual 2019 & other publication of CPWD in HPPWD shall also be applicable.
11. The Executive Engineer reserve the right to reject any or all the tenders without assigning any reason.

Executive Engineer,
Nahan Division,
HPPWD Nahan.

For & on behalf of Governor of Himachal Pradesh.

No. PWN/CB/Tender/2020-21-

Dated:-

Copy forwarded to the following for information & further necessary action:-

1. The Engineer-in-Chief, HP.PWD., Shimla please.
2. The Chief Engineer(SZ), HP.PWD., Shimla-2 please.
3. The Deputy Commissioner, Sirmaur Distt. at Nahan please.
4. The Superintending Engineer, 12th Circle, HP.PWD., Nahan please.
5. The Executive Engineer (IT Cell),Nigam Vihar, HPPWD., Shimla-2 for uploading of Notice Inviting Tenders on departmental website please.
6. The S.D.M. Nahan please.
7. The Distt. Panchayat Officer, Nahan please.
8. The Executive Officer, M.C., Nahan please..
9. All the Assistant Engineers under this division to display on their respective Notice Boards.
10. The Notice Board.

Executive Engineer,
Nahan Division,
HPPWD Nahan.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed items rate tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD, so as to reach in this office on 2.5.2022 up to 11.30 AM and shall be opened on the same day at 12.00 Noon in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 10.30 AM on 2.5.2022.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Nahan Division HP.PWD Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form
1	C/O L/R from Bohlion to Sambhalkha Km.0/0 to 6/660.(SH:-C/O R/wall at RD.1/870 to 1/882, 3/930 to 3/937 & 5/930 to 5/938)	4,95,103/-	10,000/-	02 Month	350/-
2	C/O L/R from Bohlion to Sambhalkha Km.0/0 to 6/660.(SH:-C/O R/wall at RD.4/905 to 4/912 & 4/915 to 4/930)	4,96,196/-	10,000/-	02 Month	350/-
3	C/O Salani Tedi Baroti road Km.0/0 to 5/555. (SH:-C/o balance work of 6.00 mtrs. Span RCC slab culvert at RD.2/710)	4,99,811/-	9,800/-	02 Month	350/-
4	C/O Salani Tedi Baroti road Km.0/0 to 5/555. (SH:-C/o C/O V-shape drain in Km.3/0 to 5/555)	4,95,796/-	10,000/-	02 Month	350/-
5	C/o L/R from Rukhri to Gadda Bhudi Km.0/0 to 3/400.(SH:-P/L Wet Mix Macadam(WMM) at RD.0/045 to 0/232)	4,40,943/-	9,000/-	02 Month	350/-
6	C/o L/R from Rukhri to Gadda Bhudi Km.0/0 to 3/400.(SH:-C/o protection work D/stream at RD.0/150)	4,89,712/-	10,000/-	02 Month	350/-
7	C/o L/R Bhandariyon ki Nero. (SH:-C/O both side wing walls of foot bridge)	4,99,418/-	10,000/-	02 Month	350/-
8	A/R & M/O on Banog Kheri road Km.0/0 to 39/0.(SH: C/O R/wall at RD.26/938 to 26/959)	4,98,617/-	10,000/-	02 Month	350/-
9	C/O bal. work of missing CD work on Banog Kheri road Km.0/0 to 26/935.(SH: C/O left side abutment and wing wall)	4,99,369/-	10,000/-	02 Month	350/-
10	C/O L/R Salani to banka Bara road 0/0 to 4/0. (SH: C/O 900mm dia RCC hume pipe culvert at RD.1/285 & 1/450)	4,99,880/-	10,000/-	02 Month	350/-
11	C/O L/R Salani to banka Bara road 0/0 to 4/0. (SH: C/O B/wall at RD.0/900 to 0/910 & R/wall at Rd.1/500 to 1/515).	4,98,639/-	10,000/-	02 Month	350/-
12	A/R & M/O road NH-07 Gurudwara Sahib to bankala Rakhni Km.0/0 to 5/795. (SH:- M/O earthen shoulder filling with fresh selected soil)	4,97,650/-	10,000/-	02 Month	350/-

CERTIFICATE:- It is certified that the tenders of above works are exigency/emergent nature and in public interest.

Terms & Conditions:-

1. The Contractors/Bidders must submit their Permanent Income Tax Account Number/ GST number on the tender alongwith copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof alongwith application.



Schedule of Quantity

Name of work:- C/O Link road from Bholion to Shambalka Km 0/0 to 6/660(SH:-C/O RWall at RD 1/870 to 1/882, 3/930 to 3/937 & 5/930 to 5/938)

Estimated Cost:- Rs.4,95,103 /-only
Earnest Money:- Rs.10,000/- only
Time allowed:- Two months

Sr.N o	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	54.79	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement is to four sand is to eight crushed aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	114.51	Per Cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	31.86	Per Cubic metre			
4	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614,709,1204,3.7. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	85.00	Each			
	Total:-					

Opened By Mo

Cutting

Over Writing

Erasing and

Condition

Correction

Executive Engineer,
HP.PWD., Division
Nahan.

2

Schedule of Quantity

Name of work:- C/O Link road from Bholion to Shambalka Km 0/0 to 6/660(SH:-C/O RWall at RD 4/905 to 4/912 & 4/915 to 4/930) Estimated Cost:- Rs.4,96,196 /-only
 Earnest Money:- Rs.10,000/- only
 Time allowed:- Two months

Sr.N o	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	48.46	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement is to four sand is to eight crushed aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	114.60	Per Cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	36.24	Per Cubic metre			
4	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614, 709, 1204, 3.7. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	78.00	Each			
	Total:-					

Executive Engineer,
 HP.PWD., Division
 Nahan.

Opened By Me

Outling

Over Writing

Erasing

Condition

3

Schedule of Quantity

Name of work:- C/O Salani Teddi Baroti Trilokpur road Km 0/0 to 5/555(SH:- C/O Balance work of 6.00 mtrs.RCC slab culvert at RD 2/710)

Estimated Cost:- Rs.4,99,811/-only
Earnest Money:- Rs.10,000/- only
Time allowed:- Two months

Sr.N o	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and back filling in trenches with excavated suitable material, including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	50.77	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement is to four sand is to eight crushed aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	91.25	Per Cubic metre			
3	Providing and laying concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802, 803, 1202 1203 in PCC grade M-20 in 1:2:4 (one cement is to two sand is to four grade stone aggregate nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	6.28	Per Cubic metre			
4	Providing and laying reinforced cement concrete in superstructure complete as per drawing and technical specification clauses 802, 804, 805, 806, 807, 1202 and 1204 R.C.C. grade M-25) 1:1.5:3 (one cement is to one point five sand is to three grade stone aggregate nominal size) including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	17.09	Per Cubic metre			
5	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	3.83	Per Cubic metre			
	Total:-					

Executive Engineer,
HP.PWD., Division
Nahan.

Checked By Me
Cutting
Over Writing
Erasing
Condition

5

Schedule of Quantity

Name of work:-C/O Salani Teddi Baroti Trilokpur road Km 0/0 to 5/555(SH:-C/O V-Shape drain in Km 3/0 to 5/555)

Estimated Cost:- Rs.4,95,796 /-only
Earnest Money:- Rs.10,000/- only
Time allowed:- Two months

Sr.N o	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	132.49	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:3:6 (one cement is to three sand is to six graded stone aggregate) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	92.66	Per Cubic metre			
	Total:-					

Checked by M.E.
Drawing
Over writing
Erasing
Correction

Executive Engineer,
HP.PWD., Division
Nahan.

5

Schedule of Quantity

Name of work:-C/O Link road Rukhari to Gadda Buddi Km 0/0 to 3/400 (SH:-P/L Wet Mix Macadam(WMM) at RD 0/045 to 0/232)

Estimated Cost:- Rs.4,40,943/-only
Earnest Money:- Rs.9,000/- only
Time allowed:- Two months

Sr.No	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	167.86	Per Cubic metre			
	Total:-					

Executive Engineer,
HP.PWD., Division
Nahan.

Checked By Me
Cutting
Over Writing
Erasing
Condition

1

Schedule of Quantity

Name of work:-C/O Link road Rukhari to Gadda Buddi Km 0/0 to 3/400 (SH:-C/O Protection work D/Stream at RD 0/150)

Estimated Cost:- Rs.4,89,712/-only
Earnest Money:- Rs.10,000/- only
Time allowed:- Two months

Sr.No	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and back filling in trenches with excavated suitable material, including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	135.00	Per Cubic metre			
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woved diagonally) including 10 % (Ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five Kilogramme) each as per drawing and technical Specifications Clause 1301. including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	135.00	Per Cubic metre			
	Total:-					

Executive Engineer,
HP.PWD., Division
Nahan.

Opened By Me
Cutting
Over Writing
Erasing
Condition

Schedule of Quantity

Name of work:-C/O Link road Bhandariyon Ki Neron (SH:-C/O Both side wing walls of foot bridge)

Estimated Cost:- Rs.4,99,418/-only
Earnest Money:- Rs.10,000/- only
Time allowed:- Two months

Sr.No	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal , dressing of sides and bottom and back filling in trenches with excavated suitable material. including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	43.51	Per Cubic metre			
2	Providing and laying concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802,803,1202 1203 in PCC grade M-20 in 1:2:4 (one cement is to two sand is to four grade stone aggregate nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1.64	Per Cubic metre			
3	Supplying, fitting , and placing HYSD bar reinforcement in superstructure complete as per drawing and technical specifications clauses 1002,1010 and 1202 including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts , including all incidental charges.	0.200	Per Tonne			
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement is to four sand is to eight crushed aggregates) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	98.62	Per Cubic metre			
5	Construction of embankment with approved material obtained from borrow pits transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts , including all incidental charges.	289.28	Per Cubic metre			
6	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614,709,1204,3.7. including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	26.00	Each			
	Total:-					

Checked By
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.

Name of work:-A/R & M/O on Banog Kheri road Km 0/0 to 39/0(SH:-C/O R/Wall at RD 26/938 to 26/959)

Schedule of Qauantity

Estimated Cost:-4,98,617/-only
Earnest Money:- 10,000/- only
Time allowed:- Two months

Sr.No	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal , dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	37.56	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement is to four sand is to eight crushed aggregates) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	115.56	Per Cubic metre			
3	Earth filling in foundation trenches/substructure as per drawing and technical specification Clause 305.3.9 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	174.40	Per Cubic metre			
4	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614,709,1204,3.7. including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	20.00	Each			
	Total:-					

Executive Engineer,
HP.PWD., Division
Nahan.

opened By Me
Cutting
Over Writing
Erasing
Condition

Schedule of Quantity

Name of work:- C/O Balance work of missing cross drainage work on Banog Kheri road at RD 26/935(SH:-C/O left side abutment & Wing wall)

Estimated Cost:- 4,99,369/- only
Earnest Money:- 10,000/- only
Time allowed:- Two months

Sr.No	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	23.63	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement is to four sand is to eight crushed aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	78.75	Per Cubic metre			
3	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614, 709, 1204, 3.7. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	25.00	Each			
4	Providing and laying concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802, 803, 1202 1203 in PCC grade M-20 in 1:2:4 (one cement is to two sand is to four grade stone aggregate nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	33.65	Per Cubic metre			
	Total:-					

Opened By Me
Cutting
Over Whiting
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.

SCHEDULE OF QUANTITY

Name of Work:- C/O Link road Salani to Banka Bara Km 0/0 to 4/0(SH:-C/O 900 mm dia.RCC hume pipe culvert at RD 1/285 & 1/450)

Estimated Cost:- Rs.4,99,880/- only
Earnest money:- Rs 10,000/- only
Time:- Two Months

Sr No	Sub Head/Item of work	Quantity	Unit	Rate in figure	Rate in word	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	108.02	Per Cubic metre			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:6:12(one cement is to six sand is to twelve aggregates 40mm nominal size) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	2.64	Per Cubic metre			
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement is to four sand is to eight crushed aggregates) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	68.00	Per Cubic metre			
4	Providing-and laying concrete for plain/reinforced concrete in sub-structure complete as per drawing and technical specification clause 802,803,1202 1203 in PCC grade M-20 in 1:2:4 (one cement is to two sand is to four grade stone aggregate nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	23.00	Per Cubic metre			
5	Providing and laying 900mm dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing excluding excavation protection work, back filling concrete and masonry work in head walls and parapets clause 1108 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	15.00	Per Running metre			
6	Back filling behind abutment wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	11.00	Per Cubic metre			
7	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614,709,1204,3.7. including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	32.00	Each			
	Total :-					

Opened By Me
Cutting
Over Writing
Erasing
Condition

Executive Engineer
Nahan Division,
HP,PWD, Nahan.

11

Schedule of Quantity

Name of work:-C/O Link road Salani to Banka Bara Km 0/0 to 4/0(SH:-C/O B/Wall at RD 0/900 to 0/910 & R/Wall at RD 1/500 to 1/515)

Estimated Cost:-4,98,639/-only
Earnest Money:- 10,000/- only
Time allowed:- Two months

Sr.No	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	60.00	Per Cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement is to four sand is to eight crushed aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	126.87	Per Cubic metre			
3	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614, 709, 1204, 3.7. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	25.00	Each			
	Total:-					

Opened By Me
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.

12

Schedule of Qauantity

Name of work:-A/R & M/O road NH-07 Gurudwara Sahib to Bankala Rakhani Km 0/0 to 5/795(SH:-Maintenance of earthen shoulder filling with fresh selected soil)

Estimated Cost:- Rs.4,97,650/-only
Earnest Money:- Rs.10,000/- only
Time allowed:- Two months

Sr.No	Sub Head and item of work	Qty	Unit	Rate In		Amount
				figure	Words	
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto all lead as per technical specification Clause 1903 including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	9250.00	Per Square metre			
	Total:-					

Opened By Me
Cutting
Over Writing
Erasing
Condition

Executive Engineer,
HP.PWD., Division
Nahan.