

**Himachal Pradesh
Public Works Department**

No. PW-SKT-CB -Tender/2022-23

10007-00

Dated:- 19.09.2022

To,

✓ The Executive Engineer I.T. Cell,
Nigam Bihar Shimla -2

Subject:-

Publishing of Notice inviting tenders.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website before 01.10.2022 as per notification issued by Pr. Secy. (PW) to the Govt. of HP vide letter No. PBW (B) A (3)1/2020 dated 16th July 2021. As the works mentioned in the Tender Notice are urgent nature.

DA:-As above

✓
Executive Engineer,
Sarkaghat Division
HP.PWD.Sarkaghat

Himachal Pradesh
Public Works Department
"Notice Inviting Tender"

Sealed item rate tender are hereby invited in form No. 6&7 by the Executive Engineer B&R Division, HP.PWD. Sarkaghat HP. on behalf of the Governor of Himachal Pradesh for the following works from the instruction and are also registered contractor of appropriate class enlisted in HP.PWD whose registration stood renewed as per revised instruction and are also registered dealers under the Himachal Pradesh General sales Tax Act.1968.The important dates of tender are as under:-

The last date and time of receipt of application for tender form 01.10.2022 up to 4.00 P.M.

The last date for sale of tender is up to 03.10.2022 at 4.00PM.

The tender shall be received up to 11:00 AM on 04.10.2022 to be opened on the same day at 11:30 AM. in presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non refundable) during the working hours on 04.10.2022. The earnest money in the shape of National saving certificate, time deposit account in any post office/bank in HP. duly pledged in favor of the Executive Engineer B&R Division HP.PWD. Sarkaghat must accompany with each tender Conditional & in complete tenders and the tender received without earnest money will be summarily rejected. The offer of tender shall be kept open for 90 days. The Executive Engineer, reserved the right to accept or reject, the tender without assigning any reason.


Sr. No.	Name of work	Estimated cost.	Earnest Money.	Cost of form.	Time allowed.
1.	Balance work of Science Lab at Govt. Senior Secondary School Rakhoh Tehsil Sarkaghat Distt. Mandi (HP) (SH:- Providing and laying Cement Concrete Paver block) Deposit work	284817	6000	350	One Month
2.	Restoration of Rain Damages on Various Roads Under Sarkaghat Sub- Division HPPWD Sarkaghat (SH:- Hiring of JCB /Excavator to be deployed for removal of slips)	160650	3250	350	One Month
3.	Construction of meeting Hall in Conference Hall in Combined office building at Sarkaghat Distt. Mandi (HP)(SH:- Addition/alteration in hall)	295536	6000	350	One Month

TERMS AND CONDITONS:-

Following documents should accompany with the application for tenders.

1. The contractor/firms should be registered as or/dealer under HP Sales Tax Act. 1968/GST
2. The intending contractors/firms shall have to produce the copy of latest enlistment in HPPWD.
3. The contractor is required to submit an affidavit for not having more than two works in hand in the shape of affidavit duly attested by the competent authority.
4. If any of the date mentioned above happened to be Gazette Holiday the same shall be processed on next working day.
5. The contractor should quoted the rate of all the items in the tender both in figures and in words failing which tender is likely to be rejected.
6. The copy of Employees Provident Funds (EPF Number) GST, Pan Number, should be attached with application.
7. Minimum one similar work done of amount not less than 40% (Forty percent) of the estimated cost (without liquidated Damage or compensation) in last five years)
8. The tender shall be awarded to the lowest bidder without any negotiation if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The earnest money shall be deposited duly pledged in favour of Executive Engineer B& R Division HPPWD Sarkaghat & Cost of tender form for the above works should be submitted with the application for the purchase of the tender forms.

The application received **without** earnest money & cost of tender form shall summarily be rejected.
10. All the required documents should be submitted with the application others wise single application may be rejected.



Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat

Dated: 19.09.2022

No. PW-SKT-CB-Tender/2022-23

10000-07

1. The Engineer - in- Chief HPPWD Nirman Bhawan Shimla for information please.
2. The Chief Engineer Hamirpur Zone HP.PWD . Hamirpur for information please.
3. The Superintending Engineer Dharampur Circle, HP.PWD. Dharampur for information please.
4. Block Development officer Sarkaghat for information please.
5. Copy to the Assistant Engineer B&R Sub- Division HP.PWD Sarkaghat/ Baldwara /Bhaderwar for information.
6. Copy to Drawing Branch of this office for information.
7. Notice Board.


Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of Work:- Balance work of Science Lab at Govt Senior Secondary School Rakhol, Tehsil Sarkaghat Distt Mandi (H.P.). (SH:- Providing and Laying Cement Concrete Paver Block). (Deposit work)

Description of item/Sub Head	Quantity	Estimated cost :-		Unit	Amount
		In Figure	In words		
1 Providing and laying factory made charfered edge Cement Concrete paver blocks in footpath, parks, lawns drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper mbedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-charge	221.73			Per square metre	
2 Providing and laying Cement concrete 1:2:4 (one Cement :two coarse sand: four graded crushed stone aggregate) 20 mm (twenty millimetre) nominal size, in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete as per drawing and HP, PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.	0.43			Per cubic metre	
3 Centering and shuttering including strutting, propping etcetra and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etcetra. Including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	18.92			Per square metre	
				Total:-	

Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of Work:- Restrotation Rain Damages on Various Road under Sarkaghat Sub-Division HPPWD Sarkaghat. (SH:-
Hiring of JCB/ excavator to be deployed for removal of slips).

Estimated cost :- Rs. 160650/-
Earnest Money:- Rs. 3250 /-

Time Limit:-

Sr.No	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Hiring of Excavator cum loader for cutting work filling and deposal etcetra with a minimum capacity of 30 (thirty) cubic metre per hour.Including pay of oprators, P.O.L charges repair of machinery, pay of driver and other expenses. Any accident and other damages to private and Govt. property and loss of life occurred during the working hour will be the whole responsibility of the owner of the machinery. The disposal materials will be done by the owner of machinery to the disposal point within all leads and lifts and other incidentals as per direction of Engineer- in- Charge .	119.00			P/Hour	
					Total:-	


Executive Engineer,
B&R Divison,
HP PWD, Sarkaghat.

Draft Schedule of Quantity

Name of work:-Construction of meeting hall in conference hall in Combind office building at Sakghat
Distt. Mandi (H.P.) (SH:- Addition lateration in hall)

Name of work:-Construction of meeting hall in conference hall in Combind office building at Sakghat							Estimated cost :-		Rs 2,95,536/-
Distt. Mandi (H.P.) (SH:- Addition /ateration in hall)							Earnest money:-		Rs.6,000 /-
							Time allowed:-		One month
							Rate		Unit
Sr.No	Description of item/Sub Head	Quantity	In figure	In words					
1	Providing wood work in frames of false ceiling , partitions etcetra sawn and fixed in position with necessary stainless steel screws etcetra sai wood including all leads and lifts and as per the direction of Engineer-in-Charge	0.41			Per Cubic metre				
2	Providing and fixing 19mm (Nineteen millimetre) thick water proof commercial board in shelves/box for cup board with butt joints and fixing with nails and screws etcetra including all leads and lifts and as per the direction of Engineer-in-Charge	30.08			Per Square metre				
3	Providing and fixing 1.00mm (One millimetre) thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etcetra complete. including all leads and lifts and as per and the direction of Engineer-in-Charge	25.60			Per Square metre				
4	Second class half brick masonry common burnt clay FPS non modular brick of class designation 7.5 (Seven point five) in super structure above plinth level to floor all level in cement mortar 1:4 (One cement : four Sand) including all leads and lifts and as per and the direction of Engineer-in-Charge	41.56			Per Square metre				
5	15 mm (fifteen millimetre) cement plaster on the rough side of single or half brick wall of mix : 1:6 (One cement: six fine sand) including all leads and lifts and as per the direction of Engineer-in-Charge	41.56			Per Square metre				
6	Providing and fixing aluminium work for doors, windows,board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etcetra complete as per architectural drawings and directions of engineer- in-charge.Pre-laminated particle board with decorative lamination on one side and balancing lamination on other sideincluding all leads and lifts and as per the direction of Engineer-in-Charge	1.62			Per Square metre				
7	Providing and fixing aluminium tower bolts, ISI marked,anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetra complete 300x10 mm (Three hundred fifty into ten millimetre)including all leads and lifts and as per the direction of Engineer-in-Charge	1.00			Each				

8	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS - 1868) transparent or dyed to required colour or shade, with necessary screws etcetra complete 250x10 mm (Two hundred fifty into ten millimetre)including all leads and lifts and as per the direction of Engineer-in-Charge	2.00				Each	
9	Providing and fixing bright matt finished Stainless Steel handles of approved quality and make with necessary screws etc all complete. 125 mm (One hundred twenty five)including all leads and lifts and as per the direction of Engineer-in-Charge	4.00				Each	
10	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (Zero point nine zero litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm zero point seven litreper square metre) of approved brand and manufacture including all leads and lifts and as per and the direction of Engineer-in-Charge	2.02				Per Square metre	
11	Providing and applying white cement based putty of average thickness 1 mm, (One millimetre)of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete,including all leads and lifts and as per the direction of Engineer-in-Charge	26.37				Per Square metre	
12	Distempering with dry distemper of approved brand and manufacture (two or more coats) of required shade on new work, over and including water thinnable priming coat to give an even shade including all leads and lifts and as per the direction of Engineer-in-Charge	26.37				Per Square metre	
13	Steel work in single section including cutting hoisting , fixing in position and applying a priming coat og red lead paint in R S joint channels angles and tees including all leads and lifts and as per the direction of Engineer-in-Charge	5.47				Per quintal	
14	Providing and fixing PVC panneling in walls and(Market rate) including all leads and lifts and as per the direction of Engineer-in-Charge	182.5				Per Square metre	
						Total	


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.