

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PW-MDI(Padhar)E-Tender-NIT/2022-23-

12312-14

Dated:-24/9/22

To


The Executive Engineer (IT Cell),
Nirman Bhawan ,Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 03.10.2022 up to 11:00 A.M. and the same shall be opened on the same day at 11:30 A.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 01.10.2022 upto 01:00 P.M.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of rain damages on Katindhi to Jhatingri road Km 0/0 to 28/280 (SH:- Construction of Retaining wall at RD 1/820 to 1/828.60)	1,98,326/-	4,000/-	350/-	One month
2	Restoration of rain damages on Shegali Prasher road Km 0/0 to 22/510 (SH:- Construction of Retaining wall at RD 7/525 to 7/535)	4,38,490/-	8,800/-	350/-	One month
3	Restoration of rain damages on Barot to Mayot road Km 0/0 to 7/960. (SH:- Providing and laying GSB material in Km 0/829 to 1/003 and 5/780 to 5/960 and WBM G-II in Km 0/829 to 1/003 and 5/849 and 5/960)	4,93,488/-	9,900/-	350/-	One month
4	Restoration of rain damages on Uhl Valley road Km 0/0 to 10/0. (SH:- Construction of retaining wall at RD 0/320 to 0/330)	4,09,811/-	8,200/-	350/-	One month
5	Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on Neri Duhki Behindhar Gharan road Km 0/00 to 17/810. (SH:- Construction of unlined Katcha surface drain in Km 5/000 to 17/810)	4,76,456/-	9,500/-	350/-	Three months
6	Restoration of rain damages on Shegali Prasher road Km 0/000 to 22/510.(SH:- Construction of Retaining wall at RD 7/315 to 7/330)	3,92,266/-	7,800/-	350/-	One month
7	Improvement of black spot on Uhl Valley road Km 0/0 to 10/0. (SH:- Removal of formation deficiencies at RD 9/455 to 9/515).	1,82,107/-	3,600/-	350/-	One month
8	Improvement of black spot on Uhl Valley road Km 0/0 to 10/0. (SH:- Removal of formation deficiencies at RD 9/515 to 9/560).	1,86,191/-	3,700/-	350/-	One month

1. **Certified that tender of above works are being called of emergent nature in exigency of public interest.**

TERMS AND CONDITIONS:-

- The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
- The intending Contractor/Firm Should have attached copy of registration/renewal.

3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The intending Contractors are requested to see the site of the work before submitting the tender.
5. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
6. The offer of the tender shall remain valid upto 90 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.



Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)

Schedule of Quantity

Estimated Cost:- Rs. 198326.00
 Earnest Money:- Rs. 4000.00
 Time:- One month

Name of work:- Restoration of rain damages on Katindhi to Jhatingri road Km. 0/000 to 28/280.
Sub Head:- Construction of retaining wall at RD 1/820 to 1/828.60.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	22.70 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203 . Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	32.60 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	1.67 Cum.			Per cubic metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other other incidentals as per direction of Engineer-in-Charge.	22.00 Nos.			Each	
					Total	


 Executive Engineer,
 Mandi Division No.1,
 H.P.P.W.D. at Padha


2

Schedule of Quantity

Estimated Cost:- Rs. 438490.00
Earnest Money:- Rs. 8800.00
Time:- One month

Name of work:- Restoration of rain damages on Shegali Prasher road Km. 0/000 to 22/510.
Sub Head:- Construction of retaining wall at RD 7/525 to 7/535.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	40.90 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203 . Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	70.37 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	13.80 Cum.			Per cubic metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other other incidentals as per direction of Engineer-in-Charge.	12.00 Nos.			Each	
					Total	



Executive Engineer,
Mandi Division No.1,
HP-PWD. at Padha

Schedule of Quantity

Estimated Cost:- 493488.00
 Earnest Money:- 9900.00
 Time:- One Month

Name of work:- Restoration of rain damages on Barot to Mayot road Km. 0/0 to 7/960.
Sub Head:- Providing and laying GSB material in Km. 0/829 to 1/003 and 5/780 to 5/960 and WBM G-II in Km.0/829 to 1/003 and 5/849 to 5/960

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Construction of granular sub-base by providing well graded material spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density complete as per Technical Specifications Clause 401 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	99.28 Cum.			Per cubic metre	
2	Providing, laying, spreading and compacting by manual means stone aggregates 63mm to 45mm (sixty three millimetre to forty five millimetre) of sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-one hundred kilo newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-II (two) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges as per direction of Engineer-in-Charge.	45.63 Cum.			Per cubic metre	
Total:-						



 Executive Engineer,
 Mandi Division No.1,
 P.P.P.W.D. at Padharaj

Schedule of Quantity

Estimated Cost:- Rs. 409811.00
 Earnest Money:- Rs. 8200.00
 Time:- One month

Name of work:- Restoration of rain damages on Uhl Valley road Km. 0/0 to 10/0
 Sub Head:- Construction of retaining wall at RD 0/320 to 0/330 .

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	12.20 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203 . Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	68.30 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	14.85 Cum.			Per cubic metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other other incidentals as per direction of Engineer-in-Charge.	12.00 Nos.			Each	
					Total	


 Executive Engineer,
 Mandi Division No.1,
 HP.PWD. at Padhal

3

Schedule of Quantity

Estimated Cost:- 476456.00


Earnest Money:- 9500.00

Time:- Three months

Name of work:- Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on Neri Duhki Behindhar Gharan road Km. 0/00 to 17/810.

Sub Head:- Construction of unlined Katcha surface drain in Km. 5/000 to 17/810.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Construction of unlined surface drains by manual/mechanical means of average cross-sectional area 0.40 (zero point four zero) square metre in all kinds of soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 including carriage of material within all leads, lifts and other incidentals as per the direction of Engineer-in-Charge complete in all respect.	12170.00			Per running metre	
					Total:-	


Executive Engineer,
Mandi Division No.1,
H.P. P.W.D. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 392266.00
 Earnest Money:- Rs. 7800.00
 Time:- One month

Restriction of rain damage on Annual repair and maintenance of Shegali Prasher road Km. 0/000 to 22/510.
 Name of work:- Construction of Retaining wall at RD 7/315 to 7/330.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	34.80 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203 . Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	61.38 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	18.30 Cum.			Per cubic metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other other incidentals as per direction of Engineer-in-Charge.	12.00 Nos.			Each	
					Total	

[Signature]
 Executive Engineer,
 Mandi Division No.1,
 H.P.PWD. at Padhar


7

Schedule of Quantity

Estimated Cost:- 182107.00
Earnest Money:- 3600.00
Time:- One month.

Name of work:- Improvement of black spot on Uhl Valley road Km.0/0 to 10/0.
Sub Head:- Removal of formation deficiencies at RD 9/455 to 9/515.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper and blasting work both in soft and hard rock with chiseling wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required setting out to the required line, grades, side slopes trimming bottoms and level as shown in the drawing as directed by Engineer-In-Charge at site according to technical specifications, sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of the roads or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including all leads and lift of materials or as per direction of Engineer-in-Charge.	801.00 Cum.			Per cubic metre	
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No,1	157.53 Cum.	600.00	Rupees six hundred and paise nil only	Per cubic metre	-94518.00
			Total:-			



Executive Engineer,
Mandi Division No.1,
H.P.P.W.D. at Padhar

Schedule of Quantity

Estimated Cost:- 186191.00
 Earnest Money:- 3700.00
 Time:- One month.

Name of work:- Improvement of black spot on Uhl Valley road Km.0/0 to 10/0.
 Sub Head:- Removal of formation deficiencies at RD 9/515 to 9/560.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in all heights and depths, in all kinds of soil including saturated soil comprising of pick, jumper and blasting work both in soft and hard rock with chiseling wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required setting out to the required line, grades, side slopes trimming bottoms and level as shown in the drawing as directed by Engineer-In-Charge at site according to technical specifications, sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of un-useful materials for filling in road ways, embankments for grades improvements and levelling to the required grade and then disposing of surplus excavated earth in acquired width of the roads or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if required). Any loss to the public and private property during the course of execution shall be absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including all leads and lift of materials or as per direction of Engineer-in-Charge.	804.75 Cum.			Per cubic metre	
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No.1	188.76 Cum.	600.00	Rupees six hundred and paise nil only	Per cubic metre	-113256.00
				Total:-		


 Executive Engineer,
 Mandi Division No.1,
 H.P.P.W.D. at Padharyan