



E-Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 06/10/2022 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 04/10/2022 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.


S. No.	Name of work	Estimated of cost	Earnest Money	Cost form	Time limit
1	Repair and Maintenance of National Highway of Chandigarh Mandi Manali road NH-205 Km. 105/0 to 127/0. Junction improvement work at Nauni Chowk Bilaspur Chandigarh Manali on Nh-205 & 154 (SH:- Preparation of detailed survey drawing, junction design as per latest IRC codes and preparation of detailed estimate)	Rs. 1,80,000/-	Rs. 3,600/-	Rs. 350/-	Two Month
2	C/o link road to from Tikker to Dhauldhar (SH:- C/o 900mm dia RCC hume pipe culvert at RD 1/175 and 1/495)	Rs. 3,55,747/-	Rs. 7,200/-	Rs. 350/-	Three Month
3	Construction of link road from Methi Galaa to Nali Paloun GP Methi Km. 0/0 to 2/500 (SH:- C/o 2.40 meter wide cement concrete pavement at RD 0/0 to 0/125) Deposit work	Rs. 1,19,752/-	Rs. 2,400/-	Rs. 350/-	Three month
4	Repair and Maintenance of CMM road NH-205 between 105/0 to 127/0 (SH:- Providing and laying cement concrete & Painting/writing on Rain Shelter at various RDs)	Rs. 46,943/-	Rs. 900/-	Rs. 350/-	One month
5	Restoration of Rain damages on Sh. Naina Devi ji Bhakra road Km. 13/0 to 37300 (SH:- C/o R/wall at RD 34/060 to 34/078)	Rs. 4,64,311/-	Rs. 9,300/-	Rs. 350/-	Three Month
6	Construction of Play ground at Govt. Primary School Chilla G.P. Kacholi Distt. Bilaspur (HP) (SH:- C/o C/o Cutting/Levelling)	Rs. 51,851/-	Rs. 1,100/-	Rs. 350/-	Three Month
7	Restoration of Rain damages on Navgaon Beri road Km. 4/350 to 23/700 (SH:- C/o R/wall at RD 8/900 to 8/906 and 8/987 to 8/993)	Rs. 3,27,538/-	Rs. 6,600/-	Rs. 350/-	Three Month
8	Restoration of Rain damages on Thatch Sikroha Neri Jukhala road Km. 0/0 to 18/690 (SH:- C/o R/wall at RD 9/300 to 9/308)	Rs. 95,443/-	Rs. 2,000/-	Rs. 350/-	Three Month
9	Restoration of Rain damages on Sh. Naina Devi ji Bhakra road Km. 13/0 to 37300 (SH:- C/o B/wall at RD 29/546 to 29/556 and 33/885 to 33/895)	Rs. 1,89,893/-	Rs. 3,800/-	Rs. 350/-	Three Month
10	Restoration of Rain damages on link road Harizen Basti Tiun Khas Km. 0/0 to 3/135 (SH:- C/o wire crate as a B/wall at RD 2/395 to 2/425)	Rs. 1,43,568/-	Rs. 2,900/-	Rs. 350/-	Three Month
11	A/R & M/O HPPWD Rest House at Bahaderpur Distt. Bilaspur (SH:- Providing and laying Tile work, white washing, Painting etc.)	Rs. 2,28,926/-	Rs. 4,600/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.

3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall summarily rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.


 Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

No.PW/NBT/CB/Tender-State/EA-1/2022- 10474-78

Dated:- 26-9-2022

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-1
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in along with copies of Schedule of Quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.

 Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.1,80,000/-Only.						
Earnest Money :- Rs. 3,600/- only						
Time:- Three Months.						
NAME OF WORK:- Repair and maintenance of National Highway of Chandigarh Mandi Manali road NH-205 Km 105/00 to 127/000. Junction improvement work at Nauni Chowk, Bilaspur Chandigarh Manali on NH-205 & 154.(SH:-Preparation of Detailed survey drawings , junction design as per latest IRC codes ,and preparation of detailed estimate)						
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2	3	4	5	6	7
1	Detailed Topographical survey using Digital total station with two second accuracy , showing all features on survey plan like trees, buildings, retaining walss, breast walls, electric pole, telephone poles etc.	1.00 Job			Per Job	
2	Detailed design of improvement of junction as per latest IRC Guidelines and MoRTH specifications and computerization of data on AUTOCAD Civil 3D software and printing through plotter, Preparation of plan , L-Section & Cross sections, including typical cross section etc on a readable scale complete in all respect as per the direction of Engineer-in-Charge.	1.00 Job			Per Job	
3	Preparation of Detailed estimate of junction as per analysed SOR rates of HPPWD. Printing approved 5 set and submitting the same to the divisional office.	1.00 Job			Per Job	
	Total:-					

Executive Engineer,
Bilaspur Division No. 11.
H.P.W.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.							Estimated Cost:- Rs.=3,55,747/-Only.
							Earnest money:-Rs. 7,200/-
							Time:- Three Month.
Name of Work:- Construction of link road from Tikkar to Dhauladhar km 0/00 to 2/525 (SH):- C/O 900 mm dia RCC hume Pipe Culvert at RD 1/175 & 1/495)							
Sr No.	Description of items.	Quantity	Rates in.		Unit	Total	
			Figure	Words.			
1	2	3	4	5	6	7	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out, consolidation of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs., dressing of sides and bottom and backfilling in trenches with excavated suitable material. -upto 3.00 mtrs. depth. including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	73.09	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10(one cement is to four sand is to eight graded stone aggregate 25 mm (Twenty five millimetre) nominal size) in or under water and curing complete and including pumping or bailing out water,dewatering,removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work complete in all respect as per drawing and technical specification.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	33.06	Cubic metre			Per Cubic metre	
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification PCC 1:4:8 (One :Cement :four sand: eight graded crushed stone aggregate)40 mm (Forty Millimetre) . The minimum cement content should be not less than 170 kg per cubic metre including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.17	Cubic metre			Per Cubic metre	
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802,803, 1202& 103 P.C.C. Grade M 10 (1:3:6) (One cement : Three coarse sand : Six graded stone aggregate) The minimum cement content should be not less than 220 kg per cubic metre including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.19	Cubic metre			Per Cubic metre	
5	Providing and laying reinforced cement concrete pipe NP-2 for culverts on first class bedding of granular materials in single row including fixing colour with cement mortar 1:2 but excluding excavation protection work and parapets clause 1106. 900 mm dia including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00	Running metre			Per Running metre	
6	Cement concrete flooring 1:2:4(One Cement two sand four graded stone aggregate, 20mm (Twenty millimeters) nominal size,laid in one layer finished with a floating coat of neat cement, 40mm (Forty millimeters) thick including carriage of materials , within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.52	Square Meter			Per Square Meter	

7	Back filling, behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.44	Cubic Metre		Per Cubic Metre	
8	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.00	Nos.		Each.	
					Total Rs.	

Executive Engineer,
Bilaspur Division No. H.
Jr. PWD, Bilaspur H.P.


SCHEDULE OF QUANTITY

Name of Work :- Construction of link road from Methi Galaa to Nali Paloun GP Methi Km 0/0 to 2/500 (SH:- C/o 2.40 mtr wide Cement Conceter Pavement at RD 0/0 to 0/125). Deposit Work.					Estimated cost:-	119752.00	Only
					Earnest Money:-	2400.00	Only
					Time allowed:- Three Month		
Sr. No.	Description of iteams	Quantity	Rate		Unit	Amount	
			Figures	words			
1	Preparation of sub-grade by dressing to camber (Earth work for the cutting involved for sub-grade to be measured and paid for separately) depending upon the clalssification of soil complete as per HP.PWD., Specification as per direction of Engineer-in-charge. including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	343.75			Per square metre		
2	Consolidation of sub-grade with road roller including making good the undulation etcetera with earth or quarry soil etcetera and re-rolling the sub-grade completed as per HP.PWD., specification as per direction of Engineer-in-charge. including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in Charge. The rates are inclusive , octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	343.75			Per square metre		
3	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in Charge. The rates are inclusive , octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	34.88			Per Cubic metre		
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade M 20 (Twenty) Nominal mix (1:2:4) including cost of form work and curing complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana , Toll tax , Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.00			Per Cubic metre		
Total:-							

Executive Engineer,
Bilaspur Division No. 4
H.P. PWD., Bilaspur

SCHEDULE OF QUANTITY

Name of Work :- Repair & Maintenance of CMM road NH-205 Between 105/0 to 127/0 (SH:- Providing & laying Cement Concrete & Painting/ Writing on Rain Shelter at various RDs)				Estimated cost:- ☐ 46943.00		Only
				Earnest Money:- ☐ 900.00		Only
				Time allowed:- One Month		
Sr. No.	Description of items	Quantity	Rate	Unit		Amount
				Figures	words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	23.40			Per Cubic Meter	
2	Providing and Laying cement concrete M-10 (Ten) graded crushed stone aggregate. 40mm (forty milimetre) nominal size with minimum cement contents 260kg (two hundred sixty) killogram, per cubic metre and curring complete . including cost of form work for plain /reinforce concrete in structures like U shape drain, V- Shape drain, culverts, drains and other structre as per drawing and MORD technical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts ,shoring and shuttering and curring complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material ,tools equipment safety measures and other incidentals as per the direction of Engineer-in Charge.The rate includes, octroi, royalty Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.26			Per Cubic Meter	
3	Painting one coat (excluding priming coat) on previously painted steel & other metal surfaces with readymixed paint,brushing oil, grease to give an even shade including cleaning the surface of all dirt,dust and other foreign matter With readymixed paint other than white. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	91.65			Per square Meter	
4	Writing letters or figures on any surface with black japan paint (stops,comas,lyphens and the like not to be measured and paid separately) Block letters/figures including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	2800.00			per letter Per.Cm height	
Total:-						


 Executive Engineer,
 District Engineer, H. N.
 P. H. D., Bhawanipatna

SCHEDULE OF QUANTITY.									
Estimated Cost:- Rs.=4,64,311/-Only.									
Earnest money:-Rs. 9,300/-									
Time:- Three Month.									
Name of Work:- Restoration of Rain damages on Sh. Naina Devi Ji Bakhra road km 13/000 to 37/300 (SH:- C/O R/wall at RD 34/060 to 34/078)									
Sr No.	Description of items.	Quantity		Rates in.		Unit	Total		
		Figure	Words.						
1	2	3	4	5	6	7	8		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	19.44	Cubic Metre			Per Cubic Metre	8		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10(One :Cement :five sand: Ten graded crushed stone aggregate) 40 mm (Forty Millimetre)nominal size) in or under water and curing complete and including pumping or bailing out water,dewatering,removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work complete in all respect as per drawing and technical specification.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	104.48	Cubic metre			Per Cubic metre			
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	60.00	Nos			Each			
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification,1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.20	Cubic Metre			Per Cubic Metre			
						Total			


 Executive Engineer,
 Bilaspur Division No. N.
 J.P. PWD., Bilaspur(H.P.)

SCHEDULE OF QUANTITY.				Estimated cost:- Rs.51,851/-Only.		
				Earnest Money :- Rs. 1,100/- only		
				Time:- Three Months.		
NAME OF WORK:- Construction of Play Ground at Govt. Primary School Chilla GP. Kachouli Distt. Bilaspur (SH:-C/O Cutting / Leveling of Ground) (Deposit Work)				Rates in		
Sr No.	Description of items.	Quantity	Unit	Figure.		Amount
				4	5	
1	2	3	4	5	6	7
2	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300, 1603.1, 1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road way, camber, embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of jumper work in all cases falling which recovery shall be effected on the prevailing market rates. Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, royalty, Malkana, toll tax, Goods & service Tax or other taxes imposed by the Government. A recovery of useful stones for 19.80 cubic metre @ Rs. 170/- Per cubic metre shall be done on pro-rata basis in each running bill for this item	495.00	Cubic Metre			
Total:-						

Excluded
Bilaspur Division No. N.
B.P.A.D., Bilaspur (I.P.)

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=3,27,538/-Only.					
		Earnest money:-Rs. 6,600/-					
		Time:- Three Month.					
Name of Work:- Restoration of Rain damages on Navgoan Beri road km 4/350 to 23/700 (SH:- C/O R/wall at RD 8/900to 8/906 and 8/987 to 8/993)							
Sr No.	Description of items.	Quantity	Rates in.	Unit	Total		
			Figure	Words.			
1	2	3	4	5	6	7	8
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	39.36	Cubic Metre			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10(One :five sand: Ten graded crushed stone aggregate) 40 mm (Forty Millimetre/nominal size) in or under water and curing complete and including pumping or bailing out water,dewatering,removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts including the cost of form work complete in all respect as per drawing and technical specification.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	78.72	Cubic metre			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Cubic Metre			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Nos			Each	
						Total	

Executive Engineer,
Bilaspur Division No. H,
 Bilaspur, Chhatisgarh

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.									
Estimated Cost:- Rs.=95,443/-Only.									
Earnest money:-Rs. 2,000/-									
Time:- Three Month.									
Name of Work:- Restoration of Rain Damages on Thatch Sikroha Neri Jukhala road km 0/00 to 18/690 (SH:- C/O R/wall at RD 9/300 to 9/308)									
Sl No.	Description of items.	Quantity		Rates in.		Unit	Total		
		Figure	Words.	Figure	Words.				
1	2	3	4	5	6	7	8		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	9.24	Cubic Metre			Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10(One :five sand: Ten graded crushed stone aggregate) 40 mm (Forty Millimetre)nominal size) in or under water and curing complete and including pumping or bailing out water,dewatering,removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work complete in all respect as per drawing and technical specification.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.05	Cubic metre			Per Cubic metre			
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.30	Cubic Metre			Per Cubic Metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00	Nos			Each			
						Total			

Executive Engineer,
Bilaspur Division No. N.
Bilaspur, Chhattisgarh P.

DRAFT SCHEDULE OF QUANTITY.

DRAFT SCHEDULE OF QUANTITY.									
Estimated Cost:- Rs.=1,89,893/-Only.									
Earnest money:-Rs. 3,800/-									
Time:- Three Month.									
Name of Work:- Restoration of Rain damages on Sh. Naina Devi Ji Bakhra road km 13/000 to 37/300 (SH:- C/O B/wall at RD 29/546 to 29/556 and 33/885 to 33/895)									
Sr No.	Description of items.	Quantity	Rates in.			Unit	Total		
			Figure	Words.					
1	2	3	4	5	6	7	8		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	10.80	Cubic Metre			Per Cubic Metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	24.90	Cubic Metre			Per Cubic Metre			
3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10(One :five sand: Ten graded crushed stone aggregate) 40 mm (Forty Millimetre/nominal size) in or under water and curing complete and including pumping or bailing out water,dewatering,removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work complete in all respect as per drawing and technical specification.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	23.51	Cubic metre			Per Cubic metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	8.00	Nos			Each			
5	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	31.26	Cubic metre			Per Cubic metre			
						Total			

Executive Engineer,
Bilaspur Division No. 11
Bilaspur

SCHEDULE OF QUANTITY.							Estimated cost:- Rs.1,43,568/-Only.
							Earnest Money :- Rs.2,900/-
							Time:- Three Months.
NAME OF WORK:- Restoration of Rain Damages on link road Harizan Basti Tiun khas km 0/0 to 3/135(SH:-C/o wire crate as a B/wall at RD 2/395 to 2/425)							
Sr No.	Description of items.	Quantity	Rates in		Unit	Amount	
			Figure.	Words.			
		3	4	5	6	7	
1	2	53.40	Cubic Metre		Per Cubic Metre		
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock , hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification ,2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadsand lifts.Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him.The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.						
2	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire confirming to IS:280 and IS:4826 in 100mmx100mm mesh(Woven diagonally) including 10percent extra for laps and joints laid with stone boulders weighing not less than 25kg as per drawing and technical specification clause 301. including cost of form work and curing complete including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	93.75	Cubic metre		Per Cubic metre		
					Total:-		

EXECUTED & SIGNED,
 Bileepur Division Mo. N.
 P. PWD., Bileepur(M.P.)

SCHEDULE OF QUANTITY.

Estimated Cost:- Rs.=2,28,926/-Only.

Earnest money:-Rs. 4,600/-

Time:- Three Month

Name of Work:- A/R & M/O HPPWD Rest House at Bahaderpur Distt. Bilaspur (SH:- Providing & Laying Tile work, White washing, Painting etc.)

Sr No.	Description of items.	Quantity	Rates in.		Unit	Total
			Figure	Words.		
1	Providing and laying Duro stone vetrified tiles Nitco or its equivalent(300x300mmx10mm)(Three hundred millimetre into three hundred millimetre into Ten millimetre) in grey/coloured or of approved shade in flooring, treads of steps and landing laid on a bed of 12mm(Twelve millimetre) thick cement mortar 1:3 (One cement : Three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	86.48	Square Meter		Per Square Meter	
2	Providing and laying Duro stone vetrified tiles Nitco or its equivalent(300x300mmx8mm)(Three hundred millimetre into three hundred millimetre into Eight millimetre) in grey/coloured or of approved shade in flooring, treads of steps and landing laid on a bed of 12mm(Twelve millimetre) thick cement mortar 1:3 (One cement : Three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.72	Square Meter		Per Square Meter	
3	Painting One coats (excluding priming coat) on new wood and wood based surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt dust and other foreign matter, sand papering and stopping with enamel paint other than white including carriage of materials within all leads and lifts as per direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	410.06	Square Metre		Per Square Metre	
4	supplying and fixing glass panes with putty and nails including removal of broken glass panes wherever necessary :-plain glass 4mm thick The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.66	Square Meter		Per Square Meter	
6	Distemping (one coats) with oil bound washable distemper of approved brand and manufacture and of required shade on un-decorated wall surface to give an even shade over and i/c priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter also i/c preparing the surface even and sand papered smooth including priming coat with distemper primer. including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	312.62	Square metre.		Per Square metre.	
7	Wall painting (one coat) with plastic emulsion paint of approved brand and manufacture on undecorated wall surface to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty and required for making the surface including carriage of materials within all leads and lifts as per direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	864.06	Square Metre		Per Square Metre	

8	Finishing wall with weather proof exterior grade emulsion of approved shade of (Apexultima) or its equivalent on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	417.10	Square Meter	Per Square Meter	
9	Painting One coat (excluding priming coat) on previously painted on wood work steel and other metal surfaces with ready mixed paint, brushing finishing oil, grease to give an even shade, including cleaning the surface of all dirt dust and other foreign matter. With ready-mixed paint other than white including carriage of materials, within all leads and lifts as direction by the Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	308.72	Square metre.	Per Square metre.	
10	Extra over item No. 12 for every subsequent finishing coat of paint including carriage of materials, within all leads and lifts as direction by the Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	308.72	Square metre.	Per Square metre.	
Total:-					

Engineer,
 Electrical Division No. 11,
 P.O. 1410, Bhubaneswar.