

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the **Executive Engineer Dehra Division HPPWD., Dehra** on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEULE:

1. Date and time of receipt of application for tender form: 30.09.2022 upto 4.00 PM
2. Date and time of issue of tender form: 01.10.2022 upto 5.00 PM
3. Date and time of receipt of tenders: 03.10.2022 upto 11.00 AM
4. Date and time of opening of tenders: 03.10.2022 at 11.30 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	C/O Administrative Academic Block in Govt Degree College Dhaliara Tehsil Dehra Distt. Kangra (HP) (SH:- Providing and Laying Granite in Stairs etc. & Steel work for Ground floor)	Rs.4,86,587/-	Rs.10000/-	One month	Rs.350/-
2	C/O Administrative Academic Block in Govt Degree College Dhaliara Tehsil Dehra Distt. Kangra (HP) (SH:- C/O R/wall from Main Gate at RD 0/024 to 0/032 & Steel work for Ground floor)	Rs.4,84,414/-	Rs.10000/-	One month	Rs.350/-
3	C/O Administrative Academic Block in Govt Degree College Dhaliara Tehsil Dehra Distt. Kangra (HP) (SH:- C/O R/wall from Main Gate at RD 0/00 to 0/018)	Rs.4,84,999/-	Rs.10000/-	One month	Rs.350/-
4	C/O Administrative Academic Block in Govt Degree College Dhaliara Tehsil Dehra Distt. Kangra (HP) (SH:- C/O R/wall from Main Gate at RD 0/035 to 0/040 & Stainless Steel work for ground floor & Stairs)	Rs.3,56,128/-	Rs.7000/-	One month	Rs.350/-
1.	The contractors/firms should possess the following documents(Photocopy to be attached with the application): (i) Copy of Registration/Latest renewal of enlistment. (ii) PAN (Permanent Account No.) (iii) Registration under GST No. (iv) EPF(Employee Provident Fund Account No.) (v) The proof ownership/hire/lease, buying of required machinery for micro surfacing works.				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
4	The offer of the tender shall remain valid upto 30 days after the opening.				

1. Certified that the above work is of an emergent nature in exigency of public interest .

Executive Engineer
HPPWD Division Dehra
Distt Kangra H.P

on behalf of Governor of Himachal Pradesh

Endst.No.PWD/DEH/CB/Tender/2021-22:-

8095-8100 Dated :- 22/9/22

Copy forwarded to the following:-

1. The F.C. Cum Principal Secretary(PW) to the Govt. of Himachal Pradesh Shimla-2
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, 9th Circle HP.PWD. Nurpur.
5. Notice Board.
- ✓ 6. The Computer Cell office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Departmental website.
7. All eligible Contractors


Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

BILL OF QUANTITY

Estimate Cost :- Rs. 4,86,587.00
 Earnest Money :-Rs. 9000.00
 Time Limit :- One Month.

Name of work:- C/o Administrative Academic Block in Govt. Degree College Dhaliara Tehsil Dehra District Kangra (H.P) (SH:- Providing and Laying Granite in Stairs etc & Steel work for Ground floor)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc.complete at all levels (Area of slab over 0.50 sqm) complete as per HPPWD specifications or as per direction by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Toll Tax Sales tax,GST or any other taxes imposed by the Government.	79.00 Square meter		Rupees Nil	Per Square meter	-
2	Steel work welded in built up sections trusses and framed work, composed of beams, joists, channels, angles, tees, flats and connecting plates or angle cleats etc. as in trusses and trussed purlins, main and cross beams, hip and jack rafters, purlins connected to common rafters and the like in building including cutting, fixing, lifting, hoisting and placing in position complete and applying a priming coat of red lead paint complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government. a) In trusses and trussed purlins in buildings.	19.80 Quintel		Rupees Nil	Per Quintel	-
3	Providing and fixing moulded hand rail of MS hollow pipe 50mm (fifty millimeter) diameter welded in straight length over MS flat at top of vertical balusters including one coat of red oxide priming coat complete (M.S flat and balusters of railings shall be measured and paid separately) upto all floor level, complete as per HPPWD Specification or as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	156.60 Running Metre		Rupees Nil	Each	-
	Total					-

Executive Engineer,
 Dehra Division
 HPPWD Dehra

BILL OF QUANTITY

Estimate Cost :- Rs. 4,84,414.00
 Earnest Money :-Rs. 10000.00
 Time Limit :- One Month.

Name of work:- C/o Administrative Academic Block in Govt. Degree College Dhaliara tehsil Dehra District Kangra (H.P) (SH:- C/o R/wall from Main Gate at RD 0/025 to 0/032 & Stainless Steel Work for ground Floor & stairs.)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	74.98 Cubic metre		Rupees Nil	Per Cubic metre	-
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	45.33 Cubic metre		Rupees Nil	Per Cubic metre	-

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	24.00 Numbers		Rupees Nil	Each	-
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	30.66 Cubic meter		Rupees Nil	Per Cubic meter	-
5	Steel work welded in built up sections trusses and framed work, composed of beams, joists, channels, angles, tees, flats and connecting plates or angle cleats etc. as in trusses and trussed purlins, main and cross beams, hip and jack rafters, purlins connected to common rafters and the like in building including cutting, fixing, lifting, hoisting and placing in position complete and applying a priming coat of red lead paint complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government. a) In trusses and trussed purlins in buildings.	28.60 Quintel		Rupees Nil	Per Quintel	-
Total						-


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

BILL OF QUANTITY

Estimate Cost :- Rs. 4,84,999.00
 Earnest Money :-Rs. 10000.00
 Time Limit :- One Month.

Name of work:- C/o Administrative Academic Block in Govt. Degree College Dhaliara tehsil Dehra District Kangra (H.P) (SH:- C/o R/wall from Main Gate at RD 0/00 to 0/018).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	168.70 Cubic meter			Per Cubic meter	-
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	101.98 Cubic metre			Per Cubic metre	-

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	54.00 Numbers			Each	-
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	68.99 Cubic meter			Per Cubic meter	-
	Total					-


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra

BILL OF QUANTITY

Estimate Cost :- Rs. 356128.00

Earnest Money :-Rs.7000.00

Time Limit :- One Month.

Name of work:- C/o Administrative Academic Block in Govt. degree College Dhaliara tehsil Dehra District Kangra (H.P) (SH:- C/o R/wall from Main Gate at RD 0/035 to 0/040 & Stainless Steel Work for ground Floor & stairs.)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	65.60 Cubic meter			Per Cubic meter	
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	14.58 Cubic metre			Per Cubic metre	

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	15.00 Numbers			Each	-
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	11.55 Cubic meter			Per Cubic meter	-
5	Providing and fixing railing for stair case having baluster of 35mm dia SST pipe welded 50mm dia SST pipe with a clear height of 85cm (Eighty five centimeter) at the rate of (@) 60cm (Sixty centimeter) centre to centre embedded in cement concrete steps and welded with electric welding at top along with handrail of hollow rSST pipe of 50mm dia slip resistance vertical balluster welded/jointed with each other with 2 Nos SST pipe of 20x20mm (Twenty isto twenty millimetre) complete upto all floor level as per drawing and design including carriage of materials with in all leads, lifts and other incidentals or as per direction of Engineer-in-Charge. The rate inclusive of Octroi, Toll Tax Sales tax, GST or any other taxes imposed by the Government.	41.00 Running Metre			Per Running Metre	-
6	Cutting holes up to 15x15 cm in R.C.C. floors and roofs for passing drain pipe etc. and repairing the hole after insertion of drain pipe etc. with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), including finishing complete so as to make it leak proof. complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, Toll Tax ,GST ,Sales tax or any other taxes imposed by the Government	116.00 Numbers			Each	-

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
7	Steel work welded in built up sections trusses and framed work, composed of beams, joists, channels, angles, tees, flats and connecting plates or angle cleats etc. as in trusses and trussed purlins, main and cross beams, hip and jack rafters, purlins connected to common rafters and the like in building including cutting, fixing, lifting, hoisting and placing in position complete and applying a priming coat of red lead paint complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government. (a) In trusses and trussed purlins in buildings.	4.46 Quintel			Per Quintel	
Total						


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra