

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
***** Notice Inviting Tender *****

Sealed item rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Jawalamukhi** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **04.10.2022** up to **11:00 A.M.** And the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **03.10.2022** up to **4:00 P.M** and the application for issue of tender form shall be received on **01.10.2022** up to **12:00 noon**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour **Executive Engineer, HP PWD Division Jawalamukhi**.

The conditional tender and the tender received without earnest money will summarily be rejected.
The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Construction of link road from Hardeepur to Mahr road Km 0/000 to 2/200 in Distt Kangra (HP) (SH:-Construction of 5/7 mtrs wide formation cutting at RD 0/000 to 0/900).	361942/-	7250/-	One month
2	Restoration of rain damages on various roads under Khundian Sub-Division HP PWD Khundian in Distt Kangra (HP)(SH:-Repair of pot holes by providing patch work)	499990/-	10000/-	One month
3	Construction of link rod from Baroa to Baah Km 0/000 to 1/345 in Distt Kangra (HP) (SH:-Providing and laying cement concrete pavement road in Km 1/022 to 1/092, 1/210 to 1/260 & 1/320 to 1/360).	499982/-	10000/-	Three months
4	Construction of Thill Kandi road km 0/000 to 2/500 in Distt Kangra (HP) (SH:-Providing and laying cement concrete pavement road in Km 2/00 to 2/350).	495000/-	10000/-	Three months
5	Construction of Thill kandi road Km 0/000 to 2/500 in Distt Kangra (HP) (SH:-Providing and laying cement concrete pavement road in Km 2/350 to 2/500).	495000/-	9900/-	Three months
6	Construction of Govt. Degree College at Jawalamukhi in Distt Kangra (HP) (Deposit work) (SH:-Balance work of Boundary wall).	319249/-	6400/-	Three months

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

Executive Engineer
H.P.P.W.D. Division
Jawalamukhi

HIMSUCHANA AVAM & JAN SAMPARK

(On behalf of Governor of Himachal Pradesh)

No.PW/JWL/TA/Tender/NIT/2022/

685-715

Dated/

23-9-2022

Copy to the following for information and necessary action:-

1. The Principal Secy. (PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (KZ), HPPWD, Dharamshala.
4. The Director, Information & Publications Department, H.P. Shimla
5. The Executive Engineer (IT), Nigam Vihar Shimla 2 for information. He is requested to upload the same on the department website.
6. The Superintending Engineer, 9th Circle, HPPWD, Nurpur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. All the S.E.s/E.E.s under North Zone.
9. The Sub-Divisional Officer(C) Jawalamukhi.
10. The Block Development Office Dehra.
11. All the Assistant Engineer under this Division.
12. The Drawing /Accounts Branch in this office.
13. The Contractors concerned.
14. Notice Board.

Executive Engineer
H.P.P.W.D. Division
Jawalamukhi

Schedule of Quantity

ESTIMATED COST: -Rs. 499990.00
 EARNEST MONEY : -Rs. 10000.00
 TIME LIMIT :- ONE MONTH

NAME OF WORK:- Restoration of rain damages on various roads under Khundian Sub-Division, H.P.W.D., Khundian in Distt Kangra (H.P.).

SUB HEAD: - Repair of pot holes by providing patch work.

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	2 Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and ravelling as per technical specification Clause 1906 as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental.	3 190.00 Square meters	4	5	6 Per square metre	7
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental.	1488.40 Square meters			Per square metre	
TOTAL: -						

Executive Engineer,
 Jawalmukhi Division,
 H.P.W.D., Jawalamukhi.

Schedule of Quantity

ESTIMATED COST: - Rs. 499982.00
 EARNEST MONEY: - Rs. 10000.00
 TIME LIMIT: - THREE MONTHS

NAME OF WORK :- Construction of link road from Baroa to Baah Km 0/000 to 1/345 in Distt. Kangra (H.P.)
SUB HEAD :- Providing and laying cement concrete pavement road in Km 1/022 to 1/092, 1/210 to 1/260 & 1/320 to 1/360

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimeter to forty five millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	38.43 Cubic metres			Per cubic metre	
2	Providing and laying concrete for plain reinforcement concrete in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC Grade (M-20) (M-twenty) nominal mix 1:2:4 (One cement: Two sand: Four graded/crushed stone aggregate) 20mm (Twenty millimetres) thickness as per HPPWD technical specification and as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	77.63 Cubic meters			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 Jawalamukhi Division,
 H.P.P.W.D., Jawalamukhi.

Schedule of Quantity

ESTIMATED COST: - Rs. 495000.00
EARNEST MONEY :- Rs. 9900.00
TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of Thill Kandi road Km 0/000 to 2/500 in Distt. Kangra (H.P.).
SUB HEAD :- Providing and laying cement concrete pavement road in Km 2/200 to 2/350

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing and laying concrete for plain reinforcement concrete in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC Grade (M-20) (Twenty) nominal mix 1:2:4 (One cement: Two sand: Four graded/crushed stone aggregate) 20mm (Twenty millimetres) thickness as per HPPWD technical specification and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	90.00 Cubic meters			Per cubic metre	
TOTAL :-						

Executive Engineer,
Jawalamukhi Division,
H.P.P.W.D., Jawalamukhi.

Schedule of Quantity

ESTIMATED COST :- Rs. 495000.00
EARNEST MONEY :- Rs. 9900.00
TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of Thill Kandi road Km 0/000 to 2/500 in Distt. Kangra (H.P.).
SUB HEAD :- Providing and laying cement concrete pavement road in Km 2/350 to 2/500

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Providing and laying concrete for plain reinforcement concrete in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC Grade (M-20) (M-twenty) nominal mix 1:2:4 (One cement: Two sand: Four graded/crushed stone aggregate) 20mm (Twenty millimetres) thickness as per HPPWD technical specification and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals.	90.00 Cubic meters			Per cubic metre	
TOTAL :-						

Executive Engineer,
Jawalamukhi Division,
H.P.P.W.D., Jawalamukhi.

Schedule of Quantity

ESTIMATED COST :- ₹ 361942.00
 EARNEST MONEY :- ₹ 7250.00
 TIME LIMIT :- ONE MONTH

NAME OF WORK :- Construction of link road from Hardeppur to Mahr road Km 0/000 to 2/200 in Distt. Kangra (H.P.)

SUB-HEAD :- Construction of 5/7 mtrs wide Formation Cutting at RD 0/000 to 0/900

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. Recovery of stone to the tune of 164.80 Cum (One Hundred Sixty Four Point Eighty) cubic metres quantity at the rate of 300/- (Three Hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases.	3 2060.00 Cubic meters	4	5	6 Per cubic metre	7


 Executive Engineer,
 Jawalamukhi Division,
 H.P.P.W.D., Jawalamukhi.

Schedule of Quantity

ESTIMATED COST :- Rs. 319249.00
EARNEST MONEY :- Rs. 6400.00
TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of Govt. Degree Collge at Jawalamukhi in Distt. Kangra (H.P.). (Deposit work).
SUB HEAD :- Balance work of Boundary wall

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead including entire carriage of materials within all leads, lifts and other incidentals.	18.72 Cubic metres			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	3.52 Cubic metres			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (One Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (Forty millimetres) nominal siz as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	11.36 Cubic metres			Per cubic metre	
4	Second class brick masonry using common burnt clay building bricks in super-structure upto all floor level in cement mortar 1:6 (One cement: Six sand) and curing complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	19.84 Cubic metres			Per cubic metre	
5	Providing and laying Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but including the cost of nosing of steps with 40 mm thick with 20 mm nominal size stone aggregate etc. complete and curing complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	8.64 Square metres			Per square metre	

6	15mm (Fifteen millimetre) thick cement plasters in single coat on rough side of brick/concrete/stone walls for interior plastering upto all floor level including arises, internal rounded angles, chamfers and or rounded angles not exceeding 80mm in girth and finished even and smooth with cement mortar 1:6 (One cement : Six sand) above plinth level to floor all level complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge.	227.36 Square metres			Per square metre
7	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc; Hot finished welded type tubes including Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	356.97 Kilo grams			Per kilo gram
8	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer's specification and as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	227.36 Square metres			Per square metre
9	Painting Two or more coats on new work with synthetic enamel paint of approved brand and manufacture to give an even shade :, as per manufacturer's specification and as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	19.35 Square metres			Per square metre
TOTAL :-					


 Executive Engineer,
 Jawahar Mukhi Division,
 H.P.P.W.D., Jawahar Mukhi.