

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.
NOTICE INVITING TENDER**

Sealed item rate tenders are hereby invited on Form No.6 &8 by the undersigned on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, so as to reach in this office on 06-10-2022 upto 11.00 A.M and shall be opened on the same day 11.30 A. M in the presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non- refundable) during the working day before opening upto 2:00 P.M. The earnest money in the shape of National Saving Certificate, FDRs/TDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan must accompany with each applications/tender. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserves the right to reject the any or all tender without assigning any reason.

S.N	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs)	Time	Cost of Form
1	C/O Jaman Ki Ser Harkaghat road Km 0/0 to 9/330 (SH:- P/L interlocking Paver block in Km 2/00 to 2/100) Under MMGPY (Deposit)	413804/-	8500/-	One Month	Rs.350/-
2	C/O Jaman Ki Ser Harkaghat Road Km 0/0 to 9/330 (SH:- P/L interlocking Paver block in Km 1/860 to 1/980) Under MMGPY (Deposit)	496564/-	10000	One Month	Rs.350/-
3	Construction of Boundary Wall around CCI building Village Nal Post office Dhangyar, tehsil Pachhad Distt. Sirmour H.P. (SH:- Providing fencing with barbed wires around the boundary & C/O R/Wall of Adarsh Bal Niketan, Village Nal).	452617/-	9500/-	One Month	Rs.350/-
4	Construction of Boundary Wall around CCI building Village Nal Post office Dhangyar, tehsil Pachhad Distt. Sirmour H.P. (SH:- Providing fencing with barbed wires around the boundary & C/O R/Wall of Adarsh Bal Niketan, Village Nal).	458400/-	9500/-	One Month	Rs.350/-
5	A/R & M/O Oachghat Narag Road Km 0/0 to 14/0 (SH:- P/L interlocking Paver block in Km 0/0 to 0/100)	413804/-	8500/-	One Month	Rs.350/-
6	R/R damages on various roads under Gagal Shikore Sub Division (SH:- Removal of slips)	112840/-	2200/-	One month	Rs. 350/
7	A/R & M/O to various roads under Dilman Sub Division (SH:- Supply of fuel wood for patch work)	65000/-	1300/-	One month.	Rs. 350/
8	A/R & M/O Narag Wasni Dinger road Km 0/0 to 17/600(SH:- Curve improvement at various RD's)	494031/-	10000/-	One month.	Rs. 350/
9	Construction of Link road from Naina Tikker Dagothar via Kenchi Mod 0/0 to 7/0 (SH: - ROFD from Km 0/215 to 0/295).	495256/-	10000/-	One month.	Rs. 350/
10	Construction of Link road from Naina Tikker Dagothar via Kenchi Mod 0/0 to 7/0 (SH: - ROFD from Km 0/495 to 0/580).	494035/-	10000/-	One month.	Rs. 350/
11	C/o Sub Tehsil office building at Narag Tehsil Pachhad Distt Sirmour H.P (SH:- C/O building portion including water supply and sanitary installation work, C/O septic tank, soak pit, rain water harvesting tank site development & C/O B/Wall , C/o approach road Balance work.	111345/-	2200/-	One month.	Rs. 350/
12	C/O Baru Sahib Road km 0/0 to 1/720 (SH: - C/O R/Wall of G.I wire crate at RD 0/945 to 0/960 (SCSP) Deposit.	394232/-	8000/-	One month.	Rs. 350/
13	C/O Dungaghat Baghtan road Km 0/0 to 13/0 (SH:- ROFD in Km 1/795 to 1/805, 3/435, to 3/455, , 8/840, 8/860 & C/O Unlined drain between Km 6/500 to	418277/-	8400/-	One month.	Rs. 350/

	12/500)MNP				
14	C/O Banad Bohal Gagal Shikore road km 0/0 to 5/250 (SH:- C/O G-I wire crate at RD 3/580 to 3/595) Under MMGPY deposit	374557/-	7500/-	One month.	Rs. 350/
15	R/R damages of BBRC road 7/0 to 28/00 (SH:- C/O PCC R/Wall at RD 26/495 to 26/510)	270605/-	5500/-	One month.	Rs. 350/
16	C/O Macher Jabiyana Wasni road Km 0/0 to 7/165 (SH:- P/L of interlocking paver block from RD 0/115 to 0/235)	496564/-	10000/-	One month.	Rs. 350/
17	R/R Damages of Mari Ka Ghat Sultanpur upto Batholi RD 0/00 to 16/00 (SH:- C/O R/Wall at RD 11/105 to 11/115)	165485/-	3500/-	One month.	Rs. 350/
18	C/O Shakhhol to Bagula road Km 0/0 to 1/600 (SH:- C/O G.I wire crate at RD 0/030 to 0/45) MNP	324766/-	6500/-	One month.	Rs. 350/
19	Providing CGI Sheet on veterinary department Cow Shade at Bagthan Tehsil Pachhad Distt. Sirmour H.P (SH; - Ceiling, Painting white washing etc.) Deposit	496775/-	10000/-	One month.	Rs. 350/
20	A/R & M/O Rain shelter at Kangar ghat Sarahan (SH:- Plastering , painting and steel work)	60511/-	1500/-	One month.	Rs. 350/
21	R/R damages on Macher Jabiyana Wasni road km 0/0 to 7/165(SH:- Removal of slips at various RD's)	104650/-	2300/-	One month.	Rs. 350/
22	Construction of 10 Nos Class rooms at GSSS Marighat Distt. Sirmour H.P (SH:- Balance Civil work)	496775/-	10000/-	One month.	Rs. 350/
23	R/R damages on Mari Ka Ghat Kerry Shutiya road km 10/0 to 23/0 & Bagthan Lana Baka road km 0/0 to 6/0 (SH:- Removal of slips at various Rd,s)	113750/-	2500/-	One month.	Rs. 350/
24	R/R damages Ghargaon to Daghter via Ganyar road Km 0/0 to 5/0 (SH:- ROFD in RD 0/225 to 3/00)	198137/-	4000/-	One month.	Rs. 350/
25	R/R damages on Macher Jabiyana Wasni road Km 0/0 to 7/165 (SH:- P/L of interlocking paver block from RD 0/235 to 0/355).	496564/-	10000/-	One month.	Rs. 350/
26	R/R Damages of Banethi Bagthan Rajgarh Chandol road Km 7/00 to 28/00 (SH:- C/O unlined 7/00 to 15/00 drain, removal of slips in between RD km 7/00 to 15/00)	473550/-	9500/-	One month.	Rs. 350/
27	R/R Damages Sarahan Chandigarh road Km 0/0 to 42/00 (SH:- C/O unlined drain 3/00 to 8/00)	184500/-	3800/-	One month.	Rs. 350/
28	R/R Damages of Mari Ka Ghat Kerry Shutiya road km 10/0 to 23/00 (SH: - Removal of slips in various RD's between 10/00 to 23/00).	206173/-	4300/-	One month.	Rs. 350/
29	Providing CGI Sheet on veterinary department Cow Shade at Bagthan Tehsil Pachhad Distt. Sirmour H.P (SH; - Dismantling, Providing doors wire gauge shutters, CGS sheet and plastering etc.) deposit	498392/-	10000/-	One month.	Rs. 350/
30	R/R Damages MND and Sirmouri Mandir Bagthan road Km 22/00 to 39/00 and 0/00 to 10/00 (Removal of slips in various RD's.)	292542/-	6000/-	One month.	Rs. 350/
31	R/R damages on Macher Jabiyana Wasni road Km 0/0 to 7/165 (SH:- C/O PCC R/Wall from RD 0/790 to 0/802.80)	493579/-	9900/-	One month.	Rs. 350/
32	R/R damages Dungaghat Kila Klanch road km 0/0 to 22/00 (SH:- Removal of slips in various RD's between 0/0 to 10/00)	405041/-	8200/-	One month.	Rs. 350/
33	R/R damages Sarahan Navgarh Mandi Khadana road Km 0/0 to 10/705 (SH:- Removal of slips in various RD's)	408681/-	8200/-	One month.	Rs. 350/
34	R/R damages of various road under Sarahan Sub Division (SH:- Removal of slips on Marighat Kerry Shutiya road Km 0/0 to 10/900)	465997/-	9500/-	One month.	Rs. 350/

35	R/R damages of various road under Sarahan Sub Division (SH:- Removal of slips on Bantighat Bhagyanghat road km 0/0 to 4/00 and Bantighat Lana Miun road Km 0/0 to 5/00)	214573/-	4500/-	One month.	Rs. 350/
36	R/R Damages Dungaghat Klia Klanch road Km 0/0 to 22/00 (SH:- Removal of slips in various RD's between 10/00 to 22/00)	373373/-	7500/-	One month.	Rs. 350/
37	R/R Damages on Sarahan Chandigarh road Km 0/0 to 42/00 (SH:- C/O unlined drain 34/00 to 42/00 , removal of slips in between RD km 0/00 to 42/00)	382393/-	7700/-	One month.	Rs. 350/
38	R/R Damages on Banad Bohal gagal Shikore road km 0/0 to 5/250, Kanyon Shila Anji road upto Gagal Shikore km 0/0 to 6/480 Distt Sirmour H.P (SH:- C/O unlined drain at Rd 0/00 to 6/480 at Kanyon Shila Anji road R/Wall between RD 3/405 to 3/420 at Gagal Shikore road).	487905/-	9900/-	One month.	Rs. 350/
39	R/R damages Burshing Mahadev road Km 0/00 to 2/315, Mari Ka Ghat Sultanpur road km 0/00 to 16/00, Sarahan Chadech road km 0/0 to 7/00 (SH:- Removal of slips in various RD's)	243120/-	5000/-	One month.	Rs. 350/
40	R/R Damages of various roads under Sarahan Sub Division (SH:- Removal of slips on Dalag Ghat Shershog road Km 0/0 to 9/00 , Sikken Dinger road km 0/0 to 9/360 and Jehar Mangarh road Km 0/0 to 6/360)	243379/-	5000/-	One month.	Rs. 350/
41	R/R damages Narag Wasni Dinger road 0/00 to 17/600 (SH:- Removal of slips in various RD's)	243379/-	5000/-	One month.	Rs. 350/
42	C/O Banalag Dhamesha road km 0/0 to 8/450 (SH:- C/O R/wall between RD 0/596 to 0/606, 1/510 to 1/525) SCSP Deposit.	431165/-	8800/-	One month.	Rs. 350/
43	C/O Bohal Gagal Shikore road Km 0/00 to 5/00 (SH:- P/L Paver block in Km 0/500 to 0/600) MMGPY Deposit	413804/-	8500/-	Two month	Rs. 350/
44	R/R Damages Narag Wasni Dinger road Km 0/0 to 17/600 (SH:- P/L of interlocking paver block, V-shape drain from RD 14/055 to 14/155)	496856/-	10000/-	Two month	Rs. 350/

CERTIFICATE: - It is certificate that the tenders of above work are exigency/emergent nature and in Public interest.

TERMS & CONDITIONS:-

1. The contractor/bidders must submit their Permanent Income Tax account number /GST number on the tender alongwith copy of the same be attached with the application.
2. The contractor /Firms should attach copy of Registration /renewal with the application.
3. The contractor/bidders should quote his rate both in figures and words the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc., before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender rejected after due date and time will be rejected.
6. The contractor/Firm should be produce the detail of works in hand in HPPWD and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractor who does not have more than two works in hand in any HPPWD circle/Division up to Rs 1.00 crore each.
8. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The officer shall remain valid up to 95 days.
10. The provisions of guidelines issued vide Principal Secretary (PW) to the Govt. of HP Shimla vide notification No PBW (B) A (3) 1/2020 dated Shimla-2 the 22th July 2020 regarding adoption of CPWD works manual 2019 & n other publication of CPWD in HPPWD shall also be applicable.

11. The tender form will not be issued to those contractors whose performance found unsatisfactory.
12. The Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.


Executive Engineer,
Sarahan B&R Division,
HP.PWD, Sarahan.

NO.PW-SRN/Tender/2022-23-

10284-99

Dated:- 28/9/2022

Copy forwarded to the following for information and necessary action to:-

1. The Deputy Commissioner Nahan District Sirmour (H.P).
2. The Superintending Engineer 12th Circle HP.PWD Nahan.
3. The Executive Engineer IT (Cell) Nigam Vihar HP.PWD, Shimla for uploaded of notice inviting Tender on departmental website please.
4. All the Assistant Engineer working under this Division.
5. All the leading contractor working under this division.
6. The notice board.


Executive Engineer,
Sarahan B&R Division,
HP.PWD, Sarahan.

SCHEDULE OF QUANTITY

Name of work:- C/O Jamun ki ser Harkaghat Road km 0/0 to 9/330 (SH:- P/L interlocking Paver block in km 2/00 to 2/100)

Estimated cost:-Rs. 4,13,804/-
Earnest money:- Rs. 8500/-

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per Cubic Metre.			
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter)nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per cubic meter.			
3	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	305.00	Per Square meter.			

Yadav
Executive Engineer
Sarhan Division,
HPWD, Sarhan

SCHEDULE OF QUANTITY

Name of work:- C/O Jamun ki ser Harkaghat Road km 0/0 to 9/330 (SH:- P/L interlocking Paver block in km 1/860 to 1/980)

Estimated cost:-Rs. 4,96,564/-
Earnest money:- Rs. 10000/-
Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.60	Per Cubic Metre.			
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter) nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.60	Per cubic meter.			
3	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments, and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	366.00	Per Square meter.			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Construction of Boundary Wall around CCI Building, Village Nal, Post Office Dhangyar, Tehsil Pachhad, Distt. Sirmaur (H.P.)
(SH: Providing fencing with barbed wires around the boundary & C/O R/Wall of Adarsh Bal Niketan , Village Nal)

Estimated cost:-Rs. 4,52,617/-

Earnest money: - Rs. 9500/-

Time Limit: - One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	76.80	Per Cubic Metre.			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	79.80	Per Cubic Meter.			
3	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	32.000	Each			
4	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be struttred on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc.complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre cost of total length of for separately). Payment to be made per metre cost of total length of barbed wire used.	3300.00	Per Running Metre			


Executive Engineer
Sarhan Division,
HP PWD., Sarhan

SCHEDULE OF QUANTITY

Name of work:- Construction of Boundary Wall around CCI Building, Village Nal, Post Office Dhangyar, Tehsil Pachhad, Distt. Sirmaur (H.P.)
(Sft: Providing fencing with barbed wires around the boundary & C/O R/Wall of Adarsh Bal Niketan, Village Nal)

Estimated cost:-Rs. 4,58,400/-

Earnest money: - Rs. 9500/-

Time Limit: - One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	26.62	Per Cubic Metre.			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	53.85	Per Cubic Metre.			
3	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20 (Twenty millimeter) nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	3.28	Per cubic meter.			
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	13.95	Per Cubic Metre.			
5	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	15.000	Each			
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works (Code 10.25.2)	1550.00	Per kg			

Executive Engineer
Sarhan Division,
HP PWD., Sarhan

SCHEDULE OF QUANTITY

Name of work:- Oachghat Narag Road km 0/0 to 14/0 (SH:- P/L interlocking Paver block in km 0/0 to 0/100)

Estimated cost:-Rs. 4,13,804/-
Earnest money:- Rs. 8500/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per Cubic Metre.			
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter) nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per cubic meter.			
3	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	305.00	Per Square meter.			


Executive Engineer,
Sarhan Division,
HP PWD., Sarhan

SCHEDULE OF QUANTITY

Name of work:- R/R damages on various roads under Dilman Sub -Division (SH:- Removal of slips in various RD's)

Estimated cost:-Rs. 1,12,840/-

Earnest money:- Rs. 2500/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2 Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	3 1240.00	4 Per Cubic Metre.	5	6	7

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O to various roads under Dilman Sub-Division (SH:- Supply of feul wood for patch work)

Estimated cost:-Rs. 65000/-

Earnest money:- Rs. 1,300/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2 Supply and stacking of dry mixed hard fuel wood of small size and stacked in proper stacks of proper size as per PWD specification and as per the direction of engineer in charge including carriage of material in all leads and lift including all incidental charges.	3 130.00	4 Quintal	5 5	6 6	7 7


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Narag Wasni Dinger raod km 0/0 to 17/600 (SH:- Curve improvement at various RD'S)

Estimated cost:-Rs. 494031/-

*Earnest money:- Rs. 10,000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2 Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 297.84 cum (two hundred nienty seven point eighty four) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	3 2215.06	4 Per cubic metre.	5	6	7


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Construction of Link road from Naina Tikker Dagother Via Kenchi More 0/0 to 7/0 (SH:- ROFD from km 0/215 to 0/295)

Estimated cost:-Rs. 4,95,256/-

Earnest money:- Rs. 10,000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2 Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 218.30 cum (Two hundred eighteen and paise thirty) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	3 1523.02	4 Per cubic metre.	5 5	6 6	7 7

Executive Engineer
Saraha Division,
H.P.P.W.D., Saraha

SCHEDULE OF QUANTITY

Name of work:- Construction of Link road from Naina Tikker Dagother Via Kenchi More 0/0 to 7/0 (SH:- ROFD from km 0/495 to 0/580)

Estimated cost:-Rs. 4,94,035/-

Earnest money:- Rs. 10,000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 212.46 cum (two hundred twelve point forty six) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1541.45	Per cubic metre.			

Exe
Executive Engineer
Sarhan Division,
HP.PWD., Sarhan

SCHEDULE OF QUANTITY

Name of work:- C/O of Sub-Tehsil office building at Narag Tehsil Pachhad Distt. Sirmour H.P (SH:- C/O building portion including water supply and sanitary installation work , C/O spetic tank, Soak pit, rain water harvesting tank site devlopement & C/O B/Wall C/O approach road Balance work)

Estimated cost:-Rs. 1,11,345/-

Earnest money:- Rs. 2500/-

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Providing and fixing anodized aluminum grill (anodized transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/ pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodized aluminum standard section around the opening, all complete as per requirement and direction of Engineering-charge. (Only weight of grill to be measured for payment).	119.51	Per Cubic Metre.			
2	Providing and laying Plain Cement Concrete 1:3:6(one cement: three sand: six graded hard stone aggregate 20mm(twenty) millimeter)nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.57	Per Cubic Meter.			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Baru Mangarh Road km 0/0 to 1/720 (SH:- C/O R/Wall of G.I wire crate at RD 0/930 to 0/960)

- Estimated cost:-Rs. 3,94,232/-
Earnest money:- Rs. 8000/-
Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	33.00	Per Cubic Metre.			7
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	121.88	Per Cubic Metre.			
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	35.10	Per Cubic Metre.			
4	Excavating supplying and filling of laocal earth (Including royalty) by mechanical transport upto a lead of 5 km also including ramming and watering of the earth in layhers not exceeding 20 cm in trenches 1 plinth sides of foundation etc complete.	55.50	Per Cubic Metre.			

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

DRAFT SCHEDULE OF QUANTITY

Estimated 418277

Name of work:- C/O Dungaagaht bagthan road km 0/0 to 13/0 (SH:- ROFD in km 1/795 to 1/805, 3/435 to 3/455, 8/840 to 8/860 & C/O Unlined drain between km 6/500 to 12/500)MNP

Earnest money: - Rs. 10000/-

Time Limit: - Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2 Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in -Charge for smooth riding. The recovery for stones, whether useful or not, for 14.09 cum (one hundred fourteen and paise zero nine) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	3 1140.91	4 Per Running Metre	5	6	7
2	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307.	6000.00	Per square metre			

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Banad Bohal Gagal Shikore road km 0/0 to 5/250 (SH:- C/O G.I wire crate at RD 3/580 to 3/595)MMGPY Deposit

Estimated cost:-Rs. 3,74,557/-

Earnest money:- Rs. 7500/-

Time Limit:- Two Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	47.81	Per Cubic Metre.			
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	117.19	Per Cubic Metre.			
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	42.97	Per Cubic Metre.			

Executive Engineer
Sarahan Division,
HP PWD., Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages of BBRC road 7/0 to 28/00(SH:- C/O PCC R/Wall at 26/495 TO 26/510)

Estimated cost:-Rs.2,70,605/-

Earnest money: - Rs. 5500/-

Time Limit: - one Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2 Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	3 12.96	4 Per Cubic Meter.	5	6	7
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	53.70	Per Cubic Meter.			
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	26.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	10.50	Per Cubic Meter.			

Executive Engineer
Sarhan Division,
HP PWD.. Sarhan

SCHEDULE OF QUANTITY

Name of work:- C/O Macher Jabiyana Wasni road km 0/0 to 9/0 (SH:- P/L of interlocking paver block from RD 0/115 to 0/235)

Estimated cost:-Rs. 4,96,564/-

Earnest money:- Rs. 10,000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	P	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.60	Per Cubic Metre.			
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter)nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.60	Per Cubic Metre.			
4	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments, and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	366.00	Per Square metre			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages of Mari Ka Ghat Sultanpur upto Batholi RD 0/00 to 16/00 (SH:- C/O R/Wall at RD 11/105 to 11/115)

Estimated cost:-Rs.1,65,485/-

Earnest money:- Rs. 3500/-

Time Limit:- one Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	12.90	Per Cubic Meter.			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	31.77	Per Cubic Meter.			
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	23.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in-Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	9.35	Per Cubic Meter.			


Executive Engineer
 Saranah Division,
 UP PWD., Saranah

SCHEDULE OF QUANTITY

Name of work:- C/O Shakol to Bagula road 0/0 to 1/600(SH:-C/O G.I. wire crate at RD 0/030 to 0/45)

Estimated cost:-Rs. 3,24,766/-
Earnest money:- Rs. 6500/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	P	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	41.44	Per cum			
2	Providing and laying of boulder apron laid in wire creates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification clause 1301 as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	101.55	Per cum			
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material.as per drawing and HP PWD technical specifications in carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	37.50	Per cum			

Executive Engineer
Sarhan Division,
HP PWD., Sarhan

SCHEDULE OF QUANTITY

Name of work:- Providing CGI Sheet on veterinary department Cow Shade at BagthanTeshil pachhad Distt. Sirmour H.P
(SH:-ceiling, Pantingand white washing etc)deposi

Sirmour H.P

Estimated cost:-Rs 4,96,775/-

Sr. No	Description Items of work	Qty.	Unit	Rate	Earnest money: - Rs. 10,000 Time Limit:-three month	
					in figures.	Amount
1	2	3	4	5	6	7
1	Providing and fixing wooden plankceiling with tongued and groovedjointing and wood screws/framework and cover fillets to be measured and paid for separately	69.00	Per square metre			7
2	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floorfive level, excluding cost of centering, shuttering, finishing and reinforcement :1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size)	1.04	Per cubic metre			
3	Providing and laying cement concrete 1:4:8 (1 cement:4 sand:8 graded stone aggregate 40mm nominal size) and curing complete excluding cost of form work in Foundation and plinth.	18.52	Per cubic metre			
4	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry,but excluding the cost of nosing of steps etc. complete.40 mm thick with 20 mm nominal size stone aggregate	243.75	Per square metre			
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 40 mm nominal size)	0.90	Per cubic metre			
6	Applying priming coat:With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood)including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	88.42	Per square metre			
7	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture	88.42	Per square metre			

8	Painting one coat (excluding priming coat) on previously painted wood and wood based surfaces with ready mixed paint brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping	127.56	Per square metre			
9	White washing with lime on decorated wall surfaces (one coat) to give an even shade including thoroughly brooming the surface to remove all dirt, dust, mortar drops and loose scale of lime wash and other foreign matter	435.56	Per square metre			
10	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	168.00	Per Kilo gram			
	Total					


 Executive Engineer
 Sarahan Division,
 HP.PWD., Sarahan

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Rainshelter at Kanger ghat Sarahan (SH:- Plastering, Painting and steel work)

Estimated cost:-Rs 60,511/-

Earnest money:- Rs.1500

Time Limit:-one month

Sr. No	Description Items of work	Qty.	Unit	Rate	Amount
				in figures.	in words
1	2	3	4	5	6
1	15mm cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto all floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 30cm in girth and finished even and sand opared smooth including carriage of materials within allleads and lifts..	42.92	Per square metre		7
2	15mm cement plaster in single coat on the fair side of brick/concrete/stone walls for interior plastering upto all floor level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 30cm in girth and finished even and sand opared smooth including carriage of materials within allleads and lifts..	50.48	Per square metre		
3	Providing form work with steel plates 3.15mm (three point fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etc. with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling and removal of the same for insitu reinforcement and plain concrete work In beams cantilevers girders and lintels side and soffit of beams ,beam haunchings, cantilevers, bressumers	5.94	Per square metre		
4	Steel reinforcement for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete upto plinth level.Mild steel and Medium Tensile steel barsas per direction of Engineer-in charge. (Note:- Butt hinges and necessary screws shall be paid separately) Second class teak wood	40.132	kg		
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)in foundation, footings, bases of columns and the like and mass concrete	0.36	Per kilogram		

6	Brick work with common burnt clay machine non moulded perforated bricks in :Super-structure above plinth level upto floor two level (Second Class Bricks).as per direction of Engineer-in charge. (Note:- Butt hinges and necessary screws shall be paid separately) Second class teak wood	0.87	Per cubic metre			
7	Providing and applying plaster of Paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	93.40	Per square metre			
8	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade two or more coats on new work as per direction of Engineer-in charge. (Note:- Butt hinges and necessary screws shall be paid separately) Second class teak wood	93.4	Per square metre			


 Executive Engineer
 Saranah Division,
 HP PWD., Saranah

SCHEDULE OF QUANTITY

Name of work:- R/R damages on Macher Jabiyana Wasni road km 0/0 to 7/165(SH):- Removal of slips at various RD's

Estimated cost:-Rs. 1,04,650/-

Earnest money:- Rs 2300/-

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	1150.00	Per Cubic Metre			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Construction 10 Nos class rooms at GSSS marighat Distt. Sirmour H.P (SH:- Balnce Civil work)

Estimated cost:-Rs 4,96,775/-

Earnest money:- Rs. 10,000

Time Limit:-three month

Sr. No	Description Items of work	Qty.	Unit	Rate in figures. in words	Amount
1	2	3	4	5	6
1	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters; 35 mm thick including ISI marked Stainless Steel butt hinges with necessary	42.623	Per square metre		7
2	Providing and Fixing M.S. channels door, windows frames manufactured from M.S section ISMC 75x40mm & ms Flat 75x5mm as per direction of Engineer-in-Charge and drawing including hinges jambs bead and if required angle threshold M.S angle 50x25mm welded or rigidly fixed by mechanical means with split end tails to each observer as specified and applying a coat of approved steel primer after pretreatment of surface as directed by the Engineer-in-Charge including carriage of material with all leads and lift.	198.10	Per Running Metre		
3	Providing and fixing angle iron door, window, clerestorey window frames manufactured from steel iron section of 40X40x6 mm thickness including hinges jamb, lock jambs, bead and if required angle threshold of mild steel angle of section 50x25 mm welded or rigidly fixed by mechanical means;lugs with split and tails to each jamb including steel butt hinges 2.5mm thick with provision for locking arrangement and shock absorber as specified and applying a coat of approved steel primer after pretreatment of the surface as directed by Engineer-in-charge	355.62	Per Running Metre		
4	Providing & fixing molded hand rail of M.S. hollow pipe 50mm dia welded in straight length over M.S. flat at top of vertical balusters including one coat of red oxide priming coat complete (M.S.flat & balusters of railing shall be measured & paid separately).	79.55	Per Running Metre		

5	Providing and fixing steel glazed doors window and ventilators of standard rolled steel sections joints mitred and welded with 16 X3.15 mm lugs 10 cm long embedded in cement concrete blocks 15 cm X 10 cm X10cm size of 1:3:6 20mm nominal size or with wooden plugs and screws or rawl plug and screws or with fixing clips or with bolts and nuts as required and iron fittings, including providing and fixing of glass panes with glazing clips and special metal sesh putty of approved make complete including applying a priming coat of red lead paint.	31.59	Per square metre			


 Executive Engineer
 Sarahan Division,
 HP.PWD., Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R damages on Mari Ka Ghat Keri Shutiya road km 10/0 to 23/0 & Bagthan Lana Baka road km 0/0 to 6/0 (SH:- Removal of slips at various roads)

Estimated cost:-Rs. 1,13,750/-

Earnest money:- Rs 2500/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	1250.00	Per Cubic Metre			


Executive Engineer
Sarhan Division
HP, PWD, Sarhan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages Chargon to Degothar via Ganyana Road km 0/0 to 5/0(SH:- ROFD in RD 0/225 to 3/00)

Estimated cost:-Rs.1,98,137/-

Earnest money:- Rs. 4000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road, clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in -Charge for smooth riding. The recovery for stones, whether useful or not, for 69.75 (Sixty nine point seventy five) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1231.05	Per Cubic Meter.			

Executive Engineer
Sarhan Division
HP, PWD, Sarhan

Estimated cost:-Rs. 4,96,564/-
Earnest money:- Rs. 10,000/-
Time Limit:- One Month.

Name of work:- R/R Damages Macher Jabiyana Wasni road km 0/0 to 9/0 (SH:- P/L of interlocking paver block from RD 0/235 to 0/355)

SCHEDULE OF QUANTITY

Sr. No	Description Items of work	Qty.	P	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.60	Per Cubic Metre.			
2	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter)nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.60	Per Cubic Metre.			
4	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	366.00	Per Square metre			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages of Banethi Bagthan Rajgarh Chandol road km 7/00 to 28/00(SH:- C/O unlined 7/00 to 15/00 Darin Removal of slip in between Rd km 7/00 to 15/00)

Estimated cost:-Rs.4,73,550/-

Earnest money:- Rs. 9500/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	7000.00	Per Running Metre			
2	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	2050.00	Per Cubic Metre			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages Sarahan Chandigarh road kmm 0/0 to 42/00(SH:- C/O unlined drain 3/00 to 8/00)

Estimated cost:-Rs.1,84,500/-

Earnest money:- Rs. 3800/-

Time Limit:- One Month.

Sr. No.	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines. grades, levels and dimensions as per approved design and Technical Specification Clause 307. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	4500.00	Per Running Metre	.		


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages on Mari Ka Ghat Karry Shutiya Road km 10/00 to 23/00 (SH:- Removal of slips in various Rds Between 10/00 to 23/00

Estimated cost:-Rs. 2,06,173/-

Earnest money:- Rs. 4300/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	2265.64	Per Cubic Metre			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- Providing CGI Sheet on veterinary department Cow Shade at BagthanTeshil pachhad Distt. Sirmour H.P
(SH:-Distmentling , Providing doors wire gauge shutters ,CGS sheet and plasering etc)deposit

12/14

Estimated cost:-Rs 4,98,392/-

Earnest money:- Rs. 10,000

Time Limit:-three month

Sr. No	Description Items of work	Qty.	Unit	Rate in figures.	in words	Amount
1	2	3	4	5	6	7
1	Dismantling roofing including ridges, hips, valleys, gutters etc.stacking the serviceable materialsand disposal of un-serviceablematerials within 20 Metres lead.	167.86	Per square metre			
2	Dismantling roofing including ridges, hips, valleys, gutters etc.stacking the serviceable materialsand disposal of un-serviceablematerials within 20 Metres lead.	69.00	Per square metre			
3	Demolition of brick work above G.L. upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within 20 Metres lead.	2.560	Per cubic metre			
4	Providing wood work in frames of doors, windows,clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).	0.056	Per cubic metre			
5	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding paneling which will be paid for separately, all complete as per direction of Engineer-in charge. (Note:- Butt hinges and necessary screws shall be paid separately) Second class teak wood	7.24	Per square metre			
6	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of die 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws :35 mm thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size Second class teak wood	12.18	Per square metre			
7	Providing wood work intrusses,purlins,rafters,posts,post plates,wall plates and the like wrought framed,hoisted and fixed in position.	1.63	Per cubic metre			

8	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges..	8.23	Per cubic metre		
9	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 1.00 mm thick with zinc coating not less than 275 gm/m ² 0.63 mm thick with zinc coating not less than 275 gm/ m ²	167.86	Per square metre		
10	15 (fifteen) millimeters thick cement plaster in single coat on the rough of brick / concrete/stone walls for interior plastering up to all heights including arises. Internal rounded angles, chamfers and rounded angles not exceeding 80 (eighty) millimeters in grith and finished even and smooth in cement mortar 1:6 (one cement : six sand) as per direction of Engineer-in charge and H.P. PWD. Specification, including carriage of all labour, equipment's and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	135	Per square metre		
	Total				


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Estimated cost:-Rs.2,92,542/-

Name of work:- R/R Damages MND and Sirmouri Mandir Bagthan road km 22/00 to 39/00 and 0/00 to 10/00 (Removal of slips in various Rds)

Earnest money: - Rs. 6000/-

Time Limit: - One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	3214.75	Per Cubic Metre			

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages Macher Jabiyaana Wasni road km 0/0 to 9/0 (SH:- C/O PCC R/Wall from RD 0/790 to 0/802.80)

Estimated cost:-Rs.4,93,579/-

Earnest money:- Rs. 9900/-

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	34.94	Per Cubic Meter.			
2	Providing and laying cement concrete 1:6:12 {One cement: Six sand: twelve graded crushed stone aggregate 40(Forty) millimeter nominal size} in open foundation and curing complete excluding cost of form work complete as per drawing and technical specification clause 802,803,1202 and 1203 including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge	4.22	Per Cubic Meter.			
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	93.31	Per Cubic Meter.			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven)),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	24.00	Each			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	32.26	Per Cubic Meter.			


Executive Engineer
 Sarahan Division,
 H.P.P.W.D., Sarahan

SCHEDULE OF QUANTITY

Estimated cost:- Rs.4,05,041/-

Name of work:- R/R Damages Dungaghat Kila Klanch road km 0/0 to 22/00 (SH:- Removal of slips in various Rds between 0/0 to 10/00)

Earnest money:- Rs. 8200/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	4451.00	Per Cubic Metre			


Executive Engineer
Sarhan Division
HP, PWD, Sarhan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages Sarahan Navgarh Mandi Khadana road km 0/00 to 10/705(Removal of slips in various Rds).

Estimated cost:-Rs.4,08,681/-

Earnest money:- Rs. 8200/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	4491.00	Per Cubic Metre			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Estimated cost:-Rs. 4,65,997/-
Earnest money:- Rs. 9500/-
Time Limit:- One Month.

Name of work:- R/R Damages of various road under Sarahan Sub- Division (SH):- Removal of slips on Marighat Kerry Shutiya road km

610 to 101900

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	5120.85	Per Cubic Metre			

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages of various road under Sarahan Sub- Division (SH:- Removal of slips on Bantighat Bhagyanghat road km 0/0 to 4/00 and Bhagyanghat Lana Miun road km 0/0 to 5/00

Estimated cost:-Rs. 2,14,573/-

Earnest money:- Rs. 4500/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	2357.95	Per Cubic Metre			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages Dungaghat Kila Klanch road km 0/00 to 22/0(SH:- Removal of slips in various Rds Between 10/00 to 22/00)

Estimated cost:-Rs.3,73,373/-

Earnest money:- Rs. 7500/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	4103.00	Per Cubic Metre			


Executive Engineer
Sarhan Division
HP, PWD, Sarhan

SCHEDULE OF QUANTITY

Estimated cost:-Rs.3,82,393/-

Name of work:- R/R Damages on Sarahan Chandigharh road km 0/0 to 42/00 (SH:- C/O unlined drain 34/00 to 42/00, Removal of slip in between Rd km 0/00 to 42/00)

Earnest money:- Rs. 7800/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	7500.00	Per Running Metre			
2	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	823.00	Per Cubic Metre			

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Estimated cost:-Rs.4,87,905/-

Name of work:- R/R Damages on Banad Bohal Gagal Shikore road 0/0 to 5/250, Kanyon Shila Anji road upto Gagal Shikore km 0/0 to 6/480 Distt. Sirmour HP. (SH:- C/O unlined Drain at Rd 0/00 to 6/480 at Kanyo Shila Anji road, R/wall between Rd 3/405 to 3/420 at Gagal Shikore road)

Earnest money:- Rs. 9900/-

Time Limit:- Three Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	5300.00	Per Running Metre			
2	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	12.96	Per Cubic Meter.			
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	53.70	Per Cubic Meter.			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	26.00	Each			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	10.50	Per Cubic Meter.			

Executive Engineer
Sarhan Division,
HP PWD., Sarhan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages Burshing Mahadev Road km 0/00 to 2/315, Mari Ka Ghat Sultanpur road km 0/00 to 16/00, Sarahan Chadech road km 0/0 to 7/00(SH:- Removal of Slips in various Rds)

Estimated cost:-Rs. 2,43,120/-

Earnest money:- Rs. 5000/-

Time Limit:- One Month.

Sr. • No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	2671.65	Per Cubic Metre			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages of various roads under Sarahan Sub-Division (SH:- Removal of slips on Dalagka ghat Sershog road km 0/0 to 9/00, Sikken Dinger road km 0/0 to 9/360 and Jehar Mangarh road km 0/0 to 6/360)

Estimated cost:-Rs.2,43,379/-

Earnest money:- Rs. 5000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	2674.49	Per Cubic Metre			


Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:-R/R Damages Narag Wasni Dinger Road 0/00 to 17/600(SH:- Removal of slips in Various RDs)

Estimated cost:-Rs.2,43,379/-

Earnest money:- Rs. 5000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	2674.49	Per Cubic Metre			

Executive Engineer
Sarahan Division
HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Banalag Dhamesha road km 0/0 to 8/450(SH:- C/O R/Wall between RD 0/596 to 0/606, 1/510 to 1/525)

Estimated cost:-Rs.4,31,165/-

Earnest money: - Rs. 8800/-

Time Limit: - One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	48.29	Per Cubic Meter.			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	86.11	Per Cubic Meter.			
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven) ,including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge	33.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	9.05	Per Cubic Meter.			


 Engineer-in-Charge
 Sarathi Division,
 H.P.P.W.D., Sarathi

Estimated cost:-Rs. 4,13,804/-

SCHEDULE OF QUANTITY

Name of work:- C/O Banad Bohal Gagal Shikore road km 0/00 to 5/00(SH:- P/L Paver block in km 0/500 to 0/600) MMGPY Deposit

Earnest money:- Rs.8500/-

Time Limit:- Two Month.

Sr.	Description Items of work	Qty.	Unit	Rate		Amount
				5	6	
1	2 Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	3 8.00	4 Per Cubic Meter.			7
3	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter)nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per Cubic Metre.			
4	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	305.00	Per Square metre			
				Total		0.00


 Executive Engineer
 Sarahan Division
 HP, PWD, Sarahan

SCHEDULE OF QUANTITY

Name of work:- R/R Damages Narag Wasni Dinger road 0/00 to 17/600(SH:- P/L of interlocking paver block, v-shape drain from RD 14/055 TO 14/155)

Estimated cost:-Rs. 4,96,856/-

Earnest money:- Rs.10,000/-

Time Limit:- Two Month.

Sr.	Description Items of work	Qty.	Unit	Rate		Amount
				5	6	
1	2 Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	3 19.12	4 Per Cubic Meter.			7
2	Providing and laying Plain Cement Concrete 1:3:6(one cement: three sand: six graded hard stone aggregate 20mm(twenty) millimeter)nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per Cubic Meter.			
3	Providing and laying Concrete PCC grade M-20 grade 1:2:4 (one cement: Two sand: Four graded hard stone aggregate) M-20(Twenty millimeter)nominal size for plain/reinforced concrete in open foundation complete as per drawing and HP PWD technical specifications clause 802, 803, 1202 & 1203 i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	8.00	Per Cubic Metre.			
4	Providing and laying of interlocking concrete block pavement having thickness 80mm as per drawing and technical specification clause 1504.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	335.50	Per Square metre			

Executive Engineer
Sarahan Division
HP, PWD, Sarahan