

Himachal Pradesh  
Public Works Department

Registered

NO:- PW-DKD-N.I.T/2022-23

16 69

Dated:-

3/10/2022

To

✓ The Executive Engineer (IT Cell)  
Nigam Vihar Shimla.

Subject:-


Publication of Tender notice.

Jai Haind

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. Of Himachal Pradesh letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16<sup>th</sup>. July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender & Sechedule of Quantity.

  
Executive Engineer,  
B&R Division HP.PWD,  
Dodra Kwar.



**HIMACHAL PRADESH**  
**PUBLIC WORKS DEPARTMENT**  
**NOTICE INVITING TENDERS**

Sealed item rate tenders on form No. 6 & 8 are hereby invited by the Executive Engineer B&R Division HP.PWD, Dodra kwar for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HP.PWD, so as to reach in the office as per time Schedule given below:-

1. Date of receipt of application for tenders forms:-
2. Dated of Issue /sale of tender forms:-
3. Date of receipt of tender:-
4. Date of opening of tender:-

11.10.2022

11.10.2022

12.10.2022 up to 10:30 AM

12.10.2022 at 11 AM

Sr. No.	Name of Work	Estimated Cost	EMD (Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1.	R/R Damage to RCD road km 0/00 to 92/695 ( SH:- Hiring of JCB for removal of slip/drain &, dressing of road surface km 21/00 to 51/00)	2,99,088/-	6000/-	350/-	Two months	Calss "C&D"
2.	A/R & M/O Various road under Larot Sub- Division. ( SH:- Hiring of JCB for removal of slip/drain &, dressing of road surface)	4,72,752/-	9500/-	350/-	Two months	Calss "C&D"
3.	R/R Damages to RCD Road Km. 0/00 to 92/695 ( SH:- Hiring of JCB for removal of slip/drain &, dressing of road surface Km. 51/00 to 71/750.	4,94,460/-	9500/-	350/-	Two months	Calss "C&D"
4.	R/R Damage to RCD road km 0/00 to 92/695 ( SH:- Hiring of JCB for removal of slip/drain &, dressing of road surface km 71/750 to 92/695)	2,99,088/-	6000/-	350/-	Two months	Calss "C&D"
5.	R/R Damage to RCD road km 0/00 to 92/695 ( SH:- C/O R/wall at Rd. 24/420 to 24/427.50.	1,50,626/-	3013/-	350/-	Two months	Calss "C&D"
6.	R/R Link road Helipad to Sharidhar road Km. 0/00 to 3/00.(SH:- C/O B/wqall in wire crate at RD. 0/510 to 0/530 & 0/920 to 0/940)	4,11,978/-	8240/-	350/-	Two months	Calss "C&D"
7.	C/O Link road Bakora to Gharatkhad Dogri Rajpat Jarkot road Km. 0/00 to 3/00. (SH:- C/O B/wall in R/R Masonary at Rd. 0/540 to 0/564.	4,61,735/-	9235/-	350/-	Two months	Calss "C&D"
8.	C/O Link road Bakora to Gharatkhad Dogri Rajpat Jarkot road Km. 0/00 to 3/00. (SH:- C/o B/wall in R/R Masonary at RD. 0/565 to 0/580.	2,88,584/-	5772/-	350/-	Two months	Calss "C&D"
9.	R/R Damages to link road village Kiterwari Km.0/00 to 2/900. (SH:- C/O R/wall in R/R Masonary at Rd. 2/700 to 2/721.	4,74,092/-	9482/-	350/-	Two months	Calss "C&D"
10.	R/R Damages to RCD road Km. 0/00 to 92/695.(SH:- P/L Kharanja stone soling at various Rd. 31/00 to 40/00.	4,96,206/-	9925/-	350/-	Two Months	Class "C&D"
11.	R/R Damages to Link road village Gadsari to Kharshali Km. 0/00 to 4/500.(SH:- Hiring of JCB for removal of slips & maintenance of road surface Km. 0/00 to 4/500).	4,94,460/-	9890/-	350/-	Two Months	Class "C&D"
12.	R/R Damage to RCD road km 0/00 to 92/695 ( SH:- Hiring of JCB for removal of slip/drain &, dressing of road surface km 21/00 to 51/00)	4,94,460/-	9890/-	350/-	Two months	Calss "C&D"
13.	R/R Damages to Various road under Kwar Sub-Division.(SH:- Hiring of JCB for removal of slips & Maintenance of road surface.	4,94,460/-	9890/-	350/-	Two months	Calss "C&D"
14.	R/R Damages to Various road under Kwar Sub-Division.(SH:- Hiring of JCB for removal of slips & Maintenance of road surface.	4,94,460/-	9890/-	350/-	Two months	Calss "C&D"
15.	R/R Damages to RCD road Km. 0/00 to 92/695.(SH:- Hiring of JCB for removal of slips & Maintenance of road surface Km.31/00 to 51/00.).	4,94,460/-	9890/-	350/-	Two months	Calss "C&D"




16.	R/R Damages Link road to Village Jiskoon 0/00 to 8/00. (SH:- Hiring of JCB removal of slips maintenance of road and dressing of road surface Km. 0/00 to 7/00.	4,94,460/-	9890	350/-	Two months	Calss "C&D"
17.	R/ R Damages to Link road village Jiskoon Km. 0/00 to 8/00 (SH:- Hiring of Tipper for carriage of muck 0/00 to 4/300.	4,86,500/-	9800/-	350/-	Two months	Calss "C&D"
18.	C/O Link road Khoptwari to Jarkot Km. 0/00 to 1/00. (SH:- Providing Kharanja stone soling at RD. 0/00 to 0/260.	4,96,375/-	9928	350/-	Two months	Calss "C&D"
19.	C/O Link road Khoptwari to Jarkot Km. 0/00 to 1/00. (SH:- Providing Kharanja stone soling at RD. 0/260 to 0/520	4,96,375/-	9928	350/-	Two months	Calss "C&D"
20.	R/R Damages to Link road to Village Kiterwari Km. 0/00 to 2/900. (C/O B/wall at RD. 2/775 to 2/792.	4,11,800/-	8236/-	350/-	Two months	Calss "C&D"
21.	R/R Damages to Link road to Village Jiskoon Km. 0/00 to 8/00 . C/O B/wall in wire crate at RD. 5/135 to 5/165.	4,62,310/-	9246/-	350/-	Two months	Calss "C&D"
22.	R/R Damages to RCD Road Km. 0/00 to 92/695. (SH:- C/O R/wall in PCC 1:3:6 at RD. 24/620 to 24/629.	4,61,863/-	9237/-	350/-	Two months	Calss "C&D"
23.	R/R Damages to RCD Road Km. 0/00 to 92/695. (SH:- C/O R/wall in PCC 1:3:6 at RD. 27/280, to 27/295.	2,64,915/-	5298/-	350/-	Two months	Calss "C&D"
24.	R/R Damages to RCD Road Km. 0/00 to 92/695. (SH:- C/O R/wall in PCC 1:3:6 at RD. 24/630 to 24/639.40.	4,82,563/-	9651-	350/-	Two months	Calss "C&D"
25	R/R Damages to RCD Road Km. 0/00 to 92/695. (SH:- Providing and laying Kharanja stone soling at various RD. 40/00 to 51/00.	4,96,537/-	9931-	350/-	Two months	Calss "C&D"

**Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.**

**TERMS AND CONDITIONS:-**

1. The Earnest money for the above works should be submitted with the application for the application for the purchase of the tender-documents.
2. The Contractors should quoted the rates of the items in the tenders both in figures and words.
3. Income tax & G.S.T. No. Latest clearance certificate.
4. The contractor/firms shall accompany his enlistment/renewal & EPF submit before the award of tender.
5. The Contractors should apply for two works only at a time for tenders.
6. Work should be completed by the contractor within stipulated period.
7. The Executive Engineer reserves the right to accept/rejected any tender/application or all tenders without assigning any reason.

  
Executive Engineer  
B&R Division HP.PWD,  
Dodra Kwar

NO:- PW-DKD-CB-Tender/2022-23- 1670-79  
Copy forwarded for information and wide publicity to:-

Dated:- 3/10/2022

1. The Chief Engineer (S) HPPWD Shimla-2
2. The S.E 14<sup>th</sup> Circle HPPWD Rohru
3. All the EE's under 14<sup>th</sup> Circle HPPWD Rohru
4. All the A.E's working under this Division (B&R)
5. The Sub Divisional Magistrate Dodra Kwar
6. The BDO Dodra Kwar.
7. The Naib tehsildhar Dodra Kwar
8. A/B and D/B in this office
9. Notice Board

  
Executive Engineer  
B&R Division HP.PWD,  
Dodra Kwar



JOB NO 1

**SCHEDULE OF QUANTITY**


Estimate Cost 299088

Earnest Money 6000


Time Two Month

Name of Work :- R/R Damage to RCD road km 0/00 to 92/695 ( Sh:- Hiring of JCB removal of slips maintenance of road and dressing of road surface km 21/00 to 51/00 )

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	248.00			Per Hour	
	<b>Total</b>					

  
 Executive Engineer,  
 B&R Division HPPWD,  
 Dodra Kwar

SCHEDULE OF QUANTITY						JOB NO 2	
						Estimate Cost	472752
						Earnest Money	9500
						Time	Two Month
Name of Work :- A/R & M/O Various road under Larot Sub Division ( SH:- Hiring of JCB removal of slips maintenance of road and dressing of road surface)							
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount	
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-in-charge including all leads and lifts.	392.00			Per Hour		
Total							



Executive Engineer,  
B&R Division HPPWD,  
Dodra Kwar

# **SCHEDULE OF QUANTITY**

**JOB NO 3**


**Name of Work :- R/R Damage to RCD road km 0/00 to 92/695 ( Sh:- Hiring of JCB removal of slips maintenance of road and dressing of road surface km 51/00 to 71/760)**

Estimate Cost 494460

Earnest Money 9500

Time Two Month

Sr.No.	Sub-Head and Item of work	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineers in charge including all leads and lifts.	410.00			Per Hour	
<b>Total</b>						

  
 Executive Engineer,  
 B&R Division HPPWD,  
 Doda Kavar


**SCHEDULE OF QUANTITY**

**JOB NO 4**

Estimate Cost	299088
Earnest Money	6000
Time	Two Month

Name of Work :- R/R Damage to RCD road km 0/00 to 92/695 ( Sh:- Hiring of JCB removal of slips maintenance of road and dressing of road surface km 71/750 to 92/695 )

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	248.00			Per Hour	
	<b>Total</b>					


  
 Executive Engineer,  
 B&R Division HPPWD,  
 Dodra Kwar



Job No 5

Job No 5


Name of Work :- R/R Damage to RCD road km 0/00 to 92/695				Schedule of Qty		ESTIMATED COST		150626
SH:- C/o R/wall at RD 24/420 to 24/427.50						EARNEST MONEY		3013
Sr. No						TIME LIMIT:		2 Months
Description of items.				Qty	Unit	Rate	In Words	Amount.
1	2	3	4	5	6	7		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	4.88	cum					
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	10.13	cum					
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:200 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	46.88	cum					
Total								

  
 Executive Engineer  
 B&R Division HPPWD  
 Doda Kaur




Job No 6

Schedule of Qty						
Name of Work :- R/R Damage on helipad to Sharidhar road km 0/00 to 3/00				ESTIMATED COST		411978
SH:- C/o R/wall at RD 24/420 to 24/427.50				EARNEST MONEY		8240
				TIME LIMIT:		2 Months
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
				In Fig.		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	60	cum			
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	30	cum			
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	125	cum			
Total						

  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar


Name of Work:- C/o Link road bakora to Gharatkhad Dogri rajpat Jarkot road km 0/00 to 3/00		Schedule of Qty		ESTIMATED COST		
SH:- C/o B/wall in R/R masonry at RD 0/540 to 0/564				EARNEST MONEY		
				TIME LIMIT:		
Description of items.		Qty	Unit	Rate	In Words	Amount.
1	2	3	4	In Fig.	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	28.8	cum			
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	33.12	cum			
3	Plain/rein forced cement concrete(1:6:12)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	11.04	cum			
4	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702,704,1202 and1204 Random rubble masonry in cement motar(1:6)	78.96	cum			
Total						

  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar




Job No 2

Schedule of Qty				ESTIMATED COST		288584
Name of Work:- C/o Link road bakora to Gharatkhad Dogri rajpat Jarkot road km 0/00 to 3/00				EARNEST MONEY		5772
SH:- C/o B/wall in R/R masonry at RD 0/565 to 0/580				TIME LIMIT:		2 Months
Sr. No	Description of items.	Qty	Unit	Rate	Amount.	
				In Fig.	In Words	
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	18	cum			
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	20.7	cum			
3	Plain/rein forced cement concrete(1:6:12)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	6.9	cum			
4	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702,704,1202 and1204 Random rubble masonry in cement motar(1:6)	49.35	cum			
Total						

  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar


DNIT						
Name of Work :- R/R Damage to Link road village Kiterwari km 0/00 to 2/900				ESTIMATED COST		474092
SH:- C/o R/wall at RD 2/700 to 2/721				EARNEST MONEY		9482
				TIME LIMIT:		2 Months
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
				In Fig.		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	24.15	cum			
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	30.03	cum			
3	Plain/rein forced cement concrete(1:6:12)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	11.34	cum			
4	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clause 702,704,1202 and 1204 Random rubble masonry in cement mortar(1:6)	77.49	cum			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8	15.33	cum			
Total						

  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar



Job No 10

Name of Work :- R/R Damage to RCD road km 0/00 to 92/695		Schedule of Qty		ESTIMATED COST		496206
SH:- P/L Kharanja Stone Soling at Various RD 31/00 to 40/00				EARNEST MONEY		9924
				TIME LIMIT:		2 Months
Sr. No	Description of items.	Qty	Unit	Rate In Fig.	In Words	Amount.
1	2	3	4	5	6	7
1	Preparation of sub grade by dressing to combor(Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HPPWD specification.	884.4	cum			
2	Consolidation of sub grade with roller including making good the undulation etc.with earth or quarry soil etc. and rerolling the sub-grade completed as per HPPWD Specification.	884.4	cum			
3	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HPPWD specification 230mm spread thickness(finished work including materials and ladour)	203.41	cum			
	Total					

  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar


JOB NO 11

## SCHEDULE OF QUANTITY

Estimate Cost	494460
Earnest Money	9889
Time	Two Month


Name of Work :- R/R Damage to Link road village Gadsari to Kharshali km 0/00 to 4/500 ( SH:- Hiring of JCB for removal of slips & maintenance of road surface km 0/00 to 4/500)

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	410.00			Per Hour	
	<b>Total</b>					


  
Executive Engineer,  
B&R Division HPPWD,  
Dodra Kwar



SCHEDULE OF QUANTITY						JOB NO 12
				Estimate Cost		494460
				Earnest Money		9889
				Time		Two Month
Name of Work :- R/R Damage to RCD road km 0/00 to 92/695 ( SH:- Hiring of JCB for removal of slips & maintenance of road surface km 21/195 to 51/00 )						
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	410.00			Per Hour	
	Total					


  
 Executive Engineer,  
 B&R Division HPPWD,  
 Dodra Kwar

SCHEDULE OF QUANTITY						JOB NO 13
				Estimate Cost		494460
				Earnest Money		9889
				Time		Two Month
Name of Work :- R/R Damage to various road under Kavar Sub Division ( SH:- Hiring of JCB for removal of slips & maintenance of road surface )						
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	410.00			Per Hour	
	Total					


  
 Executive Engineer,  
 B&R Division HPPWD,  
 Dodra Kavar



SCHEDULE OF QUANTITY						JOB NO 14	
						Estimate Cost	494460
						Earnest Money	9889
						Time	Two Month
Name of Work :- R/R Damage to various road under Kavar Sub Division ( SH:- Hiring of JCB for removal of slips & maintenance of road surface )							
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount	
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	410.00			Per Hour		
Total							

  
 Executive Engineer,  
 B&R Division HPPWD,  
 Dodra Kavar

SCHEDULE OF QUANTITY							JOB NO 15
					Estimate Cost	494460	
					Earnest Money	9889	
					Time	Two Month	
Name of Work :- R/R Damage to Rohru Chirgaon Dodra Kavar Road km 0/00 to 92/695 ( SH:- Hiring of JCB for removal of slips & maintenance of road surface km 31/00 to 51/00)							
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount	
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	410.00			Per Hour		
	Total						


  
 Executive Engineer,  
 B&R Division HPPWD,  
 Dodra Kavar



Job No 16

J.B.No 16

SCHEDULE OF QUANTITY						
				Estimate Cost	494460	
				Earnest Money	9500	
				Time	Two Month	
Name of Work :- R/R Damage to Link road village Jiskoon km 0/00 to 8/00 ( Sh:- Hiring of JCB removal of slips maintenance of road and dressing of road surface km 0/00 to 7/00)						
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Hiring of J.C.B (Excavator-cum-Loader) having bucket capacity .45 cum including P.O.L charges, shifting charge and other ancillary equipments as required at site as per instructions of the Engineer-In-charge including all leads and lifts.	410.00			Per Hour	
	Total					



Executive Engineer,  
B&R Division HPPWD,  
Dodra Kwar


Job No 17

Schedule of Qty

Estimate Cost	486500.00
Earliest Money	8000.00
Time	Three Month

Name of Work:- R/R Damage to Link road village Jiskoon km 0/00 to 5/00 ( 5th:- Hiring of Tipper for carriage of muck 0/00 to 4/300)

Sr.No.	Sub-Head and Item of work	Quantity	Rate in figures	Rate in words	Unit	Amount
1	Hiring of Tipper for carriage of material having capacity 400 cft. including P.O.L charge and other auxiliary equipments as required at the site of work. This work shall to be carried out as per minute of transport as per instructions of the Engineer-in-Charge including all loads and lifts.	70.00			Per Day	
	End					

  
Executive Engineer  
S&R Division HPPWD  
Dadra-Kanwar




**Schedule of Qty**

Job No 18

Estimate Cost 496375  
Earnest Money 9928  
Time Two Month

**Name of work:- C/o Link road from Khoptwari to Jarkot km 0/00 to 1/00 ( SH:-Providing Kharanja stone soling at RD 0/00 to 0/260)**

Sr. No	Sub-head and item of works.	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications and as directed by the Engineer in Charge.	958.10			Per Sqm	
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD specifications and as directed by the Engineer in Charge.	958.10			Per Sqm	
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm spread thickness (finished work including materials and labour) including all leads and lifts, as per HPPWD, specification of 1990 Volume-I, as directed by the Engineer-In-Charge.	220.36			Per Cum	

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar


**Schedule of Qty**

Job No 19

Estimate Cost      496375  
Earnest Money      9928  
Time                      Two Month


**Name of work:- C/o Link road from Khoptwari to Jarkot km 0/00 to 1/00 ( SH:-Providing Kharanja stone soling at RD 0/260 to 0/520)**

Sr. No	Sub-head and item of works.	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Preparation of sub grade by dressing to combor (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications and as directed by the Engineer in Charge.	958.10			Per Sqm	
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD specifications and as directed by the Engineer in Charge.	958.10			Per Sqm	
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm spread thickness (finished work including materials and labour) including all leads and lifts, as per HPPWD, specification of 1990 Volume-I, as directed by the Engineer-In-Charge.	220.36			Per Cum	

  
Executive Engineer  
B&R Division HPPWD  
Dodra Kwar




DNIT						
Name of Work :-R/R Damage to Link road village Kiterwari km 0/00 to 2/900				ESTIMATED COST		411800
SH:- C/o B/wall at RD 2/775 to 2/792				EARNEST MONEY		8236
				TIME LIMIT:		2 Months
Sr. No	Description of items.	Qty	Unit	Rate In Fig.	In Words	Amount.
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	20.74	cum			
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	18.36	cum			
3	Plain/rein forced cement concrete(1:6:12)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	9.18	cum			
4	Plain/rein forced cement concrete(1:4:8)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	3.4	cum			
5	Stone masonry in cement mortar for substructure complete as per drawing& technical specification Clause 702,704,1202 and 1204 Random rubble masonry in cement mortar(1:6)	68.17	cum			
Total						

  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar

Job No 21


Schedule of Qty					
Name of Work :- R/R Damage to Link road village Jiskoon km 0/00 to 8/00				ESTIMATED COST	462310
SH:- C/o B/wall in wire crate at RD 5/135 to 5/165				EARNEST MONEY	9246
				TIME LIMIT:	2 Months
Sr. No	Description of items.	Qty	Unit	Rate	Amount.
				In Fig.	
1	2	3	4	5	6
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	45	cum		
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	41.1	cum		
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	140.63	cum		
Total					

  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar




Job No 22

Name of Work :- R/R Damage to RCD road km 0/00 to 92/695				Schedule of Qty		
SH:- C/oR/wall in 1:3:6 at RD 24/620 to 24/629				ESTIMATED COST		461863
				EARNEST MONEY		9237
Sr. No				TIME LIMIT:		2 Months
Description of items.				Qty	Unit	
1	2	3	4	Rate In Fig.	In Words	Amount.
		3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	11.61	cum			
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	12.87	cum			
3	Plain/rein forced cement concrete(1:6:12)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	6.21	cum			
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C M-10 (1:3:6 nominal mix)	55.08	cum			
5	Providing weepholes in brick masonry/ Stone masonry,plain/reinforced concrete aboutment ,wing wall,return wall with 100 mm dia AC pipe extending though the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204,3.	15	cum			
6	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material	14.4	cum			
Total						

  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar

Job No 23


Name of Work :- R/R Damage to RCD road km 0/00 to 92/695		Schedule of Qty		ESTIMATED COST		264915
SH:- C/oR/wall in 1:3:6 at RD 27/280 to 27/295				EARNEST MONEY		5298
				TIME LIMIT:		2 Months
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
1	2	3	4	In Fig.	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	11.55	cum			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C M-10 (1:3:6 nominal mix)	33.45	cum			
3	Providing weepholes in brick masonry/ Stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204,3.	25	cum			
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8	8.1	cum			
Total						

  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar



Job No 24


Schedule of Qty						
Name of Work :- R/R Damage to RCD road km 0/00 to 92/695				ESTIMATED COST		482563
SH:- C/oR/wall in 1:3:6 at RD 24/630 to 24/639.4				EARNEST MONEY		9651
				TIME LIMIT:		2 Months
Sr. No	Description of items.	Qty	Unit	Rate	In Words	Amount.
				In Fig.		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	12.13	cum			
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	13.44	cum			
3	Plain/rein forced cement concrete(1:6:12)in open foundation complete as per drawing and technical specification Clauses 802,803,1202&1203	6.49	cum			
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C M-10 (1:3:6 nominal mix)	57.53	cum			
5	Providing weepholes in brick masonry/ Stone masonry,plain/reinforced concrete abutment, wing wall,return wall with 100 mm dia AC pipe extending though the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.	16	cum			
6	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	15.04	cum			
Total						

  
 Executive Engineer  
 B&R Division HPPWD  
 Doda Kaur



Job No 25

Schedule of Qty						
Name of Work :- R/R Damage to RCD road km 0/00 to 92/695				ESTIMATED COST		496537
SH:- P/L Kharanja Stone Soling at Various RD 40/00 to 51/00				EARNEST MONEY		9931
				TIME LIMIT:		2 Months
Sr. No	Description of items.	Qty	Unit	Rate		
1	2	3	4	In Fig.	In Words	Amount.
1	Preparation of sub grade by dressing to combor(Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HPPWD specification.	958.1	cum	5	6	7
2	Consolidation of sub grade with roller including making good the undulation etc.with earth or quarry soil etc. and rerolling the sub-grade completed as per HPPWD Specification.	958.1	cum			
3	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HPPWD specification 230mm spread thickness(finished work including materials and ladour)	220.36	cum			
Total						

  
 Executive Engineer  
 B&R Division HPPWD  
 Dodra Kwar