



E- Mail id – ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

“NOTICE INVITING TENDERS”

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 10/10/2022 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 07/10/2022 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be outrightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	A/R & M/O HPPWD Rest House at Sh. Naina Dev Ji Distt. Bilaspur (HP) (SH:- C/o Stand for water tank)	Rs. 2,56,423/-	Rs. 5,200/-	Rs. 350/-	Three Month
2	Restoration of Rain damages on Sh. Naina Devi Ji Bhakra road Km. 0/0 to 37/300 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion Km. 13/0 to 19/0) for the year 2022-23 Job No. 11	Rs. 1,18,050/-	Rs. 2,400/-	Rs. 350/-	Three Month
3	Restoration of Rain damages on Guru-Ka-Lahore Tarsooh road Km. 0/0 to 12/0 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion Km. 0/0 to 12/0) for the year 2022-23 Job No. 12	Rs. 1,18,050/-	Rs. 2,400/-	Rs. 350/-	Three Month
4	Restoration of Rain damages on SH. Naina Devi Ji Bhakra road Km. 0/0 to 37/300 (SH:- Hiring of one No. Excavator cum loader for removal of slip repair of berms and clearance of drains in portion Km. 25/0 to 37/300) for the year 2022-23 Job No.13	Rs. 1,18,050/-	Rs. 2,400/-	Rs. 350/-	Three Month
5	Construction of link road Chilla Chigla Behal Sai Kanita Sai Brahman GP Kacholi Km. 0/0 to 4/150 (SH:- C/o balance work of 6.00 meter span RCC culvert at RD 1/180) Job. No. 3	Rs. 4,98,505/-	Rs. 10,000/-	Rs. 350/-	Three Month
6	Repair and Maintenance of various roads under Namhol Sub-Division (SH:- Supplying of mixed material at HMP)	Rs. 4,94,912/-	Rs. 9,900/-	Rs. 350/-	One Month
7	Restoration of Rain damages on link road from Lehri Palsed Kala Kund road Km. 0/0 to 4/945 (SH:- C/o Un-lined drain in Km. 4/0 to 4/945 and C/o sub grade and earthen shoulders in Km. 4/0 to 4/945)	Rs. 85,589/-	Rs. 1,800/-	Rs. 350/-	Three Month
8	Restoration of Rain damages on Sh. Naina Devi Ji Bhakra road Km. 0/0 to 37/300 (SH:- C/o P.C.C. as a R/wall at RD 7/140 to 7/153)	Rs. 97,963/-	Rs. 5,200/-	Rs. 350/-	Three Month
9	Restoration of Rain damages on Tahtch Sikroha Neri Jukhala road Km. 0/0 to 18/690 (SH:- C/o B/wall at RD 5/195 to 5/213)	Rs. 98,694/-	Rs. 2,000/-	Rs. 350/-	Three Month
10	Restoration of Rain damages on Laraghat Bathoh Bholi road Km. 0/0 to 10/500 (SH:- Retaining wall at RD 0/290 to 0/305 and 0/360 and 0/375)	Rs. 4,99,744/-	Rs. 10,000/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.

3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall summarily rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.


Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

No.PW/NBT/CB/Tender-State/EA-1/2022- 10941-46

Dated:- 01.10.2022

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-1
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in along with copies of Schedule of Quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.


Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

SCHEDULE OF QUANTITY.

SCHEDULE OF QUANTITY.									
NAME OF WORK:- A/R & M/O HPPWD Rest House at Sh. Naina Devi Ji Distt. Bilaspur (HP)(SH):- C/O stand for water Tank		Estimated cost:- Rs.2,56,423/-Only.							
Sr No.		Earnest Money :- Rs.5,200/-							
Description of items.		Time:- Three Months.							
1	2	Quantity		Rates in		Unit	Amount		
		Figure.	Words.	Figure.	Words.				
1	Excavation in foundation trenches etc in earth work in all kinds of soil , such as pick work, pick jumper water upto all lifts, stacking the excavated soil not more than three metres clear from the edge of excavation and then returning the stacked soil in 15 cm (fifteen centimetres) layers when required in to plinth side of foundation etcetra consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth including carriage of materials, within all leads and lifts as per direction of.Engineer-in-charge.. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	2.59	Cubic metre.	5	6	7		
2	Providing and laying cement concrete 1:4:8 (One cement : Four Sand :Eight graded stone aggregate and plinth including carriage of materials within all leads, lifts and other incidentals.. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.29		Cubic metre.		Per Cubic metre.			
3	Providing and laying mechanically mixed & vibrated cement concrete 1:2:4(One cement: two sand : four graded crushed stone aggregate of 20mm (Twenty millimetres) nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in upto floor all level including carriage of materials, within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.46		Cubic Meter		Per Cubic Metre			
4	Steel work welded in built up sections, trusses and framed work, including cutting ,hoisting ,fixing in position and applying a priming coat of red lead paint in beams ,joists, channels, angles, tees, flats with connective plates or angle cleats in main and cross beams , hip and jack rafters purlins connected to common rafters and the like complete as per design .including carriage of materials , within all leads and lift and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.38		Quintal.		Per Quintal			

5	Providing and fixing 0.60mm (Zero point sixty millimeter) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including limpet and rubber washers complete with all accessories including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.64	Square Meter			Per Square metre
6	Providing and fixing M.S. BP Sheet 1.66mm One point sixty six millimetre)to 2mm (Two)millimetre thick in eaves board /facia /soffit s/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge. (Base members of steel work shall be measured & paid separately) including carriage of materials , within all leads and lift as per direction of the Engineer-in-charge. . The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.10	Square Meter			Per Square metre
7	Providing and fixing ridges or hips 60cm. (Sixty centimetres)overall with 0.60mm (Zero point sixty millimeter) thick pre-painted steel sheets in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20(Twenty) microns over 5 (Five) micron primer coating + back coat of polyester of 5 (Five) Microns over five microns primer coating including fixing with pre-painted iron, J or L hooks bolts and nuts ,6mm(Six millimetre) diameter and pre-painted G.I limpet and bitumen washer complete with all accessories as required as per the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	3.60	Running metre.			Per Running metre.
8	Supplying and fixing woven plains G.I. wire fencing of mesh 50mm to 150mm to any type of standard rails, straining bolts. etc. including provision of binding wire, staples etc. Detail of cost for one square metre including carriage of materials, within all leads and lifts as per direction of Engineer-in-charge.. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.60	Running metre.			Per Running metre.
9	Providing and Fixing G.I pipes Complete with G.I Fittings including trenching and refilling etc. (heavy grades pipes) including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					

i)	15 mm (Fifteen millimeter) dia nominal bore	118.00	Running metre.			Per Running metre.
ii)	20 mm (Twenty millimeter) dia nominal bore	15.00	Running metre.			Per Running metre.
iii)	25 mm (Twenty Five millimeter) dia nominal bore	35.00	Running metre.			Per Running metre.
iv)	32 mm (Thirty Two millimeter) dia nominal bore	17.00	Running metre.			Per Running metre.
	Providing and Fixing brass stop cock of approved quality including carriage of materials within all leads, lifts and other incidentals..The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
i)	15 mm (Fifteen millimeter) dia nominal bore	8.00	Nos.			Each
	Providing and fixing ball valve (brass of approved quality high or low pressure with plastic floats complete including carriage of materials within all leads, lifts and other incidentals..The rate includes octroi, royalty, Malkana toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
i)	15 mm (Fifteen millimeter) dia nominal bore	2.00	Nos.			Each
ii)	20 mm (Twenty millimeter) dia nominal bore	2.00	Nos.			Each
iii)	25 mm (Twenty Five millimeter) dia nominal bore	2.00	Nos.			Each
	Total:-					

Executive Engineer
 Water Division No. 6
 BPWD Bilaspur-17400
 (B)

SCHEDULE OF QUANTITY.

2

SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=1,18,050 /-Only.			
		Earnest Money:- Rs.= 2,400/-			
		Time:- one Months.			
Name of work :- Restoration of Rain Damages on Sh. Naina Devi ji Bakhra road km 0/00 to 37/300 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion km 13/00 to 19/00) For the Year 2022-23 Job No.-11					
Sr No.	Description of items.	Quantity	Rate In In Figure In words.	Unit	Amount
1	3	4	5		6
1	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	150.00	Hours	Per Hours	
Terms and Condition:-					
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge				
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery				
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period				
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work				
	Total				

Executive Engineer
Bilaspur Division No. 3
BPPWD Bilaspur-17400

SCHEDULE OF QUANTITY.						Estimated Cost:- Rs.=1,18,050 /-Only.
						Earnest Money:- Rs.= 2,400/-
						Time:- one Months.
Name of work :- Restoration of Rain Damages on Guru-Ka- Tarsooh road km 0/00 to 12/00 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion km 0/00 to 12/00) For the Year 2022-23 Job No.-12						
Sr No.	Description of items.	Quantity	Rate In In Figure	Rate In In words.	Unit	Amount
1	3 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 150.00	5		Per Hours	6
Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
Total						

Executive Engineer
 PWD Division No. 3
 HPPWD Bilaspur-17488
 Bh

4

SCHEDULE OF QUANTITY.						Estimated Cost:- Rs.=1,18,050 /-Only.
						Earnest Money:- Rs.= 2,400/-
						Time:- one Months.
Name of work :- Restoration of Rain Damages on Sh. Naina Devi ji Bakhra road km 0/00 to 37/300 (SH:- Hiring of one No. Excavator cum loader for removal of slips repair of berms and clearance of drains in portion km 25/00 to 37/300) For the Year 2022-23 Job No.-13						
Sr No.	Description of items.	Quantity	Rate In In Figure	Rate In In words.	Unit	Amount
1	3 1 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4 150.00	5	Hours	Per Hours	6
	Terms and Condition:-					
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge					
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery					
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period					
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work					
	Total					

Executive Engineer
Alleppey Division No. 8
HPPWD Bangalore-17400
Bh

SCHEDULE OF QUANTITY.						
Estimated cost:- Rs.4,98,505/-Only.						
Earnest Money :- Rs.10,000/-						
Time:- Three Months.						
NAME OF WORK:- Construction of link road Chilla Chogla Behal Sai Kanahta Sai Brahamna GP Kacholi km 0/00 to 4/150 (SH):- C/O of balance work of 6.00 meter span RCC culvert at RD 1/180)(Job-3)						
Sr No.	Description of items.	Quantity	Figure.	Rates in Words.	Unit	Amount
1	2 Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802,803,1202 & 1203 .P.C.C. grade M-15 (i) Nominal mix 1:2.5:5)(One Cement two and half sand five graded stone aggregate, including carriage of materials ,within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 53.93	4	5	6 Per Cubic Metre	7
2	Providing and laying mechanically mixed and vibrated concrete, for plain concrete in open foundations for all type of structure laying cement concrete grade M-25(Nominal mixed 1:1.5:3)(One Cement One and half sand three graded crushed stone aggregate)20mm(Twenty millimetre)nominal size)on ground or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawing and M.O.R.D technical specification Clause 800,1205.4 and 1205.4 and 1205.5 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.94			Per Cubic Metre	
3	Supplying, fitting and placing TMT bar reinforcement in Super--Structure complete as per drawings and Technical Specifications Clause 1002,1010 and 1202 cutting bending binding and placing in position complete,including cost of binding wire and carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same..	3.23			Per Metric Tonne.	
Total						

LE
17/08/2017

SCHEDULE OF QUANTITY.

Estimated Cost:- Rs.=4,94,912-Only.

Earnest Money:- Rs. 9,900/--

Time:- One Month.

Name of work :- Repair and Maintenance of various road under Namhol Sub-Division (SH:- Supplying of mixed material at HMP)

Sr.No	Sub-head and item of work.	Quantity	Rate		Unit	Amount
			Figure	words.		
1	Providing Mixed material for bitumenious concrete with 100-120 TPH batch type nearest Hot Mix plant producing an average output of 75 Tonnes per hour using crushed aggregates of specified grading ,premixed with bitumenious binder@ 5.4 to 5.6 percent of mix as per Morth specification clause No.503 complete in all respects The bitumenious, aggregate,sand and filler will be arranged by the supplier in all leads and lifts including loading of mixed material at Hot Mix plant . The mixed material will be carried by departmental tipper and work will be executed as per direction and entire satisfaction of Engineer in charge.	64.00				
					Total Rs.	

Executive Engineer
Bilaspur Division No. 6
BPPWD Bilaspur-1200

SCHEDULE OF QUANTITY.							Estimated Cost:- Rs.=85,589 /-Only.	
							Earnest Money:- Rs.= 1,800/-	
Name of work :- Restoration of Rain Damages on Link Road from Lehri Palsed Kala Kund Road Km 0/00 to 4/945.(SH:- C/o un-lined drain in km 4/00 to 4/945 and C/o subgrade and earthen shoulders in km 4/00 to 4/945)							Time:- Three Months.	
Sr No.	Description of items.		Quantity		Rate In		Unit	Amount
			In Figure	In words.				
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines grades levels and dimensions. Excavated material to be used in embankment with lift upto 3mm and lead of 50 m (average lead 25 m) as per technical specification clause 307 manual means.including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same		1030.00	Running Metre			Per Running Metre	
2	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and roads transporting to site spreading, grading ,to required slope and compacted to meet requirement of Table 300.2 with lead upto 100 m as per technical specification clause 303.1The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.		324.00	Cubic Metre			Per Cubic Metre	
Total								

Executive Engineer
 Nagar Division No. 3
 D.P.W.D. Bilaspur-17400
 B.K.

SCHEDULE OF QUANTITY.

8

Estimated cost:- Rs.97,963/-Only.
Earnest Money :- Rs.2,000/-
Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Sh. Naina Devi ji Bakhra road km 0/00 to 37/300 (SH:-C/O P.C.C as a R/Wall at RD 7/140 to 7/153)

Description of items.

Sr No.	Quantity	Figure.	Words.	Unit	Amount
1	3	4	5	6	7
1	15.73	Cubic Metre		Per Cubic Metre	7
2	40.95	Cubic metre.		Per Cubic metre	
3	14.95	Cubic metre.		Per Cubic Metre	
4	16.00	Nos.		Each.	
Total					

Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts.Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him.The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses,802,803,1202 and 1203 (1:5:10) without plum. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge.. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.

SCHEDULE OF QUANTITY.									
Estimated cost:- Rs.98,694/-Only.									
Earnest Money :- Rs.2,000/-									
Time:- Three Months.									
NAME OF WORK:- Restoration of Rain Damages on Thatch Sikroha Neri Jukhala road km 0/00 to 18/690 (SH:- C/O B/wall at RD 5/195 to 5/213)									
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount		
		Figure.	Words.	Figure.	Words.				
1	2			4	5				
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification, 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material, to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leadss and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	31.73	Cubic Metre			Per Cubic Metre	7		
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses 802.803, 1202 and 1203 (1:5:10) without plum, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	44.46	Cubic metre			Per Cubic metre			
3	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Nos.			Each.			
Total									

Executive Engineer,
Bilaspur Division No. 3
BPPVD Bilaspur-17400

SCHEDULE OF QUANTITY.									
Estimated cost:- Rs.4,99,744/-Only.									
Earnest Money :- Rs.10,000/-									
Time:- Three Months.									
NAME OF WORK:- Restoration of Rain damages on Laraghat Bathoh Bholi road km 0/00 to 10/500 (SH:-C/O Retaining Wall at RD 0/290 to 0/305 and 0/360 to 0/375)									
Sr No.	Description of items.	Quantity		Rates in		Unit	Amount		
		Figure.	Words.	Figure.	Words.				
1	2	3	4	5	6	7			
1	Earth work in excavation for structure in all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling / wedging out of rock (where blasting is prohibited) as per drawing and MORD technical specification 2014 clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, and disposal of materials up to any leads and upto any lift including dressing of sides and bottom and backfilling in trenches with excavated suitable approved material. to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shorting and shuttering and pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge and carriage of material tools machinery, tools equipment and safety measure necessary to complete the work within all leads and lifts. Any loss to the public /private property during the course of execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	96.45	Cubic Metre			Per Cubic Metre			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and Technical Specification Clauses, 802, 803, 1202 and 1203 (1:5:10) without plum, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	217.35	Cubic metre.			Per Cubic metre			
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 of MORD specification, 1200 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	44.40	Cubic metre.			Per Cubic Metre			
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials, within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	65.00	Nos.			Each.			
Total									

Executive Engineer,
Bilaspur Division No. 4.
Jharkhand P.W.D., Bilaspur