



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tenders on forms 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **09.08.2023** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **08.08.2023** between **2.00 PM** up to **4.30 P.M** and the application for issue of tender forms shall be received on **07.08.2023** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of work.	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	R/D on Various Road Under Baijnath Division, HPPWD Baijnath (SH: Hiring of Multi Utility)	Rs. 87,500/-	Rs. 1,800/-	Rs. 350/-	Three Months
2	R/D on Various Roads Under Baijnath Sub-Division. Chadhiar Section (SH: Clearing of side drains R/O Shoulders, Rain cuts & cutting bushes etc.) on Labour Rates.	Rs. 4,95,101/-	Rs. 10,000/-	Rs. 350/-	Three Months
3	Special Repair to Rain Shelter at Bir on Ahju Bir Gunehar Road at Km 3/850 (SH: Dismantling of Damaged Stone Wall, Stone Masonry, Plastering and Distemping, Tile work etc.)	Rs. 39,335/-	Rs. 800/-	Rs. 350/-	Three Months
4	C/O Chobin to lower Chobin Road km 0/00 to 0/600 (SH: P/L C.C. Pavement & W B M G-II for profile correction at km 0/500 to 0/590)	Rs. 2,96,554/-	Rs. 6,000/-	Rs. 350/-	Two Months
5	R/D on Paprola to Utrala Road Km 0/00 to 12/00 (SH: C/O R/Wall at RD 9/310 to RD 9/320)	Rs. 4,19,204/-	Rs. 8,400/-	Rs. 350/-	One Month
6	R/D on Paprola Andretta road km 0/00 to 6/300 (SH: C/O 1.00 mtr Span Slab culvert at RD 1/940)	Rs. 4,70,654/-	Rs. 9,500/-	Rs. 350/-	Two Months

Terms and conditions:-

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The Pan Number, latest Income Tax clearance certificate and EPF No(Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. The application form should accompany the earnest money in the shape of FDR/NSC duly pledged in favour of Executive Engineer, PWD Baijnath otherwise no forms will be issued.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/ Tipper , Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.

For & On behalf of the governor of H.P.


NO:-PWD/BD/TA/NIT/2023-24/-

5853-5903

Dated:- 25/7/23

1. Copy to the F.C. cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.

- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.


Executive Engineer,
Bajnath Division.,
H.P.P.W.D., Bajnath.

①

SCHEDULE OF QUANTITY

Name of Work: R/D on Various Road Under Bajjnath Division, HPPWD Bajjnath (SH: Hiring of Multy Utility)		Estimated Cost: Rs. 87500/- Earnest Money: Rs. 1800/- Time Limit : Three Months			
SCHEDULE OF WORKS					
S No.	Description of work	No. or Qty.	Unit	Estimated Rate	
				Figure	Words
1	Hiring of Multy Utility Vehicle (Mahindra Bolaro Utility) in working condition per KM basis including Sunday / Holiday. for rainy seasons as and when required (i.e. need basis). Operational and maintenance charges POI charges and other miscellaneous supply/replacement required for smooth running of vehicle will be borne by the owner of the Vehicle. The rate is including Royalty, Malkhana, Oetroi, toll tax, or any other taxes imposed by the Government including GST. Including 10% for night halt charges from out of head quarter.	5000.00	Per Km		

AMOUNT
Rs. p

TERMS AND CONDITIONS:-

1. The work should be carried out as per directions of Engineer-in-Charge.
2. The Vehicle should be inclusive of all rates as lubricants repair charges etc.
3. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge



 Executive Engineer
 Bajjnath Division
 HPPWD Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/D on Various Roads Under Baijnath Sub Division. (*Mechanics Section*)
 (SH:- Clearing of side drains R/O shoulders, Rain cuts & cutting bushes etc.) on Labour Rates.

Estimate Cost:-4,95,101.00
 Earnest Money: 10,000.00
 Time Limit: ~~06~~ 07 Month
 7 Ave

Sl. No.	Description of work	No. or Qty.	Unit	Rate to be entered by the Bidder		AMOUNT Rs. P
				Figures	Words	
1	Clearing and grubbing road land in area of non-thorny jungle including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, (three hundred millimeter) removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m (One thousand millimeter) including removal and disposal of top organic soil not exceeding 150 mm (One fifty millimeter) in thickness as per Technical Specification Clause 201. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of tolltax, GST & other taxes imposed by the government.	11.53	Per Hectore			
2	Repair of Shoulders including Pealing and filling to desired level and preparing rain cuts etc complete The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of tolltax, GST & other taxes imposed by the government.	11530.00	Per Square meter			
3	Restoration and repair and cleaning of drain to specified lines, grade, level and dimensions. Excavated material to be used in embankment with a lift upto 3m (Three meter) and lead of 50 m (Fifty meter) (average lead 25 m (twenty five meter)) as per Technical Specification Clause 307. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge The rate including of tolltax, GST & other taxes imposed by the government.	7479.00	Per Running Meter			


 Executive Engineer
 Baijnath Division
 H.P.P.W.D., Baijnath

SCHEDULE OF QUANTITY

Name of Work: Special Repair to Rain Shelter at Bir on Abju Bir Gunchar Road at Km 3/850. (SH: Dismantling of Damaged Stone Wall, Stone Masonary, Plastering and Distemperring, Tile work etc.)		Estimated Cost Earnest Money Time limit		AMOUNT Rs. P	
Sr No.	Description of work	No. or Qty.	Unit	Figure	Estimated Rate
					Words
1	Demolishing stone rubble masonry manually by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres (fifty meter) lead as per direction of Engineer-in-charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.87	Cum.		
2	Coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto floor five level Masonry work (first sort), in cement mortar 1:6 (one cement : six coarse sand). Less credit of recovery for usefull stone of 1/4 No (one hundred fourteen Numbers) @ Rs. 8/- (at the rate of rupees eight) Per no shall be effected from the contractor bill on pro-rata basis. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.73	Cum.		
3	15 mm (Fifteen milimetres) cement plaster on rough side of single or half brick wall of mix: 1:6 (one cement: six coarse sand). The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	6.64	Sqm		
4	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight percent) and conforming to IS:15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (one cement : four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three point three kilogram per square meter) including grouting the joints with white cement and matching pigments etc., complete. (Size of tiles is 600 x 600 mm (six hundred milimeter into six hundred milimeter). The rate also including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	20.880	Sqm		
5	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface. The rate also including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.64	Sqm		

6	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Govt.	23.86	Sum		
---	--	-------	-----	--	--


Executive Engineer
Bairnath Division
HPPWD Bairnath

D.N.I.T/ SCHEDULE OF QUANTITY

Name of work :- C/O Chobin to lower Chobin Road km 0/00 to 0/600 .
(SH:-P/L C. C Pavement & W B M G-II for profile correction at km 0/500 to 0/590.)

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
						Estimated Cost 296554.00 Earnest Money 6000.00 Time limit Two Months
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Government.	2.13	Per Cum			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals satisfaction. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Government.	42.53	Per Cum			
				Total		


 Executive Engineer
 Bajinath Division
 H.P.P.W.D., Bajinath

SCHEDULE OF QUANTITY

5

Name of Work:- R/D on Paprola to Utrala Road Km 0/00 to 12/00.
 Sub Head:- C/O R/Wall at RD 9/310 to RD 9/320).

Sr. No	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials, and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of fill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost.	22.60	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete nominal mix 1:4:8 (one cement is to four sand is to eight crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	81.60	Per Cubic metre			
Total						


 Executive Engineer
 Bajjnath Division
 H.P.P.W.D., Bajjnath

SCHEDULE OF QUANTITY

Name of Work :- R/D on Papprola Andretta road Km 0/00 to 6/300.
(SH:- C/O 1.00 mtr Span Slab Culvert at RD 1/940.)

Sr No.	Description of work	No.or Qty.	Unit	Figure	Estimated Rate		Estimated Cost Earnest Money Time limit	AMOUNT Rs. P
					Words	P		
1	Earthwork in excavation for all type of road structures as per drawing and technical specifications Clause 305-1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, (Fifty meters) dressing of sides and bottom and backfilling in trenches with excavated suitable material. The rate inclusive royalty, malkana, toll taxes, GST and other taxes imposed by the Government.	58.10	Cum				470654.00 9500.00 Two Months	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm (forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights, depths including the cost of form work, and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer-in-Charge including hauling, carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate inclusive royalty malkana, toll taxes, GST and other taxes imposed by the Government.	11.21	Cum					
3	Providing and laying mechanically mixed and vibrated plain cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogram) per cubic metre in or under water including curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights, depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800, 900 & 1200 and curing complete including hauling, carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	29.97	Cum					

<p>4</p> <p>Providing and laying mechanically mixed vibrated reinforced cement concrete in substructure using concrete grade M-20 (M twenty) 1:2:4 (one cement : two sand; four stone aggregate forty mm nominal size) design Mix with cement contents not less than 350 kg (three hundred and thirty kilogram) per cubic meter as per drawing and M.O.R.D. technical specification section 800, 900, 1200. Including the cost of form work in bed block and dirt wall etc. excluding the cost of reinforcement for reinforced concrete work but including curing complete as per direction of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.</p>	<p>16.48</p>	<p>Cum</p>	
<p>5</p> <p>Providing and laying mechanically mixed and vibrated reinforced cement concrete in super structure as per drawing and M.O.R.D., technical specification section 800, 900 and 1400 using R.C.C. grade M-25 (twenty five) design mix with cement contents not less than 400 kgs (four hundred kilogram) per cubic meter with 20 mm (twenty millimeter) nominal size gradrd crushed stone aggregate and curing complete including cost of form work but excluding the cost of reinforcement for reinforced concrete work in deck slab and to the entire satisfaction and direction of Engineer - in- Charge including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.</p>	<p>4.60</p>	<p>Cum</p>	
<p>6</p> <p>Steel Reinforcement for RCC work including straight The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.ening. Cutting, Bending, placing in position and binding all complete upto plinth level. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government</p>	<p>549.43</p>	<p>K.g</p>	
<p>TOTAL</p>			


 Executive Engineer
 Bailjush Division
 H.P.P.W.D., Esajmath