



"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on **11/08/2023 up to 11:30 A.M.** and will be opened on the same day at **(12:00 noon)** in the presence of intending contractors. The tender application will be received in this office on **09/08/2023 up to 10.00 A.M. to 12:30 P.M.** and tender form can be had from this office on **10/08/2023 from 2.00 P.M. to 5.00 Pm.** The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.


	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction of Khaddar Rangra Sarhoon Kolang Km. 0/0 to 3/300 (Sub Head:- Preparation of Forest Diversion case with including online submission) HPPWD Division Joginder Nagar..	Rs. 4,22,800/-	Rs. 8,500/-	Rs. 350/	Class "D"	Three months
2	Construction of Khaddar Rangra Sarhoon Kolang Km. 0/0 to 3/300 (Sub Head:- Preparation of Digital Plan with including Online submission and Digital Compensatory afforestation maps under HPPWD Division Joginder Nagar)	Rs. 4,22,000/-	Rs. 8,400/-	Rs. 350/	Class "D"	Three months
3	Construction of 200 mtr span Double Lane bridge with footpath over river Beas in G.P. Tullah near Tuine Bharari Temple in Joginder Nagar Constituency to connect the Dharampur constituency. (Sub Head:- Geotechnical Investigation for safe Bearing capacity for Both side abutments).	Rs. 4,98,000/-	Rs. 10,000/-	Rs. 350/	Class "D"	Three months
4	Construction of 200 mtr span Double Lane bridge with footpath over river Beas in G.P. Tullah near Tuine Bharari Temple in Joginder Nagar Constituency to connect the Dharampur constituency. (Sub Head:- Preparation of Hydraulic data and Geotechnical Investigation for safe Bearing capacity for centre Pier).	Rs. 4,06,000/-	Rs. 8,100/-	Rs. 350/	Class "D"	Three months
5	Construction of Rajeev Gandhi Day Boarding School at Shanan in Tehsil Joginder Nagar District Mandi (H.P.) and Construction of Govt. School at Langna in Tehsil Joginder Nagar district Mandi (HP). (Sub Head:- Preparation of contour site plan and cross section)	Rs. 1,82,000/-	Rs. 3,600/-	Rs. 350/	Class "D"	Three months
6	A/R & M/O various Non residential building under Joginder Nagar Division HPPWD Joginder Nagar (Sub Head:- Providing and fixing wooden ceiling and wooden wall paneling and polishing in VIP set at 1 st floor Rest House Lad-Bharol)	Rs. 4,84,841/-	Rs. 9,700/-	Rs. 350/	Class "D"	Three months
7	A/R & M/O various Non residential building under Joginder Nagar Division HPPWD Joginder Nagar (Sub Head:- Providing and fixing wooden ceiling and wooden wall paneling and polishing in ordinary set at 1 st floor Rest House Lad-Bharol)	Rs. 3,69,633/-	Rs. 7,400/-	Rs. 350/	Class "D"	Three months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-


1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.

4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.


Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2023-24- 9698-9747 Dated:- 26-7-2023

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.


Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

SCHEDULE OF QUANTITY

Estimated Cost:
Earnes Money:
Time:

Rs.
Rs.


422

8

Or

Name of work:- Construction of Khaddar Rangra Sarhoon Kolang Km. 0/00 To 3/300. (SH. Preparation of Forest Diversion case with including Onl Submission) HPPWD division Joginder Nagar.

S.N o.	Description	Qty.	Figure	Rate in Words	Unit	Amount
1	Preparation of Forest Deversion case under Forest Conservation Act 1980 including preparation of revenue papers of land falling on the road alignment and collection of other field data and all relevant documents/ Formats mandatory required would be attached with the case as per latest requirement of Ministry of Environment and forest conservation Govt. of India after getting the joint inspection/ site including computer typing in 6 copies, binding complete and getting it through from HP,PWD Sub-division Lad Bharol, HP,PWD Division Joginder Nagar, Office of range Officer Joginder Nagar, Office of DFO Joginder Nagar and Conservator of Forest Department Mandi including attending all the observations, if raised at any time by any office and to prepare the same by neatly and accurately filling in all the formats/Documents with scanning of all papers in PDF files as per requirement and as per direction of Engineer-in-charge. The rate is included all taxes excluding GST levy by the Govt. time to time.	1.00			Job	
					Total	


Executive Engineer,
 B&R Division, HP.PWD.,
 Joginder nagar.

SCHEDULE OF QUANTITY


Estimated Cost:
Earnes Money:
Time:

Rs.
Rs.

422000
8400
One y

Name of work:- Construction of Khaddar Rangra Sarhoon Kolang Km. 0/00 To 3/300. H.P.(SH):- Preparation of Digital Plan with including Online Submission, a Digital Compensatory afforestation maps under HPPWD Division Joginder Nagar .

S.N o.	Description	Qty.	Figure	Rate in Words	Unit	Amount
1	Preparation of plan Geo reference/Digital map and Digital Toposheet Map and Digital Compensatory afforestation maps Golobal Positioning System Coordinaters collection from site including preparation of KMLs files, with printing and scanning of all papers in PDF files as per requirement and as per direction of Engineer-in-charge. The rate is included all taxes excluding GST levy by the Govt. time to time.	1.00			Job	
					Total	



Executive Engineer,
B&R Division, HP.PWD.,
Joginder nagar.

SCHEDULE OF QUANTITY

Name of work:- C/O 200.00 mtr Span Double Lane bridge with footpath over river Beas in GP Tulaah near Tuine
 Bharari Temple in Joginder Nagar Constituency to connect the Dharampur Constituency
 (SH: Geotechnical Investigation for Safe Bearing Capacity for both side abutments)

Estimate Cost: 4,98,600
 Earnest Money: 10,000
 Time Limit: Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs.
				Figures	Words	
1	Geotechnical Investigation in manuscript form and submission of the same to higher office for approval. If any correction/ amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - In -charge complete in all respect. After approval the same should be submitted in 3 copies as per conditions of TOR.(Borehole depth upto 15 mtr. each). The rate is inclusive all taxes levy by the government time to time excluding GST.	60.00	Per Running meter			
Total						



 Executive Engineer
 B & R Division HP, PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of work: - C/O 200.00 mtr Span Double Lane bridge with footpath over river Beas in GP Tulah near Tuine
 Bharari Temple in Joginder Nagar Constituency to connect the Dharampur Constituency (SH: Preparation of
 Hydraulic data and Geotechnical Investigation for Safe Bearing Capacity for Centre Pier)

Estimate Cost: 4,06,000
 Earnest Money: 8,100
 Time Limit: Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs.
				Figures	Words	
1	Preparation of Hydraulic data such as contour site plan, L-section of nallah and approaches, Cross-section 7 (seven) numbers upto 500 metre up stream and 500 metre down stream, Index plan, catchment area as per survey sheet, proforma of hydraulic data duly filled properly and necessary discharge calculation sheet as required by the Engineer-in-Charge. The Hydraulic data in triplicate copy get approved from the Circle office as well as Chief office with relevant drawings and to attend all observations raised by design office till the approval of GAD which is evolved at circle/ zonal office and soft copy in the form of Compact Disc (C.D.) of above mentioned Hydraulic data including all formats and other incidental charges complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Per Job			
2	Geotechnical Investigation in manuscript form and submission of the same to higher office for approval. If any correction/ amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - In-charge complete in all respect. After approval the same should be submitted in 3 copies as per conditions of TOR.(Borehole depth upto 15 mtr. each).The rate is inclusive all taxes levy by the government time to time excluding GST.	30.00	Per Running meter			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

(5)

Name of work:- Construction of Rajeev Gandhi Day Boarding School at Shanan, in Tehsil Jogindernagar, Distt.-Mandi. (HP) and Construction of Govt. School at Langna, in Tehsil Jogindernagar, Distt.-Mandi. (HP)
(SH: Preparation of Contour Site Plan and Cross Section)

Estimate Cost: 1,82,000
Earnest Money: 3,600
Time Limit: Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. 1
				Figures	Words	
1	Site Survey using total station and preparation of Survey and contour plan at deseraad intervals. The Survey will be carried out to show all boundary points compound walls, roads, trees, building structures stream electric pole, telephone pole and any other man made structure with in survey permanent structure including supply of 3 sets of drawing along with soft copy of entire survey work and approval of contour plan from heigher authority as per direction of Engineer-in-Charge including other incidentals and soft copy. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.00	Per Hectare			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar


SCHEDULE OF QUANTITY

Name of Work : A/R & M/O various Non Residential Building under Joginder Nagar Division HPPWD Joginder Nagar (SH: Providing and Fixing Wooden ceiling and Wooden wall panneling and polishing in Ordinary Set at 1st floor Rest House Lad Bharol)

Estimate Cost:
Earnest Money:
Time Limit :

3,69,67,44
Three M
AMOUNT

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing 250mmx12mm (two hundred fifty by twelve millimeter) thick imported wall panneling over including 2.5" (two point five inch) beading at corner over Aluminium T Section frame etc. Complete as per drawing and as per the direction of engineer in charge complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	67.30	Per square metre			
2	Providing and fixing 250mmx12mm (two hundred fifty by twelve millimeter) thick imported Ceiling over including 2.5" (two point five inch) beading at corner over Aluminium T Section frame etc. Complete as per drawing and as per the direction of engineer in charge complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.75	Per square metre			
3	Polishing three coats with melamine french polish on new wood and wood based surfaces to give an even shade including cleaning the surface of all dirt dust and sand papered smooth and including a coat of wood filler. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	86.05	Per square metre			
Total						



Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : A/R & M/O various Non Residential Building under Joginder Nagar Division HPPWD Joginder Nagar (SH: Providing and Fixing Wooden ceiling and Wooden wall panneling and polishing in VIP Set at 1st floor Rest House Lad Bharol)

Estimate Cost: 4,84,441
Earnest Money: 9,7
Time Limit : Three M

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUN Rs.
				Figures	Words	
1	Providing and fixing 250mmx12mm (two hundred fifty by tweleve milimeter) thick imported wall panneling over including 2.5" (two point five inch) beading at corner over Aluminium T Section frame etc. Complete as per drawing and as per the direction of engineer in charge complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	74.88	Per square metre			
2	Providing and fixing 250mmx12mm (two hundred fifty by tweleve milimeter) thick imported Ceiling over including 2.5" (two point five inch) beading at corner over Aluminium T Section frame etc. Complete as per drawing and as per the direction of engineer in charge complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	34.78	Per square metre			
3	Polishing three coats with melamine french polish on new wood and wood based surfaces to give an even shade including cleaning the surface of all dirt dust and sand papered smooth and including a coat of wood filler. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	109.66	Per square metre			
Total						


Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar