

Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER

Sealed tenders on item rates on PWD form 6&7 are hereby invited by the Executive Engineer, Tauni Devi Division, HPPWD Tauni Devi for the following works. The tender shall be received in this office on or before 10.07.2023 up to 11:00 AM and the same shall be opened on the same day at 11:30 AM in the presence of the contractor /firms. The application for the issue of tender document shall be received on dated 06.07.2023 up to 1:30 PM and the tender form will be sold on cash payment (Non refundable) on dated 07.07.2023 from 11.00 AM to 3.00 PM.

Sr. No.	Name of Work	Estimated Cost (Rs.)	Earnest Money	Time limit	Cost of form
1.	C/O link road Ansla to Kangri via Khaneu road km 0/0 to 2/500 (SH:- P/L wet mix macadam at RD 0/700 to 1/200) UNDER OTMNP	462853/-	9300/-	Two months	350/-
2.	C/O link road Ansla to Kangri via Khaneu road km 0/0 to 2/500 (SH:- P/L Premix carpet between RD 0/700 to 1/150) UNDER OTMNP	491950/-	9700/-	Two months	350/-
3.	C/O link road Ansla to Kangri via Khaneu road km 0/0 to 2/500 (SH:- P/L Granular sub Base at RD 1/780 to 2/280) UNDER OTMNP	498960/-	9900/-	Two months	350/-
4.	C/O link road Lambri Nalahi Kangri via Asthatha Sauran Da Gran road km 0/0 to 6/00 (Sh:- P/L Granular sub Base at RD 3/525 to 4/00) Under OTMNP	488810/-	9800/-	Two months	350/-
5.	C/O link road Lambri Nalahi Kangri via Asthatha Sauran Da Gran road km 0/0 to 6/00 (Sh:- P/L Premix carpet between RD 3/120 to 3/570) Under OTMNP	481950/-	9700/-	Two months	350/-
6.	C/O link road Lambri Nalahi Kangri via Asthatha Sauran Da Gran road km 0/0 to 6/00 (Sh:- P/L wet mix macadam at RD 3/120 to 3/620) Under OTMNP	496453/-	9900/-	Two months	350/-
7.	Imp of black spot on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km 15/0 to 30/915 (SH:- Imp of curves at RD 21/600 to 21/645 & 21/900 to 21/937)	199294/-	4000/-	Two months	350/-
8.	A/R & M/O on link road Chowki to Bahal km 0/0 to 1/500, link road Kuthera Chalokhar via Dei Ka Naun km 0/0 to 2/700 & link road to village Kakru km .0/0 to 0/500 (Sh:- P/L Patch work)	494140/-	10000/-	Two months	350/-
9.	C/O Govt ITI Sujanpur Tihra Distt Hamirpur (HP) (Sh:- P/L interlocking concrete block pavement in front of and right side of canteen and motor mechanic workshop) (Deposit work)	483831/-	10000/-	Two months	350/-
10.	A/R & M/O on link road Ree to Gartholi via Balayana km .2/0 to 2/700, link road Chabutra Amb Gara km 0/0 to 3/500 & Link road to Gujerara Nihari Dargod Bali in km 0/0 to 4/0. (Sh:- P/L Patch work)	494664/-	10000/-	Two months	350/-
11.	A/R & M/O on Link road Chowki to Bahal km .0/0 to 1/500 (Sh:-P/L interlocking cement concrete paver block at RD 0/420 to 0/490)	464366/-	9500/-	Two months	350/-
12.	C/o link road from Basantpur to Tauni Devi via Chahar km 0/0 to 1/0 (SH:- ROFD at RD .0/585 to 0/885) Under OTMNP	497252/-	10000/-	Two months	350/-
13.	Balance work for C/o Mini Secretariat Building at Sujanpur Thira (SH:- P/L cement concrete 1:3:6) Deposit work	347312/-	7000/-	Two months	350/-
14.	Balance work for C/o Mini Secretariat Building at Sujanpur Thira (SH:- P/L paver tiles) Deposit work	435708/-	8700/-	Two months	350/-

15	R/R damages on link road to Jandral km 0/00 to 1/870 (C/o PCC R/wall at RD 1/435 to 1/442.50) (Deposit work) Under BASP	220731/-	4500/-	Two months	350/-
16	R/R damages on link road to Jandral km 0/00 to 1/870 (C/o PCC R/wall at RD 0/510 to 0/517.50) (Deposit work) Under BASP	222731/-	4500/-	Two months	350/-
17	C/O link road from village Kangri to (Shay) Khabaza Pir km 0/0 to 0/765 . (Sh:- P/L GSB at RD .0/0 to 0/500) Under OTMNP Head	499460/-	10000/-	Two months	350/-
18	C/O link road from village Kangri to (Shay) Khabaza Pir km 0/0 to 0/765 (Sh:- P/L WMM at RD .0/0 to 0/500) Under OTMNP Head	341168/-	6800/-	Two months	350/-
19	R/R damages on Bohni Chheorin Kakriar road km 0/00 to 4/905 (Sh:- C/O R/wall at RD 2/640 to 2/652)	111180/-	2300/-	Two months	350/-
20	Repair of maintenance of door and windows of Science & Arts block in Govt Degree college Sujanpur Thira. (Sh:- Repair of maintenance of door and windows , plaster wood and steel paint) (Deposit work)	397421/-	8000/-	Two months	350/-
21	C/o Thakur Jagdev Chand Memorial Govt. Degree college Sujanpur Thira Distt Hamirpur(HP) (SH:- Distempering weather proof exterior wall paint in Sciences & Arts Block) (Deposit work)	401806/-	8100/-	Two months	350/-
22	R/R damages on Jandral to Lambri road km 0/00 to 2/810 (Sh:- C/O Pusta below existing R/wall at RD .2/091 to 2/100.50)	190571/-	4900/-	Two months	350/-
23	C/O link road from Nallahi to Kangri via Asthatha (Sauran -Dagran) km 0/0 to 6/00 (Sh:- ROFD in km .4/225 to 4/375) (Under OTMNP)	418397/-	8500/-	Two months	350/-
24	Repair of link road to village Jandral km 0/00 to 1/870 (Sh:- Patch repair by providing G-III and premix carpet with seal coat km .0/0 to 1/870). Deposit work	413941/-	8500/-	Two months	350/-
25	C/o link road to village Chamiyana Di Khanauli km .0/00 to 4/00. (Sh:- 5/7 mtr .wide F/C at RD .1/255 to 1/360) Under OTMNP	484327/-	9700/-	Two months	350/-
26	R/R damages on various road under Sujanpur Sub-Division (Sh:-Hiring of JCB/front end Loader for removal of slips/ clearing of drain due to heavy rains)	130000/-	2600/-	Two months	350/-
27	R/R damages on various road under Sujanpur Sub-Division (Sh:-Hiring of JCB/front Loder for removal of slips /clearing of drain due to heavy rains) (Section -I)	195000/-	3900/-	Two months	350/-
28	C/o link road Mahila Mandal Nadiana Sadiana to Partholi Chaukla Basti in G.P . Jhaniara km 0/0 to 3/0. (Sh:- P/L WMM and M/T in km .0/060 to 0/360) . (Under OTMNP	490085/-	9800/-	Two months	350/-
29	C/o link road Mahila Mandal Nadiana Sadiana to Partholi Chaukla Baslu in G.P . Jhaniara km 0/0 to 1/0. (Sh:- Bed cutting , P/L GSB in km 0/060 to 0/360) . (Under OTMNP)	321248/-	6500/-	Two months	350/-
30	C/o link road from Kakru to Harizan Basti Nadiana Sadiana km 0/500 to 1/500 (Sh:- ROFD, P/L GSB in km 1/200 to 1/500) (Under SCSP)	370892/-	7500/-	Two months	350/-
31	C/o link road from Kakru to Harizan Basti Nadiana Sadiana km 0/500 to 1/500 (Sh:- P/L WMM in km 1/200 to 1/500) (Under SCSP)	218306/-	4400/-	Two months	350/-
32	C/o link road from Kakru to Harizan Basti Nadiana Sadiana km 0/500 to 1/500 (Sh:- M/T V-shape darin in km 1/200 to 1/500 in km 1/200 to 1/500) (Under SCSP)	447338/-	9000/-	Two months	350/-
33	R/R damages on link road Majhog Sultani Galu to Amroh road via Majhog Kalsa Sihal km 0/0 to 3/500 (SH:- P/L cement concrete paver 80mm thick at RD .0/615 to 1/652 and second leg 0/615 to 0/650) Under SCSP	377086/-	7500/-	Two months	350/-

34	C/O of link road Majhog Sultani Galu to Amroh road via Majhog Kalsa Sihai km 0/0 to 3/500 (SH:- P/L 80mm thick interlocking cement concrete paver block at RD .2/0 to 2/035 and 2/050 to 2/085) Under SCSP	477108/-	9500/-	Two months	350/-
35	C/O of link road Majhog Sultani Galu to Amroh road via Majhog Kalsa Sihai km 0/0 to 3/500 (SH:- P/L 80mm thick interlocking cement concrete paver block at RD .0/545 to 0/615) Under SCSP	475370/-	9500/-	Two months	350/-
36	A/R & M/O on link road Chabutra Amroh km .0/0 to 5/0, link road Majhog Gallu to Sayal km .0/0 to 1/500 & link road Bhalana Chaleli km .0/0 to 1/0. (SH:- P/L Patch work)	495895/-	10000/-	Two months	350/-
37	C/O link road Nakhre Sauran km 0/0 to 1/500 upto the house of Sh. Kulwant Rai (SH:- C/O 900mm dia hume pipe culvert at RD .1/200 with wing wall and V-shape drain) Under SCSP	409724/-	8200/-	Two months	350/-
38	C/O link road Nakhre Sauran km 0/0 to 1/500 upto the house of Sh. Kulwant Rai (SH:- P/L WMM at RD 1/0 to 1/500) Under SCSP	352375/-	7000/-	Two months	350/-
39	R/R damages on link road to village Barog km 0/0 to 0/300 and link road to village Dharmiana km .0/ to 0/450, link road to village Chail km 0/0 to 0/800 (SH:-Repair of pot holes)	487016/-	9700/-	Two months	350/-
40	A/R & M/O on Pastal to Bagdhar Matroh road km .0/0 to 3/0 (SH:-C/O R/wall at RD .1/405 to 1/435 and 2/120 to 2/137)	489345/-	9800/-	Two months	350/-
41	C/O link road Charian -Di-Dhar to Lambran -Di -Dhar via Bouru km 0/00 to 2/00 (Sh:- C/O R.C.C hume pipe culvert 900mm at RD 1/900 & wing wall at RD 1/893.50 to 1/898.50 & 1/901.50 to 1/906.50) (Under OTMNP)	359646/-	7200/-	Two months	350/-
42	R/R damages on Bharaiyan Di Dhar to Bouru via village Lamber km .0/0 to 4/0 (Sh:- C/o B/wall at RD .0/150 to 0/174)	483566/-	9700/-	Two months	350/-
43	R/R damages on Garna-Da-Galu to Kuthera via Panyala road km .0/0 to 4/00 (Sh:- C/O R/wall at RD 0/738 to 0/748)	203642/-	4100/-	Two months	350/-
44	R/R damages on link road from Bharmali Nag Mandir to Thanda Bawari (SH:- C/O C.C pavement at RD .0/675 to 0/703) Deposit work	99365/-	2000/-	Two months	350/-
45	C/O link road Bhalana to Chaleli km 0/0 to 2/0 (Sh:- C/O R/wall at RD 1/869.80 to 1/878.80 and 1/968 to 1/973) (Under SCSP)	260366/-	5300/-	Two months	350/-
46	A/R & M/O on Uhal to Indu-Dhar via Jandroo road km .0/0 to 22/0. (Sh:- Repair of pot holes in km 7/500 to 9/000)	345693/-	7700/-	Two months	350/-

The tender documents shall be issued only to those contractors/firms who fulfill the following criteria and submit documents with the application. The valid enlistment/ registration of contractor in appropriate class. Permanent Account Number (PAN). Earnest money in the shape of National saving certificate/ Time deposit Account in any of the Post office in H.P. / F.D.R. from any Nationalized Bank (i/c Kangra Central Cooperative Bank) duly pledged in favour of the Executive Engineer. Other special terms and condition can be seen/obtain in this office on any working day. Any ambiguous /telegraphic conditional tenders by fax shall not be entertained /considered in any case. It is also certified that tenders are urgent work and required early completion.

Executive Engineer,
Tauni Devi Division,
HP:PWD., Tauni Devi

No.PW/TDD/GA/N.I.T./2023-24

4736-86

Dated:-01/07/23

Copy forwarded for information & necessary action

1. The Engineer-in-Chief, HP:PWD, Shimla.
2. The Chief Engineer (HZ), HP:PWD, Hamirpur.
3. The Superintending Engineer, 8th Circle, HP:PWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP:PWD.
5. The Deputy Commissioner, Hamirpur.
6. ☒ The Director, Information and Public Relations, Suchna Avam Jan Sampark Bhawan, HP Shimla -2 for information and necessary action.
7. The Tehsildar, Tauni Devi.
8. The B. D. O. Tauni Devi.
9. The Municipal Committee, Hamirpur.
10. All the Assistant Engineers working under this Division.
11. Accounts Branch/ Drawing Branch/ Notice Board.
12. Lok Mitra, Tauni Devi.
13. Various Contractors/ Firms.

Anil Kumar
Executive Engineer,
Tauni Devi Division,
HP: PWD, Tauni Devi

CERTIFICATE

Certified that the tender for job No. 1 to 46 are called vide this office letter No. PW/TDD/GA/2023-24-4736-86 dated 01.07.2023 are an urgent nature and in public interest.



Executive Engineer,
Tauni Devi Division,
HP: PWD., Tauni Devi.

Schedule of Quantity

NAME OF WORK:- Construction of link road Ansla to Kangri via Khaneu road KM 0/0 to 2/500. (SH:- Providing and laying wet mix macadam at RD 0/700 to 1/200)(Under OTMNP)

		laying wet mix macadam at RD 0/700 to 1/200)(Under OTMNP)		laying and providing		Estimated Cost:-		Rs.462853.00	
						Earnest Money:-		Rs.9300.00	
Sr. No.		Description of Items		Qty.		Rate		Two Months	
				In Fig.		In Words		Unit	
								Amount	
1.00	Construction of unlined surface drain of average cross sectional area 0.4sqm(zero point four square metre) in ordinary rock to specified lines, grades, levels and dimensions as per approved design and to the requirement of clause 301 to 309. Excavated material to be used in embankment at site as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	2510.00						Per running metre	
2.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm(fifty three millimetre) to 0.075 mm(zero point seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8(eight) to 10(ten) tonne capacity to achieve the desired density, complete as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	176.00						Per cubic metre	
Terms and Condition								Total	

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division,
HP PWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Construction of link road Ansla to Kangri via Khanau road Km 0/0 to 2/500 (SH:- Providing and laying Premix carpet between RD 0/700 to 1/150) (Under OTMNP)

Estimated Cost:- Rs.481950.00
Earnest Money:- Rs.9700.00

Time:-

Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Providing and applying primer coat with bitumen emulsion(SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer @ 0.70-1.0 kilogram (zero point seven zero to one point zero kilogram per square metre) using mechanical means as per technical specification clause-502 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1417.50			Per Square metre	
2.00	Providing and applying tack coat with bitumen emulsion using emulsion (RS-I) distributor at the rate of 0.25 to 0.30 Kg (zero point two five to zero point three zero kilogram) per square metre on the prepared granular surfaces treated primer and cleaned with hydraulic Broom as per technical specification clause 503 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1417.50			Per Square metre	
3.00	Providing laying and rolling of open graded premix carpet using bitumen emulsion 20mm (twenty millimetre) thickness composed of 13.2mm (thirteen point two millimetre) to 5.6mm (five point six millimetre) crushed stone aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80/100 Km (eighty/hundred KN) static roller capacity, finished to required level and grades or be followed by seal coat type B as per technical specification clause 508 (Mechanical Means) VG-10 (S-90) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1417.50			Per Square metre	
4.00	Providing and laying seal coat sealing the voids in a bituminous surface laid the specified levels grade and cross fall using Type A Type B and Type C as per technical specification Clause 510 Type B VG-10(ten) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1417.50			Per Square metre	
Terms and Condition					Total	

1. Work shall be executed as per PWD specification.

Handwritten Signature
Executive Engineer,
Tauni Devi Division
HPPWD, Tauni Devi

Schedule of Quantity

NAME OF WORK:- Construction of link road Ansla to Kangri via Khanau road Km 0/0 to 2/500 (SH:- Providing and laying Granular Sub Base at RD 1/780 to 2/280)(Under OTMNP)

NAME OF WORK:- Construction of link road Anslia to Kangri via Khanau road Km 0/0 to 2/500 (SH:- Providing and laying Granular Sub Base at RD 1/780 to 2/280)(Under OTMNP)										Estimated Cost:- Rs.498960.00	
										Earnest Money:- Rs.9900.00	
										Time:- Two Months	
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount					
			In Fig.	In Words							
1	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete With material conforming to Grade-I (size range 75 mm(seventy five millimetre) to 0.075 mm (zero point zero seven five millimetre) having CBR Value-30(thirty) as per technical specifying clause 405. By mechanical means the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	264.00			Per Cubic metre						
Total											

Terms and Condition

1. Work shall be executed as per PWD specification.


And Gaur
Executive Engineer,
Tauni Devi Division,
HP PWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Construction of link road Lambri Nalahi Kangri via Asthotha Sauran Da Gran road KM 0/0 to 6/00. (SH:- Providing and laying Granular Sub Base at RD 3/525 to 4/00)(Under OTMNP)

6/00. (SH:- Providing and laying Granular Sub Base at RD 3/525 to 4/00)(Under OTMNP)									
Sr. No.	Description of Items	Qty.	Estimated Cost:-		Rs.488810.00				
			Earnest Money:-		Rs.9800.00				
			Time:-		Two Months				
1	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete With material conforming to Grade-I (size range 75 mm(seventy five millimetre) to 0.075 mm (zero point zero seven five millimetre) having CBR Value-30(thirty) as per technical specifying clause 405. By mechanical means the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	258.63	In Fig.	In Words	Unit	Amount			
					Per Cubic metre				
Terms and Condition					Total				
. Work shall be executed as per PWD specification.									

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HP PWD-Tauni Devi

Schedule of Quantity

NAME OF WORK:- Construction of link road Lambri Nalahi Ashotha Sauran Da Gran road Km 0/00 to 6/00.(SH:- Providing and laying Premix carpet between RD 3/120 to 3/570)(Under OTMNP)

Estimated Cost:- Rs.481950.00

Earnest Money:- Rs.9700.00

Time:- Two Months

Sr.No.	Description of Items	Qty.	In Fig.	Rate	Unit	Amount
			In Words	In Words		
1.00	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer @ 0.70-1.0 kilogram (zero point seven zero to one point zero kilogram per square metre) using mechanical means as per technical specification clause-502 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1417.50			Per Square metre	
2.00	Providing and applying tack coat with bitumen emulsion using emulsion (RS-1) distributor at the rate of 0.25 to 0.30 Kg (zero point two five to zero point three zero kilogram) per Square metre on the prepared granular surfaces treated primer and cleaned with hydraulic Broom as per technical specification clause 503 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1417.50			Per Square metre	
3.00	Providing laying and rolling of open graded premix carpet using bitumen emulsion 20mm (twenty millimetre) thickness composed of 13.2mm (thirteen point two millimetre) to 5.6mm (five point six millimetre) crushed stone aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80/100 Km (eighty/hundred KN) static roller capacity, finished to required level and grades or to be followed by seal coat type B as per technical specification clause 508 (Mechanical Means) VG-10 (S-90) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1417.50			Per Square metre	
4.00	Providing and laying seal coat sealing the voids in a bituminous surface laid the specified levels grade and cross fall using Type A Type B and Type C as per technical specification Clause 510 Type B VG-10(ten) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1417.50			Per Square metre	
	Total					

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division,
HPPWD, Tauni Devi

Schedule of Quantity

NAME OF WORK:- Construction of link road Lambri Nalahi Kangri via Asthotha Sauran Da Gran road KM 0/0 to 6/00. (SH:- Providing and laying wet mix macadam at RD 3/120 to 3/620)(Under OTMNP)

Sr. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Rs.9900.00		
			Time:-	Two Months		
			Rate			
			In Fig.	In Words		
1.00	Construction of unlined surface drain of average cross sectional area 0.4sqm(zero point four square metre) in ordinary rock to specified lines, grades, levels and dimensions as per approved design and to the requirement of clause 301 to 309. Excavated material to be used in embankment at site as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3470.00			Per running metre	
2.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm(fifty three millimetre) to 0.075 mm(zero point seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8(eight) to 10(ten) tonne capacity to achieve the desired density, complete as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	176.00			Per cubic metre	
Terms and Condition					Total	

1. Work shall be executed as per PWD specification.

Anil Kumar
Executive Engineer,
Tauni Devi Division,
HPPWD- Tauni Devi.

Schedule of Quantity

NAME OF WORK:- Improvement of black spot on Tanni Devi Uhal Kakkar Bajrol jungle Bert road km. 15/0 to 30/915.(SH:- Imp Of curves at RD. 21/600 to 21/645 & 21/900 to 21/937).

1. Work shall be executed as per PWD specification.

**Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi**

Schedule of Quantity

NAME OF WORK:- A/R & M/O on link road Chowki to Bahal km. 0/0 to 1/500, link road Kuthera Chalokhar via Dai Ka Naun km. 0/0 to 2/700 & link road to village Kakru km. 0/0 to 0/500. (SH:- Providing and laying Patch work).

Estimated Cost:- Rs. 494140.00
Earnest Money:- Rs. 10000.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring sunkeda in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1416.85			Per Square metre	
2	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm)(fifty three millimeter to zero point zero seven five millimeter) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. including entire carriage of material within all leads and lifts and other incidentals.	2.50			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.
- 2 The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

Anil Gaur
Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Dev

Schedule of Quantity


NAME OF WORK:- C/O Govt. ITI Sujapur Thira Dist. Haripur (HP). (SH:- P/L interlocking concrete block pavement in front of and right side of canteen and motor mechanic workshop). (Deposit Work).

Estimate Cost:- Rs. 483831.00
Earnest Money:- Rs. 10000.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words			
1	Loosening, leveling and compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150mm (one hundred fifty millimeters), mixed with water at OMC and then compacted by rolling so as to achieve minimum dry density as given in tables 300.1 and 300.2 for embankment construction as per technical specification clause 301.4 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	58.48				Per cubic metre	
2	Stone soling properly hand packed filling interstices with Kharaip stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP:PWD specification 100mm(one hundred millimeters) spread thickness (finished work including materials and labour) in all leads and lifts and dressing of sides and bottom and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts.	19.50				Per cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	29.24				Per cubic metre	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm(twenty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	3.00				Per cubic metre	
5	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, paths, lawns, drive ways or light traffic parking etc. of required strength, thickness and size/ shape, made by table vibratory method using PU mould, laid in required colour and pattern over 50mm (fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of interlocking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge, 80 mm (eighty millimetre) thick C.C. paver block of M-30 grade with approved color design and pattern, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	194.92				Per Square metre	
	Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HRPWD: Tauni Devi

Schedule of Quantity


NAME OF WORK:- A/R & M/O on link road Ree to Gartholi via Balayana km. 2/0 to 2/700, link road Chabutra Amb Gara km. 0/0 to 3/500 & link road to Gujerara Nihari Dargod Balli in km. 0/0 to 4/0.(SH:- P/L patch work).

Estimated Cost:- Rs. 494664.00
Earnest Money:- Rs. 10000.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring sunkeda in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogram per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogram per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogram per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1372.05			Per Square metre	
2	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) (fifty three millimeter to zero point seven five millimeter) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. including entire carriage of material within all leads and lifts and other incidentals.	10.00			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.


 Executive Engineer,
 Tauni Devi Division,
 HP PWD: Tauni Devi.

Schedule of Quantity
NAME OF WORK:- A/R & M/O on link road Chowki to Bahal Km. 0/0 to 1/500.(SH:- P/L Interlocking cement concrete paver block at RD. 0/420 to 0/490).

block at RD. 0/420 to 0/490).							Estimated Cost:-	Rs. 464366.00
							Earnest Money:-	Rs. 9500.00
							Time:-	Two Months
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount		
			In Fig.	In Words				
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	9.10			Per Cubic metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	21.00			Per Cubic metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	13.21			Per cubic metre			
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness and size/ shape, made by table vibratory method using PU mould, laid in required colour and pattern over 50mm (fifty millimetre) thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge,80 mm (eighty millimetre) thick C.C. paver block of M-30 grade with approved color design and pattern, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	210.00			Per Square metre			
Terms and Condition						Total		

1. Work shall be executed as per PWD specification.

Aashu Agr
 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- C/O link road from Basantpur to Tauni Devi via Chahar Km. 0/0 to 1/0. (SH:- ROFD at RD. 0/585 to 0/885).
(Under OTMNP).

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1, 1603.2 sorting out un-useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machines materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e 203.68/-cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs.64, 104/-only.	1222.05			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD, Tauni Devi

Schedule of Quantity

NAME OF WORK:- Balance work for Construction of Mini Secretariat Building at Sujampur Tihra.(SH:- Providing and laying cement concrete 1:3:6) (Deposit Work)				Estimated Cost:-	Rs.347312.00
				Earnest Money:-	Rs.7000.00
				Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	70.88			Per cubic metre	
					Total	

Terms and Condition

1. Work shall be executed as per PWD specification.

A. V. D. G. H.
 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Balance work for Construction of Mini Secretariat Building at Sujampur Tihra.(SH:- Providing and laying Paver tiles)(Deposit Work)

NAME OF WORK:-Balance work for Construction of Mini Secretariat Building at Sujapur Thirra,(SH:-Providing and laying Paver tiles)(Deposit Work)						
Sr. No.	Description of Items	Qty.	Estimated Cost:-		Two Months	Amount
			Earnest Money:-			
			Time:-	Rate		
			In Fig.	In Words	Unit	
1.00	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm(fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand 80 mm (eighty millimetre) thick cement concrete paver block of M-30 grade with approved color design and pattern as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	311.22			Per square metre	
Total						
Terms and Condition						

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauni Devi Division,
HPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Link road to Jandral Km 0/00 to 1/870. (SH:- Construction of PCC Retaining Wall at RD 1/435 to 1/442.50)(Deposit Work)(Under BASP)

NAME OF WORK:- Restoration of rain damages on Link road to landrail Km 0/00 to 1/870. (SH:- Construction of PCC Retaining Wall at RD 1/435 to 1/442.50)(Deposit Work)(Under BASP)		Schedule of Quantity		Estimated Cost:-		Earnest Money:-		Two Months	
Sr. No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount	Time:-	
				In Words					
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	24.23				Per cubic metre			
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	50.03				Per cubic metre			
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimeter) dia PVC pipe De plast /finolex/vectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of I(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	17.00				Each			
Terms and Condition							Total		

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD, Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Link road to Jandral Km 0/00 to 1/870. (SH:- Construction of PCC Retaining Wall at RD 0/510 to 0/517.50)(Deposit Work)(Under BASP)

Estimated Cost:- Rs.222731.00
Earnest Money:- Rs.4500.00
Time:- Two Months

St. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	26.33			Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	50.03			Per cubic metre	
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimeter) dia PVC pipe De plast /finolex/vecus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	22.00			Each	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


Handwritten Signature
Executive Engineer,
Tauri Devi Division,
HP PWD-Tauri Devi

Schedule of Quantity

NAME OF WORK:- C/O link road from village Kangri to (Shay) Khabaza Pir km. 0/0 to 0/765, (Sh:- P/L GSB at RD. 0/0 to 0/500). (Under OTMNP Head)

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Time:-		
			In Fig.	In Words		
1	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	251.25			Per cubic metre	
Terms and Condition					Total	

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 H.P. PWD: Tauni Devi

NAME OF WORK: c/O link road from village Kangri to (Shay) Khabaza Pir km. 0/0 to 0/765. (SH- P/L WMM at RD. 0/0 to 0/500). (Under OTMNP Head)

Terms and Condition

1. Work shall be executed as per PWD specification

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Bohni Chheroin Kakriar road Km 0/00 to 4/905.(SH:-
Construction of Retaining Wall at RD 2/640 to 2/652)

Estimated Cost:- Rs.111180.00
Earnest Money:- Rs.2300.00

Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre) on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m(one point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m(fifty metre) Ordinary rock as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	3.60			Per cubic metre	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	23.24			Per cubic metre	
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimeter) dia PVC pipe De plast /finolex/vectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7,as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	16.00			Each	
4.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 (granular Material) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	8.28			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

Anil Ch
Executive Engineer,
Taufi/Devi Division
HPBMD-Tauni Dev

Schedule of Quantity

NAME OF WORK:- Repair of Maintenance of door and windows of Science & Arts block in Govt. Degree College Sujanpur Tihra. (SH:- Repair of Maintenance of door and windows, plaster, wood and steel paint (Deposit work).						Estimated Cost:-	Rs.397421.00
						Earnest Money:-	Rs.8000.00
						Time:-	Two Months
Sr. No.	Description of Items	Qty.	In Fig.	Rate In Words	Unit	Amount	
1.01	Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for meeting the surface as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	1172.18			Per square metre		
2.01	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm (four millimetre) thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws second class teak wood 30 mm(thirty millimetre) thick as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	9.04			Per square metre		
3.01	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3(three) ply veneering with vertical grains or cross bands and face veneers on both faces of shutters 35 mm (thirty five millimetre) thick including ISI marked Stainless Steel butt hinges with necessary screws as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	2.64			Per square metre		
4.01	Applying priming coat with ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	18.80			Per square metre		
5.01	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty Float glass panes of nominal thickness 4mm(four millimetre) (weight not less than 10kg/sqm(ten kilogram per square metre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	3.49			Per square metre		

6.01	Providing and fixing 250x16 mm(one hundred fifty into sixteen millimetre) aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	2.00			Each	
7.01	Providing and fixing 250x10 mm(two hundred fifty into ten millimetre) aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10(ten) as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	4.00			Each	
7.02	150x10 mm (one hundred fifty into ten millimetre)	24.00			Each	
8.01	Providing and fixing 125mm (one hundred twenty five millimetre) aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidents.The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government	4.00			Each	
8.02	100mm (one hundred millimetre)	24.00			Each	
9.01	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm(zero point ninety litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm(zero point seventy five litre per ten square metre) of approved brand and manufacture as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	978.99			Per square metre	
10.01	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm(zero point ninety litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm (zero point eighty litre per ten square metre) of approved brand and manufacture as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	275.52			Per square metre	

11.01	15 mm(fifteen millimetre) cement plaster on rough side of single or half brick wall of mix 1:6 (one cement: six coarse sand) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	8.47				Per square metre	
Terms and Condition						Total	

1. Work shall be executed as per PWD specification.

A. S. D. S.
 Executive Engineer,
 Tauni Devi Division,
 HP/PWD: Tauni Devi

Schedule of Quantity				
NAME OF WORK:- Construction of Thakur Jagdev Chand Memorial Govt. Degree College Sujapur Tihra Distt. Hamirpur (H.P) (SH:- Distempering, weather proof exterior wall paint in Science & Arts Block) (Deposit Work)				
Sr. No.	Description of Items	Qty.	Estimated Cost:-	
			Earnest Money:-	Two Months
			Rate	Amount
		In Fig.	In Words	Unit
1.00	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equarlient on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2183.73		Per square metre
			Total	

Schedule of Quantity				
NAME OF WORK:- Construction of Thakur Jagdev Chand Memorial Govt. Degree College Sujapur Tihra Distt. Hamirpur (H.P) (SH:- Distempering, weather proof exterior wall paint in Science & Arts Block) (Deposit Work)				
Sr. No.	Description of Items	Qty.	Estimated Cost:-	
			Earnest Money:-	Two Months
			Rate	Amount
		In Fig.	In Words	Unit
1.00	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equarlient on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2183.73		Per square metre
			Total	

Amir Ghar
Executive Engineer,
Tauni Devi Division,
HPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Jandral to Lambri road km.0/00 to 2/810. (SH:- C/O Pusta below existing R/Wall at RD. 2/091 to 2/100.50).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Rs. 190571.00	
			Earnest Money:-		Rs. 4900.00	
			Time:-	Two Months	Unit	Amount
			In Fig.	In Words		
			Rate			
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (one point five metre) in width or 10 sqm (ten square metre on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and its and other incidentals.	24.89			Per cubic metre	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, filets, sunken floor etc., up to floor five level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and its and other incidentals.	42.75			Per cubic metre	
Terms and Condition					Total	

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division,
APPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- C/O link road from Nallahi to Kangri via Asthotha (Sauran-Da-Gran) km. 0/0 to 6/00.
(SH:- ROFD in km. 4/225 to 4/375).(Under OTMNP Head)

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Two Months	Unit	Amount
			In Fig.	In Words			
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1, 1603.2 sorting out un-useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e. 106.86/cubic metre shall be made from the contractor @ Rs. 300/- (three hundred only per cubic metre) amounting to Rs. 32,056/- only.	1491.61				Per cubic metre	
Total							

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Schedule of Quantity
NAME OF WORK:- Repair of link road to village Jandral Km. 0/00 to 1/870.(SH:- Patch repair by providing G-III and premix carpet with seal coat km. 0/0 to 1/870). (Deposit work).

Sr.No.		Description of Items	Qty.	Estimated Cost:-		Earnest Money:-		Time:-	
				Rs. 413941.00		Rs. 8500.00		Two Months	
				Rate		Unit		Amount	
		In Fig.	In Words						
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm)/fifty three millimeter to zero point zero seven five millimeter) to wet mix macadam (WMM) specification including premixing the material with water at UMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. including entire carriage of material within all leads and lifts and other incidentals.	14.96			Per cubic metre				
2	Repair to patch/pot holes (any depth) in connection with repairing including seeping free from dust and mud, scoring sunkeda in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm.(zero point six eight kilogramme per square metre) as per technical specification clause 190.4.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1173.42			Per Square metre				
Total									

Terms and Condition

1. Work shall be executed as per PWD specification.

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

Executive Engineer,
Tauni Devi Division,
HRPWD: Tauni


Schedule of Quantity

NAME OF WORK:- C/O link road to village Chamyania Di Khanauti km. 0/00 to 4/00. (SH:- 5/7mtr. Wide F/C at RD. 1/255 to 1/360). (Under OTMNP).

S.No.	Description of Items	Qty.	Estimated Cost:-		Earnest Money:-		Time:-	
			In Fig.	In Words	In Fig.	In Words	Two Months	Unit
					Rate			Amount
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1,1603.2 sorting out un-useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e.255.46/-cubic metre shall be made from the contractor @ Rs. 300/-(three hundred only per cubic metre) amounting to Rs.76,638/-only.	1648.10					Per cubic metre	
Total								

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 H.P.W.D. Tauni Devi.

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various road under Sujapur Sub-Division. (SH:- Hiring of JCB/front end loader for removal of slips/clearing of drain due to heavy rains).

Estimated Cost:- Rs. 130000.00
Earnest Money:- Rs. 2600.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	100.00			Per hour	
Total						

Terms and Condition

- 1 The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
- 2 Nothing shall be paid for idle hours
- 3 All bear and tear and POL charges are to be born by the contractor.

And all
 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various road under Sujapur Sub-Division. (SH:- Hiring of JCB/front end loader for removal of slips/clearing of drain due to heavy rains).(Section-I).

Estimated Cost:- Rs. 195000.00
Earnest Money:- Rs. 3900.00

Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday, JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	150.00			Per hour	
Total						

Terms and Condition

- 1 The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
- 2 Nothing shall be paid for idle hours
- 3 All bear and tear and POL charges are to be born by the contractor.

[Signature]
 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK: C/O link road Mahila Mandal Nadiana Sadhana to Partholi Chaukia Baslu in G.P. Jhanlaga km. 0/0 to 1/0 (SH:- P/L WMM and M/T in km. 0/060 to 0/360). (Under OTMNP)

Estimated Cost:- Rs. 490085.00

Earnest Money:- Rs. 9800.00

Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) (fifty three millimeter to zero point zero seven five millimeter) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	97.65			Per cubic metre	
2	Providing and applying tack coat using bitumen emulsion conforming to IS-8887, using emulsion pressure distributor including preparing the surface and cleaning with mechanical broom. On W.B.M / W.M.M. @ 0.4kg/sqm (zero point four kilogram per square metre), as per direction of Engineer-in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	960.75			Per Square metre	
3	2 cm (two centimeter) premix carpet surfacing with 1.8 cum (one point eight cubic metre) and 0.90 cum (zero point nine cubic metre) of stone chippings of 13.2 mm (thirteen point two millimeter) size and 11.2 mm (eleven point two millimeter) size respectively per 100 sqm (one hundred square metre) and 52 kg (fifty two kilogram) and 56 kg (fifty six kilogram) of hot bitumen per cum of stone chippings of 13.2 mm (thirteen point two millimeter) and 11.2 mm (eleven point two millimeter) size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6 to 9 tonne capacity etc. complete (tack coat to be paid for separately). With paving Asphalt grade VG - 30 with no solvent as per direction of Engineer-in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	960.75			Per Square metre	
4	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm and retained on 180 micron sieve) with bitumen using 128 kg (one hundred twenty eight kilogram) of bitumen of grade VG - 30 bitumen per cum of fine aggregate and 0.60 cum (zero point six zero only) of fine aggregate per 100 sqm of road surface, including rolling and finishing with road roller all complete, as per direction of Engineer-in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	960.75			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Taun Devi Division,
 HPWD, Taun Devi

Schedule of Quantity

NAME OF WORK:- C/O link road Mahila Mandal Nadia and Sadiana to Partholi Chauka Basu in G.P. Jhanara km. 0/0 to

Estimated Cost:- Rs. 321248.00

1/0(SH:- Bed cutting, P/L GSB in km. 0/060 to 0/360). (Under OTMNP)

Earnest Money:- Rs. 6500.00

Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm (thirty centimetre) in depth, 1.5 m (one point five metre) in width as well as 10 sqm (ten square metre on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m, (one point five metre) as directed by Engineer-in-charge Ordinary rock including entire carriage of material within all leads and lifts and other incidentals.	315.00			Per cubic metre	
2	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm (twenty two point five centimetre) depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earth with lead upto 50 metres, (fifty meter), as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	1050.00			Per cubic metre	
3	Construction of granular sub-base by providing closegraded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as With material conforming to Grade-I (size range 75 mm to 0.075 mm)seventy five millimeter to zero point zero seventy five millimetre) having CBR Value-30 per specifications and directions of Engineer-in-Charge. having CBR Value-25 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	105.53			Per cubic metre	
		Total				

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tadai Devi Division,
HP PWD, Tauni Dev

Schedule of Quantity

NAME OF WORK:- Construction of link road from Kakru to Harizan Basti Nadiana Saidana Km 0/500 to 1/500. (SH:- Providing and laying WMM in Km 1/200 to 1/500)(Under SCSP)

Estimated Cost:- Rs.218306.00
Earnest Money:- Rs.4400.00

Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm(fifty three millimetre) to 0.075 mm(zero point zero seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8(eight) to 10(ten) tonne capacity to achieve the desired density, complete as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	99.23			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

Arun Kumar
Executive Engineer,
Taupai Devi Division
HP&WD: Taupai Devi


Schedule of Quantity

NAME OF WORK:- Construction of link road from Kakru to Hartizan Basti Nadana Saidana Km 0/500 to 1/500. (SH:- Metalling and Tarring, V-Shape Drain in Km 1/200 to 1/500 in Km 1/200 to 1/500)(Under SCSP)

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Earnest Money:-	
			Time:-		Rate	
			In Fig.	In Words	Unit	Amount
1.00	Providing and applying tack coat with bitumen emulsion using emulsion (RS-1) distributor at the rate of 0.25 to 0.30 Kg (zero point two five to zero point three zero kilogram) per Square metre on the prepared granular surfaces treated primer and cleaned with hydraulic Broom as per technical specification clause 503 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	960.75			Per Square metre	
2.00	2 cm (two centimetre) premix carpet surfacing with 18 cum (one point eight cubic metre) and 0.90 cum (zero point nine cubic metre) of stone chippings of 13.2 mm (thirteen point two millimetre) size and 11.2 mm (eleven point two millimetre) size respectively per 100 sqm (one hundred square metre) and 52 kg (fifty two kilogram) and 56 kg (fifty six kilogram) of hot bitumen per cum of stone chippings of 13.2 mm (thirteen point two millimetre) and 11.2 mm (eleven millimetre) size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6 (six) to 9 (nine) tonne capacity etc. complete (tack coat to be paid for separately) With paving Asphalt grade VG - 10 heated and then mixed with solvent at the rate of 70 grams per kg (seventy grams per kilogram) of asphalt as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	960.75			Per square metre	
3.00	Providing and laying seal coat of premixed fine aggregate (passing 2.36 mm (two point three six millimetre) and retained on 180 (one hundred eighty) micron sieve) with bitumen using 128 kg (one hundred twenty eight kilogram) of bitumen of grade VG - 10 bitumen per cum of fine aggregate and 0.60 cum (zero point six cubic metre) of fine aggregate per 100 sqm (one hundred square metre) of road surface, including rolling and finishing with road roller all complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	960.75			Per square metre	
4.00	Construction of V-shape drain in cement concrete 1:3:6 (one cement :three sand: six graded stone aggregate 20mm (twenty millimetre) nominal size 10cm (ten centimetre) thick size 45 x 25cm (forty five into twenty five centimetre) as per design supplied vide E.I.n.C letter No. 1601-06 dated 16-08-2001 including excavation and necessary formats complete in all respects as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	400.00			Per running metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division
 HP PWD, Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Majhag Sultani Gali to Amroh road via Majhag Kaisa Sihal km. 0/0 to 3/500.(SH:- P/L cement concrete paver 80mm thick at RD. 0/615 to 0/652 and second leg 0/615 to 0/650).

NAME OF WORK:- Restoration of rain damages on link road Majhoga Sultani Galu to Amroha road via Majhoga Kalasa Sihal Km. 0/0 to 3/500.(SH:- P/L cement concrete paver 80mm thick at RD. 0/615 to 0/652 and second leg 0/615 to 0/650).							Estimated Cost:- Rs. 377086.00	
							Earnest Money:- Rs. 7500.00	
							Time:- Two Months	
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount		
			In Fig.	In Words				
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	7.02			Per Cubic metre			
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other	21.00			Per cubic metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	7.02			Per Cubic metre			
4	Providing and laying factory made chartered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness and size/ shape, made by table vibratory method using PU mould, laid in required colour and pattern over 50mm (fifty millimetre) thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge.80 mm (eighty millimetre) thick C.C. paver block of M-30 grade with approved color design and pattern, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	213.00			Per Square metre			
Total								

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD-Tauni Devi

Schedule of Quantity

NAME OF WORK:- Construction of link road Majnong Sultani Galu to Amroh road via Majnong Kalsa Sihal km. 0/0 to 3/500. (SH:- P/L 80mm thick interlocking cement concrete paver block at RD. 2/0 to 2/035 and 2/050 to 2/085) (Under SCSP).

NAME OF WORK:- Construction of link road Majhoga Sultani Galu to Amroha road via Majhoga Kaisa Sihal km. 0/0 to 3/500.(SH:-									
P/L 80mm thick interlocking cement concrete paver block at RD. 2/0 to 2/035 and 2/050 to 2/085)(Under SCSP).									
				Estimated Cost:-		Rs. 477108.00			
				Earnest Money:-		Rs. 9500.00			
				Time:-		Two Months			
Sr.No.		Description of Items		Qty.		Rate		Unit	
						In Fig.		In Words	
1		Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.		9.10				Per Cubic metre	
2		Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.		21.35				Per Cubic metre	
3		Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.		13.30				Per cubic metre	
4		Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness and size/ shape, made by table vibratory method using PU mould, laid in required colour and pattern over 50mm (fifty millimetre) thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge 80 mm (eighty millimetre) thick C.C. paver block of M-30 grade with approved color design and pattern, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.		210.00				Per Square metre	
								Total	

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tafol Devi Division,
HPMWD-Tauni Dev.

Schedule of Quantity

NAME OF WORK:- Construction of link road Mahhog Sultani Galu to Amroh road via Mahhog Kaisa Sihal km. 0/0 to 3/500.(SH:- P/L 80mm thick interlocking cement concrete paver block at RD. 0/545 to 0/615)(Under SCSP).

NAME OF WORK:-Construction of link road Majnogh Sultani Galu to Amroh road via Majnogh Kalasa Sihal km. 0/0 to 3/500.(SH:-P/L 80mm thick interlocking cement concrete paver block at RD. 0/545 to 0/615)(Under SCSP).										Estimated Cost:-	Rs. 475370.00
										Earnest Money:-	Rs. 9500.00
										Time:-	Two Months
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount					
			In Fig.	In Words							
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	9.10			Per Cubic metre						
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	21.00			Per Cubic metre						
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	13.30			Per cubic metre						
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc. of required strength, thickness and size/ shape, made by table vibratory method using PU mould, laid in required colour and pattern over 50mm (fifty millimetre) thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge.80 mm (eighty millimetre) thick C.C. paver block of M-30 grade with approved color design and pattern, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	210.00			Per Square metre						
Total											

Terms and Condition

1. Work shall be executed as per PWD specification.

Anil
Executive Engineer,
Taufi Devi Division,
H.P.W.D. Tauni Dev

Schedule of Quantity

NAME OF WORK:- A/R & M/O on link road Chabutra Amroh km.0/0 to 5/0, link road Majhog Gallu to Sayal km.0/0 to 1/500 & link road Bhalana Chaleli km. 0/0 to 1/0.(SH:- Providing and laying Patch work).

Estimated Cost:- Rs. 495895.00
Earnest Money:- Rs. 10000.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring sunkeda in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing lack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm. (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1418.85			Per Square metre	
2	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm)(fifty three millimeter to zero point seven five millimeter) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. including entire carriage of material within all leads and lifts and other incidentals.	3.00			Per cubic metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill

Anand Gaur
Executive Engineer,
Tauni Devi Division
HPPWD: Tauni Devi

Schedule of Quantity
NAME OF WORK:- C/O link road Nakhtr Sauran km. 0/0 to 1/500 upto the house of Sh. Kulwant Rai. (SH:- C/O 900mm dia
 hume pipe culvert at RD. 1/200 with wing wall and V-shape drain). (Under SCSP).

hume pipe culvert at RD. 1/200 with wing wall and V-shape drain), (Under SCSIP).									
Sr.No.		Description of Items		Qty.		Estimated Cost:-		Rs. 40724.00	
						Earnest Money:-		Rs. 8200.00	
						Time:-		Two Months	
				Rate					
				In Fig.		In Words		Unit	
								Amount	
1	Excavation work by mechanical means (Hydraulic excavator/ manual means in foundation trenches or drains (not exceeding upto 1.5m (one point five metre) in width or 10 sqm (ten square metre on plan), including dressing of sides and ramming of bottoms, lift lead of 50 m (fifty metre) ordinary rock in superstructure such as R/Wall, B/Wall etc. as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	40.34				Per cubic metre			
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement, three sand; six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	24.02				Per cubic metre			
3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, sills or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, surken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : two coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	34.36				Per cubic metre			
4	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement : two fine sand) including testing of joints etc. complete 900mm (nine hundred millimeters) dia R.C.C. pipe as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	7.50				Per running metre			
5	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plastifinolex/ vecus pipe having pressure 4kg per centimeter square, (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	10.00				Each			
6	Construction of road side V-shape drain of plain cement concrete M-10 (M-ten) (design mix) 10cm (ten centimeter) thick concrete and of 45x25cm (forty five into twenty five centimeter) size in accordance with the requirement of specification true to lines and grades dimensions and other particulars as per drawing and technical specification clause 1600, 700, 300 & 800 and as per direction of Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	250.00				Per running metre			
Terms and Condition									
1. Work shall be executed as per PWD specification.									
		Total							

Anil
 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi.

NAME	Schedule of Quantity
C-2 WORK:- C/O link road Nakhrer Sauran Km. 0/0 to 1/500, upto the house of Sh. Kulwant Rai. (SH:- P/L WMM at RD 1/0 to 1/500),(Under SGP)	

Terms and Condition

1. Work shall be executed as per PWD specification.

Arvind Gaur
Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road to village Barog km. 0/0 to 0/300 and link road to village Dharmiana km. 0/0 to 0/450, link road to village Chail km. 0/0 to 0/800). (SHS Repair & pot hole),

Estimated Cost:- Rs. 487016.00
Earnest Money:- Rs. 9700.00
Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to patch/pot holes (any depth) in connection with repairing including sweeping free from dust and mud, scoring sunken in road, patches etc. cutting around edges to at least 25mm (twenty five millimeters) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogramme per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm. (zero point six eight kilogramme per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1432.40			Per Square metre	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

A. K. Singh
Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Dey

NAME OF WORK:- A/R & M/O on Pastal to Bagdhar Matroh road km. 0/0 to 3/0. (SH:- C/O R/Wall at RD. 1/405 to 1/435 and 2/120 to 2/137).

Schedule of Quantity

		2/120 to 2/137).	
		C/O R/Wall at RD. 1/405 to 1/435 and	
		Estimated Cost:-	
		Rs. 489345.00	
		Earnest Money:-	
		Rs. 9800.00	
		Time:-	
		Two Months	
		</	


Handwritten Signature
Executive Engineer,
Taqni Devi Division,
HBPWD, Tauni Devi

Schedule of Quantity

Schedule of Quantity						
NAME OF WORK:- Construction of link road Charian-Di-Dhar to Lambran Di Dhar via Bouru Km 0/00 to 2/00. (SH:- Construction of R.C.C Hume pipe culvert 900mm at RD 1/900 & wing wall at RD 1/893.50 to 1/898.50 & 1/901.50 to 1/906.50)(Under OTMNP)					Estimated Cost:-	Rs.359646.00
					Earnest Money:-	Rs.7200.00
					Time:-	Two Months
Sr. No.	Description of Items	Qty.	In Fig.	Rate	Unit	Amount
				In Words		
1.00	Excavation for road work in soil with hydraulic excavator of 0.9cum (zero point nine cubic metre).Bucket capacity including cutting and loading in tipper, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross-section, and transporting to the embankment location with a lift upto 1.5m(one point five metre) and lead upto 1000m(one thousand metre) as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive of octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	6.39			Per cubic metre	
2.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive of octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	28.55			Per cubic metre	
3.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering 1:4:8 (one cement : four coarse sand : eight graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate upto plinth level including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals.The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.84			Per cubic metre	
4.00	Providing and laying cement concrete for plain/reinforced concrete in P.C.C grade M-10(M ten) nominal mix 1:3:6 (one cement: three sand: six graded crushed stone aggregate) 20mm (twenty millimeters) nominal size in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive of octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	14.49			Per cubic metre	
5.00	Providing and laying non-pressure NP2 class (light duty) reinforced cement concrete pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement : two sand) including testing of joints etc. complete 900 mm(nine hundred millimetre) dia. R.C.C. pipe as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive of octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	7.00			Per running metre	

6.00	Providing concrete for plain/reinforced concrete in P.C.C grade 1:2:4 (one cement: two sand: four graded crushed stone aggregate) 20mm (twenty millimeters) nominal size in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203 and as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents. The rates are inclusive of octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	0.07					Per cubic metre	
7.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	52.86					Per cubic metre	
8.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimeter) dia PVC pipe De plast /finolex/vectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	6.00					Each	
9.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 (granular Material) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	12.36					Per cubic metre	
Terms and Condition							Total	

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauni Devi Division,
HIRPMD: Tauni Devi

B/Wall at RD. 0/150 to 0/174).

Schedule of Quantity
via village Lamber km.

Terms and Condition

1. Work shall be executed as per PWD specification.

Work shall be executed as per PWD specification.

Amal Gur
Executive Engineer,
Taini Devi Division,
HPPWD: Taini Devi

Schedule of Quantity

Schedule of Quantity									
NAME OF WORK:- Restoration of rain damages on Gann-Da-Gallu to Kuthera via Panyala road km. 0/0 to 4/000.(SH:- C/O R/Wall at RD. 0/738 to 0/748) (Deposit work).							Estimated Cost:-		Rs. 203642.00
							Earnest Money:-		Rs. 4100.00
							Time:-		Two Months
Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount		
				In Words					
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	18.55				Per Cubic metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses filets, kerbs and steps etc. as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	43.48				Per square metre			
3	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,filets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	41.63				Per Cubic metre			
4	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plas/finolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in-Charge, including entire carriage of material within all leads and lifts and other incidentals.	17.00				Each			
						Total			

Terms and Condition

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road from Bharmali Nag Mandir to Tharida Bawari. (SH:- C/O cement concrete pavement at RD. 0/675 to 0/703). (Deposit work).

NAME OF WORK:- Restoration of rain damages on link road from Bharmali Nag Mandir to Thar,da Bawari. (SH:- C/O cement concrete pavement at RD. 0/675 to 0/703). (Deposit work).										Estimated Cost:-	Rs. 99365.00
										Earnest Money:-	Rs.2000.00
										Time:-	Two Months
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount					
			In Fig.	In Words							
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m,(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	12.81			Per Cubic metre						
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30. including entire carriage of material within all leads and lifts and other incidentals.	8.54			Per Cubic metre						
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement: four sand: eight graded stone aggregated 40mm (forty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	8.54			Per Cubic metre						
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm(twenty millimetre) nominal size/as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.	8.54			Per Cubic metre						
					Total						

Terms and Condition

1. Work shall be executed as per PWD specification.

Arind
Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.


Schedule of Quantity

NAME OF WORK:- Construction of link road Bhalana to Chaleli Km 0/0 to 2/0. (SH:- Construction of Retaining Wall at RD 1/869.80 to 1/878.80 and 1/968 to 1/973(Under SCSF)

Sr. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Time:-		
			In Fig.	In Words		
			Rate	Two Months		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre) on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m(one point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within all leads (Ordinary rock)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	31.65			Per cubic metre	
2	Providing and laying cement concrete 1:5:10 (one cement : five coarse sand: ten graded stone aggregate 40 mm(forty millimetre) nominal size)complete the cost of form work plain/reinforced concrete in retaining walls, breast walls as per drawing and HPPWD Technical Specification direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	57.94			Per cubic metre	
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimeter) dia PVC pipe De plast /finolex/vectus having pressure 4kg per sqmt (four kilogram) per square meter extending through the full width of the structures with slopes of 1(V): 20(H)(twenty) 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	24.00			Each.	
Total						

Terms and Condition

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 MRBWD: Tauni Devi

NAME OF WORK:- A/R & M/O on Uhal to Indu-Di-Dhar via jandroo road km. 0/0 to 22/0. (SH:- Repair of pot holes in km. 7/500 to 9/000).

Schedule of Quantity

Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words	Time:-		
					Estimated Cost:-		Rs. 345693.00
					Earnest Money:-		Rs. 7000.00
					Two Months		
1	Repair to patch/pot holes (any depth) in connection with repairing including seeping free from dust and mud and removal of loose material, cutting around edges to at least 25mm (twenty five millimeters) in depth coat with emulsion bitumen @ 0.300kg/sqm. (zero point three zero zero kilogram per square metre) and then providing 20mm (twenty millimeter) thick premix carpet using VG-10 bitumen @ 1.46kg/sqm (one point four six kilogram per square metre) and seal coat type-B with VG-10 bitumen @ 0.68kg/sqm (zero point six eight kilogram per square metre) as per technical specification clause 1904.2.503 and 508.2 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1061.71				Per Square metre	
Terms and Condition						Total	

Work shall be executed as per PWD specification.

The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.


Executive Engineer,
Tauni Devi Division,
HP PWD: Tauni Devi