

HPPWD NOTICE INVITING TENDER BHARWAIN DIVISION HPPWD BHARWAIN TEHSIL AMB DISTRICT UNA (H.P).
Phone No. 01976-255822, Web :- www. hppwd.gov.in & email address ee-bharw-hp@nic.in.

Sealed tenders on item rates basis are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer Bharwain Division, HPPWD, Bharwain Tehsil Amb District Una (HP) from the experienced contractors/ firms enlisted in appropriate class with Himachal Pradesh PWD for the following works. The tender shall be received in his office on or before **19.08.2023** up to 10.30 A.M and shall be opened on the same day at 11.00 A. M in the presence of contractors / firms or their authorized representatives, who wish to be present at the time of opening of tenders. The tender applications shall be entertained and tender form shall be sold up to two days before the date of opening of tender i.e. **17.08.2023** up to 12.00 Noon. Draft Notice Inviting Tenders/ Drawing/ Specifications can be seen in the office of the Executive Engineer on any working day between 11.00 A. M to 4.00P. M. Ambiguous / Telegraphic / Conditional tenders or tender by Fax shall not be entertained/ considered in any case. The earnest money in the shape of National Saving Certificate / Time Deposit Account / FDR in any of the Post Office in H.P./ Nationalized Bank duly pledged in favour of Executive Engineer must be accompanied with the application. Conditional tenders and the tenders received without earnest money will out rightly be rejected. The contractor shall accompany his enlistment/ renewal orders with his application for obtaining the tender documents. The Executive Engineer reserves the right to reject the tender without assigning any reasons. The work will be completed by the contractor within the stipulated period. The contractor will have to submit his registration under the H. P General Sale Tax Act 1968 and also labour license under contract Act 1970 from the competent authority. The contractors/ firms are requested to insert the rate of each item in words as well as figures, failing which XEN reserves the right to accept/ reject any or overall tenders. The tender shall only be issued to those contractors/ firms, who are found eligible/ suitable and competent as per the above conditions. The offer shall remain valid up to 45 days after the opening of tender. If any of the date mentioned above happens to be Local / Gazetted Holidays the same shall be process on next date. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr No	Name of work.	Estimated cost.	Earnest Money	Time Limit	Form No.	Cost of Form.
1	Restoration of rain damages on Bhaloun Sohari Choli road Km 0/0 to 12/675 & c/o Link road Village Sohari to Bagroh Km 0/0 to 3/0(SH:- Removal of slips, rain Cuts & C/o unlined surface drain etc.)	405552/-	8200/-	Three months	PWD-8	350/-
2.	Restoration of rain damages of various roads under jole Sub-Division (Chururu Section) (SH:- Removal of slips, rain Cuts & C/o unlined surface drain etc.)	485699/-	9800/-	Three Months	PWD-8	350/-
3.	Restoration of rain damages of various roads under Bharwain Sub-Division(Koharchhan Section) (SH:- Removal of slips, rain Cuts & C/o unlined surface drain etc.)	488500/-	9800/-	Three Months	PWD-8	350/-
4.	Repair/ restoration on Bharwain Chintpurni road km 0/0 to 3/100 (SH: C/O Retaining wall at RD 2/770 to 2/785)	496795/-	1000/-	Three months	PWD-8	350/-
5.	Restoration of rain damages on Nehri Mairi Polian Parohitan road Km 0/0 to 10/00(SH:- C/o Retaining wall RHS From RD 3/795 to 3/812.70 and 7/045 to 7/057.50) against DC deposit.	479121/-	10000/-	Three months	PWD-8	350/-

1. The Xen reserve the right to accept or reject the tender with assigning any reason.
2. The tender forms will not be issued to those contractors those performance is not founds satisfactory.
3. The list of similar type of work executed & work done performance certificate issued by the concerned Executive Engineer/GST/EPF No should accompanied with application.
4. Certificate: - Certificate that the tender have been invited in exigencies/emergency of work.

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

No. PWB/CB/TA /Tender /2023-

7061-7070 Dated

14/8/23


Copy forwarded to the following for information and necessary action, please.

1. The Superintending Engineer, 15th Circle, HPPWD, Una.
2. Accounts Branch / Drawing Branch in this office.
4. All the Assistant Engineer, working under this Division.
5. Notice Board.

Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Certificate

Certified that the works are of urgent in nature and for large public Interest, so there is exigencies /emergency in calling these without press vide this office letter No PWB/CB/TA-1/ Tender/2023:- 7061-7070 dated 14-08-2023.


Executive Engineer,
Bharwain Division,
HPPWD, Bharwain.

Schedule of Quantity

Estimate Cost - 405552/-
Earnest money - 8200/-
Time - Three months

me of Work:-Restoration of Rain Damages on Bhaloun Sohari Chouli road Km 0/0 to 12/675 & C/O Link road Village Sohari to Bagroh Km. 0/0 to 3/0 (SH:-
removal of slips , rain cuts & C/O unlined surface drain etc.)

Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
		Figure	Words		
Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material upto any lift and lead as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3027.42 Cum	85.00	Rs. Eighty five and paise zero only	Per Cubic metre	257331
Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	803.23 cubic metre	120.00	Rs. One hundred twenty and paise zero only	Per cubic metre	96388
Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment at site with in any lead and lift as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	1364.03 Rmt	38.00	Rs. Thirty eight and paise zero only	Per running metre	51833
Percentage rate (Above or Below)					405552

Executive Engineer
Bharwain Division
HPPWD Bharwain

Schedule of Quantity

Estimate Cost - 485699/-
 Earnest money - 98000/-
 Time - Three months
 (8)
 Name of Work:-Restoration of Rain Damages of various roads under Jole Sub-Division (Chururu Section)(SH:- Removal of slips , rain cuts & C/O unlined surface drain etc.)

Sub-Head and Items of work

Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
		Figures	Words		
Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material upto any lift and lead as per CPWD specifications 2019 complete and direction of Engineer in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3428.47	85.00	Rs. Eighty five and paise zero only	Per Cubic metre	291426
Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width by laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	1011.87	120.00	Rs. One hundred twenty and paise zero only	Per cubic metre	121424
Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions excavated material to be used in embankment at site with in any lead and lift as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	1917.24	38.00	Rs. Thirty eight and paise zero only	Per running metre	72855
Percentage rate (Above or Below)					485699

Executive Engineer
 Bharwain Division
 P.P.W.D. Bharwain

Schedule of Quantity

Estimate Cost - 488500/-
Earnest money - 9800/-
Time - Three months

Work:- Restoration of Rain Damages of various roads under Bharwain Sub-Division (Koharchhan Section) (SH:- Removal of slips, rain cuts & C/O unlined etc.)

Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
			Figures	Words		
land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of disposal of cut material upto any lift and lead as per CPWD specifications 2019 complete and direction of charge including carriage of materials/machinery required to execute the work in all leads and lifts and other . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the	3448.24	Cum	85.00	Rs. Eighty five and paise zero only	Per Cubic metre	293100
of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width a material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the alignment, level and slopes as per CPWD specifications 2019 complete and direction of Engineer-in-charge including materials/machinery required to execute the work in all leads and lifts and other incidentials. The rate includes lity, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	1017.71	cubic metre	120.00	Rs. One hundred twenty and paise zero only	Per cubic metre	122125
n of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and excavated material to be used in embankment at site with in any lead and lift as per CPWD specifications 2019 ad direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all fits and other incidentials. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other sed by the Government.	1928.29	Rmt	38.00	Rs. Thirty eight and paise zero only	Per running metre	73275
Percentage rate (Above or Below)						488500

Executive Engineer
Bharwain Division
CPWD Bharwain

Schedule of Quantity

47

Estimate Cost- 496795/-
Earnest Money-10000/-
Time- Three Months

Work:- Repair/Restoration on Bharwain Chintpurni road Km. 0/0 to 3/100 (SH:- C/O Retaining wall at RD 2/770 to 2/785 LHS)

Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
		Words	Figure		
excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and removal of slush separately directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	37.08	Cum	Rs one hundred eighty and paise zero only	Per cubic metre	6674
providing and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and curing complete including cost of centering and shuttering in Retaining wall/ Breast wall as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	120.51	Cum	Rs four thousand and paise zero only	Per cubic metre	482040
providing weepholes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) a PVC pipe OF MAKE D-PLAST/POLY having pressure of 4.5 kg per square meter extending through the full width of the structures with slope of 1V/20(H) (one vertical: twenty horizontal) towards drawing face complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	16.00	Numbers	Rs two hundred fifty and paise zero only	Each	4100
back filling with granular material behind abutment, wing wall and return wall complete as per drawing and direction of Engineer in charge including carriage of materials/machinery required to execute the work as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	7.42	Cum	Rs five hundred fifty and paise zero only	Per cubic metre	4081
Total					496795

Percentage rate (Above or Below)

Executive Engineer
Bharwain Division
CPWD Bharwain

Schedule of Quantity

Estimate Cost-479121/-
Earnest Cost-10000/-
Time- Three Months

Work:- Restoration of rain damages on Nehri Mairi Polian Parohitan road Km. 0/0 to 10/00 (SH:- C/O Retaining wall RHS from RD 3/795 to 3/812.70 and 7/045 to 7/057.50)

Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
			Figure	Words		
in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, pick and hard blasting work and saturated soil any other mixed verity of soil in dry or saturated condition upto any depth and lift upto any height hisling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any f layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in- charge carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	66.21	Cum	180.00	Rs one hundred eighty and paise zero only	Per cubic metre	11918
and laying in position cement concrete 1:4:8(one cement: four sand: eight graded/crushed stone aggregate 40mm (forty millimeter) nominal unically mixed and curing complete including cost of centering and shuttering in Retaining wall/ Breast wall-as per CPWD specifications 2019 and direction of Engineer-in-charge including carriage of material/ machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , royalty , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	124.61	Cum	3500.00	Rs three thousand five hundred and paise zero only	Per cubic metre	436138
weepholes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) pipe OF MAKE D-PLAST/POLY having pressure of 4.5 kg per square meter extending through the full width of the structures with slope of) (one vertical: twenty horizontal) towards drawing face complete as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi , Malkhana , toll tax, goods service tax , labour cess or other taxes imposed by the Govt.	66.00	Numbers	250.00	Rs two hundred fifty and paise zero only	Each	16500
ing with granular material behind abutment, wing wall and return wall complete as per drawing and direction of Engineer in charge including f materials/machinery required to execute the work as per CPWD specifications 2019 complete and direction of Engineer-in-charge including f materials/machinery required to execute the work in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll service tax, labour cess or other taxes imposed by the Government.	24.28	Cum	600.00	Rs six hundred and paise zero only	Per cubic metre	14568
Total						479121

Percentage rate (Above or Below)

Executive Engineer
Bharwan Division
CPWD Bharwan