

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

E-mail- ee-dal-hp@nic.in

No. PWD-Dal/TA/Tender /2023-24- 6420-22
To

Dated: - 12-10-2023


The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

7. Date of receipt of application for the tender
Form a/w requisite documents:-

16.10.2023 (between 2:00p.m. to 4:30.p.m.)

8. Date of issued/sale of tender form against
Cash payment (non refundable).

18.10.2023

The tender shall be received upto 3:00 PM on 19.10.2023 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Non refundable) during the working hours on 18.10.2023.

The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Restoration of Rain damage on Banikhet Dalhousie khajjiar road k.m. 15/600 to 27/0.(SH:- Hiring of Excavator cum Loader for removal of Slips at various RDs)	1,99,459/-	4000/-	Rs. 350/-	TwoMonths	Class-D & C
2.	A/R &M/O to HPPWD Circuit House at Dalhousie (Providing and Supplying , matterss, quilt Towel set ,Mink blanket ofdouble bed Mattress cover and sofa set cushion)	77,865/-	1600/-	Rs. 350/-	One Months	Class-D & C
3	A/R &M/O to HPPWD Circuit House at Dalhousie (SH:-Repair of old Sofa sets seats in lobby and Meeting Hall, Easy Chairs, Dressing Stool in Suits and Dinning Chair in Dining Room)	2,56,625/-	5200/-	Rs. 350/-	One Months	Class-D & C
4	A/R &M/O to S.E. Residence at Dalhousie (SH:- Providing and fixing Wardrobe in S.E. residence)	30,328/-	700/-	Rs. 350/-	One Months	Class-D & C
5	C/O approach road to Circuit House Dalhousie (SH:- C/O Breast wall for Protection of Circuit House yard)	4,36,725/-	9000/-	Rs. 350/-	Three Months	D & C
6	A/R &M/O to HPPWD 7 th Circle office builing at Dalhousie (SH:- Painting & Polishing work)	2,33,997/-	4700/-	Rs. 350/-	TwoMonths	D & C
7	A/R &M/O to HPPWD to Type-IV & Type III Residential Building at Dalhousie (SH:- P/F Cup Board, Marble slab, Brick word and Providing and fixing W.C. European Type in Type-IV Building and P/F second class deodar wood work in truss, Purlin and Panelled and Glazed Shutter for window in Type-III qtr.	1,58,321/-	3200/-	Rs. 350/-	TwoMonths	Class-D & C
8	Restoration of Rain damage on Devi Dehra Guniyala road (SH:- Breaking of Stone Boulder by manual mean)	1,23,417/-	2500/-	Rs. 350/-	One Months	Class-D & C
9	Restoration of Rain damage on Bounkhrimour to Nagali road k.m. 0/0 to 6/0 (SH:- C/O R/ wall at R.D. 1/385 to 1/386)	4,27,918/-	8600/-	Rs. 350/-	Three Months	Class-D & C
10	Restoration of Rain damage on Bounkhrimour to Nagali road k.m. 0/0 to 6/0 (SH:- C/O R/ wall at R.D. 2/120 to 2/135)	2,77,629/-	5600/-	Rs. 350/-	TwoMonths	Class-D & C
11	A/R &M/O of Various roads of Bathri Section under Banikhet Sub Division (SH:- S/S of Crushed stone aggregate sand and Fuel wood)	1,46,768/-	3000/-	Rs. 350/-	One Months	Class-D & C
12	Restoration of Rain damage on Brangal Wangal Mandoh road 0/0 to 39/600 (SH:- :- Hiring of Excavator cum Loader for removal of Slips at various RDs 20/0 to 39/600)	99,608/-	2000/-	Rs. 350/-	Two Months	Class-D & C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
2. The tender shall be issued to those contractor o who have not more than two works in hand.
3. GST No./Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
4. Application without all documents will not be entertained.
5. Proxy application will not be entertained.

Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Dated: - 12-10-2023

No. PWD/TA/Tender /2023-24- 6423-73
Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief , HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.

Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

Certificate

Certified that the tenders called vide this office letter No. PWD-/TA/Tender /2023-24:-6423-73 dated. 12-10-23 Is emergent nature and in Public interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Schedule of Qty.

Estimated Cost: - Rs.	199459.00
Earnest Money :- Rs.	4000.00
Time Limit :-	Two Month

Name of work: - Restoration of rain damage on Banikhet Dalhousie Khajjar road Km. 15/600 to 27/0 (SH:- Hiring of Excavator cum

Loader for removal of Slips at various RD's)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period / execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	1596.95			Per Cubic Meter	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment.

It is ensured that working progress of machine should not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note - 3) Subject of availability of funds

Executive Engineer
Dalhousie Division
R.P.W.D. Dalhousie

Schedule of Quantity.

Job No. TS No. 26 for 2023-24.

Estimated Cost: - Rs.

77865.00

Earnest Money :- Rs.

1600.00

Time Limit :-

One Month

Name of work: -A/R & M/O to HPPWD Circuit House at Dalhousie (SH:-Providing and supplying sleepwell mattresses with pillow , Double bed Quilt. Towel set of four pieces , Mink blanket of Double bed in double ply and Mattress cover)

1	2	Rate in Rs per m	m	Words	Each	
1	Providing and supplying of sleep well mattresses of size 75"x35"x6" (Seventy Five inch into thirty five inch into six inch) model spine tech air with Pillows and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.				Each	
2	Providing and supplying of Double bed quilt with cover in superior quality and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	1			Each	
3	Providing and supplying of towel set of four pieces of superior quality in white colour and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	1			Each	
4	Providing and supplying of mink blanket of double bed in double ply of superior quality in full size and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	1			Each	
5	Providing and supplying of mattress covers of superior cloth having size 75"x35"x6" (Seventy five inch into thirty five inch into six inch) and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	2			Each	
Total:-						

Executive Engineer
Dalhousie Division
H.P.P.W.D. Dalhousie

Schedule of Quantity.

Name of work: -A/R & M/O to HPPWD Circuit House at Dalhousie (SH:- Repair of old Sofa sets seats in lobby and Meeting Hall, Easy Chairs

, Dressing Stool in Suits and Dining Chair in Dining Room)

Estimated Cost: - Rs.	2,56,625.00
Earnest Money :- Rs.	5200.00
Time Limit :-	One Month

1	Repair of old sofa set seats including superior quality of cloths in different colours, sleep well Sofa set cushion of having size 21"x22"x4" (Twenty one inch into twenty two inch into four inch) with 40 (Forty) density and 25mm (Twenty five millimeter) thick sofa set feather foam of 32 (thirty two) density with all type of accessories which is required for repair with labours charges complete in all respect and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax, GST Sales tax or any other taxes imposed by the Government.	25.00	Rate in figure	Rate in word	Each Sofa Seat	
2	Repair of old easy chair including superior quality of cloths in different colours, sleep well set cushion of having size 21"x22"x4" (Twenty one inch into twenty two inch into four inch) with 40 (Forty) density and 25mm (Twenty five millimeter) thick feather foam of 32 (thirty two) density with all type of accessories which is required for repair with labours charges complete in all respect and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax, GST Sales tax or any other taxes imposed by the Government.	11.00			Each Chair	

3	Repair of old Dressing Stool including superior quality of cloths in different colours , sleep well set cushion of having size 18"x18"x3" (Eighteen inch intoeighteen inch into three inch) with 40 (Forty) density and 25mm (Twenty five millimeter) thick set feather foam of 32 (thirty two) density with all type of accessories which is required for repair with labours charges complete in all respect and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	5.00				Each Chair	
4	Repair of old Dining Chair including superior quality of cloths in different colours , sleep well set cushion of having size 18"x18"x3" (Eighteen inch intoeighteen inch into three inch) with 40 (Forty) density and 25mm (Twenty five millimeter) thick set feather foam of 32 (thirty two) density with all type of accessories which is required for repair with labours charges complete in all respect and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	8.00				Each chair	
Total:-							

Executive Engineer
Dahousie Division
S.P.P.W.D. Dathousis

Schedule of Qty.

Name of work: -A/R & M/O in SE Residence at Dallhousie (SH:-Providing & Fixing Wardrobe in SE Residence).

Estimated Cost: - Rs. 30328.00
 Earnest Money: - Rs. 700.00
 Time: - One Month.

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing 19 mm (nineteen millimetre) thick water proof termite resistant commercial board, ISI marked IS No. 1659 of uniply / green ply or its equivalent including vertical partitions & shelves for cup board with butt joints and fixing with nails and screws extra complete including 6 mm thick hard wood edging and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	21.48			Per Square Metre	
2	Providing and fixing 19mm (nineteen millimetre) thick Commercial Board water proof greenply, ecotec, century and sainik shutters for cup boards including fixing with nickel plated piano hinges with screws etc complete) as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	2.24			Per Square Metre	
3	Painting two coats (excluding priming coat) on new wood and wood based surfaces, with readymixed paint, brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping with ready mixed paint within all leads and lifts and as per direction of the Engineer-In-Charge and other incidentals. The rate including of octroi, royalty, Malkana, Tol Tax, sales tax GST or any other taxes imposed by the Government.	17.06			Per Square Metre	
4	Providing and fixing 125mm (One hundred twenty five millimeter) ISI marked oxidised M.S. handles conforming to IS: 4992 with necessary screws etc. complete as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	28.00			Each	
5	Providing and fixing plain square edged cover fillets (beading) 40mmx12mm (forty millimeter iso twelve millimeter) section with wood screws in ceiling and lining including mitring at junctions. 1st class deodar wood as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax sale tax GST or other taxes imposed by the Government.	8.40			Per Running Metre	
					Total -	

Schedule of Quantity.

Estimated Cost: - Rs. 4,36,725.00

Earnest Money :- Rs. 9000.00

Time Limit :- Three Month

Name of work: - C/O approach road to Circuit House Dalhousie (SH:- C/O Breast wall for Protection of Circuit House yard)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and upto all lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by	52.08			Per Cubic Meter	

2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all height / depth including the cost of form work complete in all respect as per the drawing and MORD technical specifications Section 800, 900, 1200 and 1604 and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rates is inclusive of the octoroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	85.68				Per Cubic Meter	
3	Providing Weepholes in brick masonry / stone masonry / plain / re-enforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and MORD technical specification clause 709, 1206.6 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates is inclusive of the octoroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	37				Each	
Total:-							


 Executive Engineer
 Dainousie Division
 HPT, W.D. Dainousie

Schedule of Quantity.

Estimated Cost: - Rs.	233997.00
Earnest Money :- Rs.	4700.00
Time Limit :-	Tba Month

Name of work: - A/R & M/O to HPPWD 7th Circle office building at Dalhousie. (SH:- Painting & Polishing work)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Two coat of Wall painting with premium acrylic emulsion paint of interior grade of Asian Paints/Nerolac surksha Paints/Berger Paints/Delux Paint having VOC (Volatile Organic Compound) content less than 50 (Fifty) grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	992.06			Per Square meter.	
2	Painting Two coat (excluding priming coat) on previously painted wood and wood based surfaces with enamel Asian Paints/Nerolac surksha Paints/Berger Paints/Delux Paint to give an even shade including cleaning of all dirt, dust and other foreign matter, sand papering and stoping with enamel paint white or other than white within all leads and lifts and as per the direction of the engineer-in-charge and other incidentals. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	748.04			Per Square meter.	
3	Painting one coat (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint other than white brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter within all leads and lifts and as per the direction of the engineer-in-charge and other incidentals. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	663.18			Per Square meter.	
Total:-						


 Executive Engineer
 Dalhousie Division
 H.P.P.W.D. Dalhousie

Schedule of Quantity.

Estimated Cost :- Rs. 1,58,321.00
 Earnest Money :- Rs. 3200.00
 Time Limit :- Two Month

Name of work: - A/R & M/O to Type-IV & Type III Residential Building at Dalhousie (SH:- P/F Cup Board, Marble slab, Brick work and Providing and fixing W.C European Type in Type-IV Building and P/F second class deodar wood work in trusses, Purlin and Panelled and Glazed Shutter for window in Type -III qtr.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Half brick masonry with common burnt clay F.P.S. (non modular) modular bricks of class designation 7.5(Seven point five) superstructure above plinth level up to floor V level in cement Mortar 1:4 (One cement is to four sand) and curing complete including carriage of materials within all leads, lifts and other incidental, and as per directions of Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST Sales tax or any other taxes imposed by the Government.	0.48			Per Square meter.	
2	Providing and fixing 19mm thick water proof Commercial Board of century /kitply/Centuary ply / Duro ply /Marino (ISI Marked) for cup board shutters. All cut portions of board shall be finished with 6mmx12mm (six millimetre into twelve millimetre) thick hard wood edging. the shutters including nickel plated bright finished M.S. piano hinges complete in all respect within all leads and lifts and as per the direction of the engineer-in-charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST Sales tax or any other taxes imposed by the Government.	4.80			Per Square meter.	
3	Providing and fixing 19mm thick water proof Commercial Board of century /kitply/Centuary ply / Duro ply /Marino (ISI Marked) for cup board shelves. All cut portions of board shall be finished with 6mmx12mm (six millimetre into twelve millimetre) thick hard wood edging. the shutters including nickel plated bright finished M.S. piano hinges complete in all respect within all leads and lifts and as per the direction of the engineer-in-charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST Sales tax or any other taxes imposed by the Government.	19.61			Per Square meter.	

4	Providing and fixing 1.0 mm thick (One Millimeter) coloured or plain lamination sheet (Summica) on Board /ply wood sheets with approved adhesive and nails etc complete in all respect within all leads and lifts and as per the direction of the engineer-in-charge. The rate including Royalty. Malkhana. Octroi, toll tax . GST Sales tax or any other taxes imposed by the Government.	24.41			Per Square meter.	
5	Steel work welded in built up sections trusses and framed work including cutting, hoisting fixing in position and applying a priming coat of red lead paint in gratings, framed guard bars, ladders, railing brackets similar work complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of toll tax , GST Sales tax or any other taxes imposed by the Government.	94.72			Per Kilogram meter.	
6	Providing and fixing 18 mm (Eighteen millimeter) thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm (Twenty millimeter) thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of toll tax , GST Sales tax or any other taxes imposed by the Government.	3.38			Per Square meter.	

7	Providing and laying 1st Quality 12 mm (Twelve millimeter) thick 300x300 mm (Three hundred into three millimeter) ceramic wall tiles conforming to IS:15622 of Resile/ Nitco/ Rak/Kajaria/ Orient& Bell/ Simpolo/Johnson/AGL/Somay in all colours, shades except burgundy. Bottel green Black of any size as approved in skirting, risers of steps and dados laid on 12mm (Twelve millimeter) thick cement mortar 1:3 (1 cement : 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three Kilogramme per Square meter) including grouting the joints with white cement and matching pigments etc., complete including grouting of joints (Payment for grouting of joints to be made) within all leads and lifts as per the direction of the engineer-in charge and other incidentals.. The rate inclusive of Octroi, toll tax , GST or any other taxes imposed by the Government.	3.60			Per Square meter.	
8	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) Star S.No. 20087 (S-10) with white solid plastic seat and lid having size 57x35x39 CM (Fifty seven into thirty five into thirty nine centimeter) Hindware/Cera/Jaguar of Star white/Snow white shade and fixed with Jet pressure , with manually controlled device (handle lever), conforming to IS : 7231. with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required complete.as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	1			Each	
9	Providing second class deodar wood work in trusses, purlins, rafters, posts,post plates, wall plates and the like wrought framed, hoisted and fixed in position complete within all leads and lifts and as per the direction of the engineer-in-charge . The rate including Royalty, Malkhana, Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	0.42			Per Cubic meter.	

10	Providing and fixing 40 mm (forty millimetre) thick second class deodar wood panelled, glazed or panelled and glazed shutters for doors, windows, clerestory windows including black enamelled iron butt hinges with necessary screws within all leads and lifts and as per the direction of the engineer-in-charge . The rate including Royalty, Malkhana, Octroi, toll tax , GST Sales tax or any other taxes imposed by the Government.	5.25					Per Square meter.	
11	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture	4.2					Per Square meter.	
							Total:-	


 Engineer
 Dainousie Division
 P.F.W.D. Dainousie

Schedule of Quantity.

Job No. S No. 37 for 2023-24

Estimated Cost: - Rs. 123417.00

Earnest Money :- Rs. Rs.2500.00

Time Limit :- One Month

Abstract of Cost

Name of work: - Restoration of Rain Damages on Devi Dehra Gunjwala road (SH:- Breaking of Stone Boulder by manual

Sr.No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Breaking of big stone boulder rolling down from hill side during rainy season and lying in road by Chiseling/wedging out of all type of rocks by manual means and safety measures and other incidentals necessary to complete the work by mechanical means and/or by labour (if any required complete as per the direction of the engineer-in-charge. Any loss to the public and private property during the breaking of stone boulder and transportation of useful and un-useful materials shall be absolute responsibility of the contractor which shall have to be duly compensated by the contractor to full extent in all respect. The recovery of useful stone 79.83 Cum @ Rs. 300/- cum shall be recovered from contractor bill including carriage of materials within all leads, lifts and other incidental, and as per directions of Engineer-in-Charge. The rate including Royalty, Malkhana, Octroi, toll tax, GST Sales tax or any other taxes imposed by the Government.	79.83			Per Cubic meter.	
Total:-						


 Engineer-in-Charge
 Traffic Division
 Muzo D. Dargachaudhary

Schedule of Quantity.

Name of work: - Restoration of rain Damages on Bounkhrimour to Nagali road km 0/0 to 6/0 (SH:- C/O R-wall at RD 1/385 to 1/386)

Estimated Cost: - Rs.	4,27,918.00
Earnest Money :- Rs.	8600.00
Time Limit :-	Three Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and upto all lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including the octoroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	28.55			Per Cubic Meter	
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all height / depth including the cost of form work complete in all respect as per the drawing and MORD technical specifications Section 800, 900, 1200 and 1604 and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rates is inclusive of the octoroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	84.48			Per Cubic Meter	

3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	13.48				Per Cubic Meter	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-enforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and MORD technical specification clause 709, 1206.6 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates is inclusive of the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30				Each	
Total:-							


 Executive Engineer
 Dalhousie Division
 N.P.W.D. Dalhousie

Schedule of Quantity.

78-231 for 2023-24

Name of work: - Restoration of rain Damages on Bounkhrimour to Nagali road km 0/0 to 6/0 (SH:- C/O R-wall at RD 2/120 to 2/135)

Estimated Cost: - Rs.	2,77,629.00
Earnest Money :- Rs.	5600.00
Time Limit :-	Two Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 and 1603 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and upto all lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including the octoroi, royalty, Malkana, toll tax, sales tax, GST or any	21.38			Per Cubic Meter	
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all height / depth including the cost of form work complete in all respect as per the drawing and MORD technical specifications Section 800, 900, 1200 and 1604 and as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rates is inclusive of the octoroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	53.55			Per Cubic Meter	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per the directions of the Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including the octoroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	12.83			Per Cubic Meter	

4	Providing Weepholes in brick masonry / stone masonry / plain / re-enforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters. PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and MORD technical specification clause 709, 1206.6 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates is inclusive of the octroi, royalty, Malkana. toll tax, sale tax , GST or other taxes imposed by the Government.	23			Each	
Total:-						


 Executive Engineer
 Dalhousie Division
 P. R. W. D. Dalhousie

T/S No. 32 for 2023-24

Schedule of Quantity.

Name of work: - A/R & M/O of Various roads of Bathri Section under Banikhet Sub Division (SH:- S/S of Crushed stone aggregate, sand and Fuel wood)

Estimated Cost: - Rs.	146768.00
Earnest Money :- Rs.	3000.00
Time Limit :-	One Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Supplying and stacking of approved quality fine crushed sand defined as passing 2.36mm (two point three six millimetre) sieve and retained on 180 (one hundred eighty) microns sieve and free from deleterious, organic or any other foreign matter properly washed and stacked in proper stacks of half cubic metre along road side clear from the road formation as per directions of the Engineer-in Charge. The material shall confirm to the MORD specification. The rate including carriage of material within all leads and lifts and other incidentals. The rate quoted by the contractor shall be inclusive of all taxes such as municipal, octroi, forest Malkana royalty toll tax, GST and other local taxes. The voids will be deducted as per latest instructions of the department.	12.00			Per Cubic Meter	
2	Supplying and stacking of approved quality crushed stone aggregate screening 13.2mm to 5.6mm (thirteen point two millimetre to five point six millimetre) nominal size free from deleterious, organic or any other foreign matter properly washed and stacked in proper stacks of half cubic metre along road side clear from the road formation as per directions of the Engineer-in Charge. The material shall confirm to the MORD specification. The rate including carriage of material within all leads and lifts and other incidentals. The rate quoted by the contractor shall be inclusive of all taxes such as municipal, octroi, forest Malkana royalty toll tax, GST and other local taxes. The voids will be deducted as per latest instructions of the department. The voids will be deducted as per latest instructions of the department.	56			Per Cubic Meter	
3	Supplying and stacking at site of work dry wood, Bansu hard fuel wood such as Ban, Dhaman of any other hard variety of wood in proper log not exceeding 1.20 (One point two zero meter) in length and diameter of log should be between 100 mm to 150 mm (One hundred millimeter into one hundred fifty millimeter with in all leads and lifts as per the direction of Engineer-in-charge and other incidentals. The rate including the octroi, royalty, Malkhana, Toll tax, GST or any other taxes imposed by the Government.	60			Quentrel	
Total:-						

Executive Engineer
Bathouse Division
BPM.D. Bathouse

Schedule of Quantity.

Estimated Cost: - Rs. 99608.00
Earnest Money :- Rs. 2000.00

TS No.38
For 2023-24

Time Limit :- Two Month

Name of work: - Restoration of rain Damages on Brangal Wangal Mandoh road km 0/0 to 39/600 (SH:- Hiring of Excavator cum Loader for removal of slips in km 20/0 to 39/600)

Sr. No.	Sub head / item of work	Qty.	Rate		Unit	Amount
			in fig.	In Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts up to any height and depth as per direction and entire satisfactions of Engineer-in-Charge. Any loss to the public/private property or any accident etcetera happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate is including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	797.63			Per Cubic Metre	
Total						

Executive Engineer
Dahouise Division
H.P.W.D. Dahouise