

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"**

Sealed percentage rate of tender form No: 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.II, HPPWD, Mandi on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before **10.10.2023** up to 12:00 Noon and the same shall be opened on the same day at 2:30 PM. in the presence of the Contractors or their authorized representatives who may be present. The tender application will be received in this office on **07.10.2023** upto 10.00 AM to 1:00 PM. and tender form can be held from this office against cash payment (Non-Refundable) on **09.10.2023** from 2.00 PM to 5.00 PM.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No. II, HPPWD, Mandi reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estt. cost	E/Money	Cost of tender form	Time limit
1	Construction of link road Dolra Balh to Pump House Dawada Km. 0/00 to 5/00. (SH:- C/O 900mm dia RCC Hume pipe Culvert at RD. 2/720 including wing walls).	Rs. 3,18,810	Rs. 6,400	Rs. 350	One Month
2	C/O Link road from Chil Khola to Thanker Nichla Barnota Km.0/0 to 2/0. (SI- ROFD between km 0/00 to 0/210).	Rs. 2,20,749	Rs. 4,500	Rs. 350	One Month
3	C/O Link road Ropri to Tehrehar via Galoo Km.0/00 to 1/00. (SH:- C/O R/wall at RD. 0/005 to 0/020.)	Rs. 2,35,393	Rs. 4,700	Rs. 350	One Month
4	RRD on Gatterbag to upper Thanout road Km. 0/00 to 8/200 (SH:- C/O R/wall at RD. 1/750 to 1/760).	Rs. 3,98,442	Rs. 8,000	Rs. 350	One Month
5	R.R.D. on Batahar to Batahan road Km. 0/00 to 6/400. (SH:- C/O PC.C.R/wall in Km.0/050 to 0/062).	Rs. 4,80,999	Rs. 9,700	Rs. 350	One Month
6	R.R.D. on Saigaloo Nahlog road Km. 0/00 to 6/400. (SH:- C/O PC.C.R/wall in Km.4/180 to 4/192).	Rs. 4,71,230	Rs. 9,500	Rs. 350	One Month
7	R.R.D.on Kushada to Samrahan road Km. 0/00 to 3/00. (SH:- C/O wire Crate R/wall at RD. 1/130 to 1/345).	Rs. 3,98,832	Rs. 8,000	Rs. 350	One Month
8	C/O Main road Deodhar to Batour 1st ward Km. 0/00 to 3/500. (SH:- C/O PCC B/wall at RD. 0/315 to 0/330) Under SCSP	Rs. 2,79,701	Rs. 5,600	Rs. 350	One Month
9	C/O Gatterbag to Upper Thanout Km. 0/00 to 8/200. (SH:- C/O PCC B/wall at RD. 6/675 to 6/700)	Rs. 4,68,118	Rs. 9,400	Rs. 350	One Month
10	Restoration of Rain Damages on link road Old Bus Stand Kotli to Village Arnayana in Km. 0/00 to 3/00.	Rs. 4,99,325	Rs. 10,000	Rs. 350	One Month
11	R.R.D.on Kun Galoo to Baroha Ropa Matyahal road Km. 0/00 to 2/500. (SH:- C/O P.C.C R/wall at RD. 0/790 to 0/800).	Rs. 2,09,619	Rs. 5,000	Rs. 350	One Month

12	C/O Bhargaon to Alag via Tilla road Km. 0/00 to 2/00. (SH:- C/O B/wall at RD. 1/345 to 1/355).	Rs. 2,11,827	Rs. 4,300	Rs. 350	One Month
13	R.R.D.on Kun Galoo to Baroha Ropa Matyahal road Km. 0/00 to 2/500.(SH:- C/O P.C.C R/wall at RD. 0/780 to 0/790).	Rs. 1,90,071	Rs. 3,900	Rs. 350	One Month
14	RRD on Sandhapatan Bharol Bangora Hard Ropri Kalg, Traimbali Basahi Drubal, Chauranj, Banwar, Kun-Ka-Tar Mandhokar Bhargaon Kotli road Km. 70/600 to 85/00. (SH:- C/O Wire crate R/wall at RD. 72/665 to 72/675).	Rs. 2,32,372	Rs. 4,700	Rs. 350	One Month
15	RRD on Roda Nallah to Karkoh Arthi road Km. 0/00 to 12/00.(SH:- C/O Wire crate R/wall at RD. 9/884 to 9/896.50).	Rs. 2,91,531	Rs. 10,000	Rs. 350	One Month
16	R.R.D.on Kun to Padhar road Km. 0/00 to 1/500. (SH:- C/O P.C.C R/wall at RD. 0/560 to 0/575).	Rs. 4,34,437	Rs. 8,700	Rs. 350	One Month
17	RRD on Deodhar Kheelgaloo road Km. 0/00 to 16/00. (SH:- C/O PCC R/wall at RD. 13/900 to 13/912).	Rs. 4,06,199	Rs. 8,200	Rs. 350	One Month
18	RRD on Sain Gujra Ropru road Km. 0/00 to 14/00. (SH:- C/O Wire crate R/wall at RD. 10/490 to 10/503.75).	Rs. 4,82,880	Rs. 10,000	Rs. 350	One Month
19	R.R.D. on Madan Ka Ghar to Samrahan road Km. 0/00 to 07/200. (SH:- C/O PCC Toe wall cumwire crate R/wall at RD. 04/500 to 04/508.75).	Rs. 3,34,614	Rs. 10,000	Rs. 350	One Month
20	R.R.D. on Madan Ka Ghar to Samrahan road Km. 0/00 to 07/200. (SH:- C/O PCC Toe wall cumwire crate R/wall at RD. 04/508.75 to 04/517.50).	Rs. 3,72,426	Rs. 7,500	Rs. 350	One Month
21	R.R.D. on Gaterbag to Chaloh road Km. 0/00 to 8/200. (SH:- C/O PCC R/wall at RD. 0/824 to 0/829).	Rs. 2,03,243	Rs. 4,100	Rs. 350	One Month
22	AVR & M/O HPPWD Rest House at Kotli, Tehsil Kotli, Distt. Mandi H.P. (SH:- Dismantling of roof & wood work, steel work, painting, concrete work and supply of furniture)	Rs. 4,02,114	Rs. 8,100	Rs. 350	One Month
23	RRD on Gaterbag to Chaloh road Km. 0/00 to 8/200. (SH:- C/O PCC R/wall at RD. 0/800 to 0/812).	Rs. 4,99,009	Rs. 10,000	Rs. 350	One Month
24	RRD on Gaterbag to Chaloh road Km. 0/00 to 8/200.(SH:-C/O PCC R/wall at RD. 0/812 to 0/824).	Rs. 4,99,741	Rs. 10,000	Rs. 350	One Month
25	RRD on Main road Deodhar Kheelgaloo to Batour 1st ward Km. 0/00 to 2/500. (SH:- C/O PCC B/wall at RD. 0/300 to 0/314).	Rs. 3,49,919	Rs. 7,000	Rs. 350	One Month
26	RRD on Main road Deodhar Kheelgaloo to Batour 1st ward Km. 0/00 to 2/500.(SH:- C/O PCC B/wall at RD. 0/314 to 0/330).	Rs. 4,00,013	Rs. 8,100	Rs. 350	One Month
27	RRD on Deodhar Kheelgaloo road Km. 0/00 to 13/00. (SH:-C/O PCC R/wall at RD. 1/900 to 1/912).	Rs. 4,96,199	Rs. 10,000	Rs. 350	One Month
28	RRD on Deodhar Kheelgaloo road Km. 0/00 to 13/00.(SH:- C/O PCC R/wall at RD. 1/912 to 1/920).	Rs. 4,99,142	Rs. 10,000	Rs. 350	One Month
29	RRD on Deodhar Kheelgaloo road Km. 0/00 to 13/00.(SH:- C/O PCC R/wall at RD. 2/300 to 2/311).	Rs. 4,63,934	Rs. 9,300	Rs. 350	One Month
30	RRD on Deodhar Kheelgaloo road Km. 0/00 to 13/00.SH:-C/O;-PCC R/wall at RD. 2/311 to 2/320	Rs. 3,79,516	Rs. 7,600	Rs. 350	One Month
31	RRD on MDR-57 Sandhapatan Bharol Kun ka Tar Kotli Road KM 0/0-85/0.(SH:- C/o R/Wall in wire crates with Toe	Rs. 4,84,960	Rs. 9,700	Rs. 350	One Month
32	Restoration of Rain Damages on link road Old Bus Stand Kotli to Village Arnayana in Km. 0/00 to 3/00	Rs. 3,19,537	Rs. 6,400	Rs. 350	One Month

33	Restoration of road damages by laying cable for Jlo Network on various road under Mandi Sub-Division No.- III, HPPWD Mandi. (SH:- Repair of pot holes in various road under Town Section) Job No.-II.	Rs. 4,89,989	Rs. 9,800	Rs. 350	One Month
34	R.R.Damages on Tarna road km 0/00 to 1/600. (SH:- C/O B/wall at RD 0/450 to 0/462)	Rs. 1,94,365	Rs. 3,900	Rs. 350	One Month
35	Restoration of rain damaged the Foot path in Thanehra Muhalla above Visvakarma Temple Mandi, Distt. Mandi H.P. (SH:- C/O foot path with railing RD. 0/00 to 0/033).	Rs. 4,99,365	Rs. 10,000	Rs. 350	One Month
36	Restoration of rain damages in the Session House building Tarna Mandi, Distt. Mandi (H.P.). (SH:- C/O Retaining wall on approach road to Session House building at RD 0/014.50 to 0/018.00) Job No.- IV	Rs. 4,92,678	Rs. 9,900	Rs. 350	One Month
37	Restoration of rain damages in the Session House building Tarna Mandi, Distt. Mandi (H.P.). H:- C/O Retaining wall on approach road to Session House building at RD 0/011 to 0/014.50) Job No.- III	Rs. 4,92,678	Rs. 9,900	Rs. 350	One Month
38	Special repair to Doctor Residence type-IV 6 Nos Qtr. at Zonal Hospital Mandi, Distt. Mandi (H.P) (SH:- Providing & Applying and painting, distempering and other repair work)	Rs. 4,90,157	Rs. 9,900	Rs. 350	One Month
39	Special repair to Doctor Residence type-IV 6 Nos Qtr. at Zonal Hospital Mandi, Distt. Mandi (H.P) (SH:- Providing and fixing, painting, distempering, steel & wood works and other repair work)	Rs. 4,99,116	Rs. 10,000	Rs. 350	One Month
40	Repair and maintenance of Residences of Civil Judge-Cum- JMFC Court No.- II Mandi, Distt. Mandi (H.P.). (SH:- C/O retraining wall in back side of building,P/L PCC 1:5:10, Weep holes and steel work for fencing around building work etc.)	Rs. 4,84,493	Rs. 9,700	Rs. 350	One Month
41	R.R.Damages on Motipur Dudar road km 0/00 to 2/500. (SH:- C/O Retaining wall at km 2/247.50 to 2/255)	Rs. 4,58,042	Rs. 9,200	Rs. 350	One Month
42	R.R.Damages on Motipur Dudar road km 0/00 to 2/500. (SH:- C/O Retaining wall at km 2/240 to 2/247.50)	Rs. 4,60,958	Rs. 9,300	Rs. 350	One Month
43	A/R & M/O Residential building PWD Colony at Jail Road Mandi H.P. (SH:- C/O B/wall behind type-II Qtr. building Block-G).	Rs. 2,58,873	Rs. 5,200	Rs. 350	One Month
44	Repair and maintenance of addl. District & Session Judge Fast track special court (POSCO) Mandi, Distt. Mandi (HP) (SH:- C/O of R/wall in back and right side of building, removal of debries, and other repair works etc.)	Rs. 4,91,279	Rs. 9,900	Rs. 350	One Month
45	Restoration of rain damages in Session House Building at Tarna Mandi, Distt Mandi (H.P.). (SH:- C/o wire Crated Retaining wall in court Yard of building)	Rs. 4,73,286	Rs. 9,500	Rs. 350	One Month
46	Restoration of rain damages in the Session House building Tarna Mandi, Distt. Mandi (H.P.). (SH:- C/O Retaining wall on approach road to Session House building at RD 0/04.00 to 0/07.50) Job No.- 1	Rs. 4,92,678	Rs. 9,900	Rs. 350	One Month
47	Restoration of rain damages in the Session House building Tarna Mandi, Distt. Mandi (H.P.). (SH:- C/O Retaining wall on approach road to Session House building at RD 0/07.50 to 0/11.00) Job No.-2	Rs. 4,92,678	Rs. 9,900	Rs. 350	One Month
48	Special Repair of Doctor Residencial building at Zonal Hospital Mandi, Distt. Mandi (H.P.) (SH:- Construction of Roof on top floor slab over Doctor Dushyant Residence).	Rs. 2,92,973	Rs. 5,900	Rs. 350	One Month

49	R.R.D. on Dudar Bharon road Km. 0/00 to 4/00.(SH:- C/O wire cret R/wall at RD. 0/720 to 0/727.50).	Rs. 4,62,827	Rs. 9,300	Rs. 350	One Month
50	R.R.D. on Dudar Bharon road Km. 0/00 to 4/00. (SH:- C/O wire cret R/wall at RD. 0/727.50 to 0/735).	Rs. 4,62,827	Rs. 9,300	Rs. 350	One Month
51	R.R.D. on Motipur Dudar Majhwar road Km. 0/00 to 12/500. (SH:- C/O wire crate R/wall at RD. 4/517.50 to 4/525).	Rs. 4,62,827	Rs. 9,300	Rs. 350	One Month
52	R.R.D. on Motipur Dudar Majhwar road Km. 0/00 to 12/500.(SH:- C/O wire crate R/wall at RD. 5/742.50 to 5/750)	Rs. 4,62,827	Rs. 9,300	Rs. 350	One Month
53	R.R.D. on Motipur Dudar Majhwar road Km. 0/00 to 12/500. (SH:- C/O wire crate R/wall at RD. 5/750 to 5/756.25).	Rs. 3,85,683	Rs. 7,800	Rs. 350	One Month
54	RRD on Ganpati Kun Ka Tar road Km. 0/00 to 21/500. (SH:-C/O PCC R/wall at RD. 2/240 to 2/250).	Rs. 3,02,070	Rs. 6,100	Rs. 350	One Month
55	RRD on Ganpati Kun Ka Tar road Km. 0/00 to 21/500. (SH:- C/O PCC R/wall at RD. 2/250 to 2/259).	Rs. 2,72,258	Rs. 5,500	Rs. 350	One Month
56	RRD on Ganpati Kun Ka Tar road Km. 0/00 to 21/500. (SH:- C/O wire crate R/wall at RD. 2/827 to 2/833).	Rs. 4,97,735	Rs. 10,000	Rs. 350	One Month
57	RRD on Ganpati Kun Ka Tar road Km. 0/00 to 21/500. (SH:- C/O wire crate R/wall at RD. 2/833 to 2/839).	Rs. 4,47,735	Rs. 9,000	Rs. 350	One Month
58	RRD on Ganpati Kun Ka Tar road Km. 0/00 to 21/500. (SH:- C/O wire crate R/wall at RD. 2/840 to 2/846).	Rs. 4,08,993	Rs. 8,200	Rs. 350	One Month
59	RRD on Ganpati Kun Ka Tar road Km. 0/00 to 21/500. (SH:- C/O wire crate R/wall at RD. 2/846 to 2/852).	Rs. 4,09,094	Rs. 8,200	Rs. 350	One Month
60	RRD on Ganpati Kun Ka Tar road Km. 0/00 to 21/500. (SH:-C/O wire crate R/wall at RD. 2/852 to 2/859.20).	Rs. 4,90,923	Rs. 10,000	Rs. 350	One Month
61	RRD on Ganpati Kun Ka Tar road Km. 0/00 to 21/500. (SH:- C/O wire crate R/wall at RD. 19/060 to 19/072.50).	Rs. 4,82,710	Rs. 10,000	Rs. 350	One Month
62	RRD on Ganpati Kun Ka Tar road Km. 0/00 to 21/500. (SH:- C/O wire crate R/wall at RD. 19/072.50 to 19/085).	Rs. 4,82,579	Rs. 10,000	Rs. 350	One Month
63	RRD on T.P.T.S. road Km. 0/00 to 11/00. (SH:- C/O B/wall at RD. 0/350 to 0/370).	Rs. 3,79,481	Rs. 8,000	Rs. 350	One Month
64	RRD on T.P.T.S. road Km. 0/00 to 11/00. (SH:- C/O wire crates B/wall at RD. 5/680 to 5/700).	Rs. 3,68,245	Rs. 7,400	Rs. 350	One Month
65	RRD on T.P.T.S. road Km. 0/00 to 11/00.(SH:- C/O wire crates R/wall at RD. 6/295 to 6/320).	Rs. 4,99,319	Rs. 10,000	Rs. 350	One Month
66	RRD on T.P.T.S. road Km. 0/00 to 11/00. (SH:- C/O wire crates R/wall at RD. 8/030 to 8/042.50).	Rs. 4,57,946	Rs. 10,000	Rs. 350	One Month
67	RRD on Link road Rihani Dhar to Vanot via Yola road Km. 0/00 to 4/00.(SH:- C/O wire crates R/wall at RD. 1/720 to 1/730).	Rs. 3,53,237	Rs. 7,100	Rs. 350	One Month
68	RRD on Link road Rihani Dhar to Vanot via Yola road Km. 0/00 to 4/00. (SH:-C/O wire crates R/wall at RD. 2/180 to 2/190).	Rs. 3,42,231	Rs. 7,000	Rs. 350	One Month
69	R.R.D. on Chail Gohar Pandoh road Km. 24/00 to 29/600.(SH:-C/O Protection work of abutments of 6.0 mtr. span RD.28/410).	Rs. 1,98,527	Rs. 4,000	Rs. 350	One Month
70	R.R.D. on Pandoh Seyog road Km. 0/00 to 4/00. (SH:- C/O wire crates R/wall at RD. 3/010 to 3/020).	Rs. 4,13,936	Rs. 8,300	Rs. 350	One Month
71	R.R.D. on Pandoh Seyog road Km. 0/00 to 4/00. (SH:- C/O R/wall at RD. 3/315 to 3/335).	Rs. 4,80,625	Rs. 9,700	Rs. 350	One Month

72	R.R.D. on Mandi Tillin Kehanwal road Km. 1/500 to 14/400. (SH:- C/O wire crates R/wall at RD. 13/400 to 13/430).	Rs. 4,56,646	Rs. 9,200	Rs. 350	One Month
73	RRD on Ratti Pul to Alathu road Km. 0/00 to 6/500. (SH:- C/O wire crates R/wall at RD. 0/125 to 0/135)	Rs. 2,48,971	Rs. 4,900	Rs. 350	One Month
74	R.R.D. on Majhwar to Giula road Km. 0/00 to 5/480. (SH:- C/O wire crate B/wall at RD. 1/055 to 1/065).	Rs. 2,00,991	Rs. 4,100	Rs. 350	One Month
75	R.R.D. on Majhwar to Giula road Km. 0/00 to 5/480. (SH:- C/O wire crate B/wall at RD. 1/055 to 1/065).	Rs. 4,98,782	Rs. 10,000	Rs. 350	One Month
76	R.R.D. on Chambi to Kuther road Km. 0/00 to 5/300. (SH:- C/O B/wall at RD. 2/310 to 2/325).	Rs. 3,77,118	Rs. 7,500	Rs. 350	One Month
77	RRD on Nanawan to Marathu road Km. 0/00 to 1/420. (SH:- C/O wire crates B/wall at RD. 0/00 to 0/030).	Rs. 3,71,128	Rs. 7,500	Rs. 350	One Month
78	M/T & CD on Ratti Pul to Janed Panchayat Ghar road Km. 0/00 to 2/00. under SCSP (SH:- Providing and laying WBM G-I at RD. 1/600 to 2/00).	Rs. 4,00,934	Rs. 8,200	Rs. 350	One Month
79	M/T & CD on Ratti Pul to Janed Panchayat Ghar road Km. 0/00 to 2/00. under SCSP (SH:- Providing and laying WBM G-I at RD. 1/250 to 1/600).	Rs. 3,50,824	Rs. 7,100	Rs. 350	One Month
80	R.R.D. on Majhwar Moviseri via Sairi Rakhoon road Km. 0/00 to 6/800. (SH:- C/O wire cret R/wall at RD. 5/865 to 5/875).	Rs. 4,99,927	Rs. 10,000	Rs. 350	One Month
81	RR.D. on Bindrawani Majhwar Kotmorse Moviseri road Km. 0/00 to 19/800. :- C/O wire crate R/wall at RD. 3/450 to 3/460).	Rs. 4,99,927	Rs. 10,000	Rs. 350	One Month
82	R.R.D. on Bindrawani Majhwar Kotmorse Moviseri road Km. 0/00 to 19/800. (SH:- C/O wire crate R/wall at RD. 3/570 to 3/575).	Rs. 4,90,099	Rs. 9,900	Rs. 350	One Month
83	R.R.D. on Bindrawani Majhwar Kotmorse Moviseri road Km. 0/00 to 19/800. (SH:- C/O wire crate R/wall at RD. 3/575 to 3/580).	Rs. 4,90,047	Rs. 9,800	Rs. 350	One Month
84	R.R.D. on Bindrawani Majhwar Kotmorse Moviseri road Km. 0/00 to 19/800.(SH:- C/O wire crate R/wall at RD. 14/477.50 to 14/485).	Rs. 4,61,360	Rs. 9,300	Rs. 350	One Month
85	R.R.D. on Bindrawani Majhwar Kotmorse Moviseri road Km. 0/00 to 19/800. (SH:- C/O wire crate R/wall at RD. 15/090 to 15/0.97.50	Rs. 4,19,832	Rs. 8,400	Rs. 350	One Month
86	R.R.D. on Bindrawani Majhwar Kotmorse Moviseri road Km. 0/00 to 19/800. (SH:- C/O wire crate R/wall at RD. 15/097.50 to 15/103.75).	Rs. 3,56,995	Rs. 7,200	Rs. 350	One Month
87	R.R.D. on Bindrawani Majhwar Kotmorse Moviseri road Km. 0/00 to 19/800.(SH:- C/O wire crate R/wall at RD. 15/952.50 to 15/960).	Rs. 4,63,195	Rs. 9,300	Rs. 350	One Month
88	RRD on Talyahar Panjethi road Km. 0/00 to 1/225. (SH: C/O R/wall at RD. 0/950 to 0/962).	Rs. 3,21,903	Rs. 6,500	Rs. 350	One Month
89	RRD on Talyahar Pairi Road Km. 0/00 to 5/100. (SH:- C/O wire crate B/wall at RD. 3/025 to 3/050).	Rs. 4,99,235	Rs. 10,000	Rs. 350	One Month
90	R.R.D. on Link road Padhiun to Kagar road Km. 0/00 to 2/800. (SH:- C/O wire crates R/wall at RD. 0/180 to 0/217.50).	Rs. 4,69,167	Rs. 9,400	Rs. 350	One Month
91	R.R.D. on Sauli Khad to Badog road Km. 0/00 to 4/00. (SH:- C/O R/wall at RD. 0/170 to 0/182)	Rs. 4,84,871	Rs. 9,700	Rs. 350	One Month
92	R.R.D. on Sauli Khad to Badog road Km. 0/00 to 4/00. (SH:- C/O R/wall at RD. 1/310 to 1/318).	Rs. 3,50,480	Rs. 7,100	Rs. 350	One Month

cial repa
Mandi
red steel
Descri

2
Division
Includ

ater pro
reparin
etc. co
ther in

er su
s, du
to giv
rials
neer


93

93	RRD on Sauli Khad to Badog road Km. 0/00 to 4/00. (SH:- C/O wire crates R/wall at RD. 2/135 to 2/145).	Rs. 4,99,927	Rs. 10,000	Rs. 350	One Month
94	RRD on Sain to Sandoh road Km. 0/00 to 14/400. (SH:- C/O R/wall at RD. 0/240 to 0/256.50).	Rs. 4,99,803	Rs. 10,000	Rs. 350	One Month
95	RRD on Sain to Sandoh road Km. 0/00 to 14/400. (SH:- C/O wire crate R/wall at RD. 9/495 to 9/507).	Rs. 4,08,414	Rs. 8,200	Rs. 350	One Month
96	RRD on Sain to Sandoh road Km. 0/00 to 14/400. (SH:- C/O R/wall at RD. 12/430 to 12/440).	Rs. 4,90,163	Rs. 9,900	Rs. 350	One Month
97	C/O Play Ground at Govt. Senior Secondary School at Baggi Tungal Distt. Mandi H.P. (Deposit work). (SH:- C/O Path and steel work for railing). Job No. III	Rs. 4,46,182	Rs. 9,000	Rs. 350	One Month
98	R.R.D. on Khalanoo to Mahan road Km. 0/00 to 2/500. (SH:- C/O B/wall in wire crates at RD. 2/710 to 2/732.50)	Rs. 4,66,231	Rs. 9,400	Rs. 350	One Month
99	RRD on Sandhapattan Bharol Bagora Bagla Hard Ropri Kalang Traimbli Drubbal Charonj Banwar Kotli Kun Ka Tar Mandonkhar Bhargaon Kotli road Km. 70/600 to 85/00. (SH:- C/O PCC R/wall at RD. 77/350 to 77/357.50).	Rs. 2,94,358	Rs. 5,900	Rs. 350	One Month
100	A/R & M/O on Saigaloo to Suka Kun road Km. 0/00 to 4/00. (SH:- P/L WBM Grade-III for correction layer and repair of pot holes between in Km. 0/00 to 1/00 and 3/00 to 4/00).	Rs. 1,59,760	Rs. 3,200	Rs. 350	One Month
101	RRD on Gokhra Lot Khajron Batahan road Km 0/00 to 8/200 (SH :-C/O crated R/wall at Rd 0/421 to 0/428).	Rs. 4,94,126	Rs. 10,000	Rs. 350	One Month
102	RRD on Gokhra Lot Khajron Batahan road Km 0/00 to 8/200 (SH-C/O crated R/wall at Rd 0/414 to 0/424).	Rs. 4,95,141	Rs. 10,000	Rs. 350	One Month
103	RRD on Gokhra Lot Khajron Batahan road Km 0/00 to 8/200 (SH C/O crated R/wall at Rd 0/407 to 0/414).	Rs. 4,96,258	Rs. 10,000	Rs. 350	One Month
104	RRD on Gokhra Lot Khajron Batahan road Km 0/00 to 8/200 (SH :-C/O crated R/wall at Rd 0/400 to 0/407).	Rs. 4,94,633	Rs. 10,000	Rs. 350	One Month
105	C/o Rachhera Dev Temple at Rachhera in Tehsil Kotli Distt. Mandi H.P. (SH:- P/L Flamed Granite Flooring in Slab portion Job-II) (D. W)	Rs. 4,98,014	Rs. 10,000	Rs. 350	One Month
106	C/o Rachera Dev Temple at Rachera in Tehsil Kotli Distt. Mandi H.P. (SH:- P/L Flamed Granite Flooring in Lawn portion Job-I) (DW)	Rs. 4,99,771	Rs. 10,000	Rs. 350	One Month
107	A/R & M/O PWD Rest House at Satahan (Sub-Division Kotli). (SH:- Providing and fixing furnishing material)	Rs. 4,15,303	Rs. 8,400	Rs. 350	One Month
108	A/R & M/O PWD Rest House at Kotli (Sub-Division Kotli). (SH:- Providing and fixing furnishing material)	Rs. 2,18,840	Rs. 4,400	Rs. 350	One Month
109	RRD on Sain to Sandoh road Km. 0/00 to 14/400. (SH: C/O R/wall at RD. 11/986 to 12/00).	Rs. 4,11,466	Rs. 8,300	Rs. 350	One Month
110	Special repair of SDM quarter No. 2 GAD Type-IV residential building at jail road Mandi, Distt. Mandi (H.P) (SH:- P/L Distempering, Painting, primer & wood work, cup board and preprinted steel sheet etc.)	Rs. 2,91,106	Rs. 3,000	Rs. 350	One Month

certificated that tender of above works are being called of emergent nature in exigency of public interest.

GENERAL CONDITIONS: -

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that, he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject accept any or all the tenders without assessing any reason.


Executive Engineer
Mandi Division No. II
HP.PWD Mandi

No.PW-MDII-CB NIT (off line) /2023-

14944-59

Dated:- 26/9/2023

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-chief, HPPWD: Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP
3. The Sub Divisional officer (Civil) Sadar Mandi Distt. Mandi HP
4. The Chief Engineer, (MZ)HPPWD: Mandi.
5. The Superintending Engineer, 1st Circle, HPPWD: Mandi.
6. The Distt. Panchyat officer Mandi Distt. Mandi HP
7. The Commissioner Nagar Nigam Mandi Distt. Mandi HP
8. All A.E,S under this division.
9. The President of Contractor's Association.
10. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies


Executive Engineer
Mandi Division No. II
HP.PWD Mandi

Name of work :- Construction of link road Dobra Bath to Pump House Dawada Km. 0/00 to 5/00.
(SE:- C/O 900mm dia RCC Hume pipe Culvert at RD. 2/720 including wing walls).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 3,18,810/-
Earnest Money Rs. 6400/-
Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	5.85	195.00	Rupees One Hundred Ninety Five Only	Per Cubic Metre	1,141.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	44.27	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	23,202.00
3	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	4.00	5840.05	Rupees Five Thousand Eight Hundred Forty and Paise Five Only	Per Cubic Metre	23,360.00
4	Providing concrete for plain concrete 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed in open foundation complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals.	11.20	6318.75	Rupees Six Thousand Three Hundred Eighteen and Paise Seventy Five Only	Per Cubic Metre	70,770.00
5	Providing and laying 900mm dia (Nine hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals.	7.50	4360.10	Rupees Four Thousand Three Hundred Sixty and Paise Ten Only	Per Running metre	32,701.00
6	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification Clause 1303 Rubble stone laid in cement mortar 1:3 (One cement : three sand) Earth work in excavation and cement concrete for bedding to be measured and paid for separately including carriage of materials with in all leads, lifts and other incidentals.	0.45	3858.30	Rupees Three Thousand Eight Hundred Fifty Eight and Paise Thirty Only	Per Cubic Metre	1,736.00
7	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	28.46	5185.20	Rupees Five Thousand One Hundred Eighty Five and Paise Twenty Only	Per Cubic Metre	1,47,571.00

<p>9</p> <p>Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.</p>	18.00	358.05	Rupees Three Hundred Fifty Eight and Paise Five Only	Each	6,445.00
<p>Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.</p>	7.84	1515.85	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	11,884.00
<p>Total</p>					3,19,810.00


 Executive Engineer,
 Mainli Division No-II,
 H.P. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Work :- C/O Link road from Chh Khola to Thanker Nichia Barnota Km. 0/0 to 2/0.
 (\$1% ROFD between km 0/00 to 0/210).

Estimated Cost Rs. 2,20,749/-
 Earnest Money Rs. 4500/-
 Time:- One month.

1	Description of items.	Quantity	Figure	Rates	Unit	Amount
			4	5		
2	Excavation in soil in Hilly area by all means in all kinds of soil such as pick work, jumper work, blasting work both in soft and hard rock with chiselling/wedging out rock (where blasting is prohibited) and other intermediate classification of soil including cutting and trimming of side slopes and disposal of unserviceable material by all modes of transport and stacking the serviceable/useful material and disposal of unserviceable materials upto all leads and lifts, disposed earth to be levelled and neatly dressed as per technical specification or directed by the Engineer-in-charge. The recovery of 75.34 cubic metre for useful stones @ Rs. 300/- per cubic metre amounting to Rs. 22,602/- only, shall be done on pro-rata basis for the quantity of cutting in earth work effected. The work shall be executed in workman like manner and avoids any damages to the private/Govt. property in the vicinity of work site. If damage access to any property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	3 752.64	293.30	Rupees Two Hundred Ninety Three and Pause Thirty Only	6 Per Cubic Metre	7 220,749.00
2	Less credit for useful stone- the recovery for useful stone shall be deducted from each running bill of the contractor on pro-rata basis against item No.1	75.34	300.00	Rupees Three Hundred Only	Total	220,749.00
					Total	198,147.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

2

Name of work:- **C/O Link road Ropri to Tehrehar via Galoo Km.0/00 to 1/00.**
 (SH:- C/O R/wall at RD. 0/005 to 0/020.)

%age Rate of SCHEDULE OF QUANTITY

Estimated cost Rs. 2,35,393/-
 Earnest cost Rs. 4700/-
 Time:- One Month

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	20.70	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	10,849
2	Random rubble masonry in cement mortar for substructure (complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar (1:6) (One cement : six sand) including carriage of materials with in all leads, lifts and other incidentals.	5.70	5529.5	Rupees Five Thousand Five Hundred Twenty Nine and Paise Fifty Only	Per Cubic Metre	31,518
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	30.15	5569.35	Rupees one thousand nine hundred thirty three and paise sixty only.	Per Cubic Metre	167,916
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments wing wall. return wall with 100mm (one hundred millimetre) dia. PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	28.00	358.35	Rupees Three Hundred Fifty Eight and Paise Thirty Five Only	Each	10,034
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	9.00	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	15,076
Total						235,393


 Executive Engineer
 Mandi Division No.-II
 H.P.P.W.D. Mandi

Name of work :- RRD on Gatterbag to upper Thanout road Km. 0/00 to 8/200
 (SH:- C/O R/wall at RD. 1/750 to 1/760).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 3,98,442/-
 Earnest Money-Rs. 8000/-

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing; removal of stumps and other deleterious material and disposal upto every level of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	29.40	493.90	Rupees Four Hundred Ninety Three and Paise Ninety Only	Per Cubic Metre	14,521.00
2	Providing and laying 1:5:10 (One cement: five sand: ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations including form work as per drawing and technical specifications clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	68.90	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	3,68,648.00
3	Back filling behind abutment wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.50	1450.85	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	12,332.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	8.00	365.70	Rupees Three Hundred Sixty Five and Paise Seventy Only	Each	2,926.00
		Total				3,98,422.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

%Rate Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Batahar to Batahan road Km. 0/00 to 6/400.
(SH:- C/O P.C.C.R/wall in Km.0/050 to 0/062).

Estimated Cost Rs. 4,80,999/-
Earnest Money Rs.9700/-
Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	3	493.90	Rupees Four Hundred Ninety Three and Paise Ninety Only	Per Cubic Metre	22,522.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	82.68	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	442,371.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	7.32	1450.85	Rupees One Thousand Four Hundred Fifty and Paise Eighty Five Only	Per Cubic Metre	10,620.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (One hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	15.00	365.70	Rupees Three Hundred Sixty Five and Paise Seventy Only	Each	5,486.00
Total:-						480,999.00


Executive Engineer
 Mandi Division No.-II
 H.P.P.W.D. Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Saigaloo Nahlog road Km. 0/00 to 6/400.
(SH- C/O PC.C.R/wall in Km.4/180 to 4/192).

Estimated Cost Rs. 471,230/-
 Earnest Money Rs.9500/-
 Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	26.28	493.90	Rupees Four Hundred Ninety Three and Paise Ninety Only	Per Cubic Metre	12,980.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	82.68	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	442,371.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	7.92	1450.85	Rupees One Thousand Four Hundred Fifty and Paise Eighty Five Only	Per Cubic Metre	11,491.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (One hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	12.00	365.70	Rupees Three Hundred Sixty Five and Paise Seventy Only	Each	4,388.00
Total:-						471,230.00


Executive Engineer
 Mandl Division No.-II
 H.P.P.W.D. Mandl

Name of work :- R.R.D.on Kushnada to Samrahan road Km. 0/00 to 3/00.
(SH:- C/O wire Crate R/wall at RD. 1/130 to 1/345).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 3,98,832/-
Earnest Money Rs. 8000/-

Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m(fifty metre) dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	11.05	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	4,800.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and (technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	108.90	3452.16	Rupees Three Thousand Four Hundred Fifty Two and Paise Sixteen Only	Per Cubic Metre	375,940.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	10.80	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	18,092.00
Total						398,832.00

Executive Engineer,
Mandi Division No-II,
HP: PWD, Mandi

Name of work : C/O Main road Deodhar to Batour 1st ward Km. 0/00 to 3/500.
 (SH: C/O PCC B/wall at RD. 0/315 to 0/330) Under SCSP

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 2,79,701/-
 Earnest Money Rs.5,600/-
 Time : One month.

1	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals	14.55	193.90	Rupees Four Hundred Ninety Three and Paise Ninety Only	Per Cubic Metre	7,186.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	50.25	5350.10	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	2,68,858.00
3	Providing weep holes in brickmasonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm AC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	10.00	365.70	Rupees Three Hundred Sixty Five and Paise Seventy Only	Each	3,657.00
Total						2,79,701.00

Executive Engineer


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

Name of work :- C/O Gatterbag to Upper Thanout Km. 0/00 to 8/200.
 (SH:- C/O PCC B/wall at RD. 6/675 to 6/700)

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 4,68,118/-
 Earnest Money Rs.9,400/-
 Time :- One month.

1	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
2		3	4	5	6	7
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals	24.25	493.90	Rupees Four Hundred Ninety Three and Paise Ninety Only	Per Cubic Metre	11,977.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	83.75	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	4,48,096.00
3	Providing weep holes in brickmasonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm AC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	22.00	365.70	Rupees Three Hundred Sixty Five and Paise Seventy Only	Each	8,045.00
Total						4,68,118.00


 Security Engineer,
 Mandi Division No-11,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain Damages on link road Old Bus Stand Kothi to Village Aranyana in Km. 0/00 to 3/00.

Estimated Cost Rs. 4,99,325/-
Earrest Money Rs. 10000/-

Time :- One month

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Providing concrete for plain/reinforced concrete 1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 20mm (Twenty millimetre nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203, including carriage of materials with in all leads, lifts and other incidentals.	7.45	8132.90	Rupees Eight Thousand One Hundred Thirty Two and Paise Ninety Only	Per Cubic Metre	60,590.00
2	Steel work welded in built up sections, trusses and framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in gratings framed guard bars, ladders, railing, brackets and similar works including carriage of materials with in all leads, lifts and other incidentals.	643.68	125.90	Rupees One Hundred Twenty Five and Paise Ninety Only	Per kilogram	81,039.00
3	Providing and laying 450mm dia (Four hundred fifty millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals.	248.40	1440.00	Rupees One Thousand Four Hundred Forty Only	Per Running metre	3,57,696.00
					Total	4,99,325.00


 Engineer,
 Mandi Division No.11,
 H.P. PWD, Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D.on Kun Galoo to Baroha Ropa Matyahal road Km. 0/00 to 2/500.
(SH:- C/O P.C.C R/wall at RD. 0/790 to 0/800).

Estimated Cost Rs. 2,09,619/-
Earnest Money Rs. 5000/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
		3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	18.20	190.40	Rupees One Hundred Ninety and Paise Forty Only	Per Cubic Metre	3,465.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	35.30	5185.20	Rupees Five Thousand One Hundred Eighty Five and Paise Twenty Only	Per Cubic Metre	183,038.00
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia.PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	24.00	350.50	Rupees Three Hundred Fifty and Paise Fifty Only	Each	8,412.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	9.70	1515.85	Rupees One Thousand Five Hundred Fifteen and Paise Eighty Five Only	Per Cubic Metre	14,704.00
Total						209,619.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Estimate of work :- C/O Bhargava to Alag via Tulla road Km. 0/00 to 2/00.
(SE:- C/O B/wall at RD. 1/345 to 1/355).

Estimated Cost Rs. 2,11,827/-
Earnest Money Rs. 4300/-
Time :- One month.

Sr.	Description of Items.	Quantity	Rates	Words	Unit	Amount
			Figure			
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including cartage of materials with in all leads, lifts and other incidentals.	3	195.00	Rupees One Hundred Ninety Five Only	Per Cubic Metre	5,969.00
2	Bedding work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	3.00	524.70	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	1,572.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specifications clauses 802, 803, 1202 and 1203 including cartage of materials with in all leads, lifts and other incidentals.	36.80	5441.20	Rupees Five Thousand Four Hundred Forty One and Paise Twenty Only	Per Cubic Metre	2,00,236.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including cartage of materials with in all leads, lifts and other incidentals.	18.00	358.35	Rupees Three Hundred Fifty Eight and Paise Thirty Five Only	Each	6,450.00
	Total					2,11,827.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

Name of work :- R.R.D. on Kun Galoo to Baroha Ropa Matyahal road Km. 0/00 to 2/500.
(SH: C/O P.C.C.R/wall at RD. 0/780 to 0/790).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 1,90,071/-
Earnest Money Rs. 3900/-
Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	17.50	190.40	Rupees One Hundred Ninety and Paise Forty Only	Per Cubic Metre	3,332.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimeter nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	32.40	5185.20	Rupees Five Thousand One Hundred Eighty Five and Paise Twenty Only	Per Cubic Metre	168,000.00
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abuments wing wall, return wall with 100mm (one hundred millimetre) dia. PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	18.00	350.50	Rupees Three Hundred Fifty and Paise Fifty Only	Each	6,309.00
4	Back filling behind abument, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.20	1515.85	Rupees One Thousand Five Hundred Fifteen and Paise Eighty Five Only	Per Cubic Metre	12,430.00
	Total					190,071.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi. S

%age Rate of SCHEDULE OF QUANTITY

Name of work : RRD on Sandhapatana Bharol Bangora Bard Ropri Kalg, Trainball Basahl Drubal, Chauranj,
 Banwar, Kun-Ka-Tar Mandhoker Bhargoon Kotli road Km. 70/600 to 85/00.
 (SH:- C/O Wire crate R/wall at RD. 72/665 to 72/675).

Estimated Cost Rs. 2,32,372/-
 Earnest Money Rs. 4700/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	28.80	524.10	Rupees Five Hundred Twenty-Four and Paise Ten Only	Per Cubic Metre	15,094.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia. GI wire conforming to IS. 280 and IS.4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	62.94	3452.15	Rupees Three Thousand Four Hundred Fifty Two and Paise Fifteen Only	Per Cubic Metre	2,17,278.00
	Total					2,32,372.00


 Executive Engineer,
 Mandi Division No-11,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work : RRD on Roda Nallah to Farroh Arthi road Km. 0/00 to 12/00.
(SR:- C/O Wire crate R/wall at RD. 9/894 to 9/896.50).

Estimated Cost Rs. 2,91,531/-
 Earnest Money Rs. 5900/-
 Time : One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto sixy feet of 50cm dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	38.00	52410	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	19,916.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	78.68	345215	Rupees Three Thousand Four Hundred Fifty Two and Paise Fifteen Only	Per Cubic Metre	2,71,615.00
Total						2,91,531.00


 Executive Engineer,
 Majdi Division No-II,
 HP. PWD, Mandi.

115

Name of work :- R.R.D.on Kun to Padhar road Km. 0/00 to 1/500.
 (SH:- C/O P.C.C R/wall at RD. 0/560 to 0/575).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 4,34,437/-
 Earnest Money Rs. 8700/-
 Time :- One month.

Sl. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m(fifty metre) dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	34.20	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	14,855.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	72.90	5185.20	Rupees Five Thousand One Hundred Eighty Five and Paise Twenty Only	Per Cubic Metre	378,001.00
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia.PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	33.00	350.50	Rupees Three Hundred Fifty and Paise Fifty Only	Each	11,567.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	19.80	1515.85	Rupees One Thousand Five Hundred Fifteen and Paise Eighty Five Only	Per Cubic Metre	30,014.00
Total						434,437.00

MS


 Engineer,
 Meadi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work : RRD on Deodhar Kheelgaloo road Km. 0/00 to 16/00.
 (SH:- C/O PCC R/wall at RD. 13/900 to 13/912).

Estimated Cost Rs. 4,06,199/-
 Earnest Money Rs. 8200/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	20.04	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only.	Per Cubic Metre	10,503.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations, complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	68.04	544.20	Rupees Five Thousand Four Hundred Forty One and Paise Twenty Only	Per Cubic Metre	3,70,219.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	12.00	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	20,102.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (N) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	15.00	358.35	Rupees Three Hundred Fifty Eight and Paise Thirty Five Only	Each	5,375.00
Total						4,06,199.00



 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Saha Gajra Ropru road Km. 0/00 to 14/00.
(SH:- C/O Wire crate R/wall at RD. 10/490 to 10/503.75).

Estimated Cost Rs. 4,82,880/-
 Earnest Money Rs. 10000/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	79.94	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	41,897.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS-4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	101.56	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	3,72,578.00
3	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 including hauling/carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	135.63	119.00	Rupees One Hundred Nineteen Only	Per Cubic Metre	16,140.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	31.20	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	52,265.00
	Total					4,82,880.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi. 2


name of work :- R.R.D. on Madan Ka Ghar to Samrahan road Km. 0/00 to 07/200.
(SH:- C/O PCC Toe wall cum wire crate R/wall at RD. 04/500 to 04/508.75).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 3,34,614/-
Earnest Money Rs. 6700/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	57.84	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	25,123.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	18.00	5185.20	Rupees Five Thousand One Hundred Eighty Five and Paise Twenty Only	Per Cubic Metre	93,334.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	50.40	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	184,895.00
4	Construction of Embankment with approved material obtained from borrow pits with any lift, transporting to site spreading, grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with any lead as per technical specification Clause 301.5 including carriage of materials with in all leads, lifts and other incidentals.	67.81	119.00	Rupees One Hundred Nineteen Only	Per Cubic Metre	8,069
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	15.30	1515.85	Rupees One Thousand Five Hundred Fifteen and Paise Eighty Five Only	Per Cubic Metre	23,193.00
		Total				334,614.00




Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Madan Ka Ghar to Samrahan road Km. 0/00 to 07/200.
 (SH:- C/O PCC Toe wall cum wire crate R/wall at RD. 04/508.75 to 04/517.50).

Estimated Cost Rs. 3,72,426/-
 Earnest Money Rs. 7500/-
 Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	46.46	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	20,180.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	18.00	5185.20	Rupees Five Thousand One Hundred Eighty Five and Paise Twenty Only	Per Cubic Metre	93,334.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	61.20	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	224,515.00
4	Construction of Embankment with approved material obtained from borrow pits with any lift, transporting to site spreading, grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with any lead as per technical specification Clause 301.5 including carriage of materials with in all leads, lifts and other incidentals.	82.69	119.00	Rupees One Hundred Nineteen Only	Per Cubic Metre	9,840
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	16.20	1515.85	Rupees One Thousand Five Hundred Fifteen and Paise Eighty Five Only	Per Cubic Metre	24,557.00
					Total	372,426.00

10


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

Name of work :- R.R.D. on Gaterbag to Chaloh road Km. 0/00 to 8/200.
(SH:- C/O PCC R/wall at RD. 0/824 to 0/829).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 2,03,243/-
Earnest Money Rs. 4100/-
Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	7.00	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	4,002.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	35.05	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	187,532.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	5.55	1450.85	Rupees One Thousand Four Hundred Fifty and Paise Eighty Five Only	Per Cubic Metre	8,052.00
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (One hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	10.00	365.70	Rupees Three Hundred Sixty Five and Paise Seventy Only	Each	3,657.00
Total						203,243.00

21


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY


Name of work :- A/R & M/O HPPWD Rest House at Kottli, Tehsil Kottli, Distt. Mandi H.P.
(SH:- Dismantling of roof & wood work, steel work, painting, concrete work and supply of furniture)

Estimated Cost Rs. 4,02,114/-
Earliest Money Rs. 8100/-
Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Dismantling roofing including ridges, hips, valleys, gutters etc. stacking the serviceable materials and disposal of un-serviceable materials with any lead (slate roofing) including carriage of materials with in all leads, lifts and other incidentals.	3	99.35	Rupees Ninety Nine and Paise Thirty Five Only	Per square metre	6815.00
2	Dismantling wood work in frames, trusses, purlins and rafters up to 10 (ten) metres span and 5 (five) metres height including stacking the material upto any lead : of sectional area below 40 (forty) square centimetres including carriage of materials with in all leads, lifts and other incidentals.	39.20	10.80	Rupees Ten and Paise Eighty Only	Per running metre	423.00
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of materials with in all leads, lifts and other incidentals.	1427.16	100.80	Rupees One Hundred and Paise Eighty Only	Per Kilogram	143858.00
4	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm (eight millimetre) diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal / vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required 0.63 mm (zero point six three millimetre) thick with zinc coating not less than 275 gm / m ² including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge	79.18	925.50	Rupees Nine Hundred Twenty Five and Paise Fifty Only	Per Square metre	73281.00
5	Providing ridges or hips of width 60 cm (sixty centimetre) overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm (eight millimetre) dia. G.I. limpet and bitumen washers complete. 0.63 mm (zero point six three millimetre) thick with zinc coating not less than 275 gm/m ² including carriage of materials with in all leads, lifts and other incidentals.	4.40	659.50	Rupees Six Hundred Fifty Nine and Paise Fifty Only	Per running metre	2902.00
6	Providing valleys of 90 cm (ninety centimetre) wide overall in plain G.S. sheet fixed with polymer coated J, or L hooks, bolts and nuts 8 mm (eight millimetre) dia G.I. limpet and bitumen washers complete : 1.60 mm (one point six zero millimetre) thick with zinc coating not less than 350 gm/m ² (three hundred fifty grams per square metre) including carriage of materials with in all leads, lifts and other incidentals.	6.00	1302.40	Rupees One Thousand Three Hundred Two and Paise Forty Only	Per running metre	7814.00
7	Providing and fixing 15 cm (fifteen centimetre) wide, 45 cm (forty five centimetre) overall semicircular plain G.S. sheet gutter with iron brackets 40x3mm (forty three millimetre) size, bolts, nuts and washers etc., including making necessary connections with rain water pipes complete. 0.63 mm (zero point six three millimetre) thick with zinc coating not less than 275 gm/m ² (two hundred seventy five grams per square metre) including carriage of materials with in all leads, lifts and other incidentals.	20.10	651.90	Rupees Six Hundred Fifty One and Paise Ninety Only	Per running metre	13103.00

22

8	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr / 10 sqm (at the rate of zero point nine zero litre per ten square metre) over an under coat of primer applied @ 0.80 ltr / 10 sqm (at the rate of zero point eight zero litre per ten square metre) of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidentals.	131.64	111.60	Rupees One Hundred Eleven and Paise Sixty Only	Per square metre	14691.00
9	Providing and fixing plain Asbestos Cement sheet ceiling with butt jointing and screws (Frame work and cover fillets to be measured and paid for separately) 6mm (six millimetre) thick Asbestos Cement sheet including carriage of materials with in all leads, lifts and other incidentals.	2.88	730.10	Rupees Seven Hundred Thirty and Paise Ten Only	Per square metre	2103.00
10	Providing plinth protection 50mm (fifty millimetre) thick in cement concrete 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm nominal size mechanically mixed finishing the surface of concrete smooth including carriage of materials with in all leads, lifts and other incidentals.	46.10	510.00	Rupees Five Hundred Ten Only	Per Square metre	23511.00
11	Providing under layer for plinth protection of 75mm (seventy five millimetre) thick (unconsolidated bed dry brick/stone aggregate 40mm (forty millimetre) nominal size) well rammed including preparation of ground including carriage of materials with in all leads, lifts and other incidentals.	46.10	330.60	Rupees Three Hundred Thirty and Paise Sixty Only	Per Square metre.	15241.00
12	Demolishing cement concrete nominal concrete 1:3:6 or leaner mix (including equivalent design mix) manually/ by mechanical means including disposal of material upto any lead as per direction of Engineer - in - charge including carriage of materials with in all leads, lifts and other incidentals.	4.39	1451.40	Rupees One Thousand Four Hundred Fifty One and Paise Forty Only	Per Cubic Metre	6372.00
13	Supply of steel Almirah for rooms including carriage of materials with in all leads, lifts and other incidentals.	4.00	23000.00	Rupees Twenty Three Thousand Only	Each	92000.00
	Total					4,02,114.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Gaterbag to Chaloh road Km. 0/00 to 8/200.
(SH:- C/O PCC R/wall at RD. 0/800 to 0/812).

Estimated Cost Rs. 4,99,009/-
 Earnest Money Rs. 10000/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	14.40	571.75	Ruppes Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	8,233.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	87.50	5350.40	Ruppes Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	4,68,160.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	13.32	1450.85	Ruppes Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	19,325.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	9.00	365.70	Ruppes Three Hundred Sixty Five and Paise Seventy Only	Each	3,291.00
Total						4,99,009.00


 Executive Engineer,
 Mandi Division No-11,
 H.P. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :: RRD on Gaterbag to Chaloh road Km. 0/00 to 8/200.
(SH:- C/O PCC R/wall at RD, 0/812 to 0/824).

Estimated Cost Rs. 4,99,741/-
Earnest Money Rs. 10000/-
Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount.
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	14.40	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	8,233.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	87.50	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	4,68,160.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	13.32	1450.85	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	19,325.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	11.00	365.70	Rupees Three Hundred Sixty Five and Paise Seventy Only	Each	4,023.00
	Total					4,99,741.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

Name of work :- RRD on Main road Deodhar Kheelgaloo to Batour 1st ward Km. 0/00 to 2/500.
 (SH:- C/O PCC B/wall at RD. 0/300 to 0/314).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 3,49,919/-
 Earnest Money Rs. 7000/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	16.10	571.75	Ruppes Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	9,205.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	62.86	5350.40	Ruppes Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	3,36,326.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	12.00	365.70	Ruppes Three Hundred Sixty Five and Paise Seventy Only	Each	4,388.00
Total						3,49,919.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

25

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Main road Deodhar Kheelgaloo to Batour 1st ward Km. 0/00 to 2/500.
(SH:- C/O FCC B/wall at RD. 0/314 to 0/330).

Estimated Cost Rs. 4,00,013/-
Earnest Money Rs. 8100/-
Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	18.40	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	10,520.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	71.84	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	3,84,373.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	14.00	365.70	Rupees Three Hundred Sixty Five and Paise Seventy Only	Each	5,120.00
Total						4,00,013.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work : RRD on Deodhar Kheelgaloo road Km. 0/00 to 13/00.
(SH:- C/O PCC R/wall at RD. 1/900 to 1/912).

Estimated Cost Rs. 4,96,199/-
Earnest Money Rs. 10000/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	16.80	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	9,605.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	86.65	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	4,63,612.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	13.32	1450.85	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	19,325.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	10.00	365.70	Rupees Three Hundred Sixty Five and Paise Seventy Only	Each	3,657.00
Total						4,96,199.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Deodhar Kheolgaloo road Km. 0/00 to 13/00.
(SH: C/O PCC R/wall at RD. 1/912 to 1/920).

Estimated Cost Rs. 4,99,142/-
Earnest Money Rs. 10000/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	16.80	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	9,605.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	87.20	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	4,66,555.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	13.32	1450.85	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	19,325.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	10.00	365.70	Rupees Three Hundred Sixty Five and Paise Seventy Only	Each	3,657.00
Total						4,99,142.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Deodhar Kheelgaloo road Km. 0/00 to 13/00.
(SH:- C/O PCC R/wall at RD. 2/300 to 2/311).

Estimated Cost Rs. 4,63,934/-
Earnest Money Rs. 9300/-
Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	15.40	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	8,805.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specifications clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	81.07	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	4,33,757.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	12.21	1450.85	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	17,715.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	10.00	365.70	Rupees Three Hundred Sixty Five and Paise Seventy Only	Each	3,657.00
Total						4,63,934.00


 Executive Engineer,
 Marghi Division No-II,
 HP. PWD, Mandi.

Name of work :- RRD on Deodhar Kheegaloo road Km. 0/00 to 13/00.
(SH:- C/O PCC R/wall at RD. 2/311 to 2/320).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 3,79,516/-
Earnest Money Rs. 7600/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	12.60	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	7,204.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	66.33	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	3,54,892.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	9.99	1450.85	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	14,494.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (N) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	8.00	365.70	Rupees Three Hundred Sixty Five and Paise Seventy Only	Each	2,926.00
Total						3,79,516.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on MDR-57 Sandhapattan Bharol Kun ka Tar Kold Road KM 0/0 - 85/0 (SH:- C/o R/Wall in wire crates with Toe wall at RD 74/020 - 74/032.5)

Estimated Cost Rs. 4,84,960/-
Earnest Money Rs. 9700/-
Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	28.25	487.31	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	13,767.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	9.00	5569.33	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	50,124.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	119.63	3452.16	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	4,12,982.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.25	980.29	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	8,087.00
	Total					4,84,960.00


 Executive Engineer,
 Mandi Division No-II,
 P.W.D, Mandi.

3

Name of work :- Restoration of Rain Damages on link road Old Bus Stand Kothi to Village Aranyana In Km. 0/00 to 3/00.

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 3,19,537/-
Earrest Money Rs. 6400/-

Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation soil in Hillly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	16.92	195.00	Rupees One Hundred Ninety Five - Only	Per Cubic Metre	3,299.00
2	Barth... .. in all kinds of soil for structure... .. drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of strumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	128.68	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	67,441.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	10.31	5441.20	Rupees Five Thousand Four Hundred Forty One and Paise Twenty Only	Per Cubic Metre	56,099.00
4	Constructing brick masonry manhole in cement mortar 1:4 (one cement : four coarse sand) with R.C.C. top slabwith 1:1.5:3 mix (one cement : one point five coarse sand (zone - III) : three graded stone aggregate 20 mm (twenty millimetre) nominal size), foundation concrete 1:4:8 mix (one cement : four coarse sand (zone- III) : eight graded stone aggregate 40 mm (forty millimetre) nominal size), inside plastering 12 mm (twelve millimetre) thick with cement mortar 1:3 (one cement : three coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm (twenty millimetre) nominal size) finished with a floating coat of neat cement complete as per standard design : Inside size 120x90 cm (one hundred twenty into ninety centumetre) and 90 cm (ninety centumetre) deep including C.I. cover with frame (medium duty) 500 mm (five hundred millimetre) internal diameter, total weight of cover and frame to be not less than 116 kg (one hundred sixteen kilogram) (weight of cover 58 kg (fifty eight kilogram) and weight of frame 58 kg (fifty eight kilogram) : With Sewer bricks conforming to IS : 4885 including carriage of materials with in all leads, lifts and other incidentals.	9.00	21410.90	Rupees Twenty One Thousand Four Hundred Ten and Paise Ninety Only	Each	1,92,698.00
Total						3,19,537.00

29


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damages by laying cable for Jio Network on various road under Mandi Sub-Division No.-III, HPPWD Mandi.
(SH:- Repair of pot holes in various road under Town Section) Job No.-II.

Estimated Cost Rs. 4,89,989/-
Earnest Money Rs. 9,800/-
Time :- Two Months.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN in static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-III Technical Specification Clause 405, including carriage of materials with in all leads, lifts and other incidentals.	18.71	3007.75	Rupees Three Thousand Seven and Paise Seventy Five Only	Per Square metre	56,275.00
2	Providing and applying tack coat with Bitumen (VG-10) using bitumen distributor at the rate of 0.25 to 9.30 Kg per sqm (zero point two five to nine point three zero kilogram per square metre) on the prepared granular surface treated with prices and cleaned with Hydraulic broom as per Technical Specification Clause 503, including carriage of materials with in all leads, lifts and other incidentals.	1247.56	22.60	Rupees Twenty Two and Paise Sixty Only	Per Square metre	28,195.00
3	20 mm thick open graded Premix Carpet using Bituminous (S-90/VG-10) penetration grade Binder. Providing and laying by manual mean and rolling of open graded premix carpet of 20 mm thickness composed of 13.2mm to 5.6mm (Thirteen point two millimetre to five point six millimetre) aggregates other using penetration grade bitumen (S-90/V-10) to required line, grade and level to serve as wearing course on a previously prepared surface/ base including mixing in a suitable plant, laying and rolling with a three wheel 80-100 KN (eighty-hundred KN) static roller capacity, finished to required level and grade to be followed by seal coat of Type B as per Technical Specification clause 508, including carriage of materials with in all leads, lifts and other incidentals.	1247.56	247.50	Rupees Two Hundred Forty Seven and Paise Fifty Only	Per Square metre	3,08,771.00
4	Providing and laying seal coat by manual means Bitumen (S-90/V-10) sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type B as per Technical Specification clause 510, including carriage of materials with in all leads, lifts and other incidentals.	1247.56	77.55	Rupees Seventy Seven and Paise Fifty Five Only	Per Square metre	96,748.00
	Total					4,89,989.00


 Executive Engineer,
 Mandi Division No-II,
 HPPWD, Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.Damages on Tarna road km 0/00 to 1/600.
(SH:- C/O B/wall at RD 0/450 to 0/462)

Estimated Cost Rs. 1,94,365/
Earnest Money Rs. 3,900/-
Time :- One Month

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	23.88	194.95	Rupees One Hundred Ninety Four and Paise Ninety Five Only	Per Cubic Metre	4,655.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m (fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge.	7.98	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	4,563.00
3	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40mm (Forty millimetre nominal size) including carriage of materials with in all leads, lifts and other incidentals.	32.25	5741.00	Rupees Five Thousand Seven Hundred Forty One Only	Per Cubic Metre	1,85,147.00
	Total					1,94,365.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi


%age Rate of SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damaged the Foot path in Thanerha Muballa above Visvakarma Temple Mandl, Distt. Mandl
H.P. (SH:- C/O foot path with railing RD. 0/00 to 0/033).

Estimated Cost Rs. 4,99,20/-
Earnest Money Rs. 10000/-
Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	2.79	497.90	Rupees Four Hundred Ninety Seven and Paise Ninety Only	Per Cubic Metre	1,37,55
2	Providing concrete for plain concrete 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed in open foundation complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other Incidentals.	2.79	6742.20	Rupees Six Thousand Seven Hundred Forty Two and Paise Twenty Only	Per Cubic Metre	18,81
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials with in all leads, lifts and other incidentals.	1174.09	122.35	Rupees One Hundred Twenty Two and Paise Thirty Five Only	Per Kilogram	1,43,65
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials with in all leads, lifts and other incidentals.	1392.30	140.20	Rupees One Hundred Forty and Paise Twenty Only	Per Kilogram	1,95
5	Providing and fixing Chequered MS BP sheet 3.00mm (three point zero zero millimetre) thick in eaves board/face/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-In-Charge (Base members of steel work shall be measured & paid separately) with in all leads and lifts of materials and other incidentals.	39.60	3539.30	Rupees Three Thousand Five Hundred Thirty Nine and Paise Thirty Only	Per Square Metre	1,40,15
Total						4,99,20

25


 Engineer,
 Mandl Division No-II,
 H.P. P.W.D. Mandl


%AGE RATE OF SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages in the Session House building Tarna Mandi, Distt. Mandi (H.P.).

(SH:- C/O Retaining wall on approach road to Session House building at RD 0/014.50 to 0/018.00) Job No.- IV Earnest Money Rs. 9,900/-

Estimated cost Rs. 4,92,678/-
Time:- One Month.


Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	46.94	194.45	Rupees One Hundred Ninety Four and Paise Forty Five Only	Per Cubic Metre	9,127.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of strumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals.	7.56	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	4,322.00
3	Providing and laying Plain cement concrete 1:5:10 (one cement : five sand : ten graded crushed stone aggregate) nominal mix in open foundation with crushed stone aggregate 40mm (forty millimetre) nominal size mechanically mixed including cost of form work and curring complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental or as per the direction of Engineer-in-charge. The rate including Royalty, Malkhana, Octroi, toll tax, sales tax or any other taxes imposed by the Government including carriage of materials with in all leads, lifts and other incidentals.	79.38	5938.75	Rupees Five Thousand Nine Hundred Thirty Eight and Paise Seventy Five Only	Per cubic metre	4,71,418.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	20	390.55	Rupees Three Hundred Ninety and Paise Fifty Five Only	Each	7,811.00
	Total					4,92,678.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

%AGE RATE OF SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages in the Session House building Tarna Mandi, Distt. Mandi (H.P.),
 (SH:- C/O Retaining wall on approach road to Session House building at RD 0/011 to 0/014.50) Job No.- III
 Estimated cost Rs. 4,92,678/-
 Earnest Money Rs. 9,900/-
 Time:- One Month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	46.94	194.45	Rupees One Hundred Ninety Four and Paise Forty Five Only	Per Cubic Metre	9,127.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals.	7.56	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	4,322.00
3	Providing and laying Plain cement concrete 1:5:10 (one cement : five sand : ten graded crushed stone aggregate) nominal mix in open foundation with crushed stone aggregate 40mm (forty millimetre) nominal size mechanically mixed including cost of form work and curing complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental or as per the direction of Engineer-in-charge. The rate including Royalty, Malkhana, Octroi, toll tax, sales tax or any other taxes imposed by the Government including carriage of materials with in all leads, lifts and other incidentals.	79.38	5938.75	Rupees Five Thousand Nine Hundred Thirty Eight and Paise Seventy Five Only	Per cubic metre	4,71,418.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	20	390.55	Rupees Three Hundred Ninety and Paise Fifty Five Only	Each	7,811.00
	Total					4,92,678.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- Special repair to Doctor Residence type-IV 6 Nos Qtr. at Zonal Hospital Mandi, Distt. Mandi (H.P)
(Sh:- Providing & Applying and painting, distemping and other repair work)

Estimated Cost Rs. 4,90,157/-
Earnest Money Rs. 9,900/-
Time :- Two Months.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of materials with in all leads, lifts and other incidentals.	1923.45	15.35	Rupees Fifteen and Paise Thirty Five Only	Per Square metre	29,525.00
2	Providing and applying white cement based putty of average thickness 1 mm (one millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete incidentals including carriage of materials with in all leads, lifts and other incidentals.	1923.45	110.25	Rupees One Hundred Ten and Paise Twenty Five Only	Per Square metre	2,12,060.00
3	Wall painting with plastic emulsion of approved shade old work (one or more coats applied @ 1.82 ltr/10 sqm (one point eighty two liter per ten square metre) including carriage of materials with in all leads, lifts and other incidentals.	1576.62	93.10	Rupees Ninety Three and Paise Ten Only	Per Square metre	1,46,783.00
4	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : old work (two or more coats) Including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	1963.14	51.85	Rupees Fifty One and Paise Eighty Five Only	Per Square metre	1,01,789.00
Total						4,90,157.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- Special repair to Doctor Residence type-IV 6 Nos. Qtr. at Zonal Hospital Mandi, Distt. Mandi (H.P)
(SH:- Providing and fixing, painting, distemping, steel & wood works and other repair work)

Estimated Cost Rs. 4,99,116/-
Earnest Money Rs. 10,000/-
Time :- Two Months.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Painting wood work with Deluxe Multi Surface. Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point ninety ltr/ten sqm) over an under coat of primer applied @0.75 ltr/10 sqm (zero point seventy five ltr/ten sqm) of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge.	3	116.30	Rupees One Hundred Sixteen and Paise Thirty Only	Per Square Metre	1,62,175.00
2	Painting on G.S. with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : New work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution including carriage of materials with in all leads, lifts and other incidentals.	432.62	144.30	Rupees One Hundred Forty Four and Paise Thirty Only	Per Square metre	62,427.00
3	Providing and fixing 19mm (ninteen millimetre) thick water proof commercial board shutters/ shelves for cup board as per drawing and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals.	45.90	2091.55	Rupees Two Thousand Ninety One and Paise Fifty Five Only	Per Square Metre	96,002.00
4	Providing and fixing 40mm (Forty millimetre) thick second class deodar wood shutters, panelled glazed or panelled and glazed shutters for doors, windows and clerestory windows and including black enamelled iron butt hinges with necessary screws including carriage of materials with in all leads, lifts and other incidentals.	8.85	5253.70	Rupees Five Thousand Two Hundred Fifty Three and Paise Seventy Only	Per Square metre	46,495.00
5	Providing and fixing 35mm (Thiry five millimetre) thick second class deodar wood wire gauge shutters using galvanized M.S. wire gauge of I.S. gauge designation 85G with wire of dia 0.56 mm (zero point five six millimetre) for doors, windows, clerestory windows including bright finished/black enamelled iron butt hinges with necessary screws including carriage of materials with in all leads, lifts and other incidentals.	3.83	3550.45	Rupees Three Thousand Five Hundred Fifty and Paise Forty Five Only	Per Square metre	13,598.00
6	Providing and fixing aluminium 100mm (one hundred millimetre) handles anodized transparent or dyed to required colour or shade with necessary screws etc. complete including carriage of materials with in all leads, lifts and other incidentals.	16	50.75	Rupees Fifty and Paise Seventy Five Only	Each	812.00
7	Providing and fixing 150mm (one hundred fifty millimetre) anodized aluminium lower bolts (barrel type) anodized transparent or dyed to required shade and colour and with screws etc. complete including carriage of materials with in all leads, lifts and other incidentals.	20	55.35	Rupees Fifty Five and Paise Thirty Five Only	Each	1,107.00

8	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials with in all leads, lifts and other incidentals.	606.15	149.60	Rupees One Hundred Forty Nine and Paise Sixty Only	Per Kilogram	90,680.00
9	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including carriage of materials with in all leads, lifts and other incidentals.	1000.00	10.55	Rupees Ten and Paise Fifty Five Only	Per Litter	10,550.00
10	Providing and fixing 15 mm (fifteen millimetre) nominal bore ball valve (brass) of approved quality, High or low pressure, with plastic floats complete including carriage of materials with in all leads, lifts and other incidentals.	6	425.65	Rupees Four Hundred Twenty Five and Paise Sixty Five Only	Each	2,554.00
11	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) : 20 mm (twenty millimetre) nominal bore including carriage of materials with in all leads, lifts and other incidentals.	6	460.20	Rupees Four Hundred Sixty and Paise Twenty Only	Each	2,761.00
12	Providing and fixing 15mm nominal bore C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms. 15mm nominal bore including carriage of materials with in all leads, lifts and other incidentals.	7	779.35	Rupees Seven Hundred Seventy Nine and Paise Thirty Five Only	Each	5,455.00
13	Providing and fixing 15mm nominal bore C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS : 8931 including carriage of materials with in all leads, lifts and other incidentals.	5	899.95	Rupees Eight Hundred Ninety Nine and Paise Ninety Five Only	Each	4,500.00
	Total					4,99,116.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- Repair and maintenance of Residences of Civil Judge- Cum- JMFC Court No.- II Mandi, Distt. Mandi (H.P.). (SH:- C/O retraining wall in back side of building, P/L PCC 1:5:10, Weep holes and steel work for fencing around building work etc.)

Estimated Cost Rs. 4,84,493/-
Earnest Money Rs. 9,700/-
Time :- Two Months.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, filets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing : 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate forty millimetres nominal size) including carriage of materials with in all leads, lifts and other incidentals.	70.00	6508.30	Rupees Six Thousand Five Hundred Eight and Paise Thirty Only	Per Cubic Metre	4,55,581.00
2	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (hundred millimetres) PVC pipe extending through the full width of the structure with slope of (V) : 20 (twenty) (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	63.00	338.80	Rupees Three Hundred Thirty Eight and Paise Eighty Only	Each	21,344.00
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials with in all leads, lifts and other incidentals.	51.00	148.40	Rupees One Hundred Forty Eight and Paise Forty Only	Per Kilogram	7,568.00
	Total					4,84,493.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

HP

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.Damages on Motipur Dudar road km 0/00 to 2/500.
(SH:- C/O Retaining wall at km 2/247.50 to 2/255)

Estimated Cost Rs. 4,58,042/-
Earnest Money Rs. 9,200/-
Time :- Two Months

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m (fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge.	23.40	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	10,164.00
2	Providing & making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size, Mesh Type 10x12 (ten into twelve) (D=100mm (D=hundred millimetre) with tolerance of ± 2%) Zinc coated, Mesh wire diameter 3.0 mm (three point zero millimetre), mechanically edged/selvedged with partitions at every 1m interval and shall have minimum 10 (ten) numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm (two point two millimetre), supplied @3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm (two hundred millimetre), as per drawing, all complete as per direction of Engineer-in-charge.including carriage of materials with in all leads, lifts and other incidentals.	117.19	3661.40	Rupees Three Thousand Six Hundred Sixty One and Paise Forty Only	Per Cubic Metre	4,29,079.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, Granular material including carriage of materials with in all leads, lifts and other incidentals or as per direction of Engineer in charge.	11.48	1637.50	Rupees One Thousand Six Hundred Thirty Seven and Paise Fifty Only	Per Cubic Metre	18,799.00
	Total					4,58,042.00


Executive Engineer
Mandi Division No.-II
H.P.P.W.D. Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.Damages on Motipur Dudar road km 0/00 to 2/500.
(SH:- C/O Retaining wall at km 2/240 to 2/247.50)

Estimated Cost Rs. 4,60,958/-
Earnest Money Rs. 9,300/-
Time :- Two Months

Br. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m (fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge.	22.50	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	9,773.00
2	Providing & making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size. Mesh Type 10x12 (ten into twelve) (D=100mm (D=hundred millimetre) with tolerance of ± 2%) Zinc coated, Mesh wire diameter 3.0 mm (three point zero millimetre), mechanically edged/selvedged with partitions at every 1m interval and shall have minimum 10 (ten) numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm (two point two millimetre), supplied @3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm (two hundred millimetre), as per drawing, all complete as per direction of Engineer-in-charge.including carriage of materials with in all leads, lifts and other incidentals.	117.19	3661.40	Rupees Three Thousand Six Hundred Sixty One and Paise Forty Only	Per Cubic Metre	4,29,079.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals or as per direction of Engineer in charge.	13.50	1637.50	Rupees One Thousand Six Hundred Thirty Seven and Paise Fifty Only	Per Cubic Metre	22,106.00
Total						4,60,958.00


 Executive Engineer
 Mandi Division No.-11
 H.P.P.W.D. Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Residential building PWD Colony at Jail Road Mandi H.P.
(SH:- C/O B/wall behind type-II Qtr. building Block-G).

Estimated Cost Rs. 2,58,873/-
Earnest Money Rs. 5200/-
Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Words	Unit	Amount
			Figure				
1	2	3	4	5	6	7	
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	11.70	464.75	Rupees Four Hundred Sixty Four and Paise Seventy Five Only	Per Cubic Metre	5,438.00	
2	Providing and laying concrete for plain concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203, including carriage of materials with in all leads, lifts and other incidentals.	0.78	5104.55	Rupees Five Thousand One Hundred Four and Paise Fifty Five Only	Per Cubic Metre	3,982.00	
3	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar (1:6) (One cement : six sand) including carriage of materials with in all leads, lifts and other incidentals.	44.59	5347.25	Rupees Five Thousand Three Hundred Forty Seven and Paise Twenty Five Only	Per Cubic Metre	2,38,434.00	
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	7.02	1569.65	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	11,019.00	
					Total	2,58,873.00	


 Exclusive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

609

%age Rate of SCHEDULE OF QUANTITY

Name of work :- Repair and maintenance of addl. District & Session Judge Fast track special court (POSCO) Mandi, Distt. Mandi (HP) (SH:- C/O of R/wall in back and right side of building, removal of debris, and other repair works etc.)

Estimated Cost Rs. 4,91,279/-
Earnest Money Rs. 9,900/-
Time :- Two Months

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead of 50 m (fifty metre) incidentals as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals	51.56	216.90	Rupees Two Hundred Sixteen and Paise Ninety Only	Per Cubic Metre	11,183.00
2	Centering and shuttering including strutting, propping etc. and removal of form for all heights : Walls (any thickness) including attached plasters, buttresses, plinth and string courses etc. incidentals as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals	60.78	525.75	Rupees Five Hundred Twenty Five and Paise Seventy Five Only	Per Square Metre	31,955.00
3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing : 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) incidentals as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals	18.90	6960.20	Rupees Six Thousand Nine Hundred Sixty and Paise Twenty Only	Per Cubic Metre	1,31,548.00

4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing : 1:5:10 (1 cement : 5 coarse sand) : 10 graded stone aggregate 40 mm nominal size).	45.00	6833.15	Rupees Six Thousand Eight Hundred Thirty Three and Paise Fifteen Only	Per Cubic Metre	3,07,492.00
5	Providing weep holes in block masonry/ stone masonry/plain reinforced concrete abutments wing wall, return wall with 100mm (Hundred PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	24	379.20	Rupees Three Hundred Seventy Nine and Paise Twenty Only	Each	9,101.00
					Total	4,91,279.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi


%age Rate of SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages in Session House Building at Tarua Mandi, Distt Mandi (H.P.).
(SH:- C/o wire Cated Retaining wall in court Yard of building)

Estimated Cost Rs. 4,73,286/-
Earnest Money Rs. 9,500/-
Time :- Two Months.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m (fifty metre), dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge.	66.00	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	28,667.00
2	Providing & making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size, Mesh Type 10x12 (ten into twelve) (D=100mm (D=hundred millimetre) with tolerance of ± 2%) Zinc coated, Mesh wire diameter 3.0 mm (three point zero millimetre), mechanically edged/selvedged with partitions at every 1m interval and shall have minimum 10 (ten) numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm (two point two millimetre), supplied @3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm (two hundred millimetre), as per drawing, all complete as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	118.80	3661.40	Rupees Three Thousand Six Hundred Sixty One and Paise Forty Only	Per Cubic Metre	4,34,974.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals or as per direction of Engineer in charge.	5.89	1637.50	Rupees One Thousand Six Hundred Thirty Seven and Paise Fifty Only	Per Cubic Metre	9,645.00
	Total					4,73,286.00

45


 Executive Engineer
 Mandi Division No.-II
 H.P.P.W.D. Mandi

%AGE RATE OF SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages in the Session House building Tarna Mandi, Distt. Mandi (H.P.).
(SH: C/O Retaining wall on approach road to Session House building at RD 0/04.00 to 0/07.50) Job No.- 1 Earnest Money Rs. 9,900/-
Estimated cost Rs. 4,92,678/-
Time:- One Month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	46.94	194.45	Rupees One Hundred Ninety Four and Paise Forty Five Only	Per Cubic Metre	9,127.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals.	7.56	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	4,322.00
3	Providing and laying Plain cement concrete 1:5:10 (one cement : five sand : ten graded crushed stone aggregate) nominal mix in open foundation with crushed stone aggregate 40mm (forty millimetre) nominal size mechanically mixed including cost of form work and curing complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental or as per the direction of Engineer-in-charge. The rate including Royalty, Malkhana, Octroi, toll tax, sales tax or any other taxes imposed by the Government including carriage of materials with in all leads, lifts and other incidentals.	79.38	5938.75	Rupees Five Thousand Nine Hundred Thirty Eight and Paise Seventy Five Only	Per cubic metre	4,71,418.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	20	390.55	Rupees Three Hundred Ninety and Paise Fifty Five Only	Each	7,811.00
	Total					4,92,678.00

45


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi

%AGE RATE OF SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages in the Session House building Tarna Mandi, Distt. Mandi (H.P.).
 (SH:- C/O Retaining wall on approach road to Session House building at RD 0/07.50 to 0/11.00) Job No.- 2 Earnest Money Rs. 9,900/-

Estimated cost Rs. 4,92,678/-
 Time:- One Month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	46.94	194.45	Rupees One Hundred Ninety Four and Paise Forty Five Only	Per Cubic Metre	9,127.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals.	7.56	571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	4,322.00
3	Providing and laying Plain cement concrete 1:5:10 (one cement : five sand : ten graded crushed stone aggregate) nominal mix in open foundation with crushed stone aggregate 40mm (forty millimetre) nominal size mechanically mixed including cost of form work and curring complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental or as per the direction of Engineer-in-charge. The rate including Royalty, Malkhana, Octroi, toll tax, sales tax or any other taxes imposed by the Government including carriage of materials with in all leads, lifts and other incidentals.	79.38	5938.75	Rupees Five Thousand Nine Hundred Thirty Eight and Paise Seventy Five Only	Per cubic metre	4,71,418.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	20	390.55	Rupees Three Hundred Ninety and Paise Fifty Five Only	Each	7,811.00
	Total					4,92,678.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

47

%age Rate of SCHEDULE OF QUANTITY

Name of work :- Special Repair of Doctor Residential building at Zonal Hospital Mandi, Distt. Mandi (H.P.)
(SH:- Construction of Roof on top floor slab over Doctor Dushyant Residence).

Estimated Cost Rs. 2,92,973/-
Earnest Money Rs. 5,900/-
Time :- Two Months.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	1	3	4	5	6	7
1	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes including carriage of materials with in all leads, lifts and other incidentals.	868.10	145.65	Rupees One Hundred Forty Five and Paise Sixty Five Only	Per Kilogram	1,26,439.00
2	2					
2	Providing and fixing 0.60mm (zero point six zero millimetre) thick pre-painted steel sheet of TATA/DUROSHINE in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating i/c fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (six millimetre) dia metre with pre-painted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	48.10	1587.60	Rupees One Thousand Five Hundred Eighty Seven and Paise Sixty Only	Per Square metre	76,364.00
3	3	27.00	1439.55	Rupees One Thousand Four Hundred Thirty Nine and Paise Fifty Five Only	Per Running metre	38,868.00
	Providing and fixing ridges or hips 90 cm (ninety centimetre) overall with 0.60mm (zero point six zero millimetre) thick pre-painted steel sheets TATA/DUROSHINE in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 (twenty) microns over 5 (five) microns primer coating + back coat of polyester of 5 (five) microns over 5 (five) microns primer coating i/c fixing with pre-painted iron J or L hooks, bolts & nuts 6mm (six millimetre) dia & pre-painted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer in Charges including carriage of materials with in all leads, lifts and other incidentals.					

	Providing and fixing valley 90 cm (ninety centimetre) overall 0.60mm (zero point six zero millimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester organic coating of back coat of polyester of 5 (five) microns over 5 (five) microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm (six millimetre) dia with prepainted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	3.40	1505.10	Rupees One Thousand Five Hundred Five and Paise Ten Only	Per Running metre	5,117.00
5	Providing and fixing prepainted Lining sheet for Chazza ceiling with all accessories as required as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	24.23	1001.50	Rupees One Thousand One and Paise Fifty Only	Per square metre	24,266.00
6	Providing and fixing prepainted Plain sheet for gutter with all accessories as required as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	3.73	1037.05	Rupees One Thousand Thirty Seven and Paise Five Only	Per square metre	3,868.00
7	Supplying and fixing expended metal to wood or steel members in partitions etc. weight exceeding 3kg (three kilogram) and not exceeding 5kg/sqm (five kilogram per Square metre) including carriage of materials with in all leads, lifts and other incidentals.	13.35	794.10	Rupees Seven Hundred Ninety Four and Paise Ten Only	Per square metre	10,601.00
8	Providing and fixing Single socketed pipes 75mm (seventy five millimetre) dia. on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10mm (ten millimetre) gap for thermal expansion, including carriage of materials with in all leads, lifts and other incidentals.	16.00	279.10	Rupees Two Hundred Seventy Nine and Paise Ten Only	Per Running metre	4,466.00
9	Providing and fixing Single socketed pipes 110mm (one hundred ten millimetre) dia. on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10mm (ten millimetre) gap for thermal expansion, including carriage of materials with in all leads, lifts and other incidentals.	7.45	371.05	Rupees Three Hundred Seventy One and Paise Five Only	Per Running metre	2,764.00

10	Providing and fixing Shoe (Plain) 75mm (seventy five millimetre) diameter on wall face unplasticised-PVC moulded fittings / accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10mm (ten millimetre) gap for thermal expansion including carriage of materials with in all leads, lifts and other incidentals.	2.00	109.80	Ruppes One Hundred Nine and Paise Eighty Only	Each	220.00
					Total	2,92,973.00


 Executive Engineer,
 Mandi Division No-II,
 H.P. PWD, Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Daudar Bharon road Km. 0/00 to 4/00.
(SH:- C/O wire crest R/wall at RD. 0/720 to 0/727.50).

Estimated Cost Rs. 4,62,827/-
Earnest Money Rs.9300/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	3	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	18,202.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS. 280 and IS:4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	429,917.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.78	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	14,708.00
	Total					462,827.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

49

Name of work :- R.R.D. on Dadar Bharon road Km. 0/00 to 4/00.
 (SH:- C/O wire crest R/wall at RD. 0/727.50 to 0/735).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 4,62,827/-
 Earnest Money Rs.9300/-
 Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	34.73	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	18,202.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	429,917.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.78	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	14,708.00
					Total	462,827.00

50


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Motipur Dudar Majhwar road Km. 0/00 to 12/500.
(SH:- C/O wire crate R/wall at RD. 4/517.50 to 4/525).

Estimated Cost Rs.4,62,827/-
 Earnest Money Rs. 9300/-
 Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	34.73	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	18,202.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	429,917.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.78	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	14,708.00
Total						462,827.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

51

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Motipur Dudar Malhwar road Km. 0/00 to 12/500.
(SH:- C/O wire crate R/wall at RD. 5/742.50 to 5/750).

Estimated Cost Rs.4,62,827/-
 Earnest Money Rs. 9300/-
 Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	34.73	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	18,202.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	429,917.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.78	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	14,708.00
Total						462,827.00

57


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Motipur Dudar Mashwar road Km. 0/00 to 12/500.
(SH:- C/O wire crate R/wall at RD. 5/750 to 5/756.25).

Estimated Cost Rs.3,85,683/-
 Earnest Money Rs. 7800/-
 Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	28.94	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	15,167.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven digonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	97.66	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	358,271.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	7.31	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	12,245.00
Total						385,683.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

53

%Age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Gaupati Kun Ka Tar road Km. 0/00 to 21/500.
(SH:- C/O RCC R/wall at RD. 2/240 to 2/250).

Estimated Cost Rs. 3,02,070/-
 Earnest Money Rs. 6100/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	12.00	195.00	Rupees One Hundred Ninety Five Only	Per Cubic Metre	2,340.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	17.00	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	8,910.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specifications clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	50.80	5320.75	Rupees Five Thousand Three Hundred Twenty and Paise Seventy Five Only	Per Cubic Metre	2,70,294.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	11.00	358.35	Rupees Three Hundred Fifty Eight and Paise Thirty Five Only	Each	3,942.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	9.90	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	16,584.00
Total						3,02,070.00


 Engineer,
 Mandi Division No-II,
 H.P. P.W.D. Mandi.

(54)

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Ganpatl Kun Ka Tar road Km. 0/00 to 21/500.
(SH:- C/O PCC R/wall at RD. 2/250 to 2/259).

Estimated Cost Rs. 2,72,258/-
Earnest Money Rs. 5500/-
Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	10.80	195.00	Rupees One Hundred Ninety Five Only	Per Cubic Metre	2,106.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	15.30	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	8,019.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	45.72	5320.75	Rupees Five Thousand Three Hundred Twenty and Paise Seventy Five Only	Per Cubic Metre	2,43,265.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	11.00	358.35	Rupees Three Hundred Fifty Eight and Paise Thirty Five Only	Each	3,942.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.91	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	14,926.00
Total						2,72,258.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

55

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Gaupatti Kun Ka Tar road Km. 0/00 to 21/500.
(SRI: C/O wire crate R/wall at RD. 2/827 to 2/833).

Estimated Cost Rs. 4,97,735/-
 Earnest Money Rs. 10000/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	40.26	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	21,100.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	127.87	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	4,69,097.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	4.50	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	7,538.00
					Total	4,97,735.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

Name of work :- RRD on Ganpati Kun Ka Tar road Km. 0/00 to 21/500.
 (SH:- C/O wire crate R/wall at RD. 2/833 to 2/839).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 4,47,036/-
 Earnest Money Rs. 9000/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	40.26	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	21,100.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven digonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	114.05	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	4,18,398.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	4.50	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	7,538.00
					Total	4,47,036.00


 P. Anand, Engineer,
 Mandi Division No-II,
 H.P. PWD, Mandi. 2

Name of work :- RRD on Gaupatt Kun Ka Tar road Km. 0/00 to 21/500.
(SH:- C/O wire crate R/wall at RD. 2/840 to 2/846).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 4,08,993/-
Earnest Money Rs. 8200/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	40.26	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	21,100.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	103.68	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	3,80,355.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	4.50	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	7,538.00
					Total	4,08,993.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

58


%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Ganpatl Kun Ka Tar road Km. 0/00 to 21/500.

(SH:- C/O wire crate R/wall at RD. 2/846 to 2/852).

Estimated Cost Rs. 4,09,094/-
Earnest Money Rs. 8200/-
Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	40.26	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	21,100.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25Kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	103.68	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	3,80,355.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	4.56	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	7,639.00
					Total	4,09,094.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

59

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Gaupati Kun Ka Tar road Km. 0/00 to 21/500.
(SH:- C/O wire crate R/wall at RD. 2/852 to 2/859.201).

Estimated Cost Rs. 4,90,923/-
 Earnest Money Rs. 10000/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	48.31	524.10	Rupess Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	25,319.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	124.42	3668.55	Rupess Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	4,56,441.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	5.47	1675.15	Rupess One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	9,163.00
	Total					4,90,923.00


Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi. 2

%age rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Ganpati Kun Ka Tar road Km. 0/00 to 21/500.
(SH:- C/O wire crate R/wall at RD. 19/060 to 19/072.50).

Estimated Cost Rs. 4,82,710/-
 Earnest Money Rs. 10000/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	70.75	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	37,080.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	4,29,917.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	9.38	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	15,713.00
					Total	4,82,710.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

Name of work :- RRD on Ganpatl Kun Ka Tar road Km. 0/00 to 21/500.
(SH:- C/O wire crate R/wall at RD. 19/072.50 to 19/085).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 4,82,579/-
Earnest Money Rs. 10000/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	70.50	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	36,949.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	4,29,917.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	9.38	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	15,713.00
					Total	4,82,579.00


Executive Engineer
Mand Division No-II,
HP. PWD, Mandi.

9

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on T.P.T.S. road Km. 0/00 to 11/00.
(SH:- C/O B/wall at RD. 0/350 to 0/370).

Estimated Cost Rs. 3,79,481/-
 Earnest Money Rs. 8000/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	55.20	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	28,930.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	64.20	5320.75	Rupees Five Thousand Three Hundred Twenty Five Only	Per Cubic Metre	3,41,592.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	25.00	358.35	Rupees Three Hundred Fifty Eight and Paise Thirty Five Only	Each	8,959.00
Total						3,79,481.00


 Executive Engineer,
 Mandi Division No-II,
 H.P. PWD, Mandi.

DRAFT SCHEDULE OF QUANTITY

Name of work :- RRD on T.P.T.S. road Km. 0/00 to 11/00.
 (SH:- C/O wire crates B/wall at RD. 5/680 to 5/700).

Estimated Cost Rs. 3,68,245/-
 Earnest Money Rs. 7400/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all bands of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	46.40	524.10	Ruppes Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	24,318.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	93.75	3668.55	Ruppes Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	3,43,927.00
Total						3,68,245.00

DNIT approved per P.O. 368245/only

[Signature]
 Executive Engineer,
 Mandi Division No-II,
 H.P. PWD, Mandi

64

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on T.P.T.S. road Km. 0/00 to 11/00.
(SH:- C/O wire crates R/wall at RD. 6/295 to 6/320).

Estimated Cost Rs. 4,99,319/-
 Earnest Money Rs. 10,000/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	23.75	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	12,447.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	4,29,917.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	34.00	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	56,955.00
		Total				4,99,319.00


 Executive Engineer
 Mandi Division No-II,
 HP. PWD, Mandi.




DRAFT SCHEDULE OF QUANTITY

Name of work :- RRD on T.P.T.S. road Km. 0/00 to 11/00.
(SH:- C/O wire crates R/wall at RD. 8/030 to 8/042.50).

Estimated Cost Rs. 4,57,946/-
 Earnest Money Rs. 10,000/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	23.50	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	12,316.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	4,29,917.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	9.38	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	15,713.00
Total						4,57,946.00

DNIT Checked and approved for Rs- 4,57,946/- only.


 Executive Engineer,
 Mandi Division No-II,
 H.P. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Link road Rihand Dhar to Vanot via Yola road Km. 0/00 to 4/00.
(SH:- C/O wire crates R/wall at RD. 1/720 to 1/730).

Estimated Cost Rs. 3,53,237/-
 Earnest Money Rs. 7100/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates	Words	Unit	Amount
			Figure			
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	38.10	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	19,968.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25Kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	85.00	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	3,11,827.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	12.80	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	21,442.00
	Total					3,53,237.00

BP


 Executive Engineer,
 Muzdi Division No-II,
 HP PWD, Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Link road Rihani Dhar to Vanot via Yola road Km. 0/00 to 4/00.

(SH:- C/O wire crates R/wall at RD. 2/180 to 2/190).

Estimated Cost Rs. 3,42,231/-
Earnest Money Rs. 7000/-
Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	38.10	524.10	Rupess Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	19,968.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	82.00	3668.55	Rupess Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	3,00,821.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	12.80	1675.15	Rupess One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	21,442.00
	Total					3,42,231.00


 Executive Engineer,
 Madhi Division, No-II,
 HP. PWD, Madhi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Chahl Gohar Pandoh road Km. 24/00 to 29/600.

(SH:- C/O Protection work of abutments of 6.0 mtr. span RD.28/410).

Estimated Cost Rs.1,98,527/-
Earnest Money Rs.4000/-
Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Stone filling in foundation trenches as per drawing and technical specification. including carriage of materials with in all leads, lifts and other incidentals.	16.20	1509.30	Rupees One Thousand Five Hundred Nine and Paise Thirty Only	Per Cubic Metre	24,451.00
2	Plain/reinforced cement concrete in foundation and plinth complete as per drawing and technical specification clauses 802, 804,805, 806,807, 1202 and 1204 for any height PCC gradel:2:4 (one cement : two coarse sand: four graded stone aggregate 20 mm (twenty millimetre) nominal size) including carriage of materials with in all leads, lifts and other incidentals.	21.44	8119.20	Rupees Eight Thousand One Hundred Nineteen and Paise Twenty Only	Per Cubic Metre	174,076.00
Total						198,527.00

69


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Pandoh Seyog road Km. 0/00 to 4/00.
***(SH:- C/O wire crates R/wall at RD. 3/010 to 3/020).**

Estimated Cost Rs.4,13,936/-
 Earnest Money Rs.8300/-
 Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	38.00	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	19,916.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS-4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	101.56	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	372,578.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	12.80	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	21,442.00
Total						413,936.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

100

Name of work :- R.R.D. on Pandoh Seyog road Km. 0/00 to 4/00.
(SH:- C/O R/wall at RD. 3/315 to 3/335).

DRAFT SCHEDULE OF QUANTITY

Estimated Cost Rs.4,80,625/-
Earnest Money Rs.9700/-
Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	17.60	195.00	Rupees One Hundred Ninety Five Only	Per Cubic Metre	3,432.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing. removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	22.80	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	11,949.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	81.60	5320.75	Rupees Five Thousand Three Hundred Twenty and Paise Seventy Five Only	Per Cubic Metre	434,173.00
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (One hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	25.00	358.35	Rupees Three Hundred Fifty Eight and Paise Thirty Five Only	Each	8,959.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	13.20	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	22,112.00
	Total					480,625.00

29

Executive Engineer,
Mandi/ Division No-II,
HP. PWD, Mandi

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Mandi Tjilin Keohanwal road Km. 1/500 to 14/400.
/SH:- C/O wire crates R/wall at RD. 13/400 to 13/430).

Estimated Cost Rs.4,56,646/-
Earnest Money Rs. 9200/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	3	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	26,729.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia (Ø) wire conforming to IS: 280 and IS:4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven digonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	429,917.00
Total						456,646.00

4


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi. S

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Ratti Pul to Alathu road Km. 0/00 to 6/500.
(SH:- C/O wire crates R/wall at RD. 0/125 to 0/135).

Estimated Cost Rs. 2,48,971/-
Earnest Money Rs. 10,000/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	13.45	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	7,049.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	62.52	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	2,29,358.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	7.50	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	12,564.00
					Total	2,48,971.00

19/9


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Malhwar to Ghula road Km. 0/00 to 5/480.
(SH:- C/O wire crate B/wall at RD. 1/055 to 1/065).

Estimated Cost Rs.2,00,991/-
 Earnest Money Rs. 4100/-
 Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	55.35	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	29,009.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven digonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	46.88	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	171,982.00
Total						200,991.00

Handwritten initials


 Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

%age Rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Randhara Banayat road Km. 0/00 to 2/00.
(SE:- C/O wire crate R/wall at RD. 0/135 to 0/160).

Estimated Cost Rs. 4,98,782/-
Earnest Money Rs. 10,000/-
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	43.50	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	22,798.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	4,29,917.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	27.50	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	46,067.00
					Total	4,98,782.00

415


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

Name of work :- R.R.D. on Chambi to Kuther road Km. 0/00 to 5/300.
(SH:- C/O B/wall at RD. 2/310 to 2/325).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs.3,77,118/-
Earnest Money Rs.7600/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	23.85	195.00	Rupees One Hundred Ninety Five Only	Per Cubic Metre	4,651.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of sumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	25.50	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	13,365.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	66.75	5320.75	Rupees Five Thousand Three Hundred Twenty and Paise Seventy Five Only	Per Cubic Metre	355,160.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (One hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	11.00	358.35	Rupees Three Hundred Fifty Eight and Paise Thirty Five Only	Each	3,942.00
Total						377,118.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.


16

Name of work :- RRD on Nanawan to Marathu road Km. 0/00 to 1/420.
 (SH: C/O wire crates B/wall at RD. 0/00 to 0/030).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 3,71,128/-
 Earnest Money Ra. 7500/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	51.90	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	27,201.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	93.75	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	3,43,927.00
Total						3,71,128.00


 Executive Engineer,
 Mandi Division No-II,
 H.P. PWD, Mandi.

Name of work :- M/T & CD on Rattu Pul to Janed Panchayat Ghar road Km. 0/00 to 2/00. under SCSP
(SH:- Providing and laying WBM G-1 at RD. 1/600 to 2/00).

%age Rate of SCHEDULE OF QUANTITY
 Estimated Cost Rs. 4,00,934/-
 Earnest Money Rs. 8200/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Words	Unit	Amount
			Figure	4			
1	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil) complete as per HP.PWD specification including hauling/ carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	1281.00	1.60		Ruppes One and Paise Sixty Only	Per Square Metre	2,050.00
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade complete as per HP.PWD specification including carriage of materials with in all leads, lifts and other incidentals.	1281.00	1.15		Ruppes One and Paise Fifteen Only	Per Square Metre	1,473.00
3	Providing, laying, spreading and compacting stone aggregates of 90mm to 45mm (Ninety millimetre) to Forty five millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 kN (Eighty - hundred kN) static roller in stages to proper grade and camber, applying and brooming stone screening / binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-I as per Technical Specification Clause 405. By Manual Means including carriage of materials with in all leads, lifts and other incidentals.	128.10	3102.35		Ruppes Three Thousand One Hundred Two and Paise Thirty Five Only	Per Cubic Metre	3,97,411.00
Total							4,00,934.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi. S. _____

78

%age Rate of SCHEDULE OF QUANTITY

Name of work : M/T & CD on Ratti Pul to Janed Panchayat Ghar road Km. 0/00 to 2/00. under SC9P
 (SH:- Providing and Laying WBM G-I at RD. 1/250 to 1/600).

Estimated Cost Rs. 3,50,824/-
 Earnest Money Rs. 7100/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Words	Unit	Amount
			Figure				
1	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil) complete as per HP.PWD specification including hauling/ carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	1120.88	1.60	Rupees One and Paise Sixty Only	Per Square Metre	1,793.00	
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade complete as per HP.PWD specification including carriage of materials with in all leads, lifts and other incidentals.	1120.88	1.15	Rupees One and Paise Fifteen Only	Per Square Metre	1,289.00	
3	Providing, laying, spreading and compacting stone aggregates of 90mm to 45mm (Ninety millimetre to Forty five millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 kN (Eighty - hundred KN) static roller in stages to proper grade and camber, applying and brooming stone screening / binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-I as per Technical Specification Clause 405. By Manual Means including carriage of materials with in all leads, lifts and other incidentals.	112.09	3102.35	Rupees Three Thousand One Hundred Two and Paise Thirty Five Only	Per Cubic Metre	3,47,742.00	
Total							3,50,824.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

79

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Majhwar Motorsect via Sakti Rakhoon road Km. 0/00 to 6/800.

(SH:- C/O wire crot R/wall at RD. 5/865 to 5/875).

Estimated Cost Rs.4,99,927/-
Earnest Money Rs.10,000/-

Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	38.00	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	19,916.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven digonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	125.00	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	458,569.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	12.80	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	21,442.00
					Total	499,927.00

86


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

366

DRAFT SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Bindrawani Mahwar Kotmorse Moviseri road Km. 0/00 to 19/800.
(SH:- C/O wire crate R/wall at RD. 3/450 to 3/460).

Estimated Cost Rs. 4,99,927/-
Earnest Money Rs. 10,000/-
Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	38.00	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	19,916.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	125.00	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	458,569.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	12.80	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	21,442.00
					Total	499,927.00

UNIT approved for Rs. 499,927 only

*Executive Engineer,
Mandi Division No-II,
D.P. PWD, Mandi.*

89

Name of work :- R.R.D. on Bindrawani Mejhwar Kotmorse Moviseri road Km. 0/00 to 19/800.
(SH:- C/O wire crate R/wall at RD. 3/570 to 3/575).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 4,90,099/-
Earnest Money Rs. 9900/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	26.60	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	13,941.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	125.00	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	458,569.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	10.50	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	17,589.00
					Total	490,099.00

Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

89

Name of work :- R.R.D. on Bindrawani Majhwar Kotnorse Moviseri road Km. 0/00 to 19/800.
(SH:- C/O wire crate R/wall at RD. 3/575 to 3/580).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 4,90,047/-
Earnest Money Rs. 9800/-
Time :- One month.

Sl. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	26.50	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	13,889.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	125.00	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	458,569.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	10.50	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	17,589.00
Total						490,047.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

65

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Bindrawani Majhwar Kotmorse Moviseri road Km. 0/00 to 19/800.
(SH:- C/O wire crate R/wall at RD. 14/477.50 to 14/485).

Estimated Cost Rs. 4,61,360/-
Earnest Money Rs. 9300/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	42.00	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	22,012.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	429,917.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	5.63	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	9,431.00
	Total					461,360.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.


84

%age Rate of SCHEDULE OF QUANTITY

Name of work: R.R.D. on Bindrawani Majhwar Kotmorse Moviseri road Km. 0/00 to 19/800.
(SH:- C/O wire crate R/wall at RD. 15/090 to 15/0.97.50).

Estimated Cost Rs. 4,19,832/-
Earnest Money Rs. 8400/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	34.73	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	18,202.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	105.47	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	386,922.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.78	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	14,708.00
					Total	419,832.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

85

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Bindrawani Malhwar Kotmorse Moriseri road Km. 0/00 to 19/800.
(SR:- C/O wire crate R/wall at RD. 15/097.50 to 15/103.75).

Estimated Cost Rs. 3,56,995/-
Earnest Money Rs. 7200/-
Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	3	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	15,167.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	89.84	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	329,583.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	7.31	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	12,245.00
	Total					356,995.00

66


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

Name of work :- R.R.D. on Bindrawani Malhwar Kotmorse Moviseri road Km. 0/00 to 19/800.
 (SH:- C/O wire crate R/wall at RD. 15/952.50 to 15/960).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 4,63,195/-
 Earnest Money Rs. 9300/-
 Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	34.73	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	18,202.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	429,917.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	9.00	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	15,076.00
					Total	463,195.00

87


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

Name of work :- RRD on Talpahar Panjethi road Km. 0/00 to 1/225.
(SH:- C/O R/wall at RD. 0/950 to 0/962).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 3,21,903/-
Earnest Money Rs. 6500/-
Time :- One month.

Sr.	Description of Items.	Quantity	Rate		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	11.04	195.00	Rupees One Hundred Ninery Five Only	Per Cubic Metre	2,153.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	10.92	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	5,723.00
3	Providing and laying concrete for plain concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40mm (Forty millimetre nominal size) in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203, including carriage of materials with in all leads, lifts and other incidentals.	5.19	4992.00	Rupees one thousand nine hundred thirty three and paise sixty only.	Per Cubic Metre	25,908.00
4	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar (1:6) (One cement : six sand) including carriage of materials with in all leads, lifts and other incidentals.	42.60	6280.20	Rupees Six Thousand Two Hundred Eighty and Paise Twenty Only	Per Cubic Metre	2,67,537.00
5	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	12.00	358.35	Rupees Three Hundred Fifty Eight and Paise Thirty Five Only	Each	4,300.00
6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	9.72	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	16,282.00
					Total	3,21,903.00

Executive Engineer,
Mandi Division No-11,
HP. PWD, Mandi

08

%age rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Talwahaar Path Road Km. 0/00 to 5/100.
 (SH:- C/O wire crate B/wall at RD. 3/025 to 3/050).

Estimated Cost Rs. 4,99,235/-
 Earnest Money Rs. 10000/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	29.25	524.10	Rupess Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	15,330.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	36.00	5320.75	Rupess Five Thousand Three Hundred Twenty and Paise Seventy Five Only	Per Cubic Metre	1,91,547.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	16.00	358.35	Rupess Three Hundred Fifty Eight and Paise Thirty Five Only	Each	5,734.00
4	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	78.13	3668.55	Rupess Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	2,86,624.00
Total						4,99,235.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

BP


Name of work :- R.R.D. on Link road Padhuan to Kagar road Km. 0/00 to 2/800.
 (SH:- C/O wire crates R/wall at RD. 0/180 to 0/217.50).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 4,69,167/-
 Earnest Money Rs. 9400/-
 Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	28.13	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	14,743.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (One hundred millimetre into One hundred millimetre) mesh (woven digonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	117.19	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	429,917.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	14.63	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	24,507.00
Total						469,167.00

00



 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi. 2

%age Rate of SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Sauli Khad to Badog road Km. 0/00 to 4/00.
(SH:- C/O R/wall at RD. 0/170 to 0/182).

Estimated Cost Rs.4,84,871/-
 Earnest Money Rs.9700/-
 Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing. removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads. lifts and other incidentals.	35.88	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	18,805.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	82.51	5320.75	Rupees Five Thousand Three Hundred Twenty Five Only	Per Cubic Metre	439,015.00
3	Providing weep holes in back masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (One hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	25.00	358.35	Rupees Three Hundred Fifty Eight and Paise Thirty Five Only	Each	8,959.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	10.80	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	18,092.00
Total						484,871.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

99

Name of work :- R.R.D. on Sauli Khad to Badog road Km. 0/00 to 4/00.
(SH:- C/O R/wall at RD. 1/310 to 1/318).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs.3,50,480/-
Earrest Money Rs.7100/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	13.68	195.00	Rupees One Hundred Ninety Five Only	Per Cubic Metre	2,668.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	8.72	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	4,570.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	60.88	5320.75	Rupees Five Thousand Three Hundred Twenty and Paise Seventy Five Only	Per Cubic Metre	323,927.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (One hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	18.00	358.35	Rupees Three Hundred Fifty Eight and Paise Thirty Five Only	Each	6,450.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	7.68	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	12,865.00
		Total				350,490.00

09


Engineer,
Mandi Division No-II,
HP. PWD, Mandi

DRAFT SCHEDULE OF QUANTITY

Name of work :- RRD on Sauli Khad to Badog road Km. 0/00 to 4/00.
 (SH: C/O wire crates R/wall at RD. 2/135 to 2/145).

Estimated Cost Rs. 4,99,927/-
 Earnest Money Rs. 10,000/-
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	38.00	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	19,916.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	125.00	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	4,58,569.00
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	12.80	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	21,442.00
					Total	4,99,927.00

DMIT approved for Rs. 4,99,927/-
 Executive Engineer,
 Nagdi Division No-II,
 P.P. PWD, Mandl.

925

DRAFT SCHEDULE OF QUANTITY

Part of work :- RRD on Sain to Sandoh road Km. 0/00 to 14/400.
(SH:- C/O R/wall at RD. 0/240 to 0/256.50).

Estimated Cost Rs 4,99,803/-
Earnest Money Rs. 10000/-
Time :- One month.

Description of Items.	Quantity	Rates		Unit	Amount
		Figure	Words		
Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	2 3	19.80	195.00	6 Per Cubic Metre	7 3,861.00
Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	28.05	524.10	Ruppes Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	14,701.00
Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	83.82	5320.75	Ruppes Five Thousand Three Hundred Twenty and Paise Seventy Five Only	Per Cubic Metre	445,985.00
Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (One hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	22.00	358.35	Ruppes Three Hundred Fifty Eight and Paise Thirty Five Only	Each	7,884.00
Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	16.34	1675.15	Ruppes One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	27,372.00
Total					499,803.00

DRAFT checked and approved for Rs. 4,99,803 only.


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

ok

Name of work :- RRD on Saln to Sandoh road Km. 0/00 to 14/400.
 (SR:- C/O wire crate R/wall at RD. 9/495 to 9/507).

Estimated Cost Rs. 4,08,414/-
 Earnest Money Rs. 8200/-
 Time :- One month.

%age Rate of SCHEDULE OF QUANTITY

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	14.40	195.00	Rupees One Hundred Ninety Five Only	Per Cubic Metre	2,808.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	26.64	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	13,962.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	99.36	3668.55	Rupees Three Thousand Six Hundred Sixty Eight and Paise Fifty Five Only	Per Cubic Metre	3,64,507.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	16.20	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	27,137.00
Total						4,08,414.00

95


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi

DRAFT SCHEDULE OF QUANTITY

Name of work :- RRD on Saini to Sandoh road Km. 0/00 to 14/400.
(SH:- C/O R/wall at RD. 12/430 to 12/440).

Estimated Cost Rs. 4,90,163/-
Earnest Money Rs. 9,900/-
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	20.40	195.00	Rupees One Hundred Ninety Five Only	Per Cubic Metre	3,978.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	16.10	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	8,438.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	84.22	5320.75	Rupees Five Thousand Three Hundred Twenty and Paise Seventy Five Only	Per Cubic Metre	448,114.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (One hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	28.00	358.35	Rupees Three Hundred Fifty Eight and Paise Thirty Five Only	Each	10,034.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	11.70	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	19,599.00
Total						490,163.00

DRAFT Checked and approved for Rs. 490,163/- only

Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

96

DRAFT SCHEDULE OF QUANTITY

**Name of work :- C/O Play Ground at Govt. Senior Secondary School at Baggi Tunggal Distt. Mandi H.P. (Deposit work).
(SH:- C/O Path and steel work for railing). Job No. III**

Estimated Cost Rs. 4,46,182/-
Earnest Money Rs. 9000/-
Time :- One month.

Sr.	Description of Items.	Rates		Unit	Amount
		Figure	Words		
1	2	4	5	6	7
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause-305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	497.90	Rupees Four Hundred Seven and Paise Ninety Only	Per Cubic Metre	4,481.00
2	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding material moorum or earth etc. complete as per HPPWD specification. 100mm spread thickness (finished work including materials and labours) including carriage of materials with in all leads, lifts and other incidentals.	2109.80	Rupees Two Thousand One Hundred Nine and Paise Eighty Only	Per Cubic Metre	9,494.00
3	Providing concrete for plain/reinforced concrete 1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 20mm (Twenty millimetre nominal size) in open foundations complete. as per drawing and technical specification clauses 802, 803, 1202 and 1203, including carriage of materials with in all leads, lifts and other incidentals.	7737.80	Rupees Seven Thousand Seven Hundred Thirty Seven and Paise Eighty Only	Per Cubic Metre	34,820.00
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials with in all leads, lifts and other incidentals.	144.95	Rupees One Hundred Forty Four and Paise Ninety Five Only	Per Kilogram	2,00,901.00
5	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	5757.90	Rupees Five Thousand Seven Hundred Fifty Seven and Paise Ninety Only	Per Cubic Metre	1,92,890.00
6	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	359.55	Rupees Three Hundred Fifty Nine and Paise Fifty Five Only	Each	3,596.00
				Total	4,46,182.00

DNIT approved for Rs. 446182/-

[Signature]
Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi

DRAFT SCHEDULE OF QUANTITY

Name of work :- R.R.D. on Khalanoo to Mahan road Km. 0/00 to 2/500.
(SH:- C/O B/wall in wire crates at RD. 2/710 to 2/732.50).

Estimated Cost Rs. 4,66,231/-
Earnest Money Rs. 9400/-
Time :- One month.

Sr.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	56.25	195.00	Rupees One Hundred Ninety Five Only	Per Cubic Metre	10,969.00
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	8.10	489.15	Rupees Four Hundred Eighty Nine and Paise Fifteen Only	Per Cubic Metre	3,962.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS: 280 and IS:4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (woven digonally including 10per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	130.73	3452.15	Rupees Three Thousand Four Hundred Fifty Two and Paise Fifteen Only	Per Cubic Metre	4,51,300.00
					Total	4,66,231.00

DNIT approved for Rs. 466,231/- only


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi

DRAFT SCHEDULE OF QUANTITY

Name of work :: RRD on Sandhapattan Bharol Bagora Bagla Hard Ropri Kalang Traimbli Drubbal Charonj Banwar Kotli
 Kun Ka Tar Mandonkhar Bhargaon Kotli road Km. 70/600 to 85/00. (SH:- C/O PCC R/wall at RD. 77/350
 to 77/357.50).

Estimated Cost Rs. 2,94,358/-
 Earnest Money Rs. 5900/-
 Time :: One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2 Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	3 15.79	4 464.20	5 Rupees Four Hundred Sixty Four and Paise Twenty Only	6 Per Cubic Metre	7 7,330.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	48.66	5285.35	Rupees Five Thousand Two Hundred Eighty Five and Paise Thirty Five Only	Per Cubic Metre	2,57,185.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	18.00	312.30	Rupees Three Hundred Twelve and Paise Thirty Only	Each	5,621.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	15.98	1515.75	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	24,222.00
Total						2,94,358.00

DNIT approved for Rs :- 2,94,358/only

[Signature]
 Executive Engineer,
 Mandi Division No-II,
 P.W.D. Mandi.

DRAFT SCHEDULE OF QUANTITY

Name of work :- A/R & M/O on Saigaloo to Sukh Kun road Km. 0/00 to 4/00.
 (SH:- P/L WBM Grade-III for correction layer and repair of pot holes between in Km. 0/00 to 1/00 and 3/00 to 4/00).
 Estimated Cos: Rs. 1,59,760/-
 Earnest Money Rs. 3200/-
 Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel roller 80-100 kN (Eighty - hundred Kn) static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per Technical Specification Clause 405 By Manual/Mechanical means including carriage of materials with in all leads, lifts and other incidentals.	20.20	3203.00	Rupees Three Thousand Two Hundred Three Only	Per Cubic metre	64,701.00
2	Providing and applying tack coat with Bitumen Emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 Kg. per sqm (zero point two five to zero point three zero kilogram per square metre) on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause 503 including hauling/carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	265.38	23.30	Rupees Twenty Three and Paise Thirty Only	Per square metre	6,183.00
3	Providing, laying and rolling of open-graded premix carpet of 20 mm (Twenty millimetre) thickness composed of 13.2 mm (Thirteen point two millimetre) to 5.6 mm (Five point six millimetre) aggregates using penetration grade bitumen VG-10/ S 90 to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN (Eighty - hundred Kn) static roller capacity, finished to required level and grades to be followed by seal coat of Type B as per technical specification Clause 508 By Manual Means including carriage of materials with in all leads, lifts and other incidentals.	265.38	256.45	Rupees Two Hundred Fifty Six and Paise Forty Five Only	Per square metre	68,057.00
4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Bitumen S-90/ VG-10 grade Type B as per Technical Specification clause 510 By Manual Means including carriage of materials with in all leads, lifts and other incidentals.	265.38	78.45	Rupees Seventy Eight and Paise Forty Five Only	Per square metre	20,819.00
	Total				Total	1,59,760.00

DRAFT amount approved for Rs. 1,59,760/- only.


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

267.

%age rate of SCHEDULE OF QUANTITY

Name of work:- RRB on Gokhra Lot Khajron Batahan road Km 0/00 to 8/200 (SI - C/O crated R/wall at Rd 0/421 to 0/428).
 Estimated Cost Rs. 4,94,126/-
 Earnest Money Rs. 10,000/-
 Time - One month.

Sr. No.	Description of items.	Quantity		Rates		Unit	Amount
		Figure	Words	Figure	Words		
1	2 Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	58.10		571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	33,219.00
2	Providing and laying 1.5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	22.75		5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	1,21,722.00
3	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS: 280 and IS: 4826 in 100mm X 100mm mesh (woven diagonally including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg each as per drawing and technical specification clause 1301 (Excluding fo wire crate) (Wire crate will be supplied by department free of cost) including carriage of materials with in all leads, lifts and other incidentals.	100.80		3254.10	Rupees Three Thousand Two Hundred Fifty Four and Paise Ten Only	Per Cubic Metre	3,28,013.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	7.70		1450.85	Rupees One Thousand Four Hundred Fifty and Paise Eighty Five Only	Per Cubic Metre	11,172.00
						Total	4,94,126.00


 Executive Engineer,
 Mandi Division No-II,
 HP, PWD, Mandi.

%age rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Gokhra Lot Khajron Batahan road Km 0/00 to 8/200 (SH : C/O crated R/wall at Rd 0/414 to 0/4214).

Estimated Cost Rs. 4,95,141/-

Earnest Money Rs. 10,000/-

Time :- One month.

Sr. No.	Description of Items.	Quantity		Rates		Unit	Amount
		Figure	Words	Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	58.10		571.75	Rupees Five Hundred Seventy One and Paise Seventy Five Only	Per Cubic Metre	33,219.00
2	Providing and laying 1:5:10 (One cement : five-sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	22.75		5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	1,21,722.00
3	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS: 280 and IS: 4826 in 100mm X 100mm mesh (woven diagonally including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg each as per drawing and technical specification clause 1301 (Excluding fo wire crate) (Wire crate will be supplied by department free of cost) including carriage of materials with in all leads, lifts and other incidentals.	100.80		3254.10	Rupees Three Thousand Two Hundred Fifty Four and Paise Ten Only	Per Cubic Metre	3,28,013.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204 3-8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.40		1450.85	Rupees One Thousand Four Hundred Fifty and Paise Eighty Five Only	Per Cubic Metre	12,187.00
						Total	4,95,141.00


 Executive Engineer,
 Mandi Division No-II,
 P. PWD, Mandi

102

%age rate of SCHEDULE OF QUANTITY

Name of work :- RRD on Gokhra Lot Khajron Batahan road Km 0/00 to S-200 (SII) -C/O crated R/wall at Rd 0/407 to 0/414.

Estimated Cost Rs. 4,96,258/-

Earnest Money Rs. 10,000/-

Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2 Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	3 58.10	4 571.75	5 Rupees Five Hundred Seventy One and Paise Seventy Five Only	6 Per Cubic Metre	7 33,219.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	22.75	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	1,21,722.00
3	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS: 280 and IS: 4826 in 100mm X 100mm mesh (woven diagonally including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1304 (Excluding to wire crate) (Wire crate will be supplied by department free of cost) including carriage of materials with in all leads, lifts and other incidentals.	100.80	3254.10	Rupees Three Thousand Two Hundred Fifty Four and Paise Ten Only	Per Cubic Metre	3,28,013.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification, Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals	9.17	1450.85	Rupees One Thousand Four Hundred Fifty and Paise Eighty Five Only	Per Cubic Metre	13,304.00
					Total	4,96,258.00


 Refutative Engineer,
 Majidi Division No-II,
 HP. PWD, Mandi.

%age rate of SCHEDULE OF QUANTITY

Name of work :- KRD on Gokhra Lot Khajron Batahan road Km 0/00 to 8/200 (SH :-C/O crated R/wall at Rd 0/400 to 0/407).

Estimated Cost Rs. 4,94,633/-
Earnest Money Rs. 10,000/-
Time :- One month.

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	3 58.10	4 571.75	5 Rupees Five Hundred Seventy One and Paise Seventy Five Only	6 Per Cubic Metre	7 33,219.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (forty millimetre nominal size) concrete for plain concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	22.75	5350.40	Rupees Five Thousand Three Hundred Fifty and Paise Forty Only	Per Cubic Metre	1,21,722.00
3	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS: 280 and IS: 4826 in 100mm X 100mm mesh (woven diagonally including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg each as per drawing and technical specification clause 1301) (Excluding to wire crate) (Wire crate, will be supplied by department free of cost) including carriage of materials with in all leads, lifts and other incidentals.	100.80	3254.10	Rupees Three Thousand Two Hundred Fifty Four and Paise Ten Only	Per Cubic Metre	3,28,013.00
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.05	1450.85	Rupees One Thousand Four Hundred Fifty and Paise Eighty Five Only	Per Cubic Metre	11,679.00
					Total	4,94,633.00


 Executive Engineer,
 Masrhi Division No-II,
 HP. PWD, Mandi.

102