

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO.PW/AD/EA-1/Tender/2023-24- 12177
To

Dated 03/01/2024

The Executive Engineer(IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2
Department,HP,Secretariat,
Shimla-2

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website.

Encl:- Copy of NIT


Executive Engineer,
Arki Divn.HP,PWD,Arki

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed item rate/percentage rate tender on Form No. 6&8 are hereby invited by the Executive Engineer, Arki Division, HP, PWD. Arki on behalf of the Governor of Himachal Pradesh for the following works from the competent (In this regard the decision of the Executive Engineer shall be final) contractors enlisted with HP, PWD in appropriate class whose registration stood renewed as per revised instruction and also registered dealers under the Himachal Pradesh sales Tax Act, 2017 so as to reach in this office on before 24.01.2024 upto 11:30 AM and the same shall be opened on the same day at 12:00 P.M. in the presence of the intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on 23.01.2024 upto 4:30 P.M and the application for issue of tender form shall be received on 22.01.2024 upto 5:00 P.M

The amount of Earnest Money in the shape of NSCs/FDR deposit at call of any of the Post Office/Bank pledged in favour of Executive Engineer, Arki Division, HP, PWD, Arki must be accompanied with the application for tender documents. Please note no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be deot open for 20 days. The Executive Engineer reserve right to reject any tender or all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

S.N o	Name of work	Estimated cost.	Earnest money	Form	Cost, of form	Time
1.	Annual Maintenanc of bridge in Arki Division(i)KBSB road 15/710,17/180,ADB road 14/485 & 17/410(SH:-Providing & Laying 25mm thick mastic asphalt wearing course	4,01,941/-	8100/-	6&8	350/-	1Months
2	Annual Maintenanc of bridge in Arki Division(i)SAKB road 4/100 ,17/500 & Arki Manjoo road 2/200(SH:-Providing & Laying 25mm thick mastic asphalt wearing course	3,98,521/-	8000/-	6&8	350/-	1months
3	R/R damages on KBSB road Km. 0/0 to 56/200(SH:-C/o B/wall for protection of existing building in km. 8/600 to 8/615	72,286/-	1500/-	6&8	350/-	1 Months

Followings documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Arki Divn. HP, PWD, Arki

Certificate

Certified that the tenders called vide this notice inviting tender for 3(Three) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer
Arki Divn. HP, PWD, Arki

SCHEDULE OF QUANTITY

Name of work:- R/R damages on KBSBB road km 0/000 to 56/200 (SH:- C/O B/wall for protection of existing building in km 8/600 to 8/615)

Estimated Cost:-Rs 72,286/- only
Earnest Money : Rs 1500/-Only
Time -One Month

S.N	Sub head and items of work	Qty.	Rate	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	5.40	Cum	Per cubic metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 including carriage of materials upto all leads and lifts.(i) 1:4:8 (40mm).	3.60	Cum	Per cubic metre	
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:3:6 (20mm nominal size)	11.70	Cum	Per cubic metre	
Total:-					

Executive Engineer
H.P PWD (B&R)
Division Arid

Schedule of quantity

Name of work:- Annual Maintenance of Bridges in Arki Division (I) SAKB road 4/100, 17/500 & Arki Manjoo road 2/200						Estimated Cost Rs. 3,98,521/- only	
(Slt:- Providing and Laying 25mm. thick mastic asphalt wearing course)						Earnest Money Rs. 8000/- only	
						Time :- One Month	
Sr. No	Description of items	Quantity		Rate		Unit	Amount
		In figure		in words			
1	Providing and applying tack coat with bitumen emulsion using emulsion (RS-1) using emulsion pressure distributor at the rate of 0.275 kg (zero point two seven five kilogramme) per square metre on the prepared bituminous/granular surfaces treated with primer and cleaned with hydraulic broom as per drawings and technical specifications MORTH Clause 503 including carriage of materials with in all leads and lifts as per the entire satisfaction and direction of Engineer-In-Charge.	218.50	Sqm			Per square metre	
2	Providing and laying bituminous concrete 25mm thick (twenty five millimetre) with 100-120 TPH capacity batch type hot mix plant producing an average output of 75 tonnes (seventy five tonnes) per hour using crushed aggregates of specified grading, premixed with bituminous binder concrete of @ 5% (five percent) of mix and filler, transporting the hot mix to work site, laying with a hydro static paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects including carriage of materials with in all leads and lifts as per the entire satisfaction and direction of Engineer-In-Charge. <i>The work should be executed as per Job Mix formula approved by department. The rates should be quoted accordingly. Nothing extra shall be applicable on this account.</i>	5.46	Cum			Per cubic metre	
3	Providing and laying 25 mm (twenty five millimeter) thick mastic asphalt wearing course with paving grade bitumen meeting the requirements given in table 500-29, prepared by using mastic cooker and laid to required level and slope after cleaning the surface, including providing antiskid surface with bitumen precoated finegrained hard stone chipping of 13.2 mm nominal size at the rate of 0.005cum per 10 sqm and at an approximate spacing of 10 cm center to center in both directions, pressed into surface when the temperature of surfaces is not less than 1000C, protruding 1 mm to 4 mm over mastic surface, all complete as per clause 515.	218.5	Sqm			Per square metre	
Total:-							

1A
 Executive Engineer
 H.P.W.D (B&M)
 Division Arki

Schedule of quantity

Annual Maintenance of Bridges in Arki Division(I) KBSB road 15/710.17/180, ADB road 15/485 & 17/410 (SH:- Providing and Laying 25mm, thick mastic asphalt wearing course)						Estimated Cost Rs. 4,01,941/-only	
						Earnest Money Rs. 8100/-only	
						Time :- One Month	
Sr. No	Description of items	Quantity	Unit	Rate		Amount	
				In figure	in words		
1	Providing and applying tack coat with bitumen emulsion using emulsion(RS-1) using emulsion pressure distributor at the rate of 0.275 kg (zero point two seven five kilogramme) per square metre on the prepared bituminous/granular surfaces treated with primer and cleaned with hydraulic broom as per drawings and technical specifications MORT&H Clause 503 including carriage of materials with in all leads and lifts as per the entire satisfaction and direction of Engineer-In-Charge.	220.34	Sqm			Per square metre	
2	Providing and laying bituminous concrete 25mm thick (twenty five millimetre) with 100-120 TPH capacity batch type hot mix plant producing an average output of 75 tonnes (seventy five tonnes) per hour using crushed aggregates of specified grading, premixed with bituminous binder concrete of @ 5% (five percent) of mix and filler, transporting the hot mix to work site, laying with a hydro static paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects including carriage of materials with in all leads and lifts as per the entire satisfaction and direction of Engineer-In-Charge. <i>The work should be executed as per Job Mix formula approved by department. The rates should be quoted accordingly.Nothing extra shall be applicable on this account.</i>	5.51	Cum			Per cubic metre	
3	Providing and laying 25 mm (twenty five millimeter) thick mastic asphalt wearing course with paving grade bitumen meeting the requirements given in table 500-29, prepared by using mastic cooker and laid to required level and slope after cleaning the surface, including providing antiskid surface with bitumen precoated finegrained hard stone chipping of 13.2 mm nominal size at the rate of 0.005cum per 10 sqm and at an approximate spacing of 10 cm center to center in both directions, pressed into surface when the temperature of surfaces is not less than 1000C, protruding 1 mm to 4 mm over mastic surface, all complete as per clause 515.	220.34	Sqm			Per square metre	
	Total:-						


 Executive Engineer
 H&A PWD (B&R)
 Division Arki