

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NO:-PW/SD/CB/TA/NIT /2023- 24-

10886

Dated- 05-01-2024

To

The Executive Engineer (IT Cell)
Nigam Vihar, Shimla-2,

Subject:- Tender Notice.

Dear Sir,

Enclosed Please find herewith the notice work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP. Letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.


1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender and sechdule of quantity.


Executive Engineer
B&R Division Shillai
HP PWD Shillai

CERTIFICATE

Certified that the tenders of works, as called vide this office letter No.PW-SD-CB-TA 2023-24- 10887- 10927 dated 05-01-24 are of urgent nature.


Executive Engineer
B&R Division Shillai
HP PWD Shillai

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed percentage rate tender on form PWD 6 & 8 are invited by the Executive Engineer Shillai, Division HP, PWD on behalf of governor of himachal Pradesh for the following works from the approved and eligible contractors enlisted in HP PWD so as to reach in this office as per time schedule given below.

1. Date of receipt of application of tenders forms:- 17.01.2024 Up to 5:00 Pm
2. Date of issue/ sale of tender Forms:- 18.01.2024 Up to 5:00 Pm
3. Date of receipt of tender :- 19.01.2024 Up to 11:30 Am
4. Date of opening of tender:- 19.01.2024 Up to 12:30 Pm

Job No.	Name of work	Estimated Cost	Earnest Money	Time of period	Cost of form	Eligible of class of Contractor
1	Restoration of rain damages on Link road Village Dhamon Km 0/0 to 4/250 (SH:- C/o of R/wall in Wire crate at RD 1/330 to 1/340).	4,97,591/-	10000/-	One Month	350/-	D Class
2	Restoration of rain damages on Manal Korga road km 0/0 to 10/500 (SH:- C/o R/wall in PCC 1:4:8 at RD 1/900 to 1/921).	4,98,397/-	10000/-	One Month	350/-	D Class
3	Restoration of rain damages on Manal Kanti Mashwa road km 0/0 to 13/450 (SH:- C/o of R/wall in PCC 1:4:8 at RD 3/110 to 3/130).	4,98,397/-	10000/-	One Month	350/-	D Class
4	A/R & M/O Salwala Sataun road Km 0/0 to 9/600(SH:- improvement of curves from Km 3/900 to 4/042)	4,96,778/-	10000/-	One Month	350/-	D Class
5	Restoration of rain damages on Manal Korga road km 0/0 to 10/500 (SH:- C/o R/wall in PCC 1:4:8 at RD 7/520 to 7/560).	4,83,156/-	9700/-	One Month	350/-	D Class
6	Restoration of rain damages on Manal Kanti Mashwa road km 0/0 to 13/450 (SH:- C/o of R/wall in wire crate at RD 2/820 to 2/836).	4,64,119/-	9300/-	One Month	350/-	D Class
7	Restoration of rain damages on Manal Kanti Mashwa road km 0/0 to 13/450 (SH:- C/o of R/wall in PCC 1:4:8 at RD 6/227 to 6/240).	4,69,096/-	9400/-	One Month	350/-	D Class
8	Restoration of rain damages on Renuka Sataun road km 13/450 to 29/060 (SH:- C/o R/wall in wire crate at RD 19/620 to 19/633).	4,54,860/-	9200/-	One Month	350/-	D Class
9	Restoration of rain damages on Renuka Sataun road km 13/450 to 29/060 (SH:- C/o R/wall in PCC 1:4:8 at RD 28/110 to 28/122).	4,30,554/-	8700/-	One Month	350/-	D Class
10	Restoration of rain damages on Sataun to Pocca road km 0/0 to 10/500 (SH:- C/o R/wall in R/R Masonry at RD 6/210 to 6/230).	4,83,408/-	9700/-	One Month	350/-	D Class
11	Restoration of rain damages on Link road Village Bokala km 0/0 to 2/00 (SH:- C/o R/wall in PCC 1:4:8 at RD 0/060 to 0/072 & 0/250 to 0/260)	4,85,335/-	9800/-	One Month	350/-	D Class
12	Restoration of rain damages on Kaffota Koti road km 0/0 to 29/500 (SH:- C/o R/wall in R/R Masonry at RD 14/115 to 14/128).	3,04,564/-	6200/-	One Month	350/-	D Class
13	Restoration of rain damages on Kaffota Koti road km 0/0 to 29/500 (SH:- C/o R/wall in R/R Masonry at RD 14/665 to 14/678).	3,70,021/-	7500	One Month	350/-	D Class
14	Restoration of rain damages on Sharli Kumli road km 0/0 to 7/700 (SH:- C/o B/wall in wire crate at RD 6/520 to 6/554).	3,04,657/-	6100	One Month	350/-	D Class
15	A/R & M/O link road from Jakhna to Sharli Manpur km 0/0 to 7/750 (SH:- Repair of abutment , CC bedding curtain walls of slab culvert at RD 3/350).	2,55,656/-	5200	One Month	350/-	D Class

16	Restoration of rain damages on Sharli Kumli road km 0/0 to 7/700 (SH:- C/o B/wall in wire crate at RD 6/240 to 6/275).	3,15,865/-	6400	One Month	350/-	D Class
17	Restoration of rain damages on Devlan Khuinak road km 0/0 to 1/350 (SH:- C/o R/wall in PCC 1:4:8 at RD 0/875 to 0/891).	4,97,599/-	10000	One Month	350/-	D Class
18	Restoration of rain damages on Link road Village Bokala km 0/0 to 1/300 (SH:- C/o R/wall in PCC 1:4:8 at RD 0/0485 to 0/499)	4,96,991/-	10000	One Month	350/-	D Class
19	Restoration of rain damages on Juinal Rangwa Pabhar road Km 0/0 to 2/500 (SH:- Construction of R/Wall in R/R Masonry at RD 1/090 to 1/109)	4,44,475/-	8900	One Month	350/-	D Class
20	Restoration of rain damages on Kaffota Koti road Km 0/0 to 29/750 (SH:- Construction of R/Wall in R/R Masonry at RD 2/690 to 2/705)	4,24,647/-	8500	One Month	350/-	D Class
21	Restoration of rain damages on Kaffota Koti road Km 0/0 to 29/750 (SH:- Construction of R/Wall in R/R Mesonry at RD 3/510 to 3/527)	3,93,066/-	7900	One Month	350/-	D Class
22	Restoration of rain damages Kaffota Koti road Km 0/00 to 29/750 (SH:- Construction of B/Wall in R/R masonry at RD 28/450 to 28/494)	4,66,684/-	9400/-	One Month	350/-	D Class
23	Restoration of rain damages on link raod to village Shawri Km 0/0 to 2/00 (SH:- Construction of R/Wall in PCC 1:4:8 at RD 1/880 to 1/916)	4,37,089/-	9700	One Month	350/-	D Class
24	Restoration of rain damages on link road to Kaffota Koti Road Km 0/0 to 29/750 (SH:- Construction of R/Wall in PCC 1:4:8 at RD 18/110 to 18/125)	4,76,164/-	9500	One Month	350/-	D Class
25	Special repair on LPRR road Km 97/00 to 112/167 (SH:- Construction of 900mm H.P.C at RD 106/150)	4,81,496/-	9700	One Month	350/-	D Class
26	Restoration of rain damages on Panog Ajroli road Km 0/0 to 3/500 (SH:- Construction of Retaining wall at RD 1/889 to 1/901)	4,95,979/-	10000	One Month	350/-	D Class
27	Restoration of rain damages Shri Kiyari Gattu Shanayil road Km 0/00 to 4/500 (SH:- Construction of R/Wall in R/R Masonry at RD 0/210 to 0/230)	4,94,605/-	10000	One Month	350/-	D Class
28	Restoration of rain damages on Rast Manal Chunoti Road Km 0/0 to 15/960 (SH:- Construction of R/Wall in R/R Masonry at RD 9/300 to 9/315 & 9/900 to 9/912)	4,98,461/-	10000	One Month	350/-	D Class
29	Restoration of rain damages on Shri Kiyari to Gattu Shanil Road Km 0/0 to 4/500 (SH:- Construction of R/Wall in R/R masonry at RD 0/075 to 0/096)	4,94,605/-	9900	One Month	350/-	D Class
30	Restoration of rain damages on Gangtoli Kunhat road Km 0/0 to 5/00 (SH:- Construction of R/Wall in Dry Rubble Masonry at RD 4/900 to 4/970)	4,97,374/-	10000	One Month	350/-	D Class
31	Construction of link road from Kafenu Kukrech Bogra Thana Konla to Manal road km 0/0 to 3/445 (SH:- Formation cutting 5/7 mtrs wide road in Km 2/760 to 3/345) Under SCSP	4,98,885/-	10000	One Month	350/-	D Class
32	Restoration of rain damages on Rajpur Section Under Sataun Sub-Division (SH:- Hiring of Excavator cum loader for on Various road)	4,96,800/-	10000	One Month	350/-	D Class
33	A/R & M/O Bharli Rudhana Thada Zizla road Km 0/0 to 4/00 (SH:- Improvement of Curve in Km 1/720 to 1/880)	4,91,850/-	10000	One Month	350/-	D Class
34	Restoration of rain damages on PDPA road Km 0/00 to 5/00 (SH:- Construction of R/Wall in PCC 1:4:8 at RD 0/400 to 0/410 & 0/450 to 0/460)	4,92,162/-	9900/-	One Month	350/-	D Class
35	Restoration of rain damages on PDPA road Km 0/00 to 5/00 (SH:- Construction of R/Wall in PCC 1:4:8 at RD 3/150 to 3/160 & 3/320 to 3/330)	4,91,630/-	9900/-	One Month	350/-	D Class
36	Restoration of rain damages on Shillai Achhoti Pandiyat road Km 0/0 to 7/500 (SH:- Construction of R/Wall in R/R Masonry at RD 1/860 to 1/881)	4,94,605/-	9900/-	One Month	350/-	D Class
37	A/R & M/O Drabil Nanidhar Hallan road Km 0/0 to 21/00 (SH:- Improvement of curves from RD 14/735 to 14/875)	4,99,604/-	10000/-	One Month	350/-	D Class
38	Restoration of rain damages Koti Uttrou road Km 0/00 to 6/00 (SH:- Construction of R/Wall in R/R Masonry at RD 0/350 to 0/374)	4,86,341/-	9700/-	One Month	350/-	D Class

38	Restoration of rain damages Koti Uttrou road Km 0/00 to 6/00 (SH:- Construction of R/Wall in R/R Masonry at RD 0/350 to 0/374)	4,86,341/-	9700/-	One Month	350/-	D Class
39	Restoration of rain damages Koti Uttrou road km 0/00 to 6/00 (SH:- construction of R/Wall In R/R Masonry at RD 5/650 to 5/674)	4,85,809/-	9700/-	One Month	350/-	D Class
40	Restoration of rain damages on Solan Meenus km 110/00 to 128/325 (SH:- construction of R/Wall In R/R Masonry at RD 118/930 to 118/949)	4,96,938/-	10000/-	One Month	350/-	D Class
41	Restoration of rain damages on Drabil Nanidhar Hallan road Km 0/0 to 21/00 (SH:-Construction of R/Wall in PCC 1:4:8 at RD 13/845 to 13/863)	4,99,753/-	10000/-	One Month	350/-	D Class
42	Restoration of rain damages on Shillai Achoti Pandiyat road Km 0/0 to 7/500 (SH:- Construction of R /Wall in R/R Masonry at RD 2/910 to 2/934)	4,98,988/-	10000/-	One Month	350/-	D Class
43	Restoration of rain damages on Kaffota Koti road Km 0/00 to 29/750 (SH:- Construction of R/Wall in R/R Masonry at RD 0/090 to 0/105 & 0/110 to 0/124)	4,95,154/-	10000/-	One Month	350/-	D Class
44	Restoration of rain damages on millah Digwa road Km 0/00 to 7/00 (SH:- Construction of R/Wall in R/R Masonry at RD 3/700 to 7/724)	4,94,800/-	9900/-	One Month	350/-	D Class
45	Restoration of rain damages on Gummath to Lani Borar road Km 0/0 to 5/555 (SH:- Construction of R/Wall in R/R Masonry at RD 1/600 to 1/610, 1/990 to 2/00 & 2/300 to 2/310)	4,99,286/-	10000/-	One Month	350/-	D Class
46	Restoration of rain damages on Timbi Section Under Timbi Sub - Division (SH:-Removal of slips from Various road)	4,97,948/-	9900/-	One Month	350/-	D Class
47	Restoration of rain damages on Shillai-2 Section under Shillai Sub-Division (SH:- Hiring of Excavator cum loader for on various road)	4,69,800/-	9400/-	One Month	350/-	D Class
48	Improvement of black spot on Shilla Gundha Tityana road Km 0/00 to 13/00 (SH:- Improvement of curves at different RDs)	4,93,500/-	9900/-	One Month	350/-	D Class

Terms and conditions:-The tender documents shall be issued only to these contractors firms who fulfill the following criteria and submit the following documents with the application

- 1 The Earnest money for the above works should be submitted with applications for the purchase of the tender documents.
- 2 The contractors should quoted the rates of all the items in the tenders both in figures and words
- 3 Income Tax and GST No. latest clearance certificate.
- 4 The contractors/firms shall accompany his enlistment /renewal and EPF submit before the award of tender.
- 5 The Executive Engineer reserves the right to accept / rejected any tender/applications or all tenders without assigning any reason.

Executive Engineer
B&R Division Shillai
HP PWD Shillai

PW-SD-CB-TA-2023-24-

10887-10927

Dated:- 05-01-2024

Copy forwarded for information and wide publicity to:-

1. The Superintending Engineer in 12th HP PWD in Nahan
2. All the Assistant Engineer working under this Division.
3. A/B and D/B in this office.
4. Notice Board.

Executive Engineer
B&R Division Shillai
HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road village Dhamon Km 0/0 to 4/250 (SH:- Construction of R/wall in wire crate at RD 1/330 to 1/340)

Job. 1

Estimated Cost:- 497591/-

Only. Earnest Money:-10000/-

Only Time Limit:- One

Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	105.00	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	30907.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 Kg each as per drawing and technical specifications Clause 1301.including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	176.40	Per cubic metre	2645.60	Rs. Two thousand Six hundred forty five & sixty paise only.	466684.00
				Total:-		497591.00

Select:-

Plus(+) (.....%)

Minus(-) (.....%)

Executive Engineer

Shillai Division

HP PWD Shillai

Name and full address of the contractor:-

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Manal Kotga road Km 0/0 to 10/500 (SH:-Construction of R/wall in PCC. 1:4:8 at RD 1/900 to 1/921)

Job. 2

Estimated Cost:- 4,98,397/- Only.
Earnest Money:-10000/- Only
Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with all modes of transportation in all leads and lifts, including all incidental charges.	69.60	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	20487.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement :four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP.PWD. Engineer-in-Charge.	105.82	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	458052.00
3	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	9.77	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	7615.00
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	46.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	12243.00
Total						498397.00

Name and full address of the contractor:-

Executive Engineer
Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Manal Kant Mashwa road Km 0/0 to 13/450 (SH:-Construction of R/wall in PCC 1:4:8 at RD 3/110 to 3/130)

Job. 3

Estimated Cost:- 498397/- Only.

Earnest Money:- 10000/- Only

Time Limit: - One Month

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	69.60	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	20487.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement :four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP.PWD. technical specifications. clauses 802,803,1202 and 1203 including all leads, lifts or as directed by the Engineer-in-Charge.	105.82	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	458052.00
3	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8.including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	9.77	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	7615.00
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of i(V):.20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 .including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	46.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	12243.00
Total						498397.00

Select:-

Plus(+)

(.....%)

Minus(-)

(.....%)

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

Draft SCHEDULE OF QUANTITY						Job:- 41	Estimated Cost:-496778/- Only. Earnest Money:-10000/- Only	Time Limit:- Two Month
Name of work:-A/R & M/O Salwala Sataun road Km 0/0 to 9/600(SH:- Improvement of curves from Km 3/900 to 1/885)								
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount		
				Figures	Words			
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soils including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification of Ministry of Rural Development for Rural Roads August, 2004 (Two Thousand Four), and clause 16.2 (Sixteen point two) of General condition for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places. in specified manner, systematically with due consideration to avoiding adverse effects on environment, trimming, filling of unevenness, blind age and finishing of the road to specified dimensions to the entire satisfaction as directed by the Engineer-in charge for smooth riding. The recovery for stones, whether useful or not, for 1039 cubic metre(One thousand thirty nine point zero seven cubic metre) in all cases at the rate of Rupees 170/= only (Rupees One hundred Seventy only) per cubic meter shall be effected on prorata basis.. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	3139.20	Per cubic metre	158.25	Rs. One hundred fifty eight & twenty five paise only.	496778.00		
				Select:-		496778.00		
				Plus(+)	(.....%)			
				Minus(-)	(.....%)			

Name and full address of the contractor:-

Executive Engineer
Shillai Division
HP PWD Shillai

Name of work:- Restoration of rain damages on Manal Korga road Km 0/0 to 10/500 (SH:-Construction of B/wall in PCC 1:4:8 at RD 1/520 to 7/5602)

SCHEDULE OF QUANTITY

Job. 5

Estimated Cost:- 483156/- Only.
Earnest Money:- 9700/- Only
Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	66.40	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	19545.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement :four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP.PWD. technical specifications clauses 802,803,1202 and 1203 including all leads, lifts or as directed by the Engineer-in-Charge.	102.80	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	444980.00
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204,3.7 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	70.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	18631.00
Total						483156.00

Name and full address of the contractor:-

Executive Engineer

Shilal Division

HP PWD Shilal

SCHEDULE OF QUANTITY							Job. 6	Estimated Cost:- 464119/-
Name of work:-Restoration of rain damages on Manal Kanti Mashwa road Km 0/0 to13/450 (SH:-Construction of R/wall in wire crate at RD 2/820 to 2/836)							Only. Earnest Money:-9300/- Only Time Limit: - One	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount		
				Figures	Words			
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	168.00	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	49451.00		
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301.including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	155.52	Per cubic metre	2666.33	Rs.Two thousand Six hundred Sixty Six & thirty three paise only.	414668.00		
					Total:-	464119.00		
					Select:-			
					Plus(+)	(.....%)		
					Minus(-)	(.....%)		

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Manal Kanti Mashwa road Km 0/0 to 13/450 (SH:-Construction of R/wall in PCC 1:4:8 at RD 6/227 TO 6/240)

Job. 7

Estimated Cost:- 469096/- Only.
Earnest Money:- 9400/- Only
Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	61.88	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	18214.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement: four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP.PWD. technical specifications, clauses 802, 803, 1202 and 1203 including all leads, lifts or as directed by the Engineer-in-Charge.	97.89	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	423727.00
3	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8, including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	9.23	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	7194.00
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	75.00	Each	266.15	Rs. Two hundred sixty six & fifteen paise only.	19961.00
Total						469096.00

Select:-

Plus(+)

Minus(-)

(%)

(%)

Name and full address of the contractor:-

Executive Engineer

Shilal Division

HP PWD Shilal

SCHEDULE OF QUANTITY							Job. 9	Estimated Cost:- 454860/-
Name of work:- Restoration of rain damages on Renuka Sataun road Km 13/450 to 29/060 (SH:-Construction of R/wall in wire crate at RD-19/620 to 19/633)							Only. Earnest Money:-9200/- Only Time Limit:- One	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount		
				Figures	Words			
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	136.50	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	40179.00		
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301.including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	159.12	Per cubic metre	2606.09	Rs. Two thousand Six hundred Six & nine paise only.	414681.00		
				Total:-		454860.00		
				Select:-	Plus(+)	(.....%)		
					Minus(-)	(.....%)		

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work: Restoration of rain damages on Renuka Sataun road Km 13/450 to 29/060 (SH:-Construction of R/wall in PCC 1:4:8 at RD 28/110 TO 28/122)

Job. 47 Estimated Cost:- 430554/- Only.

Earnest Money:-8700/- Only

Time Limit: - One Month

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	57.12	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	16813.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement :four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP.PWD. technical specifications. clauses 802,803,1202 and 1203 including all leads, lifts or as directed by the Engineer-in-Charge.	90.36	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	391132.00
3	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8.including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	8.52	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	6640.00
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	60.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	15969.00
Total						430554.00

Select:-

Plus(+) (.....%)
Minus(-) (.....%)

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Sataun to Pocca road Km 0/0 to 10/500(SH:-Construction of R/wall in R/R Masonry at RD 6/210 to 6/230)

Job - 10

Estimated Cost:-4,83,408/- Only.
Earnest Money:-9700/- Only
Time Limit: - One Month

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	81.12	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	23878.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	21.13	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	91463.00
3	Random rubble masonry in cement mortar:1:6 (one cement : six sand)in foundation complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	55.28	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	186913.00
4	Construction of dry rubble masonry for retaining walls,Breast walls,Revetment walls and parapets etc. for sub structure and superstructure complete as per drawing and technical specification clause 704, 6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	89.93	Per cubic metre	1852.15	Rs. One thousand eight hundred fifty two & paise fifteen only.	166564.00
5	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	18.72	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	14590.00
				Total:-		483408.00

Name and full address of the contractor:-

Executive Engineer
Shillai Division
HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:-Restoration of rain damages on link road village Bokala Km. 0/0 to 2/00. (SH:-Construction of R/wall in PCC 1:4:8 at RD at RD 0/060 to 0/072 & 0/250 to 0/260)

Job:- 1 Estimated Cost:-4,85,335/- Only.
Earnest Money:-9800/- Only
Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges	58.92	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	17343.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	102.74	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	444720.00
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	40.00	Each	266.15	Rs. Two hundred sixty six & fifteen paise only.	10646.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	16.20	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	12626.00
Total:-				485335.00		
Select:-				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Note:-The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All rates including octroi, royalty,malkhana,tall tex, GST or other tax imposed by the Govt.

Name and full address of the contractor:-

Executive Engineer
Shillai Division
HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:-Restoration of rain damages on Kaffota Koti road Km 0/00 to 29/500 (SH:- C/o R/Wall in R/R masonry at RD 14/115 to 14/128)

Job - 19

Estimated Cost:-304564/- Only.

Earnest Money:-6200/- Only

Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	51.48	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	15153.00
2	Providing and Laying cement concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC (Plain cement concrete) 1:6:12 (One cement : six sand : twelve graded stone aggregate) 40mm (forty millimeter) size and curing complete including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.36	Per cubic metre	3877.95	Rs. Three thousand eight hundred seventy seven & paise ninety only.	36298.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	5.72	Per cubic metre	4329.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	24765.00
4	Random rubble masonry in cement mortar1:6 (one cement : six sand)in foundation complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	43.02	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	145459.00
5	Construction of dry rubble masonry for retaining walls,Breast walls,Revetment walls and parapets etc. for sub structure and superstructure complete as per drawing and technical specification clause 704,6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	37.14	Per cubic metre	1852.15	Rs. One thousand eight hundred fifty two & paise fifteen only.	68789.00

6	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	21.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	5589.00
7	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	10.92	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	8511.00

Note:-The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All rates including octroi, royalty,malkhana,tall tex, GST or other tax imposed by the Govt.

Name and full address of the contractor:-

Select:-	Total:-	304564.00
	Plus(+)	(.....%)
	Minus(-)	(.....%)

Executive Engineer
Shillai Division
HP PWD Shillai

Name of work:- Restoration of rain damages on Kaffota Koti road Km 0/00 to 29/500 (SH:- C/o R/Wall in R/R masonry at RD 14/665 to 14/678)						Job- 12	Estimated Cost:- 370021/- Only.
SCHEDULE OF QUANTITY							
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in	Amount		
				Figures	Words		
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal of leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	69.16	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	20357.00	
2	Providing and Laying cement concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC (Plain cement concrete) 1:6:12 (One cement : six sand : twelve graded stone aggregate) 40mm (forty millimeter) size and curing complete including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	10.37	Per cubic metre	3877.95	Rs. Three thousand eight hundred seventy seven & paise ninety only.	40214.00	
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	6.11	Per cubic metre	4329.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	26454.00	
4	Random rubble masonry in cement mortar 1:6 (one cement : six sand) in foundation complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	51.52	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	174199.00	
5	Construction of dry rubble masonry for retaining walls, Breast walls, Revetment walls and parapets etc. for sub structure and superstructure complete as per drawing and technical specification clause 704,6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	49.63	Per cubic metre	1852.15	Rs. One thousand eight hundred fifty two & paise fifteen only.	91922.00	

6	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	28.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	7452.00
7	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	12.09	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	9423.00
				Total:-		370021.00

Note:- The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All rates including octroi, royalty, malikana, tail tax, GST or other tax imposed by the Govt.

Name and full address of the contractor:-

Select:-	
Plus(+)	(.....%)
Minus(-)	(.....%)

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Job. 14

Estimated Cost:- 304657/- Only.

Name of work:- Restoration of rain damages on Sharli Kumli road road Km 0/0 to 7/700 (SH:- Construction of B/wall in wire crate at RD 6/520 to 6/554)

Earnest Money:- 6100/- Only

Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	63.92	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	18815.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301.including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	116.88	Per cubic metre	2445.60	Rs. Two thousand four hundred forty four & Sixty paise only.	285842.00
				Total:-		304657.00
				Select:-		
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Note:- The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All rates including octroi, royalty, makhana, tall tex, GST or other tax imposed by the Govt.

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Job. 15

Estimated Cost:- 255656/- Only.

Earnest Money:-5200/- Only

Time Limit: - One Month

Name of work:- A/R & M/O link road from Jakhana to Shari Manpur Km 0/0 to 7/750(SH)- Repair of abutment, C.C bedding curtain walls of slab culvert at RD 3/350)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	21.64	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	6370.00
2	Plain/reinforced cement concrete in substructure complete as per drawing and technical specification clause 802,804,805 ,806,807,1202 and 1204.P.C.C. Grade M-20 (Nominal mix 1:2.5:5) (One cement: two piont five sand: four graded stone aggregate) for height upto 5.00 m(Five Metre).including carriage of material in all leads and lifts as per the direction of the Engineer- In-charge.	38.66	Per cubic metre	5325.00	Rs. Five thousand three hundred twenty five & nil paise only.	205865.00
3	Providing concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203.P.C.C. Grade M-10 (Nominal mix 1:3:6 (One cement: three sand:six graded stone aggregate)including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	6.15	Per cubic metre	4816.00	Rs. Four thousand eight hundred sixteen & nil paise only.	29618.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	17.71	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	13803.00
				Total:-		255656.00

Note:- The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All rates including octroi, royalty, malikana, tall tax, GST or other tax imposed by the Govt.

Name and full address of the contractor:-

Select:-	
Plus(+)	(.....%)
Minus(-)	(.....%)

Executive Engineer

Shillat Division

HP PWD Shillat

SCHEDULE OF QUANTITY

Job. 16

Estimated Cost:- 315865/- Only.

Name of work:- Restoration of rain damages on Sharli Kumiil road road Km 0/0 to 7/700 (SH:- Construction of B/wall in wire crate at RD 6/240 to 6/275)

Earnest Money:-6400/- Only
Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	73.50	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	21635.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301.including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	120.31	Per cubic metre	244.60	Rs. Two thousand four hundred forty four & sixty paise only.	294230.00
				Total:-		315865.00

Note:- The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All rates including octroi, royalty, malikana, tall tax, GST or other tax imposed by the Govt.

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

HP PWD Shillai

SCHEDULE OF QUANTITY					Job. 17	Estimated Cost:- 497599/- Only.
Name of work:- Restoration of rain damages to Devlan Khuinal road Km 0/0 to 1/350(SH)- Construction of R/wall in PCC 1:4:8 from RD 0/875 to 0/891)					Earnest Money:- 10000/- Only Time Limit:- One Month	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	42.70	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	12569.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement :four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP.PWD. technical specifications. clauses 802,803,1202 and 1203 including all leads, lifts or as directed by the Engineer-in-Charge.	104.72	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	453291.00
3	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of i(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	42.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	11178.00
4	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8.including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	26.38	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	20561.00
Total						497599.00

Select:-	
Plus(+)	(.....%)
Minus(-)	(.....%)

Name and full address of the contractor:-

Executive Engineer
Shillai Division
HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages to Link road village Bokala Km 0/0 to 1/300(SH:- Construction of R/wall in PCC:1:4:8 from RD 0/485 to 0/499)

Job. 19

Estimated Cost:- 496991/- Only.

Earnest Money:-10000/- Only
Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	66.64	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	19615.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement :four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP.PVD. technical specifications, clauses 802,803,1202 and 1203 including all leads, lifts or as directed by the Engineer-in-Charge.	105.42	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	456321.00
3	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	50.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	13308.00
4	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8.including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	9.94	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	7747.00
Total						496991.00

Select:-

Plus(+) (.....%)

Minus(-) (.....%)

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Job:- 19 Estimated Cost:-4,44,475/- Only.
Earnest Money:-8900/- Only
Time Limit:- One Month

Name of work:-Restoration of rain damages on Juinal Rangwa Pabhar road Km 0/0 to 2/500 (SH:- Construction of R/wall in R/R Masonry at RD 1/090 to 1/109)

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	82.08	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	24160.00
2	Providing and laying cement concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC (Plain cement concrete) 1:6:12 (One cement : six sand : twelve graded stone aggregate) 40mm (forty millimetre) size and curing complete including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.68	Per cubic metre	3877.95	Rs. Three thousand eight hundred eighty seven & paise ninety only.	53050.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In-charge.	8.36	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	36187.00
4	Random rubble masonry in cement mortar 1:6 (one cement : six sand)in foundation complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	62.22	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	210378.00
5	Construction of dry rubble masonry for retaining walls, Breast walls,Revetment walls and parapets etc. for sub structure and superstructure complete as per drawing and technical specification clause 704,.6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	54.86	Per cubic metre	1852.15	Rs. One thousand eight hundred fifty two & paise fifteen only.	101609.00
6	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3,7 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	30.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	7985.00
7	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads, lifts, and carriage of material as per the direction of the Engineer incharge.	14.25	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	11106.00
				Total:-		444475.00
				Select:-	Plus(+)	(.....%)
					Minus(-)	(.....%)

Name and full address of the contractor:-

Executive Engineer
Shilal Division
HP PWD Shilal

SCHEDULE OF QUANTITY

Name of work: Restoration of rain damages on Kaitota Koti road Km 0/0 to 29/750(SH:- Construction of R/wall in R/R Masonry at RD 2/690 to 2/705)

Job: **20**

Estimated Cost:-424647/- Only.

Earnest Money:-8500/- Only

Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	79.80	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	23489.00
2	Providing and Laying cement concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC (Plain cement concrete) 1:6:12 (One cement : six sand : twelve graded stone aggregate) 40mm (forty millimeter) size and curing complete including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	11.97	Per cubic metre	3877.95	Rs. Three thousand eight hundred eighty seven & paise ninety only.	46419.00
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802, 803, 1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	7.05	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	30517.00
4	Random rubble masonry in cement mortar 1:6 (one cement : six sand) in foundation complete as per drawing & technical specification clauses 702, 704, 1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	59.16	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	200032.00
5	Construction of dry rubble masonry for retaining walls, Breast walls, Retement walls and parapets etc. for sub structure and superstructure complete as per drawing and technical specification clause 704, 6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	57.53	Per cubic metre	1852.15	Rs. One thousand eight hundred fifty two & paise fifteen only.	106554.00
6	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	32.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	8517.00
7	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer incharge.	11.70	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	9119.00
				Total:-		424647.00
				Select:-		
				Plus(+)		(.....%)
				Minus(-)		(.....%)

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Job-21
Estimated Cost:-393066/- Only.
Earnest Money:-7500/- Only
Time Limit: - One Month

Construction of Rain damages on Kaffila Koli road Km 0/0 to 29/750(SH)-Construction of R/Wall in R/R Masonry at RD 3/510 to 3/527

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	73.44	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	21617.00
2	Providing and laying cement concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC (plain cement concrete) 1:6:12 (One cement : six sand : twelve graded stone aggregate) 40mm (forty millimeter) size and curing complete including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	12.24	Per cubic metre	3877.95	Rs. Three thousand eight hundred eighty seven & paise ninety only.	47466.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802, 803, 1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- in- charge.	7.48	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	32378.00
4	Random rubble masonry in cement mortar1:6 (one cement : six sand)in foundation complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	52.98	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	179136.00
5	Construction of dry rubble masonry for retaining walls, Breast walls, Revetment walls and parapets etc. for sub structure and superstructure complete as per drawing and technical specification clause 704, 6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	51.48	Per cubic metre	1852.15	Rs. One thousand eight hundred fifty two & paise fifteen only.	95349.00
6	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	24.00	Each	266.15	Rs. Two hundred sixty six & fifteen paise only.	6388.00
7	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	13.77	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	10732.00
				Total:-		393066.00
				Select:-		
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Kafiola Koti road Km 0/00 to 29/750 (SH:- Construction of B/wall in R/R masonry at RD 28/450 to 28/494)

Job - 29

Estimated Cost:- 4,66,684/- Only.

Earnest Money:- 9400/- Only

Time Limit:- One Month

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Figures	Rate in	Amount
				Words		
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	54.56	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	16060.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802, 803, 1202 and 1203.1:4:8 (One cement: Four Sand: eight graded stone aggregate) 25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- in- charge.	10.12	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	43805.00
3	Random rubble masonry in cement mortar 1:6 (one cement: six sand) in foundation complete as per drawing & technical specification clauses 702, 704, 1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	115.28	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	389785.00
5	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia A/C pipe extending through the full width of the structure with slopes of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	64.00	Each	266.15	Rs. Two hundred sixty six & fifteen paise only.	17034.00
				Select:-	Total:-	466684.00
				Plus(+)		(.....%)
				Minus(-)		(.....%)

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shikar

SCHEDULE OF QUANTITY

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	62.10	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	18279.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement :four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP.PWD. technical specifications.clauses 802,803,1202 and 1203 including all leads, lifts or as directed by the Engineer-in-Charge.	92.45	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	400179.00
3	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of i(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 .including all leads,lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	70.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	18631.00
Total						437089.00

Name and full address of the contractor:-

Select:-	Plus(+)	Minus(-)	(.....%)
	(.....%)	(.....%)	(.....%)

Executive Engineer
Shillai Division
HP PWD Shillai

SCHEDULE OF QUANTITY

Job 24

Estimated Cost:- 476164/- Only.

Earnest Money:- 9500/- Only

Time Limit:- One Month

Sl. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	40.80	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	12009.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement :four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) In open foundation complete as per drawing and HP.PWD. Engineer-in-Charge.	100.11	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	433336.00
3	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8.including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	25.20	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	19641.00
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	42.00	Each	266.15	Rs. Two hundred sixty six & fifteen paise only.	11178.00
Total						476164.00

Select:-

Plus(+)

(.....%)

Minus(-)

(.....%)

Name and full address of the contractor:-

Executive Engineer

Shillat Division

HP PWD Shillat

SCHEDULE OF QUANTITY

Name of work:- Special repair on LPRR road Km 97/0 to 112/167 (SH:-Construction of 900mm H.P.C at RD 106/150)

Job- **75**

Estimated Cost:- 481496/- Only.

Earnest Money:- 9700/- Only Time

Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	44.65	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	13143.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement: four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP.PWD. technical specifications, clauses 802, 803, 1202 and 1203 including all leads, lifts or as directed by the Engineer-in-Charge.	82.10	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	355378.00
3	Providing and laying reinforced concrete pipe NP2 as per design in single row, culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:3 but excluding excavation protection works back filling concrete and masonry works in head walls and parapets clause 1106 RCC pipe NP2 900mm dia as per design, including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	25.00	Per Running metre.	4106.65	Rs. Four thousand one hundred six & sixty five paise only.	102666.00
4	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8, including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	7.08	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	5518.00
5	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	18.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	4791.00
Total						481496.00

Name and full address of the contractor:-

Executive Engineer
 Shillai Division
 HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Panog Ajroli road Km 0/0 to 3/500 (SH:- Construction of Retaining wall at RD 1/889 to 1/901)

Job. 26

Estimated Cost:- 4,95,979/- Only.

Earnest Money:-10000/- Only

Time Limit: - One Month

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 Including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	24.83	Per cubic metre	294.35	Rs. Two hundred ninety four & thirty five paise only.	7309.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	109.03	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	471947.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	8.48	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	6609.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	38.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	10114.00
				Total:-		495979.00

Note:- The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All rates including octroi, quality,maikhana,tail tex, GST or other tax imposed by the Govt.

Name and full address of the contractor:-

Executive Engineer
Shillai Division
HP PWD Shillai

Job-27

Estimated Cost:-4,94,605/- Only.

One Month

Name and full address of the contractor:-

Shillai Division

7

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Rast Manal Chunoti road Km 0/0 to 15/960 (SH.-Construction of R/Wall in R/R Masonry at RD9/300 TO 9/315 & 9/900 TO 9/912)

Job No. 28

Estimated Cost:- 4,98,461/- Only.
Earnest Money:- 10000/- Only
Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	74.70	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	21988.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement :four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP.PWD. technical specifications, clauses 802, 803, 1202 and 1203 including all leads, lifts or as directed by the Engineer-in-Charge.	11.48	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	49692.00
3	Random rubble masonry 1:6 (one cement : six sand) in foundation complete as per drawing & technical specification clauses 702, 704, 1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	126.84	Per cubic metre	3381.20	Rs. Three thousand three hundred fourteen & paise seventy only.	428871.00
4	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8, including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	18.00	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	14029.00
5	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	74.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	19695.00
Total						534275.00
				Select:-		
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Shri Kiyari to Gattu Shanil road Km m 0/0 to 4/500 (SH:-Construction of R/W wall in R/R Masonry at RD 0/075 to 0/096

Job No. 29

Estimated Cost:- 4,94,605/- Only.
Earnest Money:-9900/- Only
Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, and backfilling in trenches with extra good rubble material including carriage of all labour equipment and material to various location through all modes of transport in all leads and lifts, including all incidental charges	70.98	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	20893.00
2	Graded stone aggregate 40mm (forty millimeter) nominal size) in open foundation complete as per drawing and HP.PWD. technical specifications, clauses 802,803,1202 and 1203 including all leads, lifts or as directed by the Engineer-in-Charge.		metre		thousand three hundred twenty eight & sixty paise only.	438871.00
3	Random rubble masonry in cement mortar (one cement : six sand) in foundation complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	126.84	Per cubic metre	338.20	Rs Three thousand three hundred eighty one & paise twenty only.	42887.00
5	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8.including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	23.10	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	18004.00
Total				Select:-		494605.00
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

Executive Engineer

Shilal Division

HP PWD Shilal

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Gangtoli Kunhat road Km 0/0 to 5/00 (SH:-Construction of R/Wall in Dry Rubble Masonry at RD 4/900 to 4/970)

Job No. 30

Estimated Cost:- 4,97,347/- Only.
Earnest Money:- 10000/- Only
Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	112.47	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	33106.00
3	Construction of dry rubble masonry for retaining walls, Breast walls, Revetment walls and parapets etc. for sub structure and superstructure complete as per drawing and technical specification clause 704.6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	193.89	Per cubic metre	2394.35	Rs. Two thousand three hundred ninety four & paise thirty five only.	464241.00
Total						497347.00
				Select:-		
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

Executive Engineer

Shilaj Division

HP PWD Shilaj

Job:- 211

Estimated Cost:-4,98,885/- Only.	Time
Earnest Money:-10000/- Only	
Limit: - One Month	

Name and full address of the contractor:-

**Executive Engineer
Shillai Division
HP PWD Shillai**

SCHEDULE OF QUANTITY

Name of work: Restoration of rain damages on Rajpur Section under Sataun Sub- Division (SH:- Hiring of Excavator cum loader for on Various road)

Job. 32

Estimated Cost:- 496800-
Only. Earnest Money:- 10000/-
- Only Time Limit: - Three Months

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum (Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shall be paid to the contractor.	552.00	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	496800.00
				Total:-		496800.00
				Select:-	Plus(+)	(.....%)
					Minus(-)	(.....%)

Name and full address of the contractor:-

Executive Engineer
Shillai Division
HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on PDPA road Km 0/00 to 5/00 (SH:- Construction of R/wall in in PCC 1:4:8 at RD 0/400 to 0/410 & 0/450 to 0/460)

Job. 34

Estimated Cost:- 4,92,162/- Only.

Earnest Money:- 9900/- Only Time

Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	68.40	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	20134.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement :four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP,PWD. technical specifications.clauses 802,803,1202 and 1203 including all leads, lifts or as directed by the Engineer-in-Charge.	104.00	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	450174.00
3	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8.including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	9.60	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	7482.00
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	54.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	14372.00
Total						492162.00

Name and full address of the contractor:-

Executive Engineer
Shillai Division
HP PWD Shillai

T SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on PDPA road Km 0/00 to 5/00 (SH:- Construction of R/wall in in PCC 1:4:8 at RD 3/150 to 3/160 & 3/320 to 3/330)

Job. 25
Estimated Cost:- 4,91,630/- Only,
Earnest Money:-9900/- Only Time
Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	68.40	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	20134.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement:four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP.PWD. technical specifications.clauses 802,803,1202 and 1203 including all leads, lifts or as directed by the Engineer-In-Charge.	104.00	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	450174.00
3	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8.including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	9.60	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	7482.00
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	52.00	Each	266.15	Rs. Two hundred sixty six & fifteen paise only.	13840.00
Total						491630.00

Name and full address of the contractor:-

Executive Engineer
Shillai Division
HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:-Restoration of rain damages on Shillai Achhoti Pandiyat road Km 0/0 to 7/500(SH:-Construction of R/wall in R/R Masonry at RD 1/860 to 1/881)

Job:- 96

Estimated Cost:-4,94,605/- Only.
Earnest Money:-9900/- Only
Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 Including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	70.98	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	20893.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1.4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	6.20	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	26837.00
3	Random rubble masonry in cement mortar1:6 (one cement : six sand)in foundation complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	126.84	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	428871.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3:8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	23.10	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	18004.00
				Total:-		494605.00
		Select:-		Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:-A/R & M/D Drabil Nanidhar Hallan road Km 0/0 to 21/00(SH:- Improvement of Curves from RD 14/735 to 14/875)

Job:- 87

Estimated Cost:- 499604/- Only.
Earnest Money:-10000/- Only Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in earthenwork in hilly area all heights and depths, in all kind of soils including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification of Ministry of Rural Development, in Rural Roads August, 2004 (Two Thousand Four), and clause 16.2 (Sixteen point two) of General condition for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places. in specified manner, systematically with due consideration to avoiding adverse effects on environment, trimming, filling of unevenness, blind age and finishing of the road to specified dimensions to the entire satisfaction as directed by the Engineer-in charge for smooth riding. The recovery for stones, whether useful or not, for 94.18 cubic metre (Ninety four point eighteen cubic metre) in all cases at the rate of Rupees 170/= only (Rupees One hundred Seventy only) per cubic meter shall be effected on pro-rate basis.. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	3139.20	Per cubic metre	159.15	Rs. One hundred Fifty Nine & fifteen paise only.	499604.00
				Select:-		499604.00
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

Executive Engineer

Shillar Division

HP PWD Shillar

SCHEDULE OF QUANTITY						Job - 78	Estimated Cost:- 4,86,341/- Only.
Name of work:- Restoration of rain damages Koti Uttro road Km 0/00 to 6/00 (SH:- Construction of R/ wall in R/R Masonry at RD 0/150 to 0/174)						Earliest Money:- 9700/- Only	
						Time Limit:- One Month	
Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	70.56	Per cubic metre	294.35	Rs. two hundred ninety three & thirty five paise only.	20769.00	
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802, 803, 1202 and 1203.1:4:8 (One cement: Four Sand: Eight graded stone aggregate) 25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	21.13	Per cubic metre	4328.60	Rs. four thousand three hundred twenty nine & sixty paise only.	91463.00	
4	Random rubble masonry in cement mortar 1:6 (one cement : six sand) in foundation complete as per drawing & technical specification clauses 702, 704, 1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	55.88	Per cubic metre	3381.20	Rs. three thousand three hundred eighty one & paise twenty only.	188941.00	
5	Construction of dry rubble masonry for retaining walls, Breast walls, Revetment walls and parapets etc. for sub structure and superstructure complete as per drawing and technical specification clause 704, 6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	85.20	Per cubic metre	1852.15	Rs. One thousand eight hundred fifty two & paise fifteen only.	157803.00	
6	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204, 3.7 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	48.00	Each	266.15	Rs. two hundred six & six & fifteen paise only.	12775.00	
7	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification clause 1204, 3.8 (One thousand two hundred four point three point eight) within all leads, lifts and carriage of material as per the direction of the Engineer incharge.	18.72	Per cubic metre	779.40	Rs. seven hundred seventy nine & forty paise only.	14590.00	
Total:-				486341.00			
Select:-				Plus (+)	(.....%)		
				Minus (-)	(.....%)		

Name and full address of the contractor:-

Executive Engineer
Shilal Division
HP PWD Shilal

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages Koti Uttrou road Km 0/00 to 6/00(SH:- Construction of R/ wall in R/R Masonry at RD 5/650 to 5/574)

Job No. 2191

Estimated Cost:- 4,85,809/- Only.

Earnest Money:- 9700/- Only

Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	70.56	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	20769.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size Including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	21.13	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	91453.00
4	Random rubble masonry in cement mortar 1:6 (one cement : six sand)in foundation complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	55.88	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	188341.00
5	Construction of dry rubble masonry for retaining walls, Breast walls,Revetment walls and parapets etc. for sub structure and superstructure complete as per drawing and technical specification clause 704,6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	85.20	Per cubic metre	1852.15	Rs. One thousand eight hundred fifty two & paise fifteen only.	157803.00
6	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (1V):.20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	46.00	Each	266.15	Rs. Two hundred sixty six & fifteen paise only.	12243.00
7	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	18.72	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	14590.00
				Total:-		485809.00
				Select:-		
				Plus(+)		(.....%)
				Minus(-)		(.....%)

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai



SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY							Job# 15	Estimated Cost:-4,96,938/- Only.
Name of work:- Restoration of rain damages on Solan Meenus road Km 110/0 to 128/325(SH:- Construction of R/wall in R/R Masonry at RD 118/930 to 118/949)								Earnest Money:-10000/- Only
								Time Limit: - One Month
Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount		
				Figures	Words			
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	54.72	Per cubic metre	290.95	Rs. Two hundred ninety & Ninety five paise only.	15921.00		
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	10.26	Per cubic metre	4074.80	Rs. Four thousand Seventy four & eighty paise only.	41807.00		
3	Random rubble masonry in cement mortar:1:6 (one cement : six sand)in foundation complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	119.70	Per cubic metre	3314.70	Rs. Three thousand three hundred fourteen & paise seventy only.	396770.00		
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	28.50	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	22213.00		
5	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment/wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (1/V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	76.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	20227.00		
				Total:-		496938.00		
				Select:-				
				Plus(+)	(.....%)			
				Minus(-)	(.....%)			

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Drabil Nanidhar Hallan road Km 0/0 to 21/00(SH:-Construction of R/wall in PCC 1:4:8 at RD 13/845 to 13/863

Job. 41

Estimated Cost:- 4,99,753/- Only.
Earnest Money:- 10000/- Only
Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	70.02	Per Cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	20610.00
2	Providing and laying concrete for plain/reinforced concrete 1:4:8 (One cement :four Sand: Eight graded stone aggregate 40mm (Forty millimeter) nominal size) in open foundation complete as per drawing and HP.PWD. technical specifications. clauses 802,803,1202 and 1203 including all leads, lifts or as directed by the Engineer-in-Charge.	106.56	Per Cubic metre	4328.60	Rs. Four thousand three hundred twenty eight & sixty paise only.	461256.00
3	Providing back filling with granular material behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8.including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	11.34	Per Cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	8838.00
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of i(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	34.00	Each	266.15	Rs. Two hundred sixty six & fifteen paise only.	9049.00
Total						499753.00

Select:-

Plus(+)

Minus(-)

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Shillai Achoti Pandiyat road Km 0/0 to 7/500 (SH:- Construction of R/wall in R/R Masonry at RD 2/910 to 2/934)

Job:- 14/2 Estimated Cost:- 498988/- Only.
Earnest Money:- 10000/- Only
Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	83.76	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	24655.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802, 803, 1202 and 1203.1.4.8 (One cement: Four Sand: Eight graded stone aggregate) 25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	21.13	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	91463.00
3	Random rubble masonry in cement mortar 1:6 (one cement : six sand) in foundation complete as per drawing & technical specification clauses 702, 704, 1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	55.88	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	188941.00
	Construction of dry rubble masonry for retaining walls, Breast walls, Revetment walls and parapets etc. for sub structure and superstructure complete as per drawing and technical specification clause 704, 6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	89.93	Per cubic metre	1852.15	Rs. One thousand eight hundred fifty two & paise fifteen only.	166564.00
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	48.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	12775.00
5	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer incharge.	18.72	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	14590.00
				Total:-		498988.00
				Select:-		
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work: Restoration of rain damages on Kaffota Kori road Km 0/00 to 29/750 (SH:-Construction of R/wall in R/R masonry at RD 0/090 to 0/105 & 0/110 to 0/124)

Job:- 143

Estimated Cost:-4,95,114/- Only.
Earnest Money:-10000/- Only
Time Limit: - One Month

Sr. No.	Sub-Head and Item of Work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	4.40	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	21900.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802, 803, 1202 and 1203.1:4:8 (One cement: Four Sand: Eight graded stone aggregate) 25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-Charge.	21.13	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	91463.00
3	Random rubble masonry in cement mortar 1:6 (One cement : six sand) in foundation complete as per drawing & technical specification clauses 702, 704, 1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	27.05	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	992897.00
4	Construction of dry rubble masonry for retaining walls, Breast walls, Revetment walls and parapets etc. for sub structure and superstructure complete as per drawing and technical specification clause 704, 6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	85.20	Per cubic metre	1852.15	Rs. One thousand eight hundred fifty two & paise fifteen only.	157803.00
5	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	22.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	16501.00
6	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	8.72	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	14590.00
				Total:-		495154.00
				Select:-		
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

Executive Engineer

Shilal Division

HP PWD Shilal

SCHEDULE OF QUANTITY				Job-44	Estimated Cost:-4,94,800/- Only.	
Name of work:-Restoration of rain damages on Milliah Digwa road Km 0/00 to 7/00 (SH:-Construction of R/wall in R/R masonry at RD 3/700 to 3/724)					Earnest Money:-9900/- Only Time Limit: - One Month	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of footing and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	73.20	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	21546.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1.4.8. One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	21.13	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	91463.00
3	Random rubble masonry in cement mortar 1:6 (one cement : six sand) in foundation complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	57.05	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	192897.00
4	Construction of dry rubble masonry for retaining walls, Breast walls,Revetment walls and parapets etc. for sub structure and superstructure complete as per drawing and technical specification clause 704,6 & 1302.50 including carriage of materials in all leads and lifts as per the direction of Engineer-in-Charge.	85.20	Per cubic metre	1852.15	Rs. One thousand eight hundred fifty two & paise fifteen only.	157803.00
5	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	62.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	16501.00
6	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer incharge.	18.72	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	14590.00
				Total:-		494800.00
				Select:-		
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

Executive Engineer
Shilal Division
HP PWD Shilal

SCHEDULE OF QUANTITY										Job - 4/5	Estimated Cost:-499286/- Only.
Name of work:- Restoration of rain damages on Gummath Lani Borar road Km 0/0 to 5/555 (SH:- Construction of R/wall in R/R Masonry at RD 1/600 to 1/610, 1/990 to 2/00 & 2/300 to 2/310)										Earnest Money:-10000/- Only Time Limit: - One Month	
Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount					
				Figures	Words						
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	65.10	Per cubic metre	294.35	Rs. Two hundred ninety three & thirty five paise only.	19162.00					
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	13.50	Per cubic metre	4328.60	Rs. Four thousand three hundred twenty nine & sixty paise only.	58436.00					
3	Random rubble masonry in cement mortar1:6 (one cement : six sand)in foundation complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	115.29	Per cubic metre	3381.20	Rs. Three thousand three hundred eighty one & paise twenty only.	389819.00					
4	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia AC pipe extending through the full width of the structure with slopes of (1V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	60.00	Each	266.15	Rs. Two hundred Sixty six & fifteen paise only.	15969.00					
5	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer incharge.	20.40	Per cubic metre	779.40	Rs. Seven hundred seventy nine & forty paise only.	15900.00					
				Total:-		499286.00					
				Select:-	Plus(+)	(.....%)					
					Minus(-)	(.....%)					

Name and full address of the contractor:-

Executive Engineer
Shillai Division
HP PWD Shillai

SCHEDULE OF QUANTITY					Job. 4/6	Estimated Cost:- 497948/- Only. Earnest Money:- 9900/- Only Time Limit - One Months
Name of work:- Restoration of rain damages on Timbi Section Under Timbi Sub Division (SH:-Removal of slips from Various road)						
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Removal of land slides /slips clearance . Removal of land slide in hilly area in ordinary rock not require blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left upto 1.5mtr and land up to 1000meter as per technical specification 302.3.5 abd 1611. including carriage of material in all leads and lifts as per the direction of the Engineer- In-charge.	6147.50	Per cubic metre	81.00	Rs. Eighty one & Nil paise only.	497948.00
				Total:-		497948.00
				Select:-	Plus(+)	(.....%)
					Minus(-)	(.....%)

Name and full address of the contractor:-

Executive Engineer
Shillai Division
HP PWD Shillai

Job-47

Estimated Cost:- 469800- Only.

SCHEDULE OF QUANTITY		Job - 47
Name of work:	Restoration of rain damages on Shillai-2 Section under Shillai Sub-Division (SH:- Hiring of Excavator cum loader for on Various road)	

Estimated Cost:- 469800- Only
Earnest Money:- 9400/- Only
Time Limit: - Three Months

Sr.	Sub-Head and Item of work			Quantity	Unit	Rate in		Amount
						Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum (Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. Including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shell be paid to the contractor.			522.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	469800.00
							Total:-	469800.00
			Select:-				Plus(+)	(.....%)
							Minus(-)	[.....%]

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Improvement of Black spot on Shilla Gundah road Km 0/ 0 to 33/265(SH:- Improvement of Curve from Km 5/900 to 6/045)

Job:- 48

Estimated Cost:-490500/- Only.
Earnest Money:-9800/- Only
Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soils including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification of Ministry of Rural Development for Rural Roads August, 2004 (Two Thousand Four), and clause 16.2 (Sixteen point two) of General condition for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut materials by all modes of transportations in all leads and lifts at specified places. in specified manner, systematically with due consideration to avoiding adverse effects on environment, trimming, filling of unevenness, blind age and finishing of the road to specified dimensions to the entire satisfaction as directed by the Engineer-in charge for smooth riding. The recovery for stones, whether useful or not, for 313.92 cubic metre(Three hundred thirteen one point ninety two cubic metre) in all cases at the rate of Rupees 170/= only (Rupees One hundred Seventy only) per cubic meter shall be effected on prorate basis.. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	3139.20	Per cubic metre	156.25	Rs. One hundred Seventy Nine & Sixty Seven paise only.	490500.00
				Select:-	Plus(+) Minus(-)	490500.00 (.....%) (.....%)

Name and full address of the contractor:-

Executive Engineer
Shillai Division
HP PWD Shillai