



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"SHORT TERM NOTICE INVITING TENDERS"

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **02/03/2024** up to 11.00 A.M. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **01/03/2024** up to 4.00 P.M and the application for issue of tender form shall be received on **29/02/2024** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Restoration of road damages on various road under Darang Section under Bhawarna Sub Division (SW:- Removal of slips, C/o Un-lined drain, and Maintenance of Earther shoulders)	2,93,096/-	5900/-	One Month	350/-
2	Restoration of rain damages on Thural to Challah road Km. 0/00 to 4/960 (SW:- Protection wall of culvert span 6.0 mtr at Rd 0/110)	1,93,262/-	3800/-	Two Months	350/-
3	C/o M.S.C.M Degree College Thural (SW:-C/o B/Wall to protect the approaches road) Jon No. II 9 Deposit work)	2,68,894/-	5300/-	Two Months	350/-
4	C/o link road from Duhak to Dhahi Km. 0/0 to 4/500 (SW:- Imp. of curves & Co unlined surface drain in Km. 0/0 to 2/850)	4,31,806/-	8600/-	Three Months	350/-
5	Balance work of Duhak Tikri Rakha Basti to Dhahi road Km. 0/0 to 4/380 (SW:- C/o R/Wall at Rd 2/260 to 2/278) (under NABARD)	4,88,253/-	9800/-	Three Months	350/-
6	Restoration of rain damages on Maserna to Dakrehar Km. 0/0 to 3/760) (SW:- C/o Retaining wall at Rd 0/010 to 0/025)	1,59,235/-	3200/-	Two Months	350/-
7	C/o AE office cum Residence Building at Thural Distt. Kangra (HP) (SW:- Providing and fixing cupboards of HDMR)	4,41,050/-	8800/-	Three Months	350/-
8	Restoration of road damages on various road under Bhagolu da Ghatta Section under Thural Sub Division (SW:- Removal of slips, C/o Un-lined drain, and Maintenance of Earther shoulders)	4,93,488/-	9900/-	One Month	350/-
9	Restoration of road damaged on Chah to Chander road Km. 0/0 to 2/0 (SW:- C/o Wire crate R/Wall at Rd 0/0 to 0/050)	4,86,125/-	9700/-	Two Months	350/-
10	Restoration of road damaged on link road Kharul Km. 0/0 to 8/0 (SW:- C/o Wire crate R/Wall at Rd 4/200 to 4/225)	4,77,813/-	9600/-	Two Months	350/-
11	Restoration of road damages on various road under Daroh Garh Section under Bhawarna Sub Division (SW:- Removal of slips, C/o Un-lined drain, and Maintenance of Earther shoulders)	4,60,363/-	9200/-	One Month	350/-
12	Balance work of Duhak Tikri Rakha Basti to Dhahi road Km. 0/0 to 4/380) (SW:- C/o B/Wall at Rd 2/310 to 2/322, 2/565 to 2/557 & 2/656 to 2/661.50) (under NABARD)	4,89,208/-	9700/-	Three Months	350/-
13	Restoration of road damages on various road under HPPWD Sub Division Thural (Section Bairghatta) (SW:- Removal of slips, C/o Un-lined drain, and Maintenance of Earther shoulders on various roads)	1,96,489/-	3900/-	Two Months	350/-
14	Restoration of road damages on various road under HPPWD Sub Division Dheera (SW:- Removal of slips, C/o Un-lined drain, and Maintenance of Earther shoulders on various roads)	1,97,806/-	4000/-	Two Months	350/-



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

15	Improvement of Black spots on various roads under HPPWD Sub Division Bhawarna (SW:- Providing and fixing Road studs at various stretches)	1,47,000/-	2900/-	One Month	350/-
16	Improvement of Black spots on various roads under HPPWD Sub Division Dheera (SW:- Providing and fixing Road studs at various stretches)	1,50,500/-	3000/-	Two Months	350/-
17	Improvement of Black spots on various roads under HP.PWD Sub Division Bhawarna (SW:- Providing and fixing road studs at various Stretches)	1,45,250/-	2900/-	Two Months	350/-
18	Improvement of Black spots on various roads under HPPWD Sub Division Thural (SW:- Providing and fixing Road studs at various stretches)	1,49,800/-	3000/-	One Month	350/-
19	A/R & M/O Hamirpur Sujampur Thural Maranda road (SW:- Providing and laying Thermoplastic paint in Km. 35/140 to 37/00 & 39/190 to 40/00)	4,00,500/-	8100/-	One Month	350/-
20	A/R & M/O Hamirpur Sujampur Thural Maranda road (SW:- Providing and laying Thermoplastic paint in Km. 31/00 to 32/00 & 34/00 to 35/140))	3,21,000/-	6400/-	Two Months	350/-
21	A/R & M/O various roads under Bhawarna Sub Division (SW:- Providing and fixing of Solar guard rail reflector for road safety on blind curves)	4,80,000/-	9600/-	Three Months	350/-
22	A/R & M/O various roads under Sub Division Bhawarna (Section Bhawarna-II) (SW:- Painting of Boards & Writing of Letters etc)	1,67,289/-	3300/-	Two Months	350/-
23	A/R & M/O various roads under Dheera Sub Division (SW:- Providing and fixing high intensity Engineering grade prismatic sheet)	4,99,520/-	10,000/-	Three Months	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
5. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK

[Signature]
Executive Engineer
Bhawarna Division
HPPWD Bhawarna
(On behalf of Governor of Himachal Pradesh)

No. PWD/BWD/Tender/NIT/2023-24/-

16431-490

(On behalf of Governor of Himachal Pradesh)

Dated:- 21.2.2024

Copy to following for information and necessary action:-

1. The Principal Secy.(PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (KZ), HPPWD, Dharamshala.
4. The Director, Information & Publications Department, HP Shimla.
5. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. The Sub-Divisional Officer(Civil) Palampur.
9. All the S.E.s/E.E.s under Kangra Zone.
10. All the Assistant Engineers under this Division.
11. The Drawing /Accounts Branch in this office.
12. Notice Board.

[Signature]
Executive Engineer
Bhawarna Division
HPPWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on various roads under Darang Section under Bhawarna Sub-Division. (SH:- Removal of Slips, C/o Un-Estimate Cost :- 2,93,096/-
lined drain and Maintenance of Earthen shoulders). Earnest Money :- 5900/-

S. No.		Description of Item	Quantity		Rate		Time Limit :- One Month	
			In figure	In Words	In figure	In Words	Unit	Amount Rs.
1		Removal of Land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	1749.95				Per Cubic metre	
2		Construction of un-lined surface drains of average cross sectional area 0.40 Sqm. in soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307 with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	1500.00				Per Running metre	
3		Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2160.00				Per Square metre	
Total :-								



 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Thural to Challah road Km 0/00 to 4/960 (SH:- protection wall of culvert span 6.0 mtr at Rd 0/110)

Estimated Cost :- Rs.1,93,262/-
Earnest Money :- Rs. 3800/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes	25.31			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	41.62			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15			Nos	
Total :-						



 Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of Quantity

Name of Work :- Construction M.S.C.M Degree Collage Thural (SH:-C/o RWall to protect the approaches road).Job.No. II
(Deposit work)

Estimated Cost :- Rs.2,68,894/-
Earnest Money :- Rs. 5300/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes	24.80			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	58.55			Per Cubic metre	
4	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20			Nos	
Total :-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- C/o Link road from Duhak to Dhahi Km 0/0 to 4/500 (SH-1) Imp. of curves & C/o unlined surface drain in Km 0/0 to 2/850
 Estimate Cost :- 4,31,806/-
 Earnest Money :- 8600/-
 Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in Hilly Area in all heights and depths and in all kinds of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft Rock, Hard rock, chisseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades cutting and trimming of side slopes and level as shown in the drawings and as directed by the Engineer in charge at site according to the technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useless material for filling in road way, camber, embankments for grade improvement and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and incidentals necessary to complete the 70.23 cubic metre quantity at the Rate of Rupees 300/- only (Rupees Three hundred only) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate is including octroi, royalty, Matkara, toll tax, sale tax, GST or other taxes imposed by the Government.	2340.78			Per Cubic metre	
2	Construction of un-lined surface drain of average cross sectional area 0.40 Sqm. in soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307 with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	1315.00			Per Running metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity


Name of Work :- Balance work of Duhak Tikri Rakha Basti to Dhaba road Km 0/00 to 4/380 (SH:- C/o R/wall at RD 2/260 to 2/278)
(under NABARD)

Estimate Cost :- 4,88,253/-
Earnest Money :- 9800/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	55.08			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:1:4 (One cement : ^{four} one sand : ^{eight} one graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana toll tax, sale tax or other taxes imposed by the Government.	106.56			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	30.00			Each	

4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.50			Per Cubic metre
Total :-					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Maserna to Dakrehar Km 0/0 to 3/760 (SH:- C/o Retaining wall at RD 0/010 to 0/025).

Estimated Cost :- Rs. 1,59,235/-
Earnest Money :- Rs. 3200/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling/wedding out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	21.36			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	36.95			Per Cubic metre	
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8			Each	
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.85			Per Cubic metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Construction of AE office cum Residence Building at Thural Distt. Kangra (HP) . (SW:- Providing and fixing cupboards of HDMR).

Estimate Cost :-Rs. 4,41,050/-

Earnest Money :-Rs. 8800/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and fixing 18mm (Eighteen millimeter) thick water proof, termite resistant, pre laminated HDMR (High density moisture resistance fibre board) of Green panel, Action Tesa, Century or equivalent ISI mark for cupboards with edging tape of approved shade screws etc. complete as per HPPWD specifications design drawings as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	180.00			Per Square metre	
2	Providing and fixing of stainless steel hydraulic hinges for cupboards with screws nut bolts etc complete as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	110.00			Each	
3	Providing and fixing coloured / anodized aluminum handle 125mm (one hundred twenty five millimetre) size anodized transparent or dyed to required shade or colour with necessary screws etcetera complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	70.00			Each	
4	Providing and fixing of telescopic hinges for drawers etc. in cupboards to required shade or colour with necessary screws etcetera complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	10.00			Each	


5	Providing and fixing coloured / anodized aluminum handle 200 mm (Two hundred millimetre) size anodized transparent or dyed to required shade or colour with necessary screws etcetera complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	50.00			Each	
6	Providing and fixing Magnetic Catcher for cup boards shutter with necessary screws complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	60.00			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work: Restoration of rain damages on various roads under Bhagolu da ghatta Section under Thural Sub-Division. (SH:- Removal of Slips, Estimate Cost :-4,93,488/-
C/o Up-lined drain and Maintenance of Earthen shoulders). Earnest Money :-9900/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removal of Land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	3665.42			Per Cubic metre	
2	Construction of un-lined surface drain of average cross sectional area 0.40 Sqm. in soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307 with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	2200.00			Per Running metre	
3	Maintenance of Earthen shoulder (Filling with fresh selected soil). Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2160.00			Per Square metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity


Schedule of Quantity

Name of Work :- Restoration of road damaged on Chah to Chander road Km:0/0 to 2/0 (SH:- C/o wire crate r/wall at RD 0/0 to 0/050)

Estimate Cost :- 4,86,125/-
Earnest Money :- 9700/-

Time Limit :- Two Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering, as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	69.50			Per Cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	156.25			Per Cubic metre	
Total :-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity


Schedule of Quantity

Name of Work :- Restoration of road damaged on link road to Village Kharul Km-0/0 to 8/0 (SH:- C/o Wire crate R/wall at RD 4/200 to 4/225).

Estimate Cost :-4,77,813/-
Earnest Money :- 9600/-

Time Limit :- Two Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	36.25			Per Cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	156.25			Per Cubic metre	
Total :-						



Executive Engineer
Bhawana Div 500
HP PWD Bhawana

Schedule of Quantity

Schedule of Quantity

Name of Work :- Restoration of rain damages on various roads under Daroh Garh Section under Bhawarna Sub-Division. (SH:- Removal of Slips, C/o Un-lined drain and Maintenance of Earthen shoulders). Estimate Cost :- 4,60,363/- Earnest Money :- 9200/-

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removal of Land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer in-Charge including carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	3386.25			Per Cubic metre	
2	Construction of un-lined surface drains of average cross sectional area 0.40 Sqm. in soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307 with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of toll tax, GST and any other taxes imposed by the government.	2000.00			Per Running metre	
3	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2160.00			Per Square metre	
Total :-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Schedule of Quantity

Name of Work :- Balance work of Duttik Tikri Rakha Basti to Dhatbi road Km 0/00 to 4/380 (SH-5 C/o B/wall at RD 2/310 to 2/322, 2/565 to 2/577 & 2/656 to 2/661.50) (under NABARD)

Estimate Cost :- 4,89,208/-
Earnest Money :- 9700/-

S. No.		Description of Item		Quantity	In figure	Rate In Words	Unit	Amount Rs.
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.		77.03			Per Cubic metre		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, GST or other taxes imposed by the Government.		106.50			Per Cubic metre		
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(X): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.		48.00			Each		
Total :-								



Executive Engineer
Bharwan Division
HP PWD, Bhawana

Schedule of Quantity

Estimate Cost :-Rs. 1,96,489/-
Earnest Money :-Rs. 3900/-
Time Limit :- Two Months

Name of Work :- Restoration of rain damages on various roads under HPPWD Sub-Division Thural (Section Bairghatta). (SH:- Removal of Slips, C/o Un-lined drain and Maintenance of earthen shoulder on various roads).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removal of Land slid in hilly area in ordinary rock not requiring blasting by machanical means including cutting and trimming of slopes and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1347.66			Per Square metre	
2	Construction of un lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307 with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	900.00			Per Running metre	
3	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1120.00			Per Square metre	
Total :-						



Executive Engineer
Bhawanna Division
HP PWD Bhawanna

Schedule of Quantity

Estimate Cost :-Rs. 1,97,806/-
Earnest Money :-Rs. 4000 /-
Time Limit :- Two Months

Name of Work :- Restoration of rain damages on various roads under HPPWD Sub-Division Dheera. (SH:- Removal of Slips, C/o Un-lined drain and Maintenance of earthen shoulder on various roads).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removal of Land slid in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1378.96			Per Square metre	
2	Construction of un lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307 with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	950.00			Per Running metre	
3	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1020.00			Per Square metre	
Total :-						


Executive Engineer
Bhawana Division
HP PWD Bhawana

Schedule of Quantity

Name of Work :- Improvement of Black spots on various roads under HPPWD Sub-Division Bhawarna. (SH:- Providing and fixing Road studs at various Stretches).

Estimated Cost :- Rs. 1,47,000/-
Earnest Money :- Rs. 2900/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and fixing Dual Directional reflective cat eye with 2 (Two) shank of impact resistant ABS plastic V studs 100 x 90 x 16 mm (One hundred into ninety into sixteen millimetre) ultra violet resistant yellow / red colour reflector and fixing with epoxy bitumen adhesive complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	420.00			Each	
Total :-						



 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Improvement of Black spots on various roads under HPPWD Sub-Division Dheera. (SH:- Providing and fixing Road studs at various Stretches).

Estimated Cost :-Rs. 1,50,500/-
Earnest Money :- Rs. 3000/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and fixing Dual Directional reflective cat eye with 2 (Two) shank of impact resistant ABS plastic V studs 100 x 90 x 16 mm (One hundred into ninety into sixteen millimetre) ultra violet resistant yellow / red colour reflector and fixing with epoxy bitumen adhesive complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	430.00			Each	
Total :-						



 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Improvement of Black spots on various roads under HPPWD Sub-Division Bhawarna. (SH:- Providing and fixing Road studs at various Stretches).

Estimated Cost :- Rs. 1,45,250/-
Earnest Money :- Rs. 2900/-
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and fixing Dual Directional reflective cat eye with 2 (Two) shank of impact resistant ABS plastic V studs 100 x 90 x 16 mm (One hundred into ninety into sixteen millimetre) ultra violet resistant yellow / red colour reflector and fixing with epoxy bitumen adhesive complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	415.00			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Improvement of Black spots on various roads under HPPWD Sub-Division Thural. (SH:- Providing and fixing Road studs at various Stretches).

Estimated Cost :-Rs. 1,49,800/-
Earnest Money :- Rs. 3000/-
Time Limit :- One Month


S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and fixing Dual Directional reflective cat eye with 2 (Two) shank of impact resistant ABS plastic V studs 100 x 90 x 16 mm (One hundred into ninety into sixteen millimetre) ultra violet resistant yellow / red colour reflector and fixing with epoxy bitumen adhesive complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	428.00			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of quantity

Name of Work :- A/R & M/O Hamirpur, Sujapur, Thural, Maranda Road (SW) :- Providing and laying thermoplastic paint in Km.35/140 to 37/00 & Estimate Cost :- 4,00,500/-
 34,190 to 40/00). Earnest Money :- 8100/-
 Time Limit :- One Month

S. No.	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and Laying hot applied thermoplastic compound 2.5mm (Two decimal five millimetre) thick including reflectorising glass beads at the rate of 250 grams per square metre area, thickness of 2.5mm (Two decimal five millimetre) is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes as per MORTH technical specification clause-803 complete in all respect including carriage of material within 10 kms. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	534.00			Per Square metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of quantity

Schedule of quantity

Name of Work :- R/R & M/O Hamirpur Sejampur Thural Maranda Road (SW) :- Providing and laying Thermoplastic paint in Km.31/00 to 32/00 & 34/00 to 35/140).

Estimate Cost :- 3,21,000/-

Earnest Money :- 6400/-

S. No.	Description of Item.	Quantity	Rate		Time Limit :- One Month	
			In figure	In Words	Unit	Amount Rs.
1.	Providing and Laying hot applied thermoplastic compound 2.5mm (Two decimal five millimetre) thick including reflectorising glass beads at the rate of 250 grams per square metre area, thickness of 2.5mm (Two decimal five millimetre) is exclusive of surface applied glass beads as per IRC-35. The finished surface to be level, uniform and free from streaks and holes as per MOREH technical specification-clause 803 complete in all respect including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	428.00			Per Square metre	
Total :-						

myc
Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- A/R & M/O various roads under Bhawarna Sub-Division

Estimate Cost :- 4,80,000/-
Earnest Money :- 9600/-

(SI:- Providing and fixing of Solar guard rail reflector for road safety on blind curves).

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and Fixing solar guard rail reflector made out polycarbonate (unbreakable) consist of Lithium ion battery trapezoid type with size 117 x 73 x 49 mm (one hundred seventeen into seventy three into forty nine) to be installed in 4 (four) meter of distance in W- metal beam red colour suitable with all accessories fixed with welding complete in all leads, lifts as per the entire satisfaction and direction of Engineer -in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	320.00			Each	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of quantity.

Name of Work :- A/R & M/O various roads under HPPWD Sub-Division Bhawarna (Section Bhawarna-II)

Estimated Cost :- Rs. 1,67,289/-
Earnest Money :- Rs. 3300/-

(SW:- Painting of Boards & Writing of Letters etc).

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches including carriage of materials within all leads, lifts, and other incidentals as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	86.40			Per Square Metre	
2	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	86.40			Per Square Metre	
3	Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.					
i)	Block letters/figures	40000.00			Per letter per centimetre height	
ii)	Indian(letters/figures)	45000.00			Per letter per centimetre height	
Total :-						


Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- A/R & M/O various roads under Dheera Section under Dheera Sub-Division

Estimate Cost :-4,99,520/-

Earnest Money :-10,000/-

Time Limit :- Three Months

(SIH:-Providing and fixing high intensity Engineering grade prismatic sheet)

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and Fixing of high intensity Engineering grade prismatic sheeting on the road side crash barrier size 300x450mm (three hundred into four hundred fifty millimetre) in yellow , white colour to be installed in W metal beam crash barrier for easy visibility at night complete in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	446.00			Per Running metre	
Total :-						


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna