

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Registered

NO. PWP/CB/Tender Notice/2023-24-11072374

Dated:-08-02-2024

To

The Executive Engineer (IT Cell),
HPPWD, Nigam Vihar, Shimla-2.

Subject :- Regarding publication of Tender Notice on departmental website to be opened on 20.02.2024.

Enclosed please find herewith the tender notice alongwith schedule of quantity for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP, No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.


1. Certified that the tender mentioned in the notice is exigencies/emergency of urgent nature and in public interest.

Enclosures:- Notice Inviting tender and schedule of quantity.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

Copy forwarded along with tender notice via e mail for information to:-

1. The Superintending Engineer Nahan 12th Circle HP.PWD Nahan for information please.
2. Notice Board.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage rate tender are hereby invited by the Executive Engineer Paonta (B&R) Division HP.PWD Paonta Sahib on behalf of Governor of HP from the approved/ eligible contractor registered in HPPWD for the work, so as to reach in this office on 20.02.2024 up to 2:00 PM and shall be opened on 20.02.2024 the same day at 2:30 PM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 4.00 PM on 19.02.2024 for which the applications should reach in this office up to 4.00 PM on 17.02.2024. The tender form will be issued to the contractor giving proof of registration as GST.

The earnest money in the shape of NSC / Time deposit account / Saving account in any of the Post Office in HP or FDR/CDR from nationalized bank duly pledged in the name of Executive Engineer Paonta B&R Division HP.PWD Paonta Sahib must be accompanied with the application. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all tenders without assigning the reason. If there happens to be any holiday the same will be open on the next working day.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form	Class
1	Restoration of rain damages on various roads under Bhagani Section under Paonta Sub-Division No. II. (SH:- Providing and laying patch work of various roads).	Rs. 4,79,273/-	Rs. 10,000/-	Two months	350/-	All Class
2	Restoration of rain damages on various roads under Rajban Section under Paonta Sub-Division No.II.. (SH:- Providing and laying patch work of various roads).	Rs. 4,26,066/-	Rs. 9,000/-	Two months	350/-	All Class
3	Restoration of rain damages on various roads under Bangran Section under Paonta Sub-Division No. II. (SH:- Providing and laying patch work of various roads).	Rs. 4,12,128/-	Rs. 8,500/-	Two months	350/-	All Class
4	Restoration of rain damages to link road Salwala Puruwalla km. 0/0 to 2/0. (SH:- Construction of v-shape drain from RD. 1/920 to 2/0) Both Side.	Rs. 1,39,764/-	Rs. 2800/-	Two months	350/-	All Class
5	Restoration of rain damages on various roads under Kolar Section under Dhaulakuan Sub-Division. (SH:- Providing and laying patch work of various roads).	Rs. 4,84,077/-	Rs. 10,000/-	Two months	350/-	All Class
6	Restoration of rain damages on various roads under Baila Section under Dhaulakuan Sub-Division. (SH:- Providing and laying patch work of various roads).	Rs. 4,48,633/-	Rs. 9,500/-	Two months	350/-	All Class

7.	Restoration of rain damages on Paonta to Nawada road km 0/0 to 5/0. (SH:- construction of U-shape drain from RD. 3/150 to 3/250) L.H.S.	Rs. 2,47,446/-	Rs. 5,000/-	Two months	350/-	All Class
8.	Restoration of rain damages kolar Bilaspur road km. 0/0 to 12/0. (SH:- C/O retaining wall in wire crate at RD. 3/700 to 3/705).	Rs. 1,42,550/-	Rs. 3,000/-	One month	350/-	All Class
9.	Restoration of rain damages on Jamnighat Jheel Bankabara to Dhounwala road km. 0/0 to 5/020. (SH:- C/O Brest wall in wire crate at RD. 4/010 to 4/020).	Rs. 1,23,411/-	Rs. 2,500/-	One month	350/-	All Class
10.	Restoration of rain damages on various roads under Puruwala & Jamniwala Section under Paonta Sub-Division No. I. (SH:- Providing and laying patch work of various roads).	Rs. 4,42,316/-	Rs. 9,000/-	Two month	350/-	All Class
11.	Restoration of rain damages on various roads under Jamniwala Section under Paonta Sub-Division No.I. (SH:- Providing and laying patch work of various roads).	Rs. 3,97,061/-	Rs. 8,000/-	Two month	350/-	All Class
12.	Restoration of rain damages on link road to Kotri Bagna Sawar Kolar road km. 0/0 to 8/0. (SH:- Construction of Retaining wall in cement concrete at RD. 0/165 to 0/177).	Rs. 1,07,888/-	Rs. 2,500/-	One month	350/-	All Class
13.	A/R & M/O to Rest House building at Paonta Sahib, District Sirmou. (SH:- Repair to plaster patch, putty wall painting in existing Rest House building).	Rs. 3,76,390/-	Rs. 8000/-	Two months	350/-	All Class
14.	Restoration of rain damages to link road NH-907 to Bangala Bast Ghutanpur km. 0/0 to 0/800. (SH:- Construction of retaining wall in wire crate at RD 0/454 to 0/472.50) RHS/River side.	Rs. 97,363/-	Rs. 2000/-	Two months	350/-	All Class

CERTIFICATE:- Certified that the tenders mentioned above in this notice are exigencies/emergency of urgent nature and in public interest.

Conditions:-

The tender document shall be issued to ~~only~~ those contractors / firms:-

1. Who possess valid Contractor Registration Number.
2. Who possess valid GST Registration Number and GST clearance certificate from GST deptt.
3. Who possess valid Permanent Account Number.
4. Who Possess valid EPF Number.
5. Ambiguous / telegraphic / conditional tenders or tenders by FAX / E-mail shall not be entertained / considered in any case.
6. If any date mentioned above happens to be local/gazetted holiday, the same shall be processed on next days.
7. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
8. The contractor / Firms are requested to insert the rate of each item in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
9. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and

7. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
8. The contractor / Firms are requested to insert the rate of each item in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
9. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and purchase bills alongwith proof of ownership/Affidavit hire basis.
10. Only Two tender form will be issued to one contractor.


Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib.

No.PWP/CB-Tender Notice/2022-23- 11075-11124

Dated:- 08-02-2024

Copy forwarded to the following for information and necessary action please:-

1. The Engineer-in- Chief, HP. PWD Shimla-I
2. All the Superintending Engineer, in HP.PWD
3. The Sub Divisional Magistrate Paonta Sahib.
4. All the Executive Engineer in HP.PWD.
5. The Executive Engineer I&PH Division Paonta Sahib.
6. The Block Development Officer Block Paonta Sahib.
7. All the Assistant Engineer working under this Division.
8. The Executive Officer Municipal Committee Paonta Sahib.
9. All head of the Branches in this division.
11. Notice Board.


Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib.

Job No-1.

i Schedule of Quantity

Name of Work:- Restoration of rain damage on various roads under Bhagani Section under Paonta Sub Division No.II (SH:-Providing & laying Patch work of various roads).

S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in Words	Amount
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3-wheeled static roller 80-100 (eighty to hundred) KN static roller in stages to proper grade and camber, applying and brooming, crushable screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3.(Three) as per Technical Specification Clause 404, by manual means including haulage of materials with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.	37.77	Per cubic metre	2319.60	Rs Two thousand three hundred nineteen and paise sixty only	87611
2	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surface, cleaning of surface by providing by tack coat, premix carpet of 20mm (twenty millimetre) and seal coat of type -B as per technical specification with bitumen emulsion clause 1904.2.503 and 508.1 including all leads and lifts and carriage of materials complete as per entire satisfaction the direction of Engineer-in-charge.	1206.60	Per square metre	324.60	Rupees Three hundred twenty four and paise sixty only	391662
				Total		479273

Executive Engineer,
Paonta B&R Division
HP, PWD, Paonta Sahib

Job 2

Schedule of Quantity

Name of Work:- Restoration of rain damage on various roads under Rajban Section under Paonta Sub Division No.II.(SH:-Providing & laying patch work of various roads).

Estimated cost:-426066/- only
Earnest Money:-9000/- only
Time:- Two Month

S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in		Amount
					Rs	Words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3-wheeled static roller 80-100(eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, crushable screening/ binding materials to fill-up the interspaces of coarse aggregate, watering and compacting to the required density grading 3(Three) as per Technical Specification Clause 404, by manual means including haulage of materials with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.	32.43	Per cubic metre	2319.60	Rs Three hundred nineteen and sixty only		75225
2	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surface, cleaning of surface by providing by tack coat, premix carpet of 20mm (twenty millimetre) and seal coat of type -B as per technical specification with bituman emulsion clause 1904.2.503 and 508.1 including all leads and lifts and carriage of materials complete as per entire satisfaction the direction of Engineer-in-charge.	1080.84	Per square metre	324.60	Rupees Three hundred twenty four and paise sixty only		350841
Total							426066

Executive Engineer,
Paonta B&P Division
HP. PWD, Paonta Sahib

Job No. - 3.

Schedule of Quantity

Name of Work: Restoration of rain damage on various roads under Baighran Section under Paonta Sub Division No.II. (SH- Providing & laying Patch work of various roads).

S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in Words	Amount
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3-wheeled static roller 80-100 (eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, crushable screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3(Three) as per Technical Specification Clause 404, by manual means including haulage of materials with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.	23.06	Per cubic metre	2319.60	Rs Two thousand three hundred nineteen and paise sixty only	53490
2	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surface, cleaning of surface by providing by tack coat, premix carpet of 20mm (twenty millimetre) and seal coat of type-B as per technical specification with bituminous emulsion clause 1904.2.603 and 508.1 including all leads and lifts and carriage of materials complete as per entire satisfaction the direction of Engineer-in-charge.	1104.86	Per square metre	324.60	Rupees Three hundred twenty four and paise sixty only	358638
					Total	412128



Executive Engineer,
Paonta B&R Division
MP PWD, Paonta Sahib

Job 4.

Schedule of Quantity

Name of Work:- Restoration of rain damage to link road Salwala Puruwalla Km 0/0 to 2/0 (SH) - Construction of V-shape drain from RD 1/920 to 2/00 Both side.

S.No Sub heads and items of work

Estimated cost:- 139764/- only
Earnest Money:- 2500/- only

Time:- Two Month

S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in		Amount
					Rs	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	44.00	Per cubic metre	216.90	Rs sixteen and paise ninety only	Two hundred sixteen and paise ninety only	9544
2	Providing and laying concrete 1:3:6 for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802.803, 1202 & 1203. P.C.C. grade M-10 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	22.80	Per cubic metre	5711.40	Rs seven eleven and paise forty only	Five thousand seven hundred eleven and paise forty only	130220
Total							139764

Executive Engineer,
Public D&R Division
Mr. PWD, Poonja Sahib

Job S

Schedule of Quantity					Estimated cost:- 484077/- only	
Name of Work:- Restoration of rain damage on various roads under Kotla Section under Dhaukuan Sub Division, (SH:- Providing & laying Patch work of various roads).					Earnest Money:- 10000/- only	
Sub heads and items of work					Time:- Two Month	
S.No	Qty	Unit	Figures	Rate in Words	Amount	
1	38.98	Per cubic metre	2319.60	Rs Two thousand three hundred nineteen and paise sixty only	90418	
Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3-wheeled static roller 80-100 (eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, crushable screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3(Three) as per Technical Specification Clause 404, by manual means including haulage of materials with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.						
2	1212.75	Per square metre	324.60	Rupees Three hundred twenty four and paise sixty only	393659	
Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surface, cleaning of surface by providing by tack coat, premix carpet of 20mm (twenty millimetre) and seal coat of type -B as per technical specification with bituman emulsion clause 1904.2.503 and 508.1 including all leads and lifts and carriage of materials complete as per entire satisfaction the direction of Engineer-in-Charge.						
Total					484077	

Executive Engineer,
Paonta B&R Division
H.P. PWD, Paonta Sahib

Job 6.

Schedule of Quantity

Name of Work:- Restoration of rain damage on various roads under Bailia Section under Dhaulakuan Sub Division, (SH:- Providing & laying Patch work of various roads).

Estimated cost:- 448633/- only
Earnest Money:- 9500/- only
Time:- Two Month

S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in		Amount
					Words	Words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3-wheeled static roller 80-100 (eighty to hundred) KN static roller in stages to proper grade and camber, applying and brooming, crushable screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3(Three) as per Technical Specification Clause 404, by manual means including haulage of materials with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.	46.78	Per cubic metre	2319.60	Rs Three hundred nineteen and paise sixty only	108511	
2	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surface, cleaning of surface by providing by tack coat, premix carpet of 20mm (twenty millimetre) and seal coat of type-B as per technical specification with bitumen emulsion clause 1904.2.503 and 508.1 including all leads and lifts and carriage of materials complete as per entire satisfaction the direction of Engineer-in-charge.	1047.82	Per square metre	324.60	Rupees Three hundred twenty four and paise sixty only	340122	
					Total		448633

Executive Engineer,
Paoita B&R Division
HP FWD, Paoita Sahib

Job #.

Schedule of Quantity

Name of Work:- Restoration of rain damage on Paonta to Nawada road Km 0/0 to 5/0 (SH)- Construction of U-Shape drain from RD 3/150 to 3/250) L.H.S.

S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in		Amount
					Words	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	63.00	Per cubic metre	171.40	Rs One hundred seventy one and paise forty only	10798	
2	Providing and laying concrete 1:3:6 for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802,803,1202 & 1203. P.C.C. grade M-10 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	27.00	Per cubic metre	5792.00	Rs Five thousand seven hundred ninety two and paise zero only	156384	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	6.30	Per cubic metre	5954.35	Rs Five thousand nine hundred fifty four and paise thirty five only	37512	
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	567.00	per square metre	75.40	Rupees Eighty nine and paise ninety only	42752	
							247446


Executive Engineer,
Paonta P&R Division
HP FWD, Paonta Sahib

Job 8.

SCHEDULE OF QUANTITY				
Name of work :- R/R Damages Kolar bilaspur road km 0/0 to 12/00 (SH:- C/O R/wall in wire crate at RD 3/700 to 3/705)				
		Estimated cost :- Rs. 142549/- only Earnest Money :- Rs. 3000/- only. Time allowed :- One month only.		
S. No.	Sub-head & item of works	Quantity	Rate	Amount
			Figure	Words
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including of hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer in charge.	13.65	171.40	Rs. One hundred seventy one & paise forty only.
2	Providing and laying apron laid in wire crates with 4mm dia G. I wire conforming to IS : 280 and IS:48236 in 100x100 mesh (woven diagonally) i/c 10 percent extra over lead and joints with stone boulders drawing and technical specification weighting not less than 25 kg. as per clause 1301. including of hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer in charge.	47.93	2925.30	Rs. Two thousand nine hundred twenty five & paise thirty only.
				140210
				142549

Executive Engineer,
Publicity & R.R. Division
K.O. I & O. P. P. S. S. S. S. S.

Job 9.

SCHEDULE OF QUANTITY					
Name of work: -R/R Damages on Jamnighat Jheel bankabara to dhounwala road km 0/0to 5/020 (SH :- C/O B/wall in wire crate at RD 4/010 to 4/020)					
S. No.	Sub-head & Item of Works	Quantity	Rate	Unit	Amount
			Figure	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. including of hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer in charge.	16.00	171.40	Rs. One hundred seventy one & paise forty only.	2742
2	Providing and laying apron laid in wire crates with 4mm dia G. I wire conforming to IS : 280 and IS:48236 in 100x100 mesh (woven diagonally) i/c 10 percent extra over lead and joints with stone boulders drawing and technical specification weighting not less than 25 kg. as per clause 130 L. including of hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer in charge.	41.25	2925.30	Rs. Two thousand nine hundred twenty five & paise thirty only.	120669
					123411

Executive Engineer,
Paonta B&R Division
H.P. PWD, Paonta Sahib

Schedule of Quantity					Estimated cost:- 442316/- only	
Name of Work:- Restoration of rain damage on various roads under Puruwalla & Jaminwala Section under Paonta Sub Division No.1 (SH:- Providing & laying Patch work of various roads).					Earnest Money:- 9000/- only	
Sub heads and items of work					Time:- Two Month	
S.No	Qty	Unit	Figures	Rate in Words	Amount	
1	64.44	Per cubic metre	2319.60	Rs Two thousand three hundred nineteen and paise sixty only	149475	
Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3-wheeled static roller 80-100 (eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, crushable screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3(Three) as per Technical Specification Clause 404, by manual means including haulage of materials with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.						
2	902.16	Per square metre	324.60	Rupees Three hundred twenty four and paise sixty only	292841	
Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surface, cleaning of surface by providing by tack coat, premix carpet of 20mm (twenty millimetre) and seal coat of type -B as per technical specification with bituman emulsion clause 1904.2.503 and 508.1 including all leads and lifts and carriage of materials complete as per entire satisfaction the direction of Engineer-in-charge.						
Total					442316	

Executive Engineer,
Paonta B&R Division
I.P. PWD, Paonta Sahib

Job 11.

Schedule of Quantity

Name of Work:- Restoration of rain damage on various roads on various roads under Jammu Division No.1 (SH)-Providing & laying Patch work of various roads).

Estimated cost:- 397061/- only
Earnest Money:- 8000/- only
Time:- Two Month

S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in		Amount
					Rs	Words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3-wheeled static roller 80-100 (eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, crushable screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3(Three) as per Technical Specification Clause 404, by manual means including haulage of materials with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.	59.73	Per cubic metre	2319.60	Three hundred nineteen and paise sixty only		138550
2	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surface, cleaning of surface by providing by tack coat, premix carpet of 20mm (twenty millimetre) and seal coat of type-B as per technical specification with bitumen emulsion clause 1904.2.503 and 508.1 including all leads and lifts and carriage of materials complete as per entire satisfaction the direction of Engineer-in-charge.	796.40	Per square metre	324.60	Three hundred twenty four and paise sixty only		258511
					Total		397061

Executive Engineer,
Paonta B&R Division
HP, PWD, Paonta Sahib

Job 12.

Schedule of Quantity					Estimated cost:-107888/- only	
Name of Work:-Restoration of rain damage on link road to Kotri Bagna Savar Kolar road Km 0/0 to 8/0 (SH:- Construction of Retaining wall in cement concrete at RD 0/165 to 0/177)					Earnest Money:-2500/- only	
Sub heads and items of work					Time:- Two Month	
S.No	Qty	Unit	Figures	Rate in	Words	Amount
1	18.72	Per cubic metre	171.40	Rs	One hundred seventy one and paise forty only	3209
2	20.52	Per cubic metre	4955.20	Rs	Four thousand nine hundred fifty five and paise twenty only	101681
3	10.00	each	299.90	Rs	Two hundred ninety nine and paise ninety only	2999
Total						107888

Executive Engineer,
Poonia B&R Division
HP, FWD, Poonia Sahib

Job. 13.

Schedule of Quantity

Name of Work:- A/R & M/O to Rest House building at Paonta Sahib, District Sirmaur (SH:- Repair to Plaster patch, putty wall painting in existing Rest House Building)					Estimated cost:- 376390/- only Earnest Money:- 8000/- only	
S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in Words	Amount
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete. With cement mortar 1:4 (1 cement : 4 fine sand, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	90.92	Per square metre.	264.35	Rupees Two hundred sixty four and paise thirty five only.	24035
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	167.05	per square metre	85.10	Rupees Eighty five and paise ten only	14216
3	Polishing on wood work with ready mixed wax polish of approved brand and manufacture New work with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	28.12	per square metre	92.95	Rupees Ninety two and paise ninety five	2614
4	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	230.26	per square metre	89.90	Rupees Eighty nine and paise ninety only	26094
5	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	565.04	per square metre	94.30	Rupees Ninety four and paise thirty only	53283
6	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade. One or more coats on old work with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2815.87	per square metre	58.55	Rupees Fifty eight and paise fifty five only	164869
7	Finishing walls with Acrylic Smooth exterior paint of required shade. Old work (Two or more coat applied @ 1.67 ltr/10 sqm) on existing cement paint surface with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	1236.01	per square metre	73.85	Rupees Seventy three and paise eighty five only	91279
						376390

Executive Engineer,
Public Works Division
10/7/02, Paonta Sahib

Job-14

Schedule of Quantity						
Name of Work:-Restoration of Rain Damages to link from NH 907 to Bangala basti Gufanapur km 0/00 to 0/800 (SH:-C/O)						
Retaining wall in wire crles at RD 0/454 to 0/472.50)RH.S./River side						
		Estimate cost:-Rs.99621/-		Time allowed:- Two months		
		Earnest money:- Rs. 2000/-				
Sr.No.	Description of Items	Quantity	unit	Rates in		Amount
				Figure	Words	
1	Providing and laying of boulder apron laid in wire crates with 4 mm dia G.I.wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stones boulders weighing not less than 25 kg each as per drawing and technical specifications clause 1301.	28.91	Per cubic metre	3209.5	Rupees Three thousand two hundred nine and paissa fifty only	92787
2	Backfilling behind abutment,wing wall and return wall complete as per drawings &technical specification clause 1204.3.8	3.75	Per cubic metre	12204.6 4822.6	Rupees one thousand eight hundred twenty two and paissa sixty six only	11576 6835
				Total		99621

Executive Engineer,
Paonta B&R Division
H.P. P.W.D. Paonta Sahib