

No.PW/RGH/Estt-Tender/2023-24-
To

Himachal Pradesh
Public Works Department

13263-13312

Dated:- 16-02-2024

The Director,
Information and Public Relation,
Suchna Avam Jan Sampark Bhawan,
Near HP.Admn.Tribunal Shimla-2.

Subject:- Publication of Notice inviting Tender Advertisement.


Jai Hind.


Enclose please find herewith the Notice Inviting Tender to be opened on
28.02.2024 for publication in Giri Raj weekly and two other regional news papers Himachal Pradesh.

Encl: - As above

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD.Shimla-1.
2. The Chief Engineer (South) HP.PWD.Shimla-1.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (I.T) Cell, O/O Engineer-In-Chief, HPPWD Nigam Vihar Shimla-2 for uploaded Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer,
Rajgarh Division,
HP.PWD. Rajgarh.


Executive Engineer,
Rajgarh Division,
HP.PWD. Rajgarh.

**HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT
NOTICE INVITING TENDER**

Sealed items rates tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD so as to reach in this office 28.02.2024 upto 10:30 AM and shall be opened on the same day at 11:00 AM in the presence of intending contractors or their authorised representative who may link to be present. The tender form be had from his office against cash payment (non refundable) during working hours.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Rajgarh Division HPPWD Rajgarh must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Tender Sechedule	
1	Last date for tender receipt of application for tender form	26.02.2024 upto 4:00 PM
2.	Last date of sale of tender forms.	27.02.2024 upto 5:00 PM
3.	Date of receipt of tender forms	28.02.2024 upto 10:30AM
4.	Date of opening of tenders	28.02.2024 at 11:00 AM


Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of form	Eligible Class of contractor
1	Restoration Rain damages on Solan Meenus road km 24/345 to 61/00 (SH:- Construction of PCC Retaining wall at RD 49/820 to 49/830).	4,16,664/-	10,000/-	Two Months	350/-	Class-"C&D"
2	Restoration of rain damage on Halonipul Dahan road Km 0/0 to 15/0 (SH:- C/O PCC R/wall at RD 1/245 to 1/260).	4,67,677/-	10,000/-	Two Months	350/-	Class-"C&D"
3	Restoration rain damages on Solan Meenus road Km 24/345 to 61/0 (SH:- C/O PCC R/wall at RD 40/210 to 40/220).	4,16,664/-	9,000/-	Two Months	350/-	Class-"C&D"
4	Restoration of rain damage on BBRC road Km 87/0 to 127/300 (SH:- C/O PCC R/wall at RD 121/920 to 121/935).	4,72,323/-	10,000/-	Two Months	350/-	Class-"C&D"
5	Restoration of rain damages on Nohara Khad Ghotari Pab via Gehnog road Km 0/00 to 5/800 (SH:- Construction of PCC Retaining wall between km 2/620 to 2/629).	4,84,410/-	10,000/-	Two months	350/-	Class-"C&D"
6	Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road Km 87/00 to 127/300 (SH:- Construction of PCC Retaning wall at RD 125/560 to 125/568.80)	4,84,469/-	10,000/-	Two month	350/-	Class-"C&D"
7	Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road Km 87/00 to 127/300 (SH:- Construction of PCC breast wall at RD 126/315 to 126/335).	3,01,158/-	6,500/-	Two months	350/-	Class-"C&D"
8	Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road Km 48/0 to 87/0 (SH:- Construction of PCC retaning wall at RD 52/725 to 52/740).	4,69,187/-	10,000/-	Two Months	350/-	Class-"C&D"
9	Restoration of rain damages on Kuffer Pal to Ritab Pal road Km 0/0 to 2/0 (SH:- Construction of PCC breast wall at RD 0/825 to 0/850).	3,88,475/-	8,000/-	Two month	350/-	Class-"C&D"
10	Restoration of rain damage on Habban Dhamoon road Km 0/0 to 21/645 (SH:- C/O PCC B/wall between RD 20/080 to 20/095).	2,21,676.00	5,000/-	Two months	350/-	Class-"C&D"
11	Restoration of rain damages on Chandol Ranaghat road Km 0/0 to 12/0 (SH:- Construction of PCC Retaning wall at RD 0/900 to 0/912).	4,92,807.00	10000/-	Two months	350/-	Class-"C&D"
12	Restoration of rain damages on Dhamla Manwa Dhanchukhria road Km 0/0 to 19/0 (SH:- Construction of PCC Retaning wall at RD 16/480 to 16/492).	4,92,807.00	10000/-	Two months	350/-	Class-"C&D"
13	Restoration of rain damages on Dharli to Dibber road Km 0/0 to 6/0 (SH:- Construction of PCC breast wall at RD 2/025 to 2/050).	3,69,893.00	10000/-	Two months	350/-	Class-"C&D"

14	Restoration of rain damages on Kheri Lana Cheta road Km 0/0 to 8/0 (SH:- Construction of PCC & wire crate R/wall at RD 3/310 to 3/319).	4,90,377.00	10000/-	Two months	350/-	Class-"C&D"
15	Restoration of rain damages on Ranaghat Chandol road Km 0/0 to 12/0 (SH:- Construction of PCC R/wall at RD 1/490 to 1/502).	3,73,635.00	10000/-	Two months	350/-	Class-"C&D"
16	Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road Km 87/0 to 127/300 (SH:- Construction of PCC R/wall at RD 89/930 to 89/937).	4,96,426.00	10000/-	Two months	350/-	Class-"C&D"
17	Restoration of rain damages on Kheri Lana Cheta road Km 0/0 to 8/0 (SH:- Construction of PCC B/wall between RD 3/310 to 3/320 & wire crate R/wall between RD 3/319 to 3/333).	4,77,931.00	10000/-	Two months	350/-	Class-"C&D"
18	Restoration of rain damages on Dhamla Manwa Dhanchukhria road Km 0/0 to 19/0 (SH:- Construction of PCC R/ wall at RD 15/450 to 15/462).	4,92,807.00	10000/-	Two months	350/-	Class-"C&D"
19	Special repair of Civil Hospital at Rajgarh (SH:- Providing /Fixing cupboard and Providing /Laying floor tiles in DMC(TB unit).	70,189.00	2000/-	Two months	350/-	Class-"C&D"
20	Restoration of rain damages on Rehri Gussan to Kathli Bharan road Km 0/0 to 13/0 (SH:- Construction of PCC B/wall between at RD 12/700 to 12/720).	4,42,829.00	10000/-	Two months	350/-	Class-"C&D"
21	Restoration Rain damages on on Neripul Deothi Majhgaon road km 0/00 to 12/00 (SH:- Construction of PCC R/wall between km 7/090 to 7/097.50).	4,00,069/-	10,000/-	Two months	350/-	Class-"C&D"
22	Restoration Rain damages on on Neripul Deothi Majhgaon road km 0/00 to 12/00 (SH:- Construction of PCC R/wall between km 7/098 to 7/105.50).	4,00,069/-	10,000/-	Two months	350/-	Class-"C&D"
23	Restoration Rain damages on Banethi Bagthan Rajgarh Chandol to Thor Kolan road km 0/00 to 3/510 (SH:-Construction of PCC R/wall at Rd 0/635 to 0/646.80).	4,92,274/-	10,000/-	Two months	350/-	Class-"C&D"

Certificate :- It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The above Job for consultancy work and consultants should be working with HPPWD.
2. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
3. The contractor/Firms should attached copy of the Registration/Renewal with the application.
4. The contractor/bidder should quoted in percentage rates.
5. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
6. Conditional and telegraphic tender shall be accepted and rejected straightway. Tender received after due date and time will be rejected.
7. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
8. The tender document shall be issued to only those contractors who dose not have more than two works in hand in HPPWD Division.
9. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
10. The offer shall remain valid upto 75 days.
11. The above Job is on present market rates and tender will be processed as per instruction issued by the Add. Chief Secretary (PW) to the Govt. of H.P notification No. PBW)B)A(3)1/2020 dt. 22.07.2020. Regarding adoption of CPWD works manual 2019 & other publication of CWP in HPPWD shall also be applicable.
12. The Executive Engineer reserve the right any or all the tenders without assigning any reason.
13. The tender document shall be issued to only those contractors who submit registration of GST No.


 Executive Engineer
 HPPWD Division Rajgarh
 Distt Sirmour HP
 on behalf of Governor of Himachal Pradesh
 Tel. No. 01799-224023
 Mail: ee-rai-hp@nic.in

Name of work: - Restoration Rain damages on Solan Meenus road Km 24/345 to 61/00 (SH:- Construction of PCC Retaining wall at RD 49/820 to 49/830).

SCHEDULE OF QUANTITY

Estimated cost: - Rs.4,16,664/-
Earnest money: - Rs. 9,000/-
Time Limit: -Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	35.190	Per Cubic Metre	255.20	Rupees two hundred Fifty five and paise twenty only.	8980.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Cause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 40 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	66.700	Per Cubic Metre	5890.00	Rupees five thousand eight hundred ninety and paise nil only.	392863.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	16.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	4429.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	13.50	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	10392.00
Quoted rates percentage in figure				G.Total		416664.00
Quoted rates percentage in word						


 Executive Engineer,
 Rajgarh Division,
 MPWD, Rajgarh.

SCHEDULE OF QUANTITY

Name of work: - Restoration Rain damages on Halonipul Dahan road km 0/00 to 15/00 (SH:- Construction of PCC Estimated cost - Rs.4,67,677/-
Retaining wall at RD 1/245 to 1/260). Earnest money: - Rs. 10,000/-

Time Limit: - Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	37.640	Per Cubic Metre	255.20	Rupees two hundred Fifty five and paise twenty only.	9606.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 40 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	74.890	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	441102.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	15.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	4152.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	16.65	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	12817.00
				G.Total		467677.00
	Quoted rates precentage in figure					
	Quoted rates precentage in word					


 Executive Engineer,
 Raigarh Division,
 HP PWD, Raigarh.

Name of work: - Restoration of rain damage on Solan Meenus road Km 24/345 to 61/0 (SH:- C/O PCC R/wall Estimated cost: - Rs. 4,16,664/- Earnest money: - Rs. 10,000/- Time Limit: - Two Months)

SCHEDULE OF QUANTITY

Sub-Head and Items of work	Qty.	Unit	Rate		Amount
			in figures.	in words	
1 Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	35.19	Per Cubic Metre	255.20	Rupees two hundred Fifty five and paise twenty only.	8980.00
2 Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 40 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	66.70	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	392863.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	16.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	4429.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	13.50	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	10392.00
Quoted rates precentage in figure				G.Total		416664.00
Quoted rates precentage in word						



 Executive Engineer,
 Rajgarh Division,
 HPPWD, Rajgarh.

Name of work: - Restoration rain damages on BBRC Road km 48/00 to 127/300 (SH:-Construction of PCC R/Wall Estimated cost - Rs.4,72,323/-
at Rd 121/920 to 121/935).
Earnest money:- Rs. 10,000/-
Time limit:- One Month

SCHEDULE OF QUANTITY

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	26.060	Per Cubic Metre	255.20	Rupees two hundred Fifty five and paise twenty only.	6651.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 40 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	75.340	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	443753.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	16.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	4429.00
4	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	22.72	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	17490.00
Quoted rates precentage in figure			G.Total			472323.00
Quoted rates precentage in word						


 Executive Engineer,
 Raigarh Division,
 HPPWD, Raigarh.

Name of work: - Restoration of rain damage on Nohara Khad Chotari Pab via Gehnog road km 0/00 to 5/800 (SH:- Estimated cost: - Rs. 4,84,410/-
Construction of PCC Retaining wall between km 2/620 to 2/629). Earnest money: - Rs.10,000/-
SCHEDULE OF QUANTITY
Time Limit - Two Months

Sub-Head and Items of work	Qty.	Unit	Rate		Amount
			in figures.	in words	
1 Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	63.06	Per Cubic Metre	255.20	Rupees two hundred Fifty five and paise twenty only.	16093.00
2 Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 40 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	76.72	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	451881.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	19.00	Each	276.80	Ruppes two hundred seventy six and paise eighty only.	5259.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	14.52	Per Cubic Metre.	769.80	Ruppes seven hundred sixty nine and paise eighty only.	11177.00
	Quoted rates precentage in figure			G.Total		484410.00
	Quoted rates precentage in word					


 Executive Engineer,
 Rajgarh Division,
 MP PWD, Rajgarh.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road Km 87/00 to 127/300 (SH:- Construction of PCC Retaining wall at RD 125/560 to 125/568.80).

Estimated cost - Rs.4,84,469/-
Earnest money: - Rs. 10,000/-
Time limit:- Two Months

Str. No	Sub-Head and Items of work	Qty.	Unit	in figures.	Rate in words	Amount
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	47.26	Per Cubic Metre.	255.20	Rupees two hundred fifty five and paise twenty only.	12061.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	77.92	Per Cubic Metre	5890.00	Rupees thousand eight hundred ninety and paise nil only.	458949.00
3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204,3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	15.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	4152.00

4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	12.09	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	9307.00
	Quoted rates precentage in figure				Total:-	484469.00
	Quoted rates precentage in word					


 Executive Engineer
 Rajgarh Division
 HPPWD Rajgarh

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road Km 87/00 to 127/300 (SH:- Construction of PCC breast wall at RD 126/315 to 126/335).

Estimated cost - Rs.3,01,158/-
Earnest money:- Rs.6,500/-
Time Limit:- Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	39.90	Per Cubic Metre.	255.20	Rupees two hundred fifty five and paise twenty only.	10182.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	48.32	Per Cubic Metre	5890.00	Rupees thousand eight hundred ninety and paise nil only.	284605.00
3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	8.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	2214.00

backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.		5.40	Per Cubic Metre.	769.80	Ruppes seven hundred sixty nine and paise eighty only.	4157.00
Quoted rates precentage in figure					Total:-	301158.00
Quoted rates precentage in word						


 Executive Engineer
 Rajgarh Division
 HPPWD Rajgarh

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road Km 48/0 to 87/0 (SH:- Construction of PCC retaining wall at RD 52/725 to 52/740).

Estimated cost - Rs.4,69,187/-
Earnest money: - Rs. 10,000/-

Time Limit: - Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc, and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	42.70	Per Cubic Metre.	255.20	Rupees two hundred fifty five and paise twenty only.	10897.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	74.85	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	440867.00
3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204,3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	16.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	4429.00

Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.					16.88	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	12994.00
Quoted rates precentage in figure								Total:-	469187.00
Quoted rates precentage in word									


 Executive Engineer
 Rajgarh Division
 HP PWD Rajgarh

SCHEDULE OF QUANTITY
 Name of work:-Restoration of rain damages on Kuffer Pal to Ritab Pal road Km 0/0 to 2/0 (SH:- Construction of PCC breast wall at RD 0/825 to 0/850).

Estimated cost - Rs.3,88,475/-
 Earnest money:- Rs.8,000/-
 Time Limit:- Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	in figures.	Rate in words	Amount
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	47.25	Per Cubic Metre.	255.20	Rupees hundred five and paise twenty only.	12058.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	60.25	Per Cubic Metre	5890.00	Rupees thousand eight hundred ninety and paise nil only.	354873.00
3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	9.00	Each	276.80	Rupees hundred seventy six and paise eighty only.	2491.00

Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	24.75	Per Cubic Metre.	769.80	Rupees seven hundred nine and paise eighty only.	19053.00
				Total:-	388475.00
Quoted rates precentage in figure					
Quoted rates precentage in word					


 Executive Engineer
 Raigarh Division
 HPPWD Raigarh

Name of work: - Restoration Rain damages on Habban Dhamoon road km 0/00 to 21/645 (SH:-Construction of PCC B/wall at Rd 20/080 to 20/095).

SCHEDULE OF QUANTITY

Estimated cost: - Rs. 2,21,676/-
Earnest money: - Rs. 5,000/-
Time Limit: - Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	23.770	Per Cubic Metre	255.20	Rupees two hundred Fifty five and paise twenty only.	6066.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 40 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	36.200	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	213218.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	5.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	1384.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	1.31	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	1008.00
				G.Total		221676.00
	Quoted rates precentage in figure					
	Quoted rates precentage in word					


 Rajgadh Division,
 Executive Engineer,
 HP PWD, Rajgadh.

Name of work:- Restoration of rain damages on Chandol Ranaghat road Km 0/0 to 12/0 (SH:- Construction of PCC Retaining wall at RD 0/900 to 0/912).

SCHEDULE OF QUANTITY

Estimated cost - Rs.4,92,807/-
Earnest money:- Rs.10,000/-
Time Limit:- Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc, and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	31.27	Per Cubic Metre.	255.20	Rupees two hundred fifty five and paise twenty only.	7980.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	80.15	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	472084.00
3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204.3.7, all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	13.00	Each	276.80	Rupees hundred seventy six and paise eighty only.	3598.00

Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.					11.88	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	9145.00
Quoted rates precentage in figure								Total:-	492807.00
Quoted rates precentage in word									


 Executive Engineer
 Rajgarh Division
 HP PWD Rajgarh

Name of work:- Restoration of rain damages on Dhamla Manwa Dhanchukhria road Km 0/0 to 19/0 (SH:- Construction of PCC Retaining wall at RD 16/480 to 16/492).

Time Limit: -Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate	Amount
				in figures. in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	31.27	Per Cubic Metre.	255.20 Rupees hundred fifty five and paise twenty only.	7980.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One hundred : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations. In all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	80.15	Per Cubic Metre	5890.00 Rupees thousand eight hundred ninety and paise nil only.	472084.00
3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	13.00	Each	276.80 Rupees hundred seventy six and paise eighty only.	3598.00

backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	11.88	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	9145.00
				Total:-	492807.00
Quoted rates precentage in figure					
Quoted rates precentage in word					


 Executive Engineer
 Rajgarh Division
 HPPWD Rajgarh

SCHEDULE OF QUANTITY
Name of work:-Restoration of rain damages on Dharti to Dibber road Km 0/0 to 6/0(SH.- Construction of PCC breast wall at RD 2/025 to 2/050).

Estimated cost: - Rs.3,69,893,
 Earnest money: - Rs.8,000/-
 Time Limit: -Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc, and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	47.25	Per Cubic Metre	255.20	Rupees two hundred fifty five and paise twenty only.	12058.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	60.33	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	355344.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	9.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	2491.00
					Total:-	369893.00
	Quoted rates precentage in figure					
	Quoted rates precentage in word					


 Executive Engineer
 Rajgarh Division
 HPPWD Rajgarh

Name of work:- Restoration of rain damages on Kheri Lana Cheta road Km 0/0 to 8/0 (SH:- Construction of PCC & wire crate R/wall at RD 3/310 to 3/319).

SCHEDULE OF QUANTITY

Estimated cost - Rs.4,90,377/-
Earnest money:- Rs. 10,000/-
Time Limit:- Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical Specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	18.00	Per Cubic Metre.	255.20	Rupees two hundred fifty five and paise twenty only.	4594.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations In all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	79.56	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	468608.00
3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	20.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	5536.0

Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.					15.12	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	11639.00
Quoted rates presentage in figure								Total:-	490377.00
Quoted rates presentage in word									


 Executive Engineer
 Raigarh Division
 HPPWD Raigarh

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Ranaghat Chandol road Km 0/0 to 12/0 (SH:- Construction of PCC R/wall at RD 1/490 to 1/502).

Estimated cost - Rs.3,73,635/-
 Earnest money: - Rs. 8,000/-
 Time Limit: -Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	33.00	Per Cubic Metre.	255.20	Rupees two hundred fifty five and paise twenty only.	8422.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight Graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	59.88	Per Cubic Metre	5890.00	Rupees thousand eight hundred ninety and paise nil only.	352693.00
3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	13.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	3598.00

backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.

	11.59	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	8922.00
Quoted rates precentage in figure				Total:-	373635.00
Quoted rates precentage in word					


Executive Engineer
Raigarh Division
H.P.W.D. Raigarh

SCHEDULE OF QUANTITY

Name of work:-Restoration of rain damages on Banethi Bagthan Rajgath Chandel road Km 87/0 to 127/300(SH:- Construction of PCC R/wall at RD 89/930 to 89/937).

Estimated cost - Rs.4,96,426/-
Earnest money:- Rs. 10,000/-
Time Limit:- Two Months

Sr.No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	25.20	Per Cubic Metre.	255.20	Rupees two hundred fifty five and paise twenty only.	6431.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	80.28	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	472849.00
3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	14.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	3875.00

4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	17.24	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	13271.00
					Total:-	496426.00
	Quoted rates precentage in figure					
	Quoted rates precentage in word					


 Executive Engineer
 Raigarh Division
 HPWD Raigarh

SCHEDULE OF QUANTITY
Name of work:-Restoration of rain damages on Kheri Lana Cheta road Km 0/0 to 8/0 (SH:- Construction of PCC B/wall between RD 3/310 to 3/320 & wire crate R/wall between RD 3/319 to 3/333).

Estimated cost - Rs.4,77,931/-
Earnest money: - Rs. 10,000/-
Time Limit: -Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	46.46	Per Cubic Metre.	255.20	Rupees two hundred fifty five and paise twenty only.	11857.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	24.10	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	141949.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm(four millimeter) dia GI wire conforming to IS:280 (two hundred eighty) and IS:4826(four thousand eight hundred twenty six) in 100 mm x 100 mm(one hundred millimeter) mesh (woven diagonally) including 10(ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specifications Clause 1301,(one thousand three hundred one) including carriage of all labour equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	109.34	Per Cubic Metre	2723.20	Rupees Two thousand seven hundred twenty three and paise twenty only.	297755.00

4	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	10.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	2768.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	30.66	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	23602.00
Quoted rates precentage in figure					Total:-	477931.00
Quoted rates precentage in word						


 Executive Engineer
 Raigarh Division
 HPPWD Raigarh

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Dhamla Manwa Dhanchukhria road Km 0/0 to 19/0 (SH:- Construction of PCC R/ wall at RD 15/450 to 15/462).

Estimated cost: - Rs.4,92,807/-
 Earnest money: - Rs. 10,000/-
 Time Limit: - Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	in figures.	Rate in words	Amount
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	31.27	Per Cubic Metre.	255.20	Rupees two hundred fifty five and paise twenty only.	7980.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One hundred Three : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	80.15	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	472084.00
3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	13.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	3598.00

Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	11.88	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	9145.00
Quoted rates precentage in figure					
Quoted rates precentage in word					
				Total:-	492807.00


 Executive Engineer
 Rajgarh Division
 HPPWD Rajgarh

SCHEDULE OF QUANTITY
Name of Work :- Special repair of Civil Hospital at Rajgarh (SI:- Providing /Fixing cupboard and Providing /Laying floor tiles in DMC(TB unit)).

Providing /Laying floor tiles in DMC(TB unit).									
Estimated cost:-Rs.70,189/-									
Earnest money:-Rs.2,000/-									
Time Limit:- Two months									
Sr. No	Description of items	Qty.	Unit	Rate		Amount			
				In figure	In word				
1	Providing and laying 19mm (nineteen millimetre)thick commercial board shuttelse with hard wood edging and PGI sheet lining inside of shutter of approved size including bright finished iron butt hinges etc. Complete as per detailed arch. Drawing for the work and as per HP.PWD specification, including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.76	Per Square metre	1865.30	Rupees thousand hundred sixty five and paise thirty only.	one eight hundred sixty five and paise thirty only.	18205.00		
2	Providing and fixing 19mm (nineteen millimeter) thick water proof commercial board in shelves/ box for cup board with butt joints & fixing with nails & screws etc complete), including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	8.34	Per Square metre	2167.70	Rupees thousand hundred sixty seven and paise seventy only.	two thousand one hundred sixty seven and paise seventy only.	18079.00		
3	Providing & fixing 1.00 mm (one millimeter) thick decorative high pressure laminated sheet of plain/ wood grain in gloss/matt/suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.76	Per Square metre	814.00	Rupees hundred forty seven and paise fifty only.	six hundred forty seven and paise fifty only.	7945.00		
4	Providing and fixing Double strip (harizontal type) magnetic catcher of approved quality in cupboard/ wardrobe shutters, including fixing with necessary screws etc. complete including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	40.00	Each	42.00	Rupees forty two and paise nil only.	Rupees forty two and paise nil only.	1680.00		

5	Providing and laying vitrified floor tiles 600 X 600 mm (Six hundred millimeter into Six hundred millimeter) (AGL, NITCO, kazaria of approved shade and sample or it's equivalent) in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (Zero point zero eight percent) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimeter) thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three point thirty kilogramme) including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm (Six hundred into six hundred millimetre) as per HP.PWD specification, including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.	10.47	Per Square metre	1870.00	Rupees thousand hundred seventy and paise nil only.	one eight hundred seventy and paise nil	19579.00
6	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08% (Zero point zero eight percent) and conforming to IS. 15622, of approved ake, in all colours & shade, in skirting, riser of steps, over 12 mm (twelve millimetre) thick bed of cement mortar 1:3 (1cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 k/g sqm (three point thirty kilogramme) including grouting the joint with white cement & matching pigments etc. complete as per HP.PWD specification, including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.	1.30	Per Square metre	1942.00	Rupees thousand hundred forty two and paise nil only.	one thousand nine hundred forty two and paise nil	2525.00
7	Providing and fixing aluminium 100mm (One hundred millimetre)handles, ISI marked, (anodic coadic coating not less than grade AC as per IS : 1868 transparent or dyed to required colour or shade, with necessary screws etc. complete.	32.00	Each	68.00	Rupees eight and paise nil only.	sixty eight and paise nil	2176.00
Quoted rates precentage in figure						Total:	70189.00
Quoted rates precentage in word							


 Executive Engineer,
 Raigarh Division,
 HP.PWD, Raigarh.

SCHEDULE OF QUANTITY
Name of work: -Restoration Rain damages on Rehri Gussan to Kathibharan road km 0/00 to 13/00 (SH:- Estimated cost - Rs.4,42,829/-
Construction of PCC B/wall at Rd 12/700 to 12/720).

Earnest money: - Rs. 10,000/-
 Time Limit: -Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	57.200	Per Cubic Metre	255.20	Rupees hundred Fifty five and paise twenty only.	14597.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 40 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	72.000	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	424080.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	15.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	4152.00
	Quoted rates percentage in figure			G.Total		442829.00
	Quoted rates percentage in word					


 Executive Engineer,
 Raigarh Division,
 HPPWD, Raigarh.

SCHEDULE OF QUANTITY

Name of work: - Restoration Rain damages on on Neripul Deothi Majngaon road km 0/00 to 12/00 (SH:- Estimated cost - Rs. 4,00,069/-
Construction of PCC R/wall between km 7/090 to 7/097.50).
Earnest money: - Rs. 10,000/-

Time Limit: -Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	44.460	Per Cubic Metre	255.20	Rupees two hundred Fifty five and paise twenty only.	11346.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 40 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	64.210	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	378197.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	13.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	3598.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	9.00	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	6928.00
	Quoted rates precentage in figure			G.Total		400069.00
	Quoted rates precentage in word					


 Executive Engineer,
 Raigarh Division,
 Jharkhand, Raigarh.

SCHEDULE OF QUANTITY

Name of work: - Restoration Rain damages on on Neripul Deothi Majhgaon road km 0/00 to 12/00 (SH:- Estimated cost: - Rs. 4,00,069/-
Construction of PCC R/wall between km 7/098 to 7/105.50).
Earnest money: - Rs. 10,000/-

Time Limit: - Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chisling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	44.460	Per Cubic Metre	255.20	Rupees two hundred Fifty five and paise twenty only.	11346.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Cause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 40 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	64.210	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	378197.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge,	13.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	3598.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	9.00	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	6928.00
				G.Total		400069.00
	Quoted rates precentage in figure					
	Quoted rates precentage in word					


 Executive Engineer,
 Rajgarh Division,
 HPWD, Rajgarh.

SCHEDULE OF QUANTITY

Name of work: - Restoration Rain damages on Banethi Bagthan Rajgarh Chandol to Thor Kolan road km 0/00 to Estimated cost - Rs. 4,92,274/-
3/510 (SH:-Construction of PCC R/wall at Rd 0/635 to 0/646.80).
Earnest money:- Rs. 10,000/-
Time Limit:- Two Months

Sr. No	Sub-Head and Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	41.520	Per Cubic Metre	255.20	Rupees two hundred Fifty five and paise twenty only.	10596.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as par drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand, Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 40 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	78.710	Per Cubic Metre	5890.00	Rupees Five thousand eight hundred ninety and paise nil only.	463602.00

3	Providing weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing walls, return wall with 100mm (One hundred) millimetre dia AC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709,1204.3.7. all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	21.00	Each	276.80	Rupees two hundred seventy six and paise eighty only.	5813.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material. as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	15.93	Per Cubic Metre.	769.80	Rupees seven hundred sixty nine and paise eighty only.	12263.00
				G.Total		492274.00
	Quoted rates precentage in figure					
	Quoted rates precentage in word					


 Executive Engineer,
 Raigarh Division,
 HPPWD, Raigarh.