HIMACHAL PRADESH
P W D

No. PW.CHD.CB.Tender/2024- 87-73 **Dated:** 18/6/24

To

The Executive Engineer (IT Cell),
Nigam Vihar Shimla,
District Shimla, H.P.

Subject :- Publication of tender Notice.

Sir,

Enclosed please find herewith the tender Notice of work(s) as given in the Notice Inviting Tender for uploading on departmental website as per notification Pr.Secy. (PW) to the Government of Himachal Pradesh letter No. PBW(B)1/2020 dated 27th May 2021 and PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender notice are urgent in nature and in public interest.

Executive Engineer,
Chopal Division, HPPWD Chopal
On behalf of Governor of H.P.

Copy forwarded for information to :-

1. The Superintending Engineer, 4th Circle, HPPWD Shimla.
2. The Computer Cell O/O Executive Engineer (IT Cell) Nigam Vihar Shimla-2.

Executive Engineer,
Chopal Division, HPPWD Chopal
On behalf of Governor of H.P.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

No. PW.CHD.CB.Tender/2024- 874-973 **Dated:** 18/6/24.

Sealed percentage rate tender(s) is/are hereby invited by the Executive Engineer HPPWD Chopal District Shimla H.P. in form No. 6 & 8 on behalf of Governor of H.P. for the following work(s) from the contractors of appropriate class enlisted with HPPWD. The tender(s) shall be opened in the presence of the contractors/firms or their representative who wish to be present.

TIME SCHEDULE OF TENDER

1. Date and time of receipt of application for tender form : 28.06.2024 up to 04:00 PM
2. Date and time of issue of tender form : 28.06.2024 04:00 PM to 05:00 PM
3. Date and time of receipt of tenders : 29.06.2024 11:00 AM
4. Date and time of opening of tender : 29.06.2024 11:30 AM

Sl. No	Name of Work	Estimated Cost	Earnest Money (in Rs.)	Cost of tender form	Time allowed
1.	Restoration of rain damages on Nerwa to Dhadu road km. 0/0 to 6/500 (SH: C/o wire crated R/wall at R.D. 3/105 to 3/112.50).	377799/-	8000/-	350/-	One month
2.	Restoration of rain damages on Chopal to Kumbra road km. 0/0 to 18/300 (SH: C/o wire crated B/wall at R.D. 13/860 to 13/885).	387300/-	8000/-	350/-	One month
3.	C/o link road Kulalani to Dhar Chandna km. 0/0 to 0/750 (SH: Removal of formation deficiency at R.D. 0/0 to 0/750 and R/wall at R.D. 0/510 to 0/530).	486312/-	10000/-	350/-	One month
4.	C/o link road Kimaha to Dhar km. 0/0 to 0/450 (SH: Removal of formation deficiency at R.D. 0/0 to 0/450 and R/wall at R.D. 0/345 to 0/358).	340633/-	7000/-	350/-	One month
5.	A/R & M/O Sainj Chopal Nerwa Feduj road km. 20/0 to 90/0 (SH: Patch work in between km. 77/0 to 82/0).	476783/-	10000/-	350/-	One month
6.	Restoration of rain damages on various roads under Kuthar Section of PIU Sub Division (SH: Hiring of JCB for removal of slips/debris etc.)	99960/-	2000/-	350/-	One month
7.	Restoration of rain damages on link road to H.B. Chowkia km. 0/0 to 3/0 (SH: C/o R/wall at R.D. 0/720 to 0/740).	376625/-	8000/-	350/-	One month

TERMS AND CONDITIONS:

1. The earnest money in the shape of National Saving Certificate, Time Deposit Account in any of the post office in HP/FDR of any Bank duly pledged in favour of Executive Engineer, Chopal Division HPPWD Chopal must be accompanied with the application for receipt of tender form along with cost of tender form in cash (Non refundable).

2. The conditional tender(s) and the application received without earnest money will summarily be rejected without assigning any reason(s).
3. The contractor/firms should possess the following documents (photo copy to the self attested with application for obtaining the tenders documents :-
    a. Latest enlistment/renewal orders with application.
    b. GST Number issued by the Sale Tax Department.
    c. PAN (Permanent Account Number) issued by the Income Tax Department shall contain scanned copies of EPF issued from competent authority.
4. The Executive Engineer, Chopal Division HPPWD Chopal reserves the right to reject any tender without assigning any reason(s).
5. Only two number tender forms will be issued to the eligible contractor. If he bids for more than two works, only the first two works in sequence will be opened.
6. The work shall has to be started within fifteen days from the date of award. If the contractor fails to start the work within fifteen days, the work shall be cancelled and earnest money deposited will be forfeited.
7. The Cess Charges @ 1% will be deducted from the gross amount of work done of the contractor.
8. The work will be completed by the contractor within the stipulated period.
9. The contractor/firms are required to insert the rate of percentage in words as well as in figures, failing which Executive Engineer reserves the right to accept/reject any/overall tender.
10. The tender shall be issued to only those contractor/firms who are eligible suitable and competent.
11. The tender forms shall be issued to eligible contractors depending upon their past performance and work experience.
12. The contractor/firm having necessary documents and past adequate experience shall be preferred.
13. The contractor who has failed to start/complete the work already allotted in his favour within stipulated period shall not be issued tender forms.
14. A contractor enlisted in a particular class is eligible to tender for his own class and one step below.
15. If any kind of holiday to be happened, the tender documents shall be sold/opened on the next working day at the same time and venue.
16. GST will be deducted as per rates fixed by the Government.

CERTIFICATE

It is certified that tender for the above work(s) is/are required please.

Executive Engineer,
Chopal Division, HPPWD Chopal
On behalf of Governor of H.P.

Copy forwarded for information to :-

1. The Chief Engineer (Shimla Zone) HPPWD Shimla
2. The Superintending Engineer, 4th Circle, HPPWD Shimla.
3. The Deputy Commissioner, Shimla.
4. The SDO(C) Chopal Tehsil Chopal District Shimla HP
5. The SDO(C) Kupvi Tehsil Kupvi District Shimla HP
6. The BDO Chopal Tehsil Chopal District Shimla HP
7. The BOD Kupvi Kupvi Tehsil Kupvi District Shimla HP
8. All the Assistant Engineer working under this division.
9. All the intending contractors in HPPWD
10. Notice Board.

Executive Engineer,
Chopal Division, HPPWD Chopal
On behalf of Governor of H.P.

HIMACHAL PRADESH
P W D

CERTIFICATE

Certified that the tender(s) of work(s) as called vide this office NIT No.PW.CHD.CB.E-9/2024- 874-973 dated 18/06/2024 is/are of urgent nature work(s).

Executive Engineer,
Chopal Division, HPPWD Chopal
On behalf of Governor of H.P.

SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 377799
Earnest Money	Rs. 8000
Time Allowed	One Month

Name of work : R/R damage on Nerwa to Dhadu road km 0/00 to 6/100

(SH : C/o R/wall at R.D. 3/105 to 3/112.50 :) ~~Above CC Pusta~~

Sl. No	Description of item	Qty.	Rate In figure	Rate In words	Unit	Amount
1	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	127.92	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre	370968
2	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	7.19	950.00	Rupees nine hundred fifty and paisa zero only	Per cubic metre	6831
	Quoted rate in figure.				Total	377799
	Quoted rate in words.					

Executive Engineer
B&R Division HPPWD
Chopal

(5)

SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 486312
Earnest Money	Rs. 10000
Time Allowed	One Month

Name of work : C/o Link road from Kularlani to Dhar Chandna road km 0/00 to 0/750

(SH : R.O.F.D. at RD 0/00 to 0/750 and R/wall at RD 0/510 to 0/530)

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift up to 1.5 m and a lead upto 20 m as per drawing and technical specification clause 1603.1 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol 1 and as per direction of Engineer in Charge at site in all leads and lifts.	1120.47	195.00	Rupees one hundred ninety five and paisa zero only	Per cubic metre	218492
2	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious materialand disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol 1 and as per direction of Engineer in Charge at site in all leads and lifts.	20.80	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre	4368
3	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone agreegate 20mm nominal dia mixing by machenical concrete mixing 0.4/0.28 cubic metre & viberated mechanically so as to give a compressive strength and curring complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts	47.01	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre	244452
4	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	12.00	950.00	Rupees nine hundred fifty and paisa zero only	Per cubic metre	11400
5	Providing weep holes in brick masonry plain/reinforced concrete abutment wing wall retaining wall with 100mm dia AC pipe extending through the full width of the structures with slope of 1 (v) 20 (h) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7. including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol 1 and as per direction of Engineer in Charge at site in all leads and lifts.	38.00	200.00	Rupees two hundred and paisa zero only	Per running metre	7600
					Total	486312
	Quoted rate in figure.					
	Quoted rate in words.					

Executive Engineer
B&R Division HPPWD
Chopal

(4)

SCHEDULED OF QUANTITY.

Estimated Rs. 340634/-
Earnest Rs. 7000
Time allowed One Month

Name of Work: C/o link road from Kimaha to Dhar km. 0/0 to 0/450 (SH: Removal of formation deficiency at R.D. 0/0 to 0/450 & R/wall at R.D. 0/345 to 0/358).

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Cutting in earth work in all heights and depths in all kinds of soils including saturated soils comprising of pick work, jumper works any blasting works both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and there intermediate classification of soils including dewatering where ever required, setting, out true to the required lines grades, side slopes, triming bottoms and levels as shown on the drawing including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	821.30	195.00	(Rupees one hundred ninety five) only.	Per cubic metre.	160154
2	Earth work in excavation for structure as per drawing and technical specifications clause 305.1 i/c setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal up to a lead of 50 metre dressing of side and bottom and back-filling in trenches with excavated suitable materials ordinary soil upto 3.00 metre depth including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	17.42	210.00	(Rupees two hundred ten) only.	Per cubic metre.	3658
3	Providing and laying cement concrete 1:4:8 (one cement four sand eight graded stone aggregate 25mm nominal size) and curing complete excluding the cost of form work in foundation and plinth including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	31.30	5200.00	(Rupees five thousand two hundred) only.	Per cubic metre.	162760
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8. (i) Granular material including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	9.75	950.00	(Rupees nine hundred fifty) only.	Per cubic metre.	9263
5	P/F PVC pipe weep hole 100 mm dia including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts	24.00	200.00	(Rupees two hundred) only.	Per running metre	4800
					Total	**340634**

	Quoted rate in figure		
	Quoted rate in words		

Executive Engineer
B&R Division HPPWD
Chopal

SCHEDULED OF QUANTITY.

Estimated cost Rs. 476783/-
Earnest Money Rs. 10000
Time allowed : One Month

Name of Work: A/R & M/O Sainj Chopal Nerwa Fedujroad km. 20/0 to 90/0 (SH: Patch work in between km.R.D. 77/0 to 82/0).

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Providing and applying tack coat using bitumen emulsion (RS-I) using emulsion pressure distributor @ 0.25 to 0.30 kg per square metre on the prepared dry and hungry bituminios surface cleaned with hydrolic broom as per technical specification clause 503. including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts	1333.10	19.00	(Rupees nineteen) only	Per sqare metre	25329
2	Providing laying and rolling of close graded Mix Seal Surfacing ,surfacing material of 25 mm thickness composed of 11.2 mm to 0.90mm (Type A) @ 0.338 kg per 10 suare metre aggregates using penetration grade bitumen,binder content @ 27.50 kg per 10 square metre or 5.11 % by weight and minimum density of MSS should be 2.10 gm /cc to required line ,grade and level to serve as wearing course on a previously prepared base ,including mixing in a suitable plant ,laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grade as per technical specification clause 509 including all leads ,lifts and carriage of materials complete as per entire satisfication of the Engineer in charge.	1333.10	338.65	(Rs two three hundred thirty eight and paisa sixty five only)	Per sqare metre	451454
					Total	**476783**

	Quoted rate in figure		
	Quoted rate in words		

Executive Engineer,
S&R Division HPPWD
Chopal

SCHEDULED OF QUANTITY.

Estimated cost Rs. 99960/-
Earnest Money Rs. 2000
Time allowed : One Month

Name of Work: A/R & M/O Sainj Chopal Nerwa Fedujroad km. 20/0 to 90/0 (SH: Patch work in between km.R.D. 77/0 to 82/0).

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Hiring of excavator-cum-loader for removal of slips and dressing of berms etc. including Operator and POL and all carriage of unserviceable material and stacked serviceable material in all leads and as per HPPWD specification of 1990 Vol.I and as per the direction of Engineer in Charge at site, any loss of machinery and loss of land of the adjoining land owners will be born by the supplier/owner at his own risk and cost.	98.00	1020.00	(Rupees one thousand and twenty) only	Per hour	99960
					Total	**99960**

	Quoted rate in figure		
	Quoted rate in words		

Conditions:-

(i) The POL charges shall be borne by the contractor

(ii) All the repair of machinery shall be done by the contractor

(iii) For any minior/major repair or any accident, contractor shall be responsible.

(iv) Any damages or losses to Govt./private property during course of work shall have to be made by the contractor.

Executive Engineer
B&R Division HPPWD
Chopal

(7)

SCHEDULED OF QUANTITY.

376625/-

Estimated cost Rs. ~~340634~~/-
Earnest Money Rs. 8000
Time allowed : One Month

Name of Work: Restoration of rain damages on link road to H.B. Chowkia km. 0/0 to 3/0 (SH: C/o R/wall at R.D. 0/720 to 0/740).

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation for structure as per drawing and technical specifications clause 305.1 i/c setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal up to a lead of 50 metre dressing of side and bottom and back-filling in trenches with excavated suitable materials ordinary soil upto 3.00 metre depth including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	37.50	210.00	(Rupees two hundred ten) only.	Per cubic metre.	7875
2	Providing and laying cement concrete 1:4:8 (one cement four sand eight graded stone aggregate 25mm nominal size) and curing complete excluding the cost of form work in foundation and plinth including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	30.00	5200.00	(Rupees five thousand two hundred) only.	Per cubic metre.	156000
3	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS:280 and IS:4826 in 100x100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications clause 1301 including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	62.50	2900.00	(Rupees two thousand nine hundred) only.	Per cubic metre.	181250
4	P/F PVC pipe weep hole 100 mm dia including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts	15.00	200.00	(Rupees two hundred) only.	Per running metre	3000
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8. (i) Granular material including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in Charge at site in all leads and lifts.	30.00	950.00	(Rupees nine hundred fifty) only.	Per cubic metre.	28500
					Total	376625

	Quoted rate in figure		
	Quoted rate in words		

Executive Engineer
B&R Division HPPWD
Chopal

SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 391300
Earnest Money	Rs. 8000
Time Allowed	One Month

Name of work : R/R damages on Chopal to Kumbra road km 0/00 to 18/300

(SH : C/o wire crated B/wall at RD 13/860 to 13/885)

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious materialand disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	62.50	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre	13125
2	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone agreegate 20mm nominal dia mixing by machenical concrete mixing 0.4/0.28 cubic metre & viberated mechanically so as to give a compressive strength and curring complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	54.50	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre	283400
3	Stone soling properly hand packed filling interies with kharanja stone and consolidation with power road roller to the required gradient and camber including spreading watering and rolling of widding materuials moorum or earth etc including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	4.00	2600.00	Rupees two thousands six hundred and paisa zero only	Per cubic metre	10400
4	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming IS: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	29.09	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre	84375
					Total	391300
	Quoted rate in figure.					
	Quoted rate in words.					

Executive Engineer
B&R Division HPPWD
Chopal