



Office of
Executive Engineer B&R Division HP.PWD, Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Scaled item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 11-07-2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 10-07-2024 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on 09-07-2024-2024 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction of Veterinary Hospital building at Lad Bharol in Tehsil Lad Bharol Distt. Mandi (H.P.) (SH:- Geotechnical Investigation for Safe Bearing Capacity).	Rs.2,25,450/-	Rs.4,500/-	Rs.350/-	Class "D"	One month
2	Construction of Horticulture office cum residence building at Chaunta in Tehsil Joginder Nagar District Mandi (H.P.) (SH:- Geotechnical Investigation for Safe Bearing Capacity).	Rs.1,87,675/-	Rs. 3,800/-	Rs.350/-	Class "D"	One month
3	A/R & M/O Joginder Nagar Sarkaghat Ghumarwin road km. 0/00 to 34/300 (SH:- Providing and fixing L-shape High Mount Gantry Information Display at km. 34/300).	Rs4,99,768/-	Rs.10,000/-	Rs.350/-	Class "D"	Three months
4	Construction of Motorable bridge over Binwa Khad at Bharan with approaches (MLA priority-II for 2022-23) (SH:- Preparation of Detail Project Report (DPR)	Rs.4,15,000 /-	Rs.8,300/-	Rs.350/-	Class "D"	Six months
5	Construction of Sericulture Centre building at Chaunta in Tehsil Joginder Nagar District Mandi (H.P.) (SH:- Geotechnical Investigation for Safe Bearing Capacity).	Rs.1,00,200/-	Rs.2,000/-	Rs.350/-	Class "D"	One month
6	A/R & M/o Baijnath Ladbharol Kandapattan road km. 0/00 to 46/0 (SH:- Providing and fixing L Shape High Mount Gantry Information Display at km. 22/400)	Rs.4,99,768 /-	Rs.10,000/-	Rs.350/-	Class "D"	Three Months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar,
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW/JND-B&R-EA/INIT/Press/2023-24- 3717-66

Dated: 20/06/2024

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (M2), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

Schedule of Quantity

Estimated Cost:- 225450.00
 Earnest Money:- 4500.00
 Time:- One Month

Name of work:- Construction of Veterinary Hospital building at Lad Bharol in Tehsil Lad Bharol District (H.P.)
 (SH: Geotechnical Investigation for Safe Bearing Capacity.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Geotechnical Investigation in manuscript form and submission of the same to higher office for approval. If any correction/ amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - In -charge complete in all respect. After approval the same should be submitted in 3 copies as per conditions of TOR. (Borehole 3 nos. depth upto 9.00 mtr. each) The rate is inclusive all taxes levy by the government time to time excluding GST	27.00			Per Running meter	
					Total:-	

Executive Engineer,
 B & R Division
 H.P. PWD, Joginder Nagar

Assistant Engineer
 Lad Bharol Sub-Division
 H.P. PWD, Lad Bharol

(2)

Schedule of Quantity

Estimated Cost:- 187875.00
Earnest Money:- 3800.00
Time:- One Month

Name of work:- Construction of Horticulture office cum residence building at Chauntra in Tehsil Jogindernagar District (H.P.)
(SH: Geotechnical Investigation for Safe Bearing Capacity.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Geotechnical Investigation in manuscript form and submission of the same to higher office for approval. If any correction/ amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - In -charge complete in all respect. After approval the same should be submitted in 3 copies as per conditions of TOR. (Borehole 3 nos. depth upto 7.50 mtr. each) The rate is inclusive all taxes levy by the government time to time excluding GST.	22.50			Per Running meter	
					Total:-	

Executive Engineer,
B & R Division
HPJWD, Joginder Nagar

73

SCHEDULE OF QUANTITY

Name of Work: A/R & M/O Joginder Ngar Sarkaghat Ghumarwin Road km 0/00 to 34/300
(SH: Providing and fixing L Shape High Mount Gantry Information Display at km 34/300)

Estimate Cost: 4,99,768.00
Earnest Money: 10,000.00
Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing Very High Intensity type 4 (four) (Typically unmetallized microprismatic element) retro reflective Over head Gantry (L-shaped Gantry) for signages system informatory board made of 2mm (two millimeter) thick aluminium sheet conforming to LS 736 of area of information on each side of size 1.2 (one point two) meter x 4.80 (four point eight) meter on both side with a span 6 (six) meter respectively as required as persite to be covered with SCOTTLIGHT/ KIWLIGHT (3m) or equilent with high intensity grade retro reflectorised sheet with colour and design specification of IRC 67 or ASTM D 4956, the retro reflectorised sheet fixed after etaching treatment of aluminium sheet, back of aluminium sheet in smoke grey epoxy paint of standard make the informatory plate fixed in MS angle frame of 32x32x4mm (thirty two by thirty two by four millimeter) and shall fixed with clumps with MS Tube structure of 300 mm (three hundred millimeter) (NB) dia medium weight of ISI Make. The whole structure fixed on a MS Plate of 10 mm (ten millimeter) size 900mmx900mm fixed with 12 (twelve) nos foundation bolt of 25mm (twenty five millimeter) thick 1 (one) meter long fixed in design RCC M-20 (1:2:4) (One cement isto two sand isto four stone aggregate of 10-20mm (two to twenty millimeter)), constructed at site completed in all respect with all leads and lift as per specification within all leads, lifts carriage of material and other incidentials. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
Total						


 Executive Engineer
 B & R Division HP, PWD,
 Joginder Nagar

1892

42

Schedule of Quantity

Estimated Cost:- Rs. 415000.00
Earnest Money:- Rs. 8300.00
Time:- Six months

Name of Work:- Construction of Motorable bridge over Birwa Khad at Bharan with approaches (MLA priority-II for 2022-23)

Sub Head:- Preparation of Detail Project Report (DPR)

Sr. No.	Description of item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Preparation of detailed working estimate of bridge in manuscript shape along with both side approaches complete with approaches drawings such as X-section, Plan, L-section, Retaining walls, Breast walls and other necessary provision taken in the estimate and its checking from competent authority. After the approval of manuscript copy the same should be submitted in five copies duly computerized along with soft copy complete in all respect along with relevant working drawings (Five sets of DPR's and five sets of working drawings complete) of above mentioned DPR's. The rates are including all taxes levy by the Govt. time to time excluding GST.	1,000			Per Job	
					Total	

Executive Engineer,
B&R Division HP, PWD,
Joginder Nagar

(5)
Schedule of Quantity

Estimated Cost:- 100200.00
 Earnest Money:- 2000.00
 Time:- One Month

Name of work:- Construction of Sericulture Centre building at Chauntra in Tehsil Jogindernagar District (H.P.)
(SH: Geotechnical Investigation for Safe Bearing Capacity.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Geotechnical Investigation in manuscript form and submission of the same to higher office for approval. If any correction/ amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - In -charge complete in all respect. After approval the same should be submitted in 3 copies as per conditions of TOR. (Borehole 2 nos. depth upto 6.00 mtr. each) The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00			Per Running meter	
Total:-						


 Executive Engineer,
 B & R Division
 HPI/PWD, Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work: **A/R & M/O Baijnath Ladbharol Kandapatran road km 0/00 to 46/00**
 (SH: Providing and fixing I-Shape High Mount Gantry Information Display at km 22/400)

Estimate Cost: 4,99,768.00
 Earnest Money: 10,000.00
 Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing Very High Intensity type 4 (four) (Typically unmetallized microprismatic element) retro reflective Over head Gantry (L-shaped Gantry) for signages system informatory board made of 2mm (two millimeter) thick aluminium sheet conforming to I.S 736 of area of information on each side of size 1.2 (one point two) meter x 4.80 (four point eight) meter on both side with a span 6 (six) meter respectively as required as per site to be covered with SCOTLIGHT/ KIWLIGHT (3m) or equivalent with high intensity grade retro reflectorised sheet with colour and design specification of IRC67 or ASTM D 4956, the retro reflectorised sheet fixed after etching treatment of aluminium sheet, back of aluminium sheet in smoke grey epoxy paint of standard make the informatory plate fixed in MS angle frame of 32x32x4mm (thirty two by thirty two by four millimeter) and shall fixed with clumps with MS Tube structure of 300 mm (three hundred millimeter) (NB) dia medium weight of ISI Make. The whole structure fixed on a MS Plate of 10 mm (ten millimeter) size 900mmx900mm fixed with 12 (twelve) nos foundation bolt of 25mm (twenty five millimeter) thick 1 (one) meter long fixed in design RCC M-20 (1:2:4) (One cement isto two sand isto four stone aggregate of 10-20mm (two to twenty millimeter)) constructed at site completed in all respect with all leads and lift as per specification within all leads, lifts carriage of material and other incidentials. The rate is inclusive all taxes levy by the government time to time excluding GST.	1.00	Each			
Total						


 Executive Engineer
 B & R Division HP, PWD,
 Jodhpur Nagar