

Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER

Sealed item rate tenders on PWD form 6 & 8 are hereby invited by the Executive Engineer, /-Theog Division, H.P.P.W.D., Theog on behalf of the Governor of HP. for the following works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered /-under the H.P. General Sales Tax Act,1968 so as to reach in this office on or before **04.11.2024 up to 11.00 A.M.** and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on **02.11.2024 up to 4.00 P.M.** and the application for issue of tender form shall be received on **01.11.2024 up to 4.00 P.M.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/ Bank duly pledged in favour of XEN HPPWD. Theog must be accompanied with the application for tender documents. Please note no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 120 days. The Executive Engineer reserves the right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue.

Sr.No	Name of work	Name of Divn.	Estimated cost(Rs.)	Earnest money (Rs.)	Cost of form (Rs)	Time Allowed
1	2	3	4	5	6	
1	Geotechnical investigation for C/o Sr. Sec. School building at Chanair in the state of Himachal Pradesh.	Theog	2,40,900/-	4,818/-	350/-	One Month
2	A/R & M/O PWD rest house at Theog (SH:- C/o R/wall and door shutter in out house etc.)	Theog	3,64,112/-	7,300/-	350/-	One Month
3	R/R damages on Sainj Deha Chopal road km 0/0 to 20/700 (SH:- C/o PCC R/wall at RD 15/020 to 15/035)	Theog	4,07,176/-	8,200/-	350/-	One Month
4	A/R & M/O Rest house building at Theog District Shimla (HP) (SH:- Repair of toilets,painting & distempering etc.)	Theog	4,65,716/-	9,400/-	350/-	One Month
5	A/R & M/O Rest house building at Theog District Shimla (HP) (SH:- Repair of toilets,painting & distempering etc.)	Theog	4,97,680/-	10,000/-	350/-	One Month
6	Balance work of C/O Govt. Sr. Sec. School Sarog Tehsil Theog Distt . Shimla H.P (Block - B)	Theog	4,02,707/-	8,100/-	350/-	One Month
7	R/R of rain damages on various roads under Matiana Sub-Division (SH:- Hiring of JCB for removal of slips in various roads under Matiana Section.)	Theog	99,750/-	2,000/-	350/-	One Month

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

Following documents should accompany the application for tenders: -

- (1) The contractors are required to be produce a copy of their PAN No.GST. NO and should produce a copy of enlistment /renewal letter.
- (2) Special care should be taken to write the rates both in figures and in words failing which tender is likely to be rejected
- (3) The contractor will have to submit the proof of registration Under Employees Provident Fund & Miscellaneous Provision Act 1952 (EPF number) within a month from award of work/contract. Failure to observe this condition shall render the tender of contractor liable to summary rejection.
- (4) The bidder are advised to quote rates inclusive of G.S.T. as applicable notified vide Additional Chief Secretary (PW) to the Govt. of H.P. letter No. PBW(B)C(17)2/2012 dated 07/08/2018 .G.S.T. shall not be paid extra.
- (5) Contractors are allowed to bid only two works, if he bids for more than two works only the first two works in sequence will be considered.



Executive Engineer

"Exigency Certificate"

It is certified that the tenders for various works as called for vide this office letter No. PW/THD/CB/Tender/2024-25 7158-57 dt. 22~~2~~ are of emergent nature in exigency of public interest.

Dated 14th August 2024

Place Theog,


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

SCHEDULE OF QUANTITY


Estimated Cost 240900.00

Earnest Money: 4818.00

Time: 15 Days

Name of work:- Geotechnical Investigation For C/O Sr. Sec. School at Chanair in The State of Himachal Pradesh.

Sr. No.	Description of Item	QTY	Rate in fig.	Rate	Unit	Amount
				Rate in words		
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia for investigation of soil rock conditions at site of work including mobilization and de-mobilization for drilling shifting of machinery to bore site making platform and water arrangement for drilling . The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of material within all leads and lift as per the direction of Engineer-in-Charge.	33.00	7300.00	Rupees Seven Thousand three Hundred Rupees only.	Per running meter	240900.00
Total						240900.00
			Quoted rate in figer+/(%-----)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 364112/
Earnest Money:7300/
Time: One months

Name of Work : AR and M/O to PWD Rest House Theog (SH:- C/O R/wall of and door shutter in out houses etc.)

Sl. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. (Ordinary Soil)	26.60	220.00	Rupees Hundred Only Two Twenty	Per cubic meter	5852
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 25 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	11.81	4550.00	Rupees Thousand Hundred Fifty Only Four Five	Per cubic meter	53736
3	Square rubble masonry with hard stone of approved quality in foundation and plinth including raking of joints in CM 1:6 (1cement 6 sand)with in all leads and lifts of materials with in all leads and lifts as per direction of the Engineer-in-Charge.)	8.09	6507.10	Rupees Thousand Hundred Seven and Paise Ten Only Six Five	Per cubic meter	52642
4	Stone masonry in cement mortar for substructure complete as per drawing and technical specification clause 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:5 including all leads and lifts as per direction of the Engineer-in-Charge.)	39.62	5003.00	Rupees Thousand Only Five Three	Per cubic meter	198219
5	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	28.00	270.00	Rupees Hundred Only Two Seventy	each	7560
6	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	31.05	1050.00	Rupees Thousand Fifty Only One	Per cubic meter	32603
7	Providing wood work in frames of doors, windows clearstory window and other frame wrought framed and fixed inposition 2nd class deodar wood. including all leads and lifts as per the direction of Engineer-in-Charge.	0.048	105000	Rupees One Lakh Five Thousand Only One	Per cubic meter	5040

		1.60	4500.00	Rupees Thousand Hundred Only	Four Five Only	Per square metre	7200
	Providing and fixing panelled glazed or pabelled and glazed shutter for door and window and clearstory windows including brick enamelled iron butt hinges with necessary screw 40 mm thick 2nd class d/wood including all leads and lifts as per the direction of Engineer-in-Charge.	1.60	4500.00				
	Prviding and fixing anodized aluminum slinding door bolt anodized colour tran sparent or dyed to to requird shade and colour with screws etc. complete 300x16mm including all leads and lifts as per the direction of Engineer-in-Charge.	1.00	350.00	Rupees Hundred Only	Three Fifty Only	Per cubic meter	350
0	Providing and fixing aluminum tower bolt anodized transparent to dyed to required colour of shade with necessary screws etc complete 200mm. X10 mm including all leads and lifts as per the direction of Engineer-in-Charge.	2.00	80.00			Each	160
11	Providing and fixing aluminum handels anodized transparent to dyed to required colour of shade with necessary screws etc complete 125 mm. including all leads and lifts as per the direction of Engineer-in-Charge.	2.00	100.00	Rupees Hundred Only	One Only	Each	200
12	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knotting Readymixed paint brushing wood primer pink	3.20	75.00	Rupees Five Only	Seventy	Per square metre	240
13	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping	3.20	97.00	Rupees Seven Only	Ninety	Per square metre	310
							364112
				Quoted rate in figer +/- (%.....)			
				Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

3

SCHEDULE OF QUANTITY

Estimated Cost Rs.407176
Earnest Money:8200/
Time: One months

Name of Work : R/R Damages on Sainj Deha Chopal road km 0/0 to 20/700 (SH:- C/O PCC R/wall at RD 15/020 to 15/035.)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer-in-Charge. all kind of Soil)	57.30	214.10	Rupees Two Hundred Fourteen and Paise Ten Only	Per cubic meter	12268
2	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (1 cement 4 sand : 8graded stone agg. 40 mm nominal size)in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203including all leads and lifts as per direction of the Engineer-in-Charge	84.90	4378.40	Rupees Four Thousand Three Hundred Seventy Eight and Paise Forty Only	Per cubic meter	371726
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer-in -Charge.	45.00	242.15	Rupees Two Hundred Forty Two and Paise Fifteen Only	Each	10897
4	Stone filling behind the retaining wall. all leads and lifts as per direction of the Engineer-in -Charge.	11.70	1050.00	Rupees One Thousand Fifty Only	Per cubic meter	12285
						407176
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.465716
Earnest Money:9400/
Time: One months


4

Work:- A/R & M/O The building of Rest House at theg Distt.Shimla HP.(SH:- Repair of toilets,Painting & Distempering etc.)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Dismantling of tiled floors upto floor two level including stacking of serviceable materials and disposal of un-serviceable materials within 20 metres lead (joists to be measured and paid for separately).	94.60	25.80	Rupees Twenty Five and Paise Eighty Only	P/sqm	2441
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 PCC grade M/o Nominal mix 1:3:6 (Hand Mixing)	3.52	6200.00	Rupees Six Thousand Two Hundred Only	P/cum	21824
3	Providing and laying 1 st classs matt finish spartic ceramic tiles 5.5mm.thick in flooring (300 x300mm. size)treads of steps laid on a bed of 12mm. thick cement mortar 1:3(1cement: 3 sand) finished with flush pointing with pigment to match the shade in toilet of Nitco /Somany or its equivalent including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	26.67	1400.00	Rupees One Thousand Four Hundred Only	Per square metre	37338
4	White glazed tiles 6 mm thick in skirting risers of steps and dado 12 mm thick cement mortar 1:3 (1 cement :3 sand) and jointed with cement slurry.including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	69.90	1450.00	Rupees One Thousand Four Fifty Only	Per square metre	101355

5	Distemping (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper prime including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	797.81	80.00	Rupees Only	Eighty	Per square metre	63825
6	Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on decorated wall surfaces (one coat) to give an even shade after thoroughly brushing the surface to remove all dirt, loose or softened paint including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	188.19	105.00	Rupees Hundred Only	One Five	Per square metre	19760
7	15mm Cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	173.80	255.00	Rupees Hundred Five Only	Two Fifty	Per square metre	44319
8	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete. including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	374.40	93.00	Rupees Three Only	Ninety	Per square metre	34819

9	Painting two coats (excluding priming cost on new steel and other metal surfaces eith enamel paint brushin to give an even shade including cleaning the surface of all dirt,dust and other foregin matters Enamel paint other than white including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	92.00	65.00	Rupees Sixty Five Only	Per square metre	5980
10	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including leaning the surface of dirt,dust and other foreign matter,sand papering & stoping With enamel paint other than white including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	1175.04	75.00	Rupees Seventy Five Only	Per square metre	88128
11	Polishing two coats with french polish on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt,dust,and sand papered smooth and including a coat of wood filler. including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	306.18	150.00	Rupees Hundred Only	Per square metre	45927
		Quoted rate in figer +/- (%.....)				
		Quoted rate in words				
				465716		


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

5

SCHEDULE OF QUANTITY

Estimated Cost Rs.497680

Earnest Money:9500/

Time: One months

name of work:- A/R & M/O The building of Rest House at theog Distt.Shimla HP.(SH:- Repair of toilets,Painting & Distempering, water tank stand etc.)

S. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out ,construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 mtr.dressing of sides and bottom and back filling in trenches with excavated suitable material including all leads and lifts as per direction of the Engineer -in -Charge.	1.44	280.00	Rupees Two Hundred Eighty Only	P/cum	403
2	Providing and laying cement concrete work 1:2:4 (1 Cement:2 Sand:4 graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in including all leads and lifts as per direction of the Engineer -in -Charge.	1.44	7200.00	Rupees Seven Thousand Two Hundred Only	P/cum	10368
3	Providing and fixing ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately)12mm thick ply including all leads and lifts as per direction of the Engineer -in -Charge.	101.81	600	Rupees Six Hundred Only		61086
4	Providing and fixing pine wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately)including all leads and lifts as per direction of the Engineer -in -Charge.	101.81	1600	Rupees One Thousand Six Hundred Only	P/sqm	162896

5	Providing and fixing Polyethelene-AluminiumPolyethelene PE-AL-PE Composite Pressure Pipes conforming to IS - 15450, U.V. stabilized with carbon black having thermal stability for hot & cold water supply, capable to withstand temperature up to 80°C, including all special fittings of composite material (engineering plastic blend and brass inserts wherever required) e.g. elbows, tees, reducers, couplers & connectors etc., with clamps at 1.00 metre spacing. This includes the costs of cutting chases and including testing of joints complete as per direction of the engineer in charge.	99.3	350	Rupees Three Hundred Only	P/Rmt	34755
1	100mm nominal size	12.4	400	Rupees Four Hundred Only		4960
2	75 mm nominal size	20.12	350	Rupees Three Hundred Only	P/Rmt. Each	7042
	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. complete.(i)150mmincluding all leads and lifts as per direction of the Engineer -in -Charge.					
	100mm nominal size	24	150	Rupees One Hundred Only	Each	3600
	75 mm nominal size	24	100	Rupees One Hundred Only	Each	2400
	Providing and fixing PVC bend ISI marked including fixing with approved adhesive etc. complete.including all leads and lifts as per direction of the Engineer -in -Charge.					
	With oval access door insertion rubber washer 3mm thick bolts and nuts complete:					

1	100mm nominal size	4	180	Rupees One Hundred Eighty Only	Each	720
2	75 mm nominal size	4	125	Rupees Hundred Twenty Five Only	Each	500
	Single equal branch of required degree:					
	With oval access door insertion rubber washer 3mm thick bolts and nuts complete:					
1	100mm nominal size	3	220	Rupees Hundred Twenty Only	Each	660
2	75 mm nominal size	3	190	Rupees One Hundred Ninety Only	Each	570
	Single equal branch of required degree:					
	Plain					
1	100mm nominal size	3	200	Rupees Two Hundred Only	Each	600
2	75 mm nominal size	3	180	Rupees One Hundred Eighty Only	Each	540
	Collar :					
1	100mm nominal size	32	100	Rupees One Hundred Only	Each	3200
2	150mm nominal size	32	80	Rupees Eighty Only	Each	2560
	Providing and fixing cast iron floor trap of self cleaning design with sand cast iron screwed down or hinged grating with out vent arm complete including cost of cutting and making goods the walls and floors including all leads and lifts as per direction of the Engineer - in -Charge.					

	100mm	4	220	Rupees Hundred Twenty Only	Two	Each	880
13	Providing and fixing 100 mm dia chromium plated grating of superior quality for floor, gully or nahani trap including all leads and lifts as per direction of the Engineer -in -Charge.	8	80	Rupees Eighty Only	Each	Each	640
14	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required including all leads and lifts as per direction of the Engineer -in -Charge.						
15	W.C. pan with ISI marked white solid plastic seat and lid	4	16000	Rupees Sixteen Thousand Only	Each	Each	64000
	Providing and fixing vitreous China wash basin with pedestal no. 10054 of Hindware with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings including all leads and lifts as per direction of the Engineer -in -Charge.						
	Flat back						
	630mmx450mm	4	2000	Rupees Two Thousand Only	Each	Each	8000
	oval wash basin no. 10016 below counter top (ivory white)						
16	Providing and fixing vitreous China pedestal for wash basin complete recessed at the back for the reception of pipes and fittings including all leads and lifts as per direction of the Engineer -in -Charge.						
17	Providing and fixing M.I. Union for wash basin or sink including all leads and lifts as per direction of the Engineer -in -Charge.						
	32mm dia	4	50	Rupees Fifty Only	Each	Each	200

18	Providing and fixing C.P. Brass waste for wash basin or sink including all leads and lifts as per direction of the Engineer -in - Charge.	4	80	Rupees Eighty Only	Each	320
19	32mm dia P/F PVC waste pipe 32mm nominal size including all leads and lifts as per direction of the Engineer -in -Charge.	4	100	Rupees One Hundred Only	Each	400
20	Providing and fixing charomium plated brass soap dish cat no. 907 (wall mounted) of ess. Ess. with C.P. Brass brackets fixed to wooden cleats with C.P. Brass screws.including all leads and lifts as per direction of the Engineer -in -Charge.	8	120	Rupees One Hundred Twenty Only	Each	960
21	Providing and fixing liquid soap container with C.P. Brass lid and brackets fixed to wooden plugs with C.P. Brass screwsincluding all leads and lifts as per direction of the Engineer -in -Charge.	4	500	Rupees Five Hundred Only	Each	2000
22	Providing and fixing toilet paper holder CP Brass including all leads and lifts as per direction of the Engineer -in -Charge.	4	350	Rupees Three Hundred Fifty Only		1400
23	Providing and fixing P.V.C connection with brass unions.including all leads and lifts as per direction of the Engineer -in -Charge.					
	300/450mm length :-					
	15mm nominal bore	20	200	Rupees Two Hundred Only	Each	4000
24	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931including all leads and lifts as per direction of the Engineer -in -Charge.	32	700	Rupees Seven Hundred Only	Each	22400
25	Providing and fixing C.P Brass bib tap with Capstan head including all leads and lifts as per direction of the Engineer -in - Charge.	12	650	Rupees Six Hundred Fifty Only	Each	7800

6	Providing and fixing C.P Brass pillar tap with Capstan head including all leads and lifts as per direction of the Engineer -in - Charge.	4	1000	Rupees One Thousand Only	Each	4000
	15mm dia , Swan neck					
7	Providing and fixing PTMT jet spray of approved quality and colour with 1.5 mtr. tube.including all leads and lifts as per direction of the Engineer -in -Charge.	4	400	Rupees Four Hundred Only	Each	1600
8	Providing and fixing 600mm x 450 mm bevelled edge mirror of superior glass mounted on 6mm thick A.C. Sheet or plywood sheet and fixed to wooden plugs with C.P. Brass screws and washers. including all leads and lifts as per direction of the Engineer -in - Charge	4	900	Rupees Nine Hundred Only	Each	3600
9	Providing and fixing 600mm x 120 mm glass shelf with C.P. Brass bracket and guard rail complete, fixed to wooden pluges with C.P. Brass screws. including all leads and lifts as per direction of the Engineer -in -Charge	4	680	Rupees Six Hundred Eighty Only	Each	2720
0	Providing and fixing C.P. Brass Towell rail cat no. 907 ess.ess. complete with C.P. Brass brackets fixed to wooden pluges with C.P. Brass screws including all leads and lifts as per direction of the Engineer -in -Charge					
	600mm x 20mmm	4	700	Rupees Seven Hundred Only	Each	2800
1	Providing and fixing PVC water storage tank of ISI : 12701 marked,G.I. inlet and outlet connection, 15mm nominal bore ball valve and mosquito proof PVC cover with locking arrangement including hoisting upto all heights above ground level :- 2000 Lit.capacity including all leads and lifts as per direction of the Engineer -in -Charge.	2	17600	Rupees Seventeen Thousand Six Hundred Only	Each	35200

SCHEDULE OF QUANTITY

Estimated Cost Rs.402707


Earnest Money:8100/

Time: One months

Balance work of C/O Govt. Sr. Sec.School Sarog Tehsil Theog Distt. Shimla H P(Block-B)

Sl. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Providing and fixing multipurpose partical board ceiling of approved quality with butt jointing and nail (frame work and cover fillets to be paid for separately.Particle board (bwp phenol bonded exterior/interior grade) 6 mm thick.including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	117.3	650.00	Rupees Hundred Fifty Only	Per square metre	76245
2	15mm cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering upto floor two level including arrises.internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. Cement mortar 1:6 (1 cement:6 and).including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	321.24	300.00	Rupees Hundred Only	Per square metre	96372
3	15mm cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering upto floor two level including arrises.internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. Cement mortar 1:4 (1 cement:4 and).including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	251.34	320.00	Rupees Hundred Only	Per square metre	80429
4	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete. including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	672.58	110.00	Rupees Hundred Ten Only	Per square metre	73984
5	Distemping (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	507.63	90.00	Rupees Ninety Only	Per square metre	45687

6	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equariled on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	259.14	110.00	Rupees Hundred Ten Only	One	28505
7	Painting two coats (excluding priming cost on new steel and other metal surfaces either enamel paint brushin to give an even shade including cleaning the surface of all dirt, dust and other foregin matters Enamel paint other than white including carriage of Material with in all leads and lifts as per the direction of Engineer-in-charge	27	55.00	Rupees Only	Five	1485
		Quoted rate in figer +/- (%.....)				
		Quoted rate in words		402707		



 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Name of work:-(1)R/R damages on Various Roads in Matiana Sub Division(SH: Hiring of J.C.B for removal of slips in various Road Matiana Section)

Estimate Cost 99750.00
 Earnest Money 2000.00
 Time one Month

Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of J.C.B(Excavator-Cum-Loader) including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work, pick work, Jumper work, soft rock, hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of snow shall have to be neatly stacked along road side on road burms. Minimum 20 cubic meter of snow work shall be done by machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	95.00	1050.00	Rupees one thousand & fifty only	Per hour	99750.00
	Total					99750.00
		Quoted Rates in fig.				
		Quoted Rates in words				


 Executive Engineer
 Theog Division
 HP PWD Theog