




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS,
AS CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2023-
24/- 13727-35 DATED 29-11-2024 ARE URGENT
NATURE AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:- ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **17.12.2024** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **16.12.2024 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **13.12.2024 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimate least	Earnest Money	Cost of tender form	Time limit
1	Repair of Rain Shed Paprola Utrala Road km 0/015 (SH: Dismantling G.I sheet Roofing, P/L Preapainted G I Sheet Roofing, Tiles work, White washing Cement Plaster etc.)	Rs.1,10,385/-	Rs.2,300/-	Rs.350/-	Two Months
2	C/O Kothikohar Khad bridge, Barot Bridge on Barot Nalotha road km 0/00 to 15/500 (SH: Providing 25mm thick Mastic Asphalt over Barot Bridge, Kothikohar Khad Bridge at 10/400)	Rs.4,16,238/-	Rs.8,400/-	Rs.350/-	Two Months
3	C/O Uhl Khad bridge on Bir Barot road km. 0/00 to 48/00 (SH: Providing 25mm thick Mastic Asphalt over Uhl Khad Bridge at 28/525)	Rs.2,30,174/-	Rs.4,600/-	Rs.350/-	Two Months
4	C/O Chaugan to Village Chougan road km 0/00 to 1/165 (SH: C/O V-Shape Drain at RD 0/555 to 0/605 & 0/825 to 0/900 and Edge wall at RD 0/925 to 0/940)	Rs.1,37,479/-	Rs.2,800/-	Rs.350/-	Two Months
5	Construction of Link Road Bhadar Singh Gharat to Shiv Mandir Dhampani (SH: Improvement of curves Cutting in earth work in various reaches)	Rs.4,92,169/-	Rs.9,900/-	Rs.350/-	Two Months
6	Repair and Maintenance of Rest House Chadhiar (SH: C/O Civil work Gate and W S and S.I installation)	Rs.2,46,250/-	Rs.5,000/-	Rs.350/-	Two Months
7	Repair and Maintenance of HPBOSE Book distribution centre Paprola at Taragarh (SH: Painting, Distemping, Plastering, Plaster of Patches S/F Glass Panes etc.)	Rs.3,24,325/-	Rs.6,500/-	Rs.350/-	Two Months
8	C/O Pucca Path from Jaswant Lagwal to Ishwar Das House (SH: P/L 40mm thick Paver Block at Km 0/00 to 0/055) SDP/2024/829	Rs.98,970/-	Rs.2,000/-	Rs.350/-	Two Months
9	C/O link road from Doli Khurad Chordu Dangore km 0/00 to 4/900 (SH: P/L G-I at km 3/615 to 3/815 and 3/913 to 4/125 & C.C. Pavement at km 4/075 to 4/125)	Rs.4,98,988/-	Rs.10,000/-	Rs.350/-	Two Months
10	C/O Dharer to Kandkosri road km 0/00 to 4/00 (SH: P/L G-II For profile correction & C.C. Pavement at k 0/170 to 0/245 and 0/470 to 0/530)	Rs.4,90,036/-	Rs.9,900/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.

E.E.

4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Bajjnath Division.,
H.P.PWD..Bajjnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2024-25/- 13727-35

Dated:- 29.11.2024

- 1 Copy to the F.C.Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Bajjnath Division.,
H.P.PWD..Bajjnath.

DNIT/DRAFT SCHEDULE OF QUANTITY

① (a)

Name of Work : - Repair of Rain Shed Paprola Utrala Road km 0/015 .

(Sh:- Dismantling G.I sheet Roofing , P/L Prepainted G I Sheet Roofing, Tiles work , White washing Cement Plaster etc)

Estimate Cost: 1,10,385.00


Earnest Money: 2300.00

Time Limit : Two Months

SCHEDULE OF WORKS

Sl. No.	Description of work	No.or Qty.	Unit	Rates		AMOUNT Rs. P
				Figures	Words	
1	Dismantling G.I. Sheet roofing including ridges, hips, valleys, gutters etc. stacking the serviceable materials and disposal of un-serviceable materials within 20 metres lead. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	31.50	Per Square metre			
2	Providing and fixing pre-painted sheet roofing of kotar metal single skin trapezoidal sheeting 0.60mm (sixty millimetre) thickness having 1060mm (one thousand sixty millimetre) cover width cover all width 1126mm (one thousand one hundred twenty six millimetre) , 28mm (twenty eight millimetre) crest depth at 353mm (three hundred fifty three millimetre) 2.50mm (two point fifty millimetre) the main crest with at top 25mm (twenty five) and at lower 81mm (eighty one millimetre) base metal of coil rolled steel coil with zinc waiting top coat with regular modified polysters coating of approved shade and balancing reverse coat with self topping screws 5.5mm (five decimal five millimetre) dia and 55mm (fifty five millimetre) length with EPDM seal complete in all respect as per approved drawing design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	31.50	Per square metre			
3	Providing and fixing plain M.S. B.P. sheet 1.66mm (one decimal sixty six millimetre) thick to 2.00mm in evels board/ Facia / Soffit / Ceilling including cutting fixing jointing with gass/electric welding to steel roofs members and applying a coat of red lead primer complete as per PWD specification (frame work is to be measured paid for separately). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	16.48	Per square metre			
4	Providing and fixing pre-painted sheet ridge or hips 60cm (sixty centimetre) over all of kotar metal skin trapezoidal profiled sheeting 0.60mm (zero point sixty centimetre) cover with over all width 1126mm (one thousand one hundred twenty six) 28mm (twenty eight) crest depth at 353mm (three hundred fifty three) 2mm (two millimetre) C/C crest distance. There will be two ribs at the centre for stiffening heaving crest depth of 2.50mm (two point five millimetre) the main crest with at top zinc waiting top coat with regular modified polyster coating of approved shade and balancing reverse coat 5.5mm (five decimal five millimetre) dia and 55mm (fifty five millimetre) length with EPDM seal complete in all respect as per approved drawing design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.50	Per running metre			

5	Kota stone slab 25 mm thick cement mortar 1:3 (1 cement :3 sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs including rubbing and polishing 20 cm flagged stone flooring laid in cement mortar 1:5 (1 cement :5 sand) The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	14.16	Per square metre			① (6)
6	Kota stone slab 25 mm thick in risers of steps,skirting dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement :3 sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs including rubbing and polishing 20 cm flagged stone flooring laid in cement mortar 1:5 (1 cement :5 sand) The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.96	Per square metre			
7	White washing with lime on undecorated wall surfaces two coats to give an even shade including thoroughly brooming the surface to remove all dirt dust mortar dirt and other foreign matter. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	13.96	Per square metre			
8	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises,internal rounded angles,chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth Cement Mortar 1:6 (one Cement:six Sand). . The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	10.80	Per square metre			


 Executive Engineer
 Baijnath Division,
 H.P.P.W.D. Baijnath (H.P.)

DNIT/DRAFT SCHEDULE OF QUANTITY

2

Name of Work: -C/O Kothikohar Khad bridge , Barot Bridge on Barot Nalotha road km 0/00 to 15/500
(Sh: -Providing 25 mm thick Mastic Asphalt over Barot Bridge, Kothikihar Khad Bridge at 10/400)

Estimate Cost: 4,16,238.00

Earnest Money: 8,400.00

Time Limit : Two Months

SCHEDULE OF WORKS

Sl. No.	Description of work	No.or Qty.	Unit	Rate to be entered by the Bidder in		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying bitumen mastic wearing course (as per specifications) with industrial bitumen of grade 85/25 conforming to IS:702, prepared by using mastic cooker and laid to required level and slope, including providing antiskid surface with bitumen precoated fine grained hard stone chipping of approved size at the rate of 0.005 cum per 10 sqm and at approximate spacing of 10 cm centre to centre in both directions, pressed into surface protruding 1 mm to 4mm over mastic surface, including cleaning the surface, removal of debris etc. all complete.(Considering bitumen using 10.02% as per MORTH specification).25 mm thick.	259.50	Sqm			

Executive Engineer
Bajnath Division,
H.P.P.W.D. Bajjnath (H.P.)

DNIT/DRAFT SCHEDULE OF QUANTITY

3

Name of Work: -C/O Uhl Khad bridge on Bir Barot road Km 0/00 to 48/00
(Sh: -Providing 25 mm thick Mastic Asphalt over Uhl Khad Bridge at 28/525)

Estimate Cost: 2,30,174.00
Earnest Money: 4,600.00
Time Limit : Two Months

SCHEDULE OF WORKS

Sl. No.	Description of work	No.or Qty.	Unit	Rate to be entered by the Bidder in		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying bitumen mastic wearing course (as per specifications) with industrial bitumen of grade 85/25 conforming to IS:702, prepared by using mastic cooker and laid to required level and slope, including providing antiskid surface with bitumen precoated fine grained hard stone chipping of approved size at the rate of 0.005 cum per 10 sqm and at approximate spacing of 10 cm centre to centre in both directions, pressed into surface protruding 1 mm to 4mm over mastic surface, including cleaning the surface, removal of debris etc. all complete.(Considering bitumen using 10.02% as per MORTH specification). 25 mm thick.	143.50	sqm			

Executive Engineer
Bajnath Division,
H.P.P.W.D. Bajjnath (H.P.) 3/

DNIT/DRAFT SCHEDULE OF QUANTITY

(4)

Name of Work : C/O Chaugan to Village Chaugan road km 0/00 to 1/165 . (S H : C/O V-shape Drain at RD 0/555 to 0/605 & 0/825 to 0/900 and Edge wall at RD 0/925 to 0/940)				Estimate Cost: 1,37,479.00/- Earnest Money: 2,800.00/- Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	20.31	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M tcn) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	23.29	Per cubic metre			
Total						

Executive Engineer
Bajjnath Division,
H.P.P.W.D. Bajjnath (H.P.)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction of Link Road Bhadar singh Gharat to Shiv Mandir Dhampani . (SH: Improvement of curves Cutting in earth work in various reaches)				Estimate Cost: 4,92,169.00/- Earnest Money: 9900.00/- Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 49.80 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work excuted. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost.	2345	Per Cubic metre			
Total						

Executive Engineer
Bajjnath Division,
H.P.P.W.D. Bajjnath (H.P.)

DNIT/DRAFT SCHEDULE OF QUANTITY

6(a)

Name of Work : - Repair and Maintenance of Rest House Chadhiar.
(Sub Head : C/O Civil work Gate and W S and S.I installation).

Estimate Cost: 2,46,250.00

Earnest Money: 5,000.00

Time Limit : Two Months

Sl. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Demolition of R.B. Work above G.L. upto floor two level including disposal of unserviceable materials within 20 metres lead and including cutting the necessary reinforcement and separating out from R.C.C. /R.B. Works The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	0.45	Per cubic metre			
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven Point Five) in foundations and plinth in :cement mortar 1:4 (one cement : four coarse sand) The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	10.54	sqm			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.45	Per cubic metre			
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	54.00	kg			
5	Providing and fixing stainless steel kitchen sink 610 x460 mm (six hundred ten into four hundred sixty millimeter) with bowl depth 200 mm (two hundred millimeter) size of approved standard ISI make with drain board and C.P. waste with C.I. or M.S. Brackets painted white including cutting holes and making good the same but excluding fitting. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.00	Each			
6 a	Providing and fixing 15mm (Fifteen milimetres) diameters C.P. brass bib tap of ESS-ESS / Cera / Hindware with capstan head, within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	2.00	Each			
6 b	Providing and fixing C.P. brass pillar tap of ESS-ESS / Cera / Hindware with capstan head 15mm (fifteen millimetre) dia (Heavy duty makes ISI marked No. 8931 & 8934) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.00	Each			
7	Providing and fixing 32mm (Thirty two millimetres) diameters C.P. brass waste ESS-ESS (Heavy duty make ISI marked NO-8931 & 8934) for wash basin or sink. Within all leads, lifts of materials and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.00	Each			

8	Providing and fixing on wall face PVC (D-plast) rain water pipes of working pressure not less than 4.5 kg (four decimal five kilogram) per square meter including filling the joints with approved adhesive complete 100 mm (one hundred millimeter) dia. including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	4.00	Per running metre			5(b)
9	Providing and fixing Gizer of 10 ltr water capacity of approved brand complete in all fittings and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.00	Each			
10	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mited and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	38.61	kg			
11	Providing and fixing glazing in aluminium door, window, ventilator shutters and partition etc with PVC/neoprens gasket etc. complete as per the architectural drawings and the directions of Engineer-In charge (cost of aluminium snap beading shall be paid in basic item.) Glazing with glass panes of 5.50mm thickness (weight not less than 13.75 kg/ sqm. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	2.80	sqm			
12	Providing and fixing 100 mm (hundred milimeter) diameter Cast iron floor trap of self cleaning design with sand cast iron screwed down or hinged grating without vent arm complete including cost of cutting and making goods the walls and floors including carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.00	Each			
13	Providing and fixing Utensil stand of approved brand complete in all fittings and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.00	Each			
14	Providing and fixing canealed C.P. stop cock of ESS-ESS 15mm (fifteen millimetre) dia (Heavy duty makes ISI marked No. 8931 & 8934) including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	3.00	Each			
15	Providing and fixing C PVC pipe of approved brand complete in all fittings and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	20.00	Rmt			

16	Providing and fixing Exhaust Fan of approved brand complete in all fittings and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.00	Each			60
17	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position in beams, joists, channels, angles, tee, flats with connecting plates or angle cleats as in straps, wall ties, inserts, knee pieces and similar works, including cutting, hoisting, fixing in position & applying a priming coat of red lead paint complete including entire carriage of materials within all leads and lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	550.00	Per kg			
18	Providing and laying granite stone in flooring 20mm (twenty millimeter) (average) thickness base of cement mortar 1:3 (one cement to three sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of granite stone i/c rubbing and polishing complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.40	Per square metre			
19	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero point zero eight) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimeter) thick cement mortar 1:4 (one cement : four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three kilogram square metre) including grouting the joints with white cement and matching pigments etc., complete Size of Tile 600x600 mm (six hundred into six Hundred) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	15.78	sqm			
20	White glazed tiles 6 mm thick in skirting risers of steps and dado 12 mm thick cement mortar 1:3 (1 cement : 3 sand) and jointed with cement slurry The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	29.46	Per square metre			
21	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	45.65	sqm			
22	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	21.60	sqm			

23	Providing and fixing 40 mm (Forty millimetre) thick second class Deodar wood wire gauge shutters using galvanised MS wire gauge of IS gauge designation 85G with wire of dia 0.56 mm (Zero decimal five six millimetre) for doors, windows and clearstory windows including bright finished black enamelled iron hinges with necessary screws as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	2.00	Per square metre			⑥ (d)

Executive Engineer
 Baijnath Division,
 H.P.P.W.D. Baijnath (H.P.)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - Repair and Maintenance of HPBOSE Book distribution center Paprola at Taragarh
(Sub Head : Painting , Distemping , Plastering , Plaster of Patches S/F Glass Panes etc).

Estimate Cost: 3,24,325.00
Earnest Money: 6500.00
Time Limit : Two Months

(7/a)

SCHEDULE OF WORKS

Sl. No.	Description of work	No.or Qty.	Unit	Rates		AMOUNT Rs. P
				Figures	Words	
1	Painting two or more coats(excluding priming costs) on new steel and other metal surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	464.33	Per square metre			
2	Applying a priming coat over on new steel and other metal surfaces after and including preparing the surface by thoroughly cleaning, oil, grease, dirt and other foreign matter, sand papering and knotting with ready mixed paints brushing on new steel and other metal surfaces as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	327.17	Per square metre			
3	Painting two coats (excluding priming coat) on new wood and wood based surfaces, with readymixed paint other than white, brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	499.64	Per square metre			
4	Painting one coat (excluding priming coat) on previously painted steel and other metal surfaces with enamel paint other than white brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	22.64	Per square metre			
5	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	92.34	Per square metre			
6	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equalised on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	287.81	Sqm			
7	Distemping (two coats) with synthetic washable distemper of Asian/ Nerolac brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including and priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	983.40	Per square metre			

8	Repairs to plaster in patches of 2.50 Sq.M. (Two point five square meter) and under and 10 to 15mm (ten to fifteen millimeter) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 metres (twenty meter) with Cement Mortar 1:6 (one Cement isto six Sand) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	92.34	Per square metre				7(b)
9	Supplying and fixing 4mm (four millimeter) thick Plain glass panes with putty and nails including removal of broken glass panes wherever necessary The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.95	Per Square metre				


 Executive Engineer
 Baijnath Division
 H.P.R.W.D., Baijnath

D.N.I.T/ SCHEDULE OF QUANTITY

Name of work :- C/O Pucca Path from Jaswant Lagwal to Ishwar Das House

(Sh:- P/L 40mm thick Paver Block at Km 0/00 TO 0/055). SD P/2024/829

Estimated Cost: Rs.

98970.00

Earnest Money: Rs.

2,000.00

Time Limit :

Two Month

SCHEDULE OF WORKS

Sr No.	Description of work	No.or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:4:8 stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	2.52	Cum			
2	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC Grade M-20 Nominal Mix 1:2:4 (one cement : two sand; four aggregate) per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.88	Cum			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Chage 40mm thick cement concrete paver block of M-35 grade with approved colour, design & pattern.The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	55.00	Sqm			
TOTAL						

Executive Engineer
Bajinath Division,
H.P.P.W.D. Bajinath (H.P.)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O link road from Doli Khurad Chordu Dangore km 0/00 to 4/900 .

(SH:- (SH:-P/L G-I at km 3/615 to 3/815 and 3/913 to 4/125 & C. C Pavement at km 4/075 to 4/125)

Estimate Cost: 4,98,988.00/-

Earnest Money: 10,000.00/-

Time Limit :Two Months

9

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
					Words	
1	Providing and Laying, spreading and compacting stone aggregates size 90mm to 45 mm (Ninety millimeter to forty five millimeter) grading-I (100 mm Consolidated thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming. Crushable type such as Moorum or Gravel for grading-I @ 0.30 cum per ten square meter and binding material at the rate of 0.08 cum (Zero point zero eight cubic meters) per ten Sqm (ten square meters) to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading II as per MORD technical specification clause no 405 complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.	138.43	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	20.01	Per Cubic metre			
Total						

Executive Engineer

Bajnath Division,

H.P.W.D. Bajnath (H.P.)

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Dharer to Kandkosri road km 0/00 to 4/00 .

(SH:-P/L G-II For profile correction & C. C Pavement at km 0/170 to 0/245 and 0/470 to 0/530)

Estimate Cost: 4,90,036.00/-

Earnest Money: 9,900.00/-

Time Limit :Two Months

10

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
					Words	Rs.	P
1	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the intersitices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	17.44	Per Cubic Metre				
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	62.78	Per Cubic metre				
Total							

Executive Engineer
Bajnath Division,
H.P.P.W.D. Bajinath (H.P.)