



Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail: ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed Item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 11.12.2024 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 09.12.2024 up to 10.00 A.M. to 12:30 P.M. and tender form can be had from this office on 10.12.2024 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction of Pipal Galu to Lower Batnagar in G.P. Batnagar in G.P. Nauhli under Deposit SID: BSP/2024/186 (SH:- Providing and laying of wearing G-II & Cement Concrete pavement from Km. 0/090 to 0/139).	Rs. 1,67,141/-	Rs. 3,300/-	Rs. 350/-	Class "D"	Three Months
2	Construction of road from Joginder Nagar Arthi road to Harizan Basti Garoru Km. 0/0 to 1/500 (SH:- Construction of RCC Hume Pipe culvert along with both side wing wall at km. 0/130).	Rs. 2,37,987/-	Rs. 4,800/-	Rs. 350/-	Class "D"	Three Months
3	Construction of road from Joginder Nagar Arthi road to Harizan Basti Garoru Km. 0/0 to 1/500 (SH:- Construction of RCC Hume Pipe culvert along with both side wing wall at km. 0/250).	Rs. 2,38,981/-	Rs. 4,800/-	Rs. 350/-	Class "D"	Three Months
4	Construction & M/T on Link road Gayola Harizan Basti Kass to Kumharda road km. 0/0 to 1/700 (SH:-Construction of Breast wall/Protection wall at km.1/357 to 1/377).	Rs. 2,99,942/-	Rs. 6,000/-	Rs. 350/-	Class "D"	Three Months
5	Construction & M/T on Link road Gayola Harizan Basti Kass to Kumharda road km. 0/0 to 1/700 (SH:-Construction of RCC Hume Pipe Culvert along with both side wing wall at km. 1/450).	Rs. 2,20,053/-	Rs. 4,400/-	Rs. 350/-	Class "D"	Three Months
6	Construction & Maintenance of road from Kothi to Basoa Rihra km. 0/0 to 1/500 under SCSP (SH:- Providing and Laying soling Grade-I, 90mm to 45mm size from km. 0/900 to 1/500).	Rs. 4,95,048/-	Rs. 9,900/-	Rs. 350/-	Class "D"	Three Months
7	Construction of Harizan Basti Ahju link road km. 0/0 to 3/0 under SCSP (SH:- Providing and Laying soling Grade-I from km. 2/750 to 3/00).	Rs. 1,91,048/-	Rs. 3,300/-	Rs. 350/-	Class "D"	Three Months
8	Construction of link road Harizan Basti Sandral to Bhattu Muhal under Deposit SDP/2024/2010 for Rs. 1.50 lac. (SH:- Hiring of excavator cum loader for construction of road).	Rs. 1,48,050/-	Rs. 3,300/-	Rs. 350/-	Class "D"	One month
9	Construction of C.C. link road NH Mohanghatti towards Bag road km. 0/0 to 0/400 under MGNREGA (SH:- Supplying and Stacking of crushed stone aggregate 20mm, coarse sand and boulder).	Rs. 2,09,778/-	Rs. 4,200/-	Rs. 350/-	Class "D"	Three Months
10	Construction of concrete road Main road se Hariyali side under MGNREGA (SH:- Supplying and Stacking of crushed stone aggregate 20mm, coarse sand and boulder).	Rs. 2,09,778/-	Rs. 4,200/-	Rs. 350/-	Class "D"	Three Months
11	Construction of 19.75 mtr span bridge at RD. 7/200 over Nagdyara Nallah on Machhyal Bhararu Bihun road under SCSP (SH:- Providing and laying soling Grade-I, wearing Grade-II and tarring on approaches).	Rs. 3,46,632/-	Rs. 4,700/-	Rs. 350/-	Class "D"	Three Months
12	Restoration of rain damages on Joginder Nagar Sarkaghat Gumarwin road Km. 0/0 to 34/300 (Sub Head:- Construction retaining wall at Km. 16/450 to 16/465)	Rs. 1,98,489/-	Rs. 4,000/-	Rs. 350/-	Class "D"	Three months
13	Restoration of rain damages on link road to Harizan basti Pohli Km. 0/0 to 1/500 under SCSP (Sub Head:- Construction of Breast wall for portion sinking portion in Km. 0/350 to 0/370)	Rs. 2,58,654/-	Rs. 5,200/-	Rs. 350/-	Class "D"	Three months

14	Construction of Arthi Suri Majharnoo road Km. 0/0 to 2/0 (Sub Head:- Improvement of formation width by providing retaining wall at Km. 1/205 to 1/220)	Rs. 2,07,302/-	Rs. 4,100/-	Rs. 350/-	Class "D"	Three months
15	Restoration of rain damages on Ahju Matroo road Km. (Sub Head:- Construction of Breast wall at Km. 1/585 to 1/593).	Rs. 94,197/-	Rs. 1,900/-	Rs. 350/-	Class "D"	Three months
16	Restoration of rain damages on Ahju Matroo road Km. (Sub Head:- Construction of Breast wall at Km. 1/595 to 1/603).	Rs. 93,919/-	Rs. 1,900/-	Rs. 350/-	Class "D"	Three months
17	Special repair to State level Revenue Training Institute at Joginder Nagar (SH: Providing and Fixing in Boys hostel, Girls Hostel and Admin Block)	Rs. 53,603/-	Rs. 11,00/-	Rs. 350/-	Class "D"	Two months
18	Repair and maintenance of Drubbal to Harizan Basti Basoti Ropru road Km. 0/0 to 1/500 (SH:- Construction of breast wall at Km. 0/475 to 0/490 (under Head repair & maintenance of road under SCSP).	Rs. 2,01,398/-	Rs. 4,000/-	Rs. 350/-	Class "D"	Three months
19	Repair and maintenance of Drubbal to Harizan Basti Basoti Ropru road Km. 0/0 to 1/500 (SH:- Construction of retaining wall at Km. 0/470 to 0/480 & 0/490 to 0/505 (under Head repair & maintenance of road under SCSP).	Rs. 3,58,824/-	Rs. 7,200/-	Rs. 350/-	Class "D"	Three months
20	Construction of link road village Sajehar to Khajri Panara GP. Nauhli Km. 0/0 to 1/500 (SH:- ROFD in Km. 0/0 to 0/217 under Head MMGSY)	Rs. 4,21,916/-	Rs. 8,400/-	Rs. 350/-	Class "D"	Three months
21	Construction of road from main road Majharnu Kufroo Galu to Nichla Baned Km. 0/0 to 1/0 (SH:- Formation cutting between Km. 0/045 to 0/810 at various reaches)	Rs. 4,38,562/-	Rs. 8,800/-	Rs. 350/-	Class "D"	Three months
22	Repair and maintenance of Kamal Galu to Harizan Basti Lower Nauhli road under SCSP (SH:- Construction of retaining wall at RD, 12/335 to 12/365 (under Head repair & maintenance of road under SCSP).	Rs. 3,74,818/-	Rs. 7,500/-	Rs. 350/-	Class "D"	Three months
23	Construction of Mela Ground at Joginder Nagar Distt, Mandi (HP) P (SH:- Construction of retaining wall at RD, 0/0 to 0/040 and pusta wall at RD, 0/0 to 0/020 under Deposit).	Rs. 4,81,790/-	Rs. 9,600/-	Rs. 350/-	Class "D"	Three months

1. Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2024-25-

16888-937

Dated:- 23/11/2024

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

Job - 1

SCHEDULE OF QUANTITY

Name of Work : Construction of Pipal Galu to Lower Batnaharin G.P. Nauhali under Deposit SID: BSP/2024/186 (S.H. : Providing and laying of Wearing G-II & Cement Concrete pavement from km 0/090 to 0/139)				Estimate Cost: 1,67,141.00 Earnest Money: 3,300.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (Two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	11.58	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	19.30	Per Cubic metre			
	Total					


~~Executive Engineer~~
B & R Division HP.PWD.
Joginder Nagar

Job No - 2

SCHEDULE OF QUANTITY

Name of Work : Construction of road from Joginder Nagar Arthi road to Harizan Basti Garoru km 0/00 to 1/500 (Sub Head:- Construction of RCC 900mm dia RCC Hume Pipe culvert along with both side wing walls at km 0/130)					Estimate Cost: Earnest Money: Time Limit :			2,37,987.00 4,800.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Figures	Rate		Words	AMOUNT	
					Figures	Words		Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	42.26	Per cubic metre						
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	9.73	Per cubic metre						
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	19.87	Per cubic metre						
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	3.35	Per cubic metre						
5	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	0.49	Per cubic metre						

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
6	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.50	Per running metre			
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.72	Per cubic metre			
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

Job-3

SCHEDULE OF QUANTITY

Name of Work : Construction of road from Joginder Nagar Arthi road to Harizan Basti Garoru km 0/00 to 1/500 (Sub Head:- Construction of RCC 900mm dia RCC Hume Pipe culvert along with both side wing walls at km 0/205)				Estimate Cost: 2,38,981.00 Earnest Money: 4,800.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	44.18	Per cubic metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	9.73	Per cubic metre			
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	19.87	Per cubic metre			
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	3.35	Per cubic metre			
5	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification. Rubble stone laid in cement mortar 1:5 (one cement : five sand) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	0.49	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
6	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.50	Per running metre			
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.72	Per cubic metre			
8	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			
	Total					


~~Executive Engineer~~
 B & R Division HP.PWD,
 Jalandhar Nagar

Job-4

SCHEDULE OF QUANTITY

Name of Work : Construction & M/T on link road Gayola Harizan Basti Kass to Kumharda road km 0/00 to 1/750 (SH: Construction of Breast/ protection wall at km 1/357 to 1/377)				Estimate Cost: Earnest Money: Time Limit :		2,99,942.00 6,000.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.00	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	57.87	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	16.00	Each			
	Total					



 Executive Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

Job-5

SCHEDULE OF QUANTITY

Name of Work : Construction & M/T on link road to Harizan Basti Gyola km. 0/0 to 1/700 under SCSP (Sub Head:- Construction of RCC 900mm dia RCC Hume Pipe culvert along with both side wing walls at km 1/405)					Estimate Cost: 2,20,053.00 Earnest Money: 4,400.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	30.15	Per cubic metre				
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	15.18	Per cubic metre				
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	15.56	Per cubic metre				
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	10.00	Each				


5	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentials. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.40	Per cubic metre			
6	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentials. The rate is inclusive all taxes levy by the government time to time excluding GST.	7.50	Per running metre			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

Job-6

DNT/DRAFT SCHEDULE OF QUANTITY

Name of Work : Construction & Maintenance of road from Lower Kothi to Basoa Rihra km 0/00 to 1/500 under SCSP (Sub Head:- Providing and laying soling Grade-I, 90 to 45mm size from km 0/900 to 1/500)				Estimate Cost: Earnest Money: Time Limit :			4,95,048.00 9,900.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate			AMOUNT	
				Figures	Words		Rs.	P
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-1 (one) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charg. The rate is inclusive all taxes levy by the government time to time excluding GST.	189.00	Per cubic metre					
Total								


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

WP

Job - 7

SCHEDULE OF QUANTITY

Name of Work : Construction of Harijan Basti Ahju link road Km. 0/0 to 3/0.under SCSP (Sh:-Providing & laying soling grade-I from km.2/750 to 3/0)				Estimate Cost: Earnest Money: Time Limit :		1,91,048.00 3,800.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 20-400 MM (eighty hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening binding materials to fillup the interstices of coarse aggregate watering and compacting to the required density Grading-I (one) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges.The rate is inclusive all taxes levy by the government time to time excluding GST.	78.75	Per Cubic metre			
	Total					


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job - 8

Schedule of Quantity

Estimated Cost:- 146050.00
Earnest Money:- 3000.00
Time:- One month

Name of work:- C/O link road from Harizan Basti Sandral to Bhattu Muhal under deposit SDP/2024/210 for Rs. 1.50 lac. (SH: Hiring of excavator cum loader for construction of road).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for construction of road etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	115.00			Per working hours	
				Total:-		


Executive Engineer
B&R Division HP.PWD,
Joginder Nagar

Job-9

Schedule of Quantity

Estimated Cost:- 209778.00
Earnest Money:- 4200.00
Time:- Three months

Name of work:- C/O C.C. link road NH Mohanghatti towards Bag road Km. 0/0 to 0/400 under MGNREGA.
(SH. Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	60.75			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	31.72			Per cubic metre	
				Total:-		

Executive Engineer
B&R Division, HP. PWD,
Jalandhar Nagar


Job - 10

Schedule of Quantity

Estimated Cost:- 209778.00
 Earnest Money:- 4200.00
 Time:- Three months

Name of work:- C/O Concrete road Main road se Hariyali side under MGNREGA.
 (Sh: Supply and Stacking of Crushed stone aggregate 20 mm, Course Sand and Boulder)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate 20mm (twenty millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	60.75			Per cubic metre	
2	Supply and stacking of course sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	31.72			Per cubic metre	
				Total:-		


 Executive Engineer
 B&R Division, HP PWD,
 Joginder Nagar

Job - 11

SCHEDULE OF QUANTITY

Name of Work : Construction of 19.75mtrs span bridge at RD 7/200 over Nagdyara Nallah on Machhyal Bhararu Bihun road under SSCP. (Sub Head:- Providing and laying soling grade-I, Wearing Grade-II & tarring on approaches)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Preparation of sub grade by dressing to camber (Earth work for cutting involved for sub grade to paid for separately depending upon the classification of soil completed as per HPPWD specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	367.50	Per square metre			
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and re-rolling the sub grade complete as per HPPWD Specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	367.50	Per square metre			
3	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-1 (one) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	36.75	Per cubic metre			
4	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	27.56	Per Cubic metre			

5	Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of coarse aggregate watering and compacting to the required density Grading-3 (three) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	27.56	Per Cubic metre		
6	Providing and applying primer/tack with bituminous primer (VG-10) at the rate of 1.00 (one point zero zero) kilogram per square metre on existing WBM (Water bound macadam) surface cleaned with mechanical brooms as per HP.PWD/MORD specification complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.	367.50	Per square metre		
7	Providing, laying and rolling by mechanical means bitumen (VG-10) of open graded premix carpet of 20mm (twenty millimetre) thickness composed of 13.2mm to 5.6mm (thirteen point two millimetre to five point six millimetre) aggregates either using penetration grade bitumen at the rate of 1.46 (one point four six) kilograme per square metre to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in suitable plant, laying and rolling with a three wheel 80-100 kN (eighty-hundred kilo newton) static roller capacity, finished to required level and grades to be followed by seal coat of Type-B as per technical specification Clause 508 including all corrective measures such as patching pot holes, sealing of cracks including all profile correction for all depths and hauling of material with in all leads and lifts by all modes of transportation. The rate is inclusive all taxes levy by the government time to time excluding GST.	367.50	Per square metre		
8	Providing and laying seal coat Type-B by mechanical means sealing the voids in a bituminous surface laid to the specified levels, grade and crossfall using Bitumen (VG-10) at the rate of 0.68 (zero point six eight) kilograme per square metre as per technical specification Clause 510 including hauling of material with in all leads and lifts by all modes of transportation. The rate is inclusive all taxes levy by the government time to time excluding GST.	367.50	Per square metre		
	Total				



 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job - 12

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages Joginder Nagar Sarkaghat Ghumarwin Road km 0/00 to 34/300 (SH: Construction of Retaining wall at km 16/450 to 16/465)				Estimate Cost: Earnest Money: Time Limit :			1,98,489.00 4,000.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	11.70	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	35.40	Per cubic metre				

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.10	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	14.00	Each			
	Total					

 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar


Job-13

SCHEDULE OF QUANTITY

Name of Work : Restoration of Rain Damages on Link road to Harizan Basti Pohli Under SCSP km 0/00 to 1/500 (SH: Construction of Breast wall for protection Sinking portion in km 0/350 to 0/370)					Estimate Cost: 2,58,654.00 Earnest Money: 5,200.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost.The rate is inclusive all taxes levy by the government time to time excluding GST.	21.40	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 160/0 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	15.00	Per cubic metre				

(29)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	47.20	Per cubic metre			
4	Providing weep holes in brick masonry, stone masonry plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	19.00	Each			
	Total					



 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job - 14

SCHEDULE OF QUANTITY

Name of Work : Construction of Arthi Syuri Majharnoo road km 0/00 to 2/00 (S/L: Improvement of formation width by providing Retaining wall at km 1/205 to 1/220)				Estimate Cost: Earnest Money: Time Limit :			2,07,302.00 4,100.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	11.55	Per cubic metre					
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	35.25	Per cubic metre					

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	18.00	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	23.00	Each			
	Total					



 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

Job - 15

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain Damages on Ahju Matroo road km. (SH: Construction of Breast wall at km 1/585 to 1/593)				Estimate Cost: Earnest Money: Time Limit :			94,197.00 1,900.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.60	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Per cubic metre				

3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	18.80	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	7.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job-16

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain Damages on Ahju Matroo road km. (SH: Construction of Breast wall at km 1/595 to 1/603)				Estimate Cost: 93,919.00 Earnest Money: 1,900.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.60	Per cubic metre			
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost . The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Per cubic metre			

3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	18.80	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job -17

SCHEDULE OF QUANTITY

Name of work : Special repair to State level Revenue Training Institute at Joginder Nagar (SH: Providing and Fixing in Boys hostel, Girls Hostel and Admin Block)					Estimate Cost: Earnest Money: Time Limit :			53,603.00 1,100.00 Two Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate	Words		AMOUNT	
					Figures		Rs.	P
1	Providing and fixing 32mm dia (thirty two millimeters) PVC waste for wash basin or sink including PVC fittings. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer -In- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	15.00	Each					
2	Providing and fixing 8 mm (eight millimeter) dia C.P. / S.S. Jet with flexible tube upto 1 (one) metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	10.00	Each					
3	Providing and fixing 15mm nominal bore C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer -In- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	30.00	Each					
4	Providing and fixing PVC connection pipe with brass unions 45cm (fourty five centimeter) long 15mm (fifteen millimeter) nominal bore complete with all accessories as required as per the direction of Engineer-In-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	140.00	Each					
5	Providing and fixing 15mm (Fifteen millimetres) diameters C.P. brass bib cock of approved quality, as per the direction and entire satisfaction of Engineer-In-Charge. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	19.00	Each					
	Total							


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-18

SCHEDULE OF QUANTITY

Name of Work : Repair and Maintenance of Drubbal to Harizan Basti Basoti Ropru road km 0/00 to 1/500 (SH:Construction of Breast wall at km 0/475 to 0/490 . (Under Head :-Repair & Maintenance of road Under SCSP)				Estimate Cost: Earnest Money: Time Limit :			2,01,398.00 4,000.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Words	AMOUNT	
				Figures			Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost.The rate is inclusive all taxes levy by the government time to time excluding GST.	17.78	Per cubic metre					
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner. filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	11.55	Per cubic metre					

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	35.25	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	14.00	Each			
	Total					



 Executive Engineer
 B & R Division HP.PWD.
 Jogindpur Nagar

Job-19

SCHEDULE OF QUANTITY

Name of Work : Repair & Maintenance of Drubbal to Harizan Basti Ropru road km 0/00 to 1/500 (SH: Construction of Retaining wall at km 0/470 to 0/480 & 0/490 to 0/505. (Under Head:- Repair & Maintenance of Road under SCSP)					Estimate Cost: Earnest Money: Time Limit :		3,58,824.00 7,200.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit		Rate	Words	AMOUNT Rs. P
					Figures		
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specifications section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	18.80	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	58.75	Per cubic metre				


Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	30.38	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	23.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD.
 Jalandhar Nagar

Tab-20

SCHEDULE OF QUANTITY

Name of Work: Construction of link road village Sajehr to Khajri Panara GP Nauhli km. 0/0 to 1/500 (Sub Head:- ROFD in km.0/0 to 0/217 under Head MMGSY)				Estimate Cost: Earnest Money: Time Limit :			4,21,916.00 8,400.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 23.34 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2062.05	Per cubic metre				
Total							


Executive Engineer
B & R Division HP PWD,
Joginder Nagar

Job - 21

SCHEDULE OF QUANTITY

Name of Work: Construction of link road from main road Majharnu Kufroo Galu to Nichla Baned Km. 0/0 to 1/0. (Sh:-Formation cutting between km.0/045 to 0/810 at various reaches)				Estimate Cost: 4,38,562.00 Earnest Money: 8,800.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 23.34 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	2031.32	Per cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job - 22

SCHEDULE OF QUANTITY

Name of Work : Repair & maintenance of Kamal Galu to Harizan Basti Loer Nauhli road under SSCP (Sub Head: Construction of retaining wall at RD 12/335 to 12/365 under Head repair & maintenance of road under SSCP)				Estimate Cost: 3,74,818.00 Earnest Money: 7,500.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	21.60	Per cubic metre			
2	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	70.50	Per cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	17.55	Per cubic metre			

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is inclusive all taxes levy by the government time to time excluding GST.	28.00	Each				
Total							


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job-23

SCHEDULE OF QUANTITY

Name of Work : Construction of Mela Ground at Joginder Nagar Distt. Mandi (HP) (Sub Head:-Construction of retaining wall at RD 0/0 to 0/040 and pusta wall at RD 0/0 to 0/020 under Deposit)				Estimate Cost: 4,81,790.00 Earnest Money: 9,600.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	57.20	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	93.78	Per cubic metre			
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	27.00	Each			
Total						

Executive Engineer
B & R Division, H.P.W.D.
Joginder Nagar

Executive Engineer
B & R Division, H.P.W.D.
Joginder Nagar (H.P.)