




Office of  
Executive Engineer Baijnath Division HP.PWD, Baijnath  
Himachal Pradesh Public works Department Baijnath-176125  
Phone No. 01894-263035 Fax 262704 e-mail:-[ee-baij-hp@nic.in](mailto:ee-baij-hp@nic.in)

## **CERTIFICATE**

**CERTIFIED THAT THE TENDERS OF WORKS, AS  
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2024-25/-  
14989-97 DATED 12-12-2024 ARE URGENT NATURE  
AND PUBLIC INTEREST.**

  
**Executive Engineer,  
Baijnath Division,  
HP.PWD, Baijnath.**



**Office of**  
**Executive Engineer Baijnath Division HP.PWD, Baijnath**  
**Himachal Pradesh Public works Department Baijnath-176125**  
**Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in**

**"NOTICE INVITING TENDER"**

Sealed item rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **28.12.2024** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **27.12.2024 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **26.12.2024 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O Road from Shri Pami Kumar House to Sh. Gyan Chand House Mohal (SH: P/L C.C. Pavement & Kharnja Soling) Deposit work SDP/2024/838)	Rs.98,562/-	Rs.2,000/-	Rs.350/-	Two Months
2	C/O Bahi Rangehar via Chobu Road Portion Kudail to Rangehar (SH: P/L G-II & C.C. Pavement at Km 0/300 to 0/360)	Rs.2,33,440/-	Rs.4,700/-	Rs.350/-	Two Months
3	C/O Pucca Path from Sh. Payar Chand House to SC Basti Nagehar Mohal (SH: P/L C.C. Pavement & Kharnja Soling) (Deposit work SDP/2024/835)	Rs.98,912/-	Rs.2,000/-	Rs.350/-	Two Months
4	Link Road from Pantehar to Ghirtholi road Km 0/00 to 1/00 (SCSP) (SH: P/L Kharnja Stone soling and C.C. Pavement & RCC Slab)	Rs.1,26,698/-	Rs.2,600/-	Rs.350/-	Two Months
5	A/R & M/O Sehal to Bir Khas road km 0/00 to 13/00 (SH: C/O B/Wall at RD 3/465 to 3/495 and R/Wall in wire Crates at RD 7/915 to 7/935) (MMSY)	Rs.4,74,300/-	Rs.9,500/-	Rs.350/-	Two Months
6	C/O Uparli Bheth to Sakari GP Ghorpith (Under MMSY) (SH: Hiring of Hydraulic Excavator/Breaker/JCB cum loader)	Rs.4,99,400/-	Rs.10,000/-	Rs.350/-	One Month

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- The contractor will also have to attach the labour employer license from the labour office with the application.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/Tipper,Mixture,water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,  
Baijnath Division.,  
H.P.PWD..Baijnath.

For & On behalf of the governor of H.P.

Dated:-12.12.2024

NO:-PWD/BD/TA/NIT/2024-25/-

- Copy to the F.C.Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- The Engineer-in-chief, HPPWD, Shimla.
- The Chief Engineer (MZ), HPPWD, Mandi.
- The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- All the Assistant Engineer working under this Division.
- Drawing Branch in this office.
- Notice Board.
- The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,  
Baijnath Division.,  
H.P.PWD..Baijnath.



**DNIT/DRAFT SCHEDULE OF QUANTITY**

①

Name of work :- C/O Road from Shri Pami Kumar House to Sh Gyan Chand House Mohal (SH:- P/L C. C Pavement & Kharnja Soling )( Deposit work SDP/2024/838 )				Estimate Cost: 98,56200/- Earnest Money: 2000.00/- Time Limit :Two months			
SCHEDULE OF WORKS							
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Providing and laying hard stone Soiling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested graident and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.25	Per Cubic metre				
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	11.25	Per Cubic metre				
Total							

Executive Engineer  
Baijnath Division  
HPPWD Baijnath

**DNIT/DRAFT SCHEDULE OF QUANTITY**

2


Name of work :- C/O Bahi Rangehar via Chobu Road Portion Kudail to Rangehar (SH:-P/L G-II & C. C Pavement at km 0/300 to 0/360 )				Estimate Cost: 2,33,440.00/- Earnest Money: 4,700.00/- Time Limit :Two Months		
SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
					Words	
1	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the intersitices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.24	Per Cubic Metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	33.08	Per Cubic metre			
	Total					

Executive Engineer  
Bajjnath Division  
HPPW/Bajjnath

**DNIT/DRAFT SCHEDULE OF QUANTITY**

②

Name of work :- C/O Pucca Path from Sh. Payar Chand house to SC Basti Nagehar Mohal (SH:- P/L C. C Pavement & Kharnja Soling )( Deposit work SDP/2024/835 )				Estimate Cost: 98,912.00/- Earnest Money: 2000.00/- Time Limit : Two months		
SCHEDULE OF WORKS						
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying hard stone Soiling properly hand packed intersects with kharanja staone and consolidating with power / hand roller to requested graident and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	3.96	Per Cubic metre			
2	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Milimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803,1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	13.20	Per Cubic metre			
Total						


  
 Executive Engineer  
 Bajnath Division  
 HPPWD Bajnath



**DNIT/DRAFT SCHEDULE OF QUANTITY**

④

Name of work :-Link Road from Pantehar to Ghirtholi road km 0/00 to 1/00 (SCSP) (SH:-P/L kharanja stone solling and C C Pavement & R C C slab ).						Estimate Cost: 1,26,698.00/- Earnest Money: 2,600.00/- Time Limit : Two Months	
Sr	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Providing and laying hard stone Soiling properly hand packed intersects with kharanja stone and consolidating with power / hand roller to requested graident and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	4.70	Per Cubic metre				
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805 ,806,807,1202 and 1205 RCC M 20 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.70	Cum				
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 800,1205.4 and 1205.5 RCC M-25 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.35	Cum				
4	Supplying, fitting, and placing HYSD bar reinforcement in structure complete as per drawing and technical specifications Clauses 1002, 1005,1010 and 1202 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	522.00	Kg				

  
 Executive Engineer  
 Baijnath Division  
 HPPWD Baijnath

**DNIT/DRAFT SCHEDULE OF QUANTITY**

(5) 61

Name of work:A/R & M/O Sehla to Bir Khasroad km 0/00 to 13/00 ( Sh:- C/O B/Wall at RD 3/465 TO 3/495 and R/Wall in wire Crates at RD 7/915 to 7/935 ). ( MMSY )				Estimate Cost: 4,74,300.00/- Earnest Money: 9,500.00/- Time Limit :Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	43.20	Per Cum			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	54.00	Per Cum			
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS 4826 in 100mm x 100 mm mesh (woven diagonally) including 10 per extra for laps and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specifications clause 1301 Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	57.60	Per Cubic metre			
4	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	16.80	Per Cum			

6 (b)

5	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.00	Each			
	Total					

Executive Engineer  
Baijnath Division,  
H.P.P.W.D. Baijnath (H.P.)



6

## D.N.I.T/ SCHEDULE OF QUANTITY

Name of Work:-C/O Uparli Bheth to Sakari GP ghorpith (Under MMSY )  
(SH:Hiring of Hydraulic Excavator/Breaker /JCB cum loader .)

Estimated Cost:- Rs 4,99,400.00

Earnest Money:- Rs 10,000.00

Time:- One Months

SR. No.	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				In Figure	Figures	
1	Hiring of Hydraulic Excavator cum Breaker to be deployed dressing of road side katcha drain and removal of slips Debries etc Including cost of fuel oil lubricants wages of opreating staff The fuel and operational staff for Excavator/Breaker shall be borne by the contractor/ owner.Shifting of Machinery from one place to other place will be absolute responsibilty of contractor ,Earth Cutting in all kind of soil including loading into tipper/ truck The daily log book will be maintained at site which should be duly verified by the Engineer in charge. The rates are inclusive all taxes levy by the govt time to time including GST .	50.00	Per hour			
2	Hiring of Hydraulic Excavator/JCB cum loader having capacity of 0.9 Cum (zero point nine cubic meter ) in working condition urgently required for removal of snow , slips Boulder and debris etc from road surface upto any height , depth and lead including slips, boulders in all kind and classification of soil including rocky portion and saturated soil due to non-availability of departmental machinery any loss to the public/ private property or any accident etc. happened during the course of hiring period/ execution shall be the absolute responsibility of the JCB/ Excavator owner which shall have to be fully compensated by the contractor in all cases.it should be ensure that the output of machine should not be less than 20 cum per hour The fuel and operational staff for JCB/ Excavator shall be borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer in charge. The rates are inclusive all taxes levy by the govt time to time including GST .	354.00	Per hour			
Total:-						

Executive Engineer  
Bajinath Division  
H.P.W.D. Bajinath