H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEDULE:

1. Date and time of receipt of application for tender form: 24.12.2024 upto 12.00 Noon
2. Date and time of issue of tender form: 26.12.2024 upto 5.00 PM
3. Date and time of receipt of tenders: 27.12.2024 upto 10.30AM
4. Date and time of opening of tenders: 27.12.2024 at 11.00 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	Construction of link road from Highway Bhangwar to Bansi Ram House via Kallar Khad G.P. Dohag Paloti KM 0/0 to 1/00 (SH: C/o Cement Concrete Pavement & V-Shape Drain at RD 0/800 to 0/890).	Rs. 4,92,536/-	Rs.10,000/-	Three Months	Rs.350/-
2	Restoration of Rain Damages on Ranital Kotla Bhedi Dhar Road KM 0/0 to 6/00 (SH: Repair of Dipressed Portion & Profile Correction between KM 2/00 to 6/00).	Rs. 4,92,450/-	Rs.10,000/-	Three Months	Rs.350/-
3	Restoration of Rain Damages on Kandreti Chandua Road KM 0/0 to 4/00 (SH: C/o B/Wall at RD 0/060 to 2/082 and R/Wall at RD 2/105 to 2/120 & 3/430 to 3/440).	Rs. 4,96,886/-	Rs.10,000/-	Three Months	Rs.350/-
4	Restoration of Rain Damages on Kandreti Chandua Road KM 0/0 to 4/00 (SH: C/o B/Wall at RD 1/990 to 2/060).	Rs. 4,92,354/-	Rs.10,000/-	Three Months	Rs.350/-
5	Stock Storage at HPPWD Division Dehra in Distt. Kangra (H.P.) (SH: Supplying and Stacking of Machine Made Brick 1st Class).	Rs. 2,70,000/-	Rs.6,000/-	One Month	Rs.350/-
6	Restoration of Rain Damages on Nehranpukhar to Sount Road KM 0/0 to 2/00 (SH: C/o U-Shape Drain at RD 0/450 to 0/560 & R/Wall at RD 1/120 to 1/135).	Rs. 3,68,647/-	Rs. 5,000/-	One Months	Rs.350/-
7	Construction of Haripur to Bhatoli Phakorian Road KM 0/0 to 3/100 (SH: C/o Rain Shelter at RD 3/100) under Road Side Amenities.	Rs. 2,29,072/-	Rs. 5,000/-	Two Months	Rs.350/-
8	Construction of link road from Haripur Dosarka to Bhiloo Nag Mandir including Sanyala under G.P. Sherlohara in KM 0/0 to 1/700 (SH: C/o Cement Concrete Pavement alongwith Approach Wall from 1/345 to 1/425).	Rs. 4,98,733/-	Rs.10,000/-	Two Months	Rs.350/-
9	Construction of link road from Gameerpur to Lahardian to G.P. Nandpur in KM 0/0 to 4/700 (SH: C/o Hume Pipe Culvert at RD 2/525, 3/650 & 4/315).	Rs. 4,94,252/-	Rs.10,000/-	Two Months	Rs.350/-
10	Construction of Govt. Sen. Sec.School Serabari Bari Khas Dhiman Basti to Dehra Jawali Raja-ka-Talab Road KM 0/0 to 1/500 (SH: C/o Slab Culvert 3.00mtr. Span at RD 1/282) OTMNP.	Rs. 4,99,720/-	Rs.10,000/-	Three Months	Rs.350/-
11	Construction of Govt. Sen. Sec.School Serabari Bari Khas Dhiman Basti to Dehra Jawali Raja-ka-Talab Road KM 0/0 to 1/500 (SH: C/o Slab Culvert 3.00mtr. Span at RD 1/195) OTMNP.	Rs. 4,98,332/-	Rs.10,000/-	Three Months	Rs.350/-

12	Restoration of Rain Damages on Gopipur Chamukha Road KM 0/0 to 6/00 (SH: C/o R/Wall at RD 4/320 to 4/327).	Rs. 4,52,758/-	Rs.10,000/-	Three Months	Rs.350/-
13	Construction of Road from Tutru (Dehra Bharwain Road) via Bhagnoria, Choudhary & Harizan Basti upto GPS Bharwara KM 0/0 to 2/500 (SH: C/o R/Wall at RD 1/425 to 1/450 & C/o U-Shape Drain at RD 1/575 to 1/685 & V-Shape Drain at RD 1/825 to 1/935).	Rs. 4,45,137/-	Rs.9,000/-	Two Months	Rs.350/-

1 (i) (ii) (iii) (iv)	The contractors/firms should possess the following documents(Photocopy to be attached): Latest renewal of enlistment. PAN (Permanent Account No.) Registration under HP GST/ (TIN No.). EPF(Employee Provident Fund Account No.)
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.
3	If any of the date mentioned above happened/to be Gazetted Holidays the same shall be processed on next working day.
4	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).
5	The Contractor will have to submit affidavit alongwith application for issue of tender that he has not more than two works in hand.
6	The next tender will be issued only after completion of previous works in hand.
7	The offer of the tender shall remain valid upto 30 days after the opening.

Executive Engineer
HPPWD Division Dehra
Distt Kangra H.P
on behalf of Governor of Himachal Pradesh

Endst.No.PWD/DEH/CB/Tender/2024-25:- 8264-73 Dated :- 11/12/2024

Copy forwarded to the following:-

1. The FC-Cum secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President NAC Dehra.
9. The BDO Dehra /Pragpur/ Nagrota Surian.
10. Notice Board.
11. All the Head of Branches.
12. All the Contractors working under Dehra Division.
13. The Computer Cell office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

(241)

PRECENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,92,536.00
Earnest Money :- Rs. 10000.00
Time Limit :- Three months.

Name of work:- **C/o link road from Highway Bhangwar to Bansi Ram House via Kallar khad G.P. Dahog Paloti km 0/00 to 1/000 (S.H.:- Construction of CC pavement & V-shape drain at RD 0/800 to 0/890.**

Sr.	Description of Item	Qty.	Unit	Rate	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material.completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	29.75	P/Cum	290.00	8628.00
2	Construction of granular sub-base of grading II by providing close graded Material conforming to specifications, mixing in mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density as per MORTH Technical specification clause No. 509 including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	20.25	P/Cum	1700.00	34425.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (1:3:6) 1 cement : 3 sand : 6 aggregate of nominal 20mm size)as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	43.35	P/Cum	4950.00	214583.00

4	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C M 20 nominal mix 1:2:4 in Dirt wall and bed block.as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	40.50	P/Cum	5800.00	234900.00
	Total =				**4,92,536.00**
	% Above/below				
	Quoted Amount in Figures				
	Quoted Amount in Words				

Bill of quantity checked and approved for Rs. 4,92,536.00/- only.

Executive Engineer
Dehra Division
HP.PWD. Dehra

243

PRECENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,92,450.00
Earnest Money :- Rs. 10000.00
Time Limit :- Three months.

Name of work:- Restoration of rain Damages on Ranital Kotla Bhedi Dhar road km 0/000 to 6/000.(S.H.:- Repair of dipressed portion & profile correction between KM 2/000 to 6/000.)

Sr.	Description of Item	Qty.	Unit	Rate	Amount
1	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material within all lifts and lead upto 1km (by mechanical means)as per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1005.00	Sqm	25.00	25125.00
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge .The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	150.75	P/Cum	1300.00	195975.00
3	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete asper specifications and directions of Engineer-in-Charge. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	150.75	P/Cum	1800.00	271350.00
					4,92,450.00
	% Above/below				
	Quoted Amount in Figures				
	Quoted Amount in Words				

Bill of quantity checked and approved for Rs. 4,92,450.00/- only.

Executive Engineer
Dehra Division
HP.PWD. Dehra

244

PRECENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,96,886.00
Earnest Money :- Rs. 10000.00
Time Limit :- Three months.

Name of work:- **Restoration of rain Damages on Kadreti Chandua road km 0/000 to 4/000.(S.H.:-C/o B/wall at RD 0/060 to 2/082 and R/wall at RD 2/105 to 2/120 & 3/430 to 3/440.)**

Sr.	Description of Item	Qty.	Unit	Rate	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	67.81	P/Cum	290.00	19665.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C nominal mix 1:4:8 (40 mm aggregates)completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	111.82	P/Cum	4050.00	452871.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	38.00	Each	250.00	9500.00
4	Back filling behind abutment, wing wall and return wall complete as per drawing & Technical Specification Clause-1204.3.8 Granular material completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	19.8	P/Cum	750.00	14850.00
	Total =				**4,96,886.00**
	% Above/below				
	Quoted Amount in Figures				
	Quoted Amount in Words				

Bill of quantity checked and approved for Rs. 4,96,886.00/- only

Executive Engineer
Dehra Division
HP.PWD. Dehra

245

PRECENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,92,354.00
Earnest Money :- Rs. 10000.00
Time Limit :- Three months.

Name of work:- **Restoration of rain Damages on Kadreti Chandua road km 0/000 to 4/000.(S.H.:-C/o B/wall at RD 1/990 to 2/060).**

Sr.	Description of Item	Qty.	Unit	Rate	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	54.60	P/Cum	290.00	15834.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C nominal mix 1:4:8 (40 mm aggregates)completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	113.40	P/Cum	4050.00	459270.00
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 completeas per MORTH Technical specification including hauling of material in all leads, lifts as per entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads,lifts and other incidental. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	69.00	Each	250.00	17250.00
	Total =				**4,92,354.00**
	% Above/below				
	Quoted Amount in Figures				
	Quoted Amount in Words				

Bill of quantity checked and approved for Rs 4,92,354.00 Lumpy.

Executive Engineer
Dehra Division
HP.PWD. Dehra

249

JOB NO-1

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 270000.00
Earnest Money :-Rs. 6000.00
Time Limit :- One Month.

Name of work:-Stock Storage at Dehra HPPWD Division Dehra (SH:-Supplying and Stacking of Machine Made Brick 1st class)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Supplying and Stacking at HPPWD Dehra Division Dehra Store in uniform stacks Machine Made 1st class Bricks of good quality and durabiliti including inclusinve of octroi. Royality. Malkhana. Toll Tax Toll Plaza. Sale Tax. GST or any other taxes imposed by the Government time to time. material should confirm to Technical specification made by Department and to the entire satisfaction of Engineer-in-Charge and nothing shell be paid for non specified rejected material.	10000.00 No.s	27.00	Twenty Seven Rupees	Numbers	2,70,000.00
	Total					**270000.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 270000/- only.

Executive Engineer.
Dehra Division.
HPPWD Dehra

PARCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 368647.00
Earnest Money :- Rs. 8,000.00
Time Limit :- One Month.

Name of work:- Restoration of Rain Damages on Nehranpukhar to saunt Road Km. 0/00 to 2/00 (SH - C/o U-Shape drain at RD 0/450 to 0/560 & Rwall at RD 1/120 to 1/135)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	70.20 Cubic metre	300.00	Rupees Three Hundred Only	Per Cubic metre	21,060.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) nominal mix 1:3:6 (One cement isto three sand isto six graded crushed stone aggregate 40mm(Forty millimeter) nominal size), in or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water)including removal of slush which may arise at time of laying under water for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	39.60 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	1,96,020.00
3	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material with in all leads lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	32.94 Cubic metre	4050.00	Rupees Four Thousand Fifty Only	Per Cubic metre	1,33,407.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V). 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government	13.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	3,250.00
5	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	19.88 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	14,910.00
	TOTAL					3,68,647.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked & approved for Rs. 368647/-

Executive Engineer
Dehra Division
HPPWD Dehra

250

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 2,29,072.00
Earnest Money :-Rs. 5,000.00
Time Limit :- Two Months.

lame of work:- Construction of Haripur to Bhatoli Phakorian Road Km 0/000 to 3/100 (SH:- Construction of Rain Shelter at RD 3/100). (Under road side Amenities).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains of soil such as pick work, jumper work, pick jumper work, blasting work, jumper blasting work, soft and hard blasting and saturated soil, de-watering, including wedging out rocks where blasting work is prohibited, chiseling or any other mixed variety of soil, including shoring, strutting or bailing out water upto any depth or any height quantum of water including de-watering removal of slush and stacking the serviceable and un-serviceable material clear from the edge of excavation as per direction of Engineer-in-Charge and returning the stacked soil in 15cm (Fifteen centimeter) layers, when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming, watering and then disposing of all excavated earth including carriage of material within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-Incharge. The rate is inclusive of octroi, royality, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	10.39 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	3,013.00
2	Providing and laying cement concrete 1:4:8 (One cement isto four sand isto eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete excluding cost of forms work in foundation and plinth within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of Octroi, Royality, Malkhana, Toll tax, Sale tax, GST and any other taxes imposed by the Government.	7.91 Cubic metre	4955.20	Rupees Four Thousand Nine Hundred Fifty Five And Paise Twenty Only	Per Cubic metre	39,196.00
3	Random rubble masonry with hard stone of approved quality in foundation and plinth including levelling up with cement concrete 1:6:12 (One cement isto Six coarse sand isto Twelve graded stone aggregate 20mm (Twenty millimetre) nominal size upto plinth level including raking out joints in cement mortar 1:6 (One cement : Six coarse sand) complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royality, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	5.52 Cubic metre	5360.00	Rupees Five Thousand Three Hundred Sixty Only	Per Cubic metre	29,587.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and laying 40mm (forty millimeter) thick cement concrete flooring 1:2:4 (One cement isto two sand isto four graded stone. aggregate 20mm (Twenty millimetre) nominal size) laid one layer finished with a floating coat of neat cement. including preparation of surface grading complete and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royality, Malkhana, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	9.86 Square metre	378.95	Rupees Three Hundred Seventy Eight And Paise Ninety Five Only	Per Square metre	3,736.00
5	Providing form work with steel plates 3.15mm (Three point one five millimeters) thick, welded with angle iron in frame 30x30x5mm (Thirty into Thirty into Five millimeters) so as to give a fair finish including centering, shuttering strutting and propping etc, with wooden battens and ballies, height of propping and centering in all heights. below supporting floor to ceiling and removal of the same for in situ reinforced concrete and plain concrete work in Suspended floors, roofs, landings, balconies, shelves and access platform and the like floor, etc. up to any thickness, up to all floor level and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll Tax Sales tax or any other taxes imposed by the Government.	4.50 Square metre	486.30	Rupees Four Hundred Eighty Six And Paise Thirty Only	Per Square metre	2,188.00
6	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (One cement isto one & half coarse sand) isto three graded stone aggregate 20mm (Twenty millimetre) nominal size complete and as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll Tax Sales tax or any other taxes imposed by the Government.	0.34 Cubic metre	7835.75	Rupees Seven Thousand Eight Hundred Thirty Five And Paise Seventy Five Only	Per Cubic metre	2,664.00
7	Providing and laying Tor steel of TATA/SAIL reinforcement for Reinforced Cement Concrete work including bending, binding, cutting, straightening and placing in position complete including cost of binding wire and other incidentals for its completion up to all floor level complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government.	28.90 Kilogram	76.85	Rupees One Hundred One And Paise Thirty Only	Per kilogram	2,221.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
8	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven point five) in foundation and plinth above plinth level upto all floor level in cement mortar 1:6 (one cement isto six sand) and curing complete as per approved drawing, design, specification and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.68 Cubic metre	6164.00	Rupees One Hundred One And Paise Thirty Only	Per Cubic metre	28,848.00
9	Providing and applying 15mm (fifteen millimeters) thick cement plaster with cement mortar 1:6 (one cement isto six sand) in single coat on rough side of brick/concrete/ stone walls for interior plastering upto all floor level including arises, internal rounded angles, chamfers and/or rounded angles in all girth and finished even and smooth complete as per HPPWD specifications and as per direction by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royality, Malkhana, Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government.	32.40 Square metre	196.45	Rupees One Hundred One And Paise Thirty Only	Per Square metre	6,365.00
10	Steel work of Tata/Sail, riveted, bolted or welded in built up sections, framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royality, Malkhana, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	354.19 Kilogram me	107.45	Rupees One Hundred Seven And Paise Forty Five Only	Per Kilogram me	38,058.00
11	Providing and fixing 0.60mm (zero point six zero millimetre) thick ISI marked Z-120 (Z-one hundred twenty) prepainted steel sheet of TATA/Sail/Relience/Jindal in roofing over steel trusses with hot dip metalic zinc coated sheet with top coat of regular modified polyster (RMP) Organic coating of 20 (TWENTY) microns over 5 (five) microns of primer back coat of polyster of 5 (five) microns over 5 (five) primer coating including finishing with prepainted, iron J or L hoks, bolts and nuts 6mm (six millimeter) diametre with prepainted limpet and rubber washer filled with required colour and laid completely with all accessories or required as per direction of Engineer In-charge including carriage of materials with in all lead and lift and other incidental as per the direction of Engineer-in-Charge. The rate including Royality, Malkhana, Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government.	44.28 Square metre	1086.00	Rupees One Thousand Eighty Six Only	Per Square metre	48,088.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
12	Providing and fixing ridges or hips 60cm (Sixty centimetre) over all with 0.60 (zero point six zero millimetre) thick prepainted steel sheet of TATA/Sail in roofing with hot dip metalic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (five) microns of primer back coat of polyster of 5 (five) microns over 5 (five) primer coating including finishing with prepainted iron J or L hoks, bolts and nuts 6mm (six millimeter) diametre with prepainted limpet and rubber washer complete with all accessories or required as per direction of Engineer-in-Charge including carriage of materials with in all lead and lift and other incidental. The rate including Royality, Malkhana, Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government.	14.00 Running metre	721.90	Rupees Seven Hundred Twenty One And Paise Ninety Only	Per Running metre	10,107.00
13	Providing and fixing **M.S. black plain sheet 2.00mm** (Two point zero zero millimeter) thick in facia/eaves boards/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per HPPWD specifications and as direction by the Engineer-in-Charge, (base members of steel work shell be measured and paid for separately), including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Octroi, GST, Toll Tax Sales tax or any other taxes imposed by the Government.	3.84 Square metre	1692.40	Rupees One Thousand Six Hundred Ninety Two And Paise Forty Only	Per Square metre	6,499.00
14	Painting steel work with Deluxe Multi Surface Paint to give an even shade Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.80 ltr/10 sqm of approved brand and manufacture completed and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	20.00 Square metre	89.90	Rupees Eighty Nine And Paise Ninety Only	Per Square metre	1,798.00
15	Distempering (two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	32.40 Square metre	96.85	Rupees Ninety Six And Paise Eighty Five Only	Per Square metre	3,138.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
16	Finishing walls with weather proof exterior emulsion paint of Asian/Dulux /Berger/Nerolac Suraksha paints of approved shade having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	32.40 Square metre	110.05	Rupees One Hundred Ten And Paise Five Only	Per Square metre	3,566.00
	TOTAL					**2,29,072.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 229,072.00/- only.

Executive Engineer,
Dehra Division ,
HPPWD Dehra

(251)

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,98,733.00
Earnest Money :-Rs. 10,000.00
Time Limit :- Two Months.

Name of work:- Construction of Link road from Haripur Dosarka to Bhiloo Nag Mandir including Sanyala under GP Sherlohara in Km 0/0 to 1/700 (SH:- Construction of Cement Concrete pavement alongwith approach walls from RD 1/345 to 1/425).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation **in foundation for all types** of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	22.05 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	6,395.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in Retaining wall/breast wall and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	57.75 Cubic metre	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic metre	2,22,338.00
3	Construction of embankment with approved materials obtained from borrow pits with all litfs upto transporting to site spreading grading and compacted to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, including spreading the embankment material with motor–Grader in successive layers of 200mm (two hundred millimeter) uniform thickness, and compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 as per MORD technical specification section 300 & 1600 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	126.00 Cubic metre	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	31,500.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Construction of Gravel/Granular sub base/base 175mm (one hundred seventy five millimeter) compacted thickness by providing well graded material as per table 400.1 spreading in uniform layers with tractor mount grader on prepared surface, mixing by mix in place method with tractor mount appropriate rotavator at OMC and compacting with three wheel 80-100 (eighty – Hundred) kN static roller to achieve the desired density, complete as per MORD technical specification section 400 for grading-I material and as per the direction and entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, GST, Toll tax or any other taxes imposed by the Government.	30.00 Cubic metre	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Cubic metre	40,500.00
5	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in open foundation Grade-M20 (M-Twenty) Nominal mix ***1:2:4*** (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) **in open foundation** etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete for all heights/depths and any quantum of water complete including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, Toll tax or any other taxes imposed by the Government.	36.00 Cubic metre	5500.00	Rupees Five Thousand Five Hundred Only	Per Cubic metre	1,98,000.00
	Total					**4,98,733.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved for Rs. 4,98,733.00 only.

Executive Engineer,
Dehra Division,
HPPWD Dehra

252

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,94,252.00
Earnest Money :-Rs. 10,000.00
Time Limit :- Two Months.

Name of work:- Construction of Link road from Gameerpur to Lahardiyan to GP Nandpur in Km 0/00 to 4/700 (SH:- Construction of Hume Pipe Culvert at RD 2/525, 3/650 & 4/315).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation **in foundation for all types** of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	93.88 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	27,225.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete nominal mix **1:4:8** (One cement isto four sand isto eight graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in **Retaining wall/breast wall** and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900, 1200 and 1600 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	70.20 Cubic metre	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic metre	2,66,760.00
3	Providing and laying mechanically mixed and vibrated concrete for plain-cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) on ground or under water in drain including pumping or bailing out water/ dewatering removal of the slush as required at site which may arise at the time of laying concrete, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification section 800, 900 and 1200 or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	21.38 Cubic metre	4650.00	Rupees Four Thousand Six Hundred Fifty Only	Per Cubic metre	99,417.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
5	Providing 100mm (One Hundred millimeter) dia ***PVC pipe Weep Holes in brick*** masonry/ stone masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra, extending through the full width of the structure with slope of IV:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 & 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	24.00 Numbers	220.00	Rupees Two Hundred Twenty Only	Each	5,280.00
5	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix 1:2½:5 (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, in Abutments and toe walls etcetera including cost of form work and curing complete as per MORD technical specification clauses 802, 804, 805, 806, 807, 1202 & 1204 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	2.12 Cubic metre	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per Cubic metre	10,070.00
6	Providing and laying (to level or slope) **900mm dia** (Nine hundred millimeter) diametre reinforced cement concrete heavy duty non pressure pipes IS Class **NP-3** for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement isto two sand) but excluding the cost of excavation, protection works, back filling, pipe bedding concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1100 and as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	22.50 Running metre	3800.00	Rupees Three Thousand Eight Hundred Only	Per Running metre	85,500.00
	Total					**4,94,252.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked and approved
-Rs Rs. 4,94,252.00/only

Executive Engineer,
Dehra Division ,
HPPWD Dehra

254

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 499720.00
Earnest Money :- Rs. 10,000.00
Time Limit :- Three Months.

Name of work:- C/o Govt Senior Secondary School Serabari Bari Khas Dhiman Basti Harizan Basti to Dehra Jawali Raja Ka Talab road in Km 0/0 to 1/500 (SH - C/o Slab Culvert 3 00mtr Span at RD 1/282) **OTMNP**

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures*** such as retaining walls, breast walls culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305 1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads lifts and other incidentals. The rate is including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	60 57 Cubic metre	275 00	Rupees Two Hundred Seventy Five Only	Per Cubic metre	16 657 00
2	Providing and laying mechanically mixed and vibrated cement concrete ***1:4:8*** (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete in or under water ***in open foundation for all types of structures,*** including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax	0 98 Cubic metre	4050 00	Rupees Four Thousand Fifty Only	Per Cubic metre	3 969 00
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix ***1:2½:5*** (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, ***in Abutments and toe walls etcetera*** including cost of form work and curing complete as per MORD technical specification clauses 802 804, 805, 806 807 1202 & 1204 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Toll tax, Sale tax or any other taxes imposed by the Government	71 30 Cubic metre	5050 00	Rupees Five Thousand Fifty Only	Per Cubic metre	3 60 065 00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked ***P.V.C. pipe Weep Holes*** in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V) 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614,709,1204 3 7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals The rates including Royality, Malkhana, Octroi Toll tax, Sale tax, GST or any other taxes imposed by the Government	20 00 Numbers	250 00	Rupees Two Hundred Fifty Only	Each	5,000 00
5	***Back filling behind abutment Retaining wall/Breast wall, Wing walls*** and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604 7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads lifts and other incidentals The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	47.20 Cubic metre	750 00	Rupees Seven Hundred Fifty Only	Per Cubic metre	35,400 00
6	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub structure Grade-M20 (M-Twenty) Nominal mix ***1:2:4*** (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) ***in Bed block and Dirt wall*** etcetera including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete for all heights/depths and any quantum of water complete including carriage of materials within all leads, lifts and other incidentals The rate is including Octroi Royality, Malkana GST Toll tax or any other taxes imposed by the Government	3 12 Cubic metre	5800 00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	18,096 00
7	Fitting and placing ***HYSD bar reinforcement in sub-structures*** in bridge complete as per drawings and MORT&H technical specifications Clause 1600 and 2200, including cutting bending, binding and placing in position complete in all respect including the cost of binding wire upto any floor level and as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental The rate is including of Octroi Royality, Malkhana, Toll Tax, Sale Tax, GST or other Taxes imposed by the Government	0 500 Metric Tonne	17000 00	Rupees Seventeen Thousand Only	Per Metric Tonne	8,500 00
8	Providing and fixing ***drainage spouts*** complete 100mm (Hundred millimeters) diameter corrosion resistant down pipe Typical head of 6mm (six millimeters) as per drawings and MORT&H technical specification 2705 or as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials within all leads lifts and other incidental The rate is including Octroi, Royality Malkana, Toll Tax Sale Tax GST or other Taxes imposed by the Government	4 00 Numbers	700 00	Rupees Seven Hundred Only	Each	2,800 00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
9	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M Twenty five) nominal mix ***1:1.5:3*** (One cement isto one and half sand isto three graded crushed stone aggregate 20mm (Twenty millimeter) nominal size ***in open foundation*** as per drawing and MORD technical specification clause 802, 803 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts. The rates including Royality Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	5 45 Cubic metre	6850 00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	37,333 00
10	Ffitting and placing ***HYSD bar reinforcement in super structure*** complete as per drawing and MORD technical specifications Clause 1002, 1010 and 1202 including cutting, bending, binding and placing in position complete in all respect including cost of binding wire upto any heights as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including of Octroi, Royality Malkhana Toll Tax, Sale Tax or other Taxes imposed by the Government.	0 700 Metric Tonne	17000 00	Rupees Seventeen Thousand Only	Per Metric Tonne	11 900 00
	TOTAL:					**4,99,720.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Conditions:

1 The work will be strictly executed as per HPPWD specifications
2 The contractor will procure cement at their own level from Civil Supply Depott. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt of HP vide No PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
3 The Tor steel will be provided by the deapartment free of cost Only the carriage of steel from the store to site of work and labour will be paid to the contractor.
4 The bills of all materials procured by the contractor and M/X form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

Bill of quantity checked and approved for Rs 4,99,720/- only.

Executive Engineer
Dehra Division
HPPWD Dehra

253

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 498332.00
Earnest Money :- Rs. 10,000.00
Time Limit :- Three Months.

Name of work:- C/o Govt Senior Secondary School Serabari Bari Khas Dhiman Basti Harizan Basti to Dehra Jawali Raja Ka Talab road in Km 0/0 to 1/500 (SH - C/o Slab Culvert 3.00mtr Span at RD 1/195) **OTMNP**

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	***Earth work in excavation in foundation for all types of structures*** such as retaining walls, breast walls, culvers drains parapets and other similar structures in all kinds and classification of soil including saturated soil comprising of ordinary mix soil ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305 1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals The rate is including Royality Malkhana Octroi Toll tax Sale tax GST or any other taxes imposed by the Government	60 57 Cubic metre	290 00	Rupees Two Hundred Ninety Only	Per Cubic metre	17 565 00
2	Providing and laying mechanically mixed and vibrated cement concrete ***1:4:8*** (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete in or under water ***in open foundation for all types of structures,*** including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802 803 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material with in all leads lifts and other incidentals The rates including Royality Malkhana Octroi Toll tax Sale tax GST or any other taxes imposed by the Government.	0 98 Cubic metre	4050 00	Rupees Four Thousand Fifty Only	Per Cubic metre	3 969 00
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-15 (M-Fifteen) Nominal mix ***1:2½:5*** (one cement isto two and half sand isto five graded crushed stone aggregate (40mm) forty millimeter nominal size) in or under water, including pumping or bailing out water/ dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, ***in Abutments and toe walls etcetera*** including cost of form work and curing complete as per MORD technical specification clauses 802, 804, 805, 806 807, 1202 & 1204 and as per the direction and the entire satisfaction of Engineer-in Charge including carriage of materials within all leads, lifts and other incidentals. The rate including Royality Malkhana Octroi, Toll tax Sale tax or any other taxes imposed by the Government	72 51 Cubic metre	5050 00	Rupees Five Thousand Fifty Only	Per Cubic metre	3 66 176 00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked ***P.V.C. pipe Weep Holes*** in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V) 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709,1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	20 00 Numbers	250 00	Rupees Two Hundred Fifty Only	Each	5,000 00
5	***Back filling behind abutment Retaining wall/Breast wall, Wing walls*** and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi Toll tax, Sale tax, GST or any other taxes imposed by the Government	47 20 Cubic metre	750 00	Rupees Seven Hundred Fifty Only	Per Cubic metre	35,400 00
6	Provicing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub structure Grade-M20 (M-Twenty) Nominal mix ***1:2:4*** (one cement isto two sand isto four graded crushed stone aggregate (40mm) forty millimeter nominal size) ***in Bed block and Dirt wall*** etcetera, including cost of form work and curing complete as per drawing and MORD technical specification section 800 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete for all heights/depths and any quantum of water complete including carriage of materials within all leads lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, Toll tax or any other taxes imposed by the Government.	2 88 Cubic metre	5800 00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	16,704 00
7	Fitting and placing ***HYSD bar reinforcement in sub-structures*** in bridge complete as per drawings and MORT&H technical specifications Clause 1600 and 2200 including cutting bending, binding and placing in position complete in all respect including the cost of binding wire upto any floor level and as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including of Octroi, Royality, Malkhana, Toll Tax, Sale Tax, GST or other Taxes imposed by the Government	0 450 Metric Tonne	17000 00	Rupees Seventeen Thousand Only	Per Metric Tonne	7,650 00
8	Providing and fixing ***drainage spouts*** complete 100mm (Hundred millimeters) diameter corrosion resistant down pipe Typical head of 6mm (six millimeters) as per drawings and MORT&H technical specification 2705 or as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including Octroi, Royality, Malkana, Toll Tax, Sale Tax, GST or other Taxes imposed by the Government.	4 00 Numbers	700 00	Rupees Seven Hundred Only	Each	2,800 00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
9	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete Grade-M-25 (M Twenty five) nominal mix ***1:1.5:3*** (One cement isto one and half sand isto three graded crushed stone aggregate 20mm (Twenty millimeter) nominal size ***in open foundation*** as per drawing and MORD technical specification clause 802, 803 1202 and 1203 including the cost of form work and curing complete but excluding cost of reinforcement for reinforced concrete work as per satisfaction and direction of Engineer-in-Charge, including carriage of materials up to all leads, lifts The rates including Royality, Malkhana Octroi, Toll tax Sale tax GST or any other taxes imposed by the Government	4 55 Cubic metre	6850 00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	31,168 00
10	Ffitting and placing ***HYSD bar reinforcement in super structure*** complete as per drawing and MORD technical specifications Clause 1002 1010 and 1202 including cutting, bending, binding and placing in position complete in all respect including cost of binding wire upto any heights as per direction of Engineer-in-Charge including carriage of materials within all leads lifts. The rate including of Octroi, Royality, Malkhana Toll Tax, Sale Tax or other Taxes imposed by the Government.	0 700 Metric Tonne	17000 00	Rupees Seventeen Thousand Only	Per Metric Tonne	11,900 00
	TOTAL:					**4,98,332.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Conditions:

1 The work will be strictly executed as per HPPWD specifications
2 The contractor will procure cement at their own level from Civil Supply Depott After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt of HP vide No PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
3 The Tor steel will be provided by the deapartment free of cost Only the carriage of steel from the store to site of work and labour will be paid to the contractor
4 The bills of all materials procured by the contractor and M/X form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill

Bill of quantity checked and approved for Rs. 4,98,332-00/- only

Executive Engineer
Dehra Division
HPPWD Dehra

(255)

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.452758.00
Earnest Money :-Rs. 10000.00
Time Limit :- Three Months.

Name of work:- Restoration of Rain damages on Gopipur Chamukha Road Km. 0/00 to 6/000 (SH:-C/o R/wall at RD 4/320 to 4/327)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royality Malkhana, Octroi toll tax, sale tax, GST or any other taxes imposed by the Government	50.31 Cubic meter	330.00	Rupees Three Hundred Thirty Only	Per Cubic meter	16,602.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material with in all leads lifts and other incidentals. The rates including Royality Malknana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	101.25 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	4,10,063.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Back filling behind abutment Retaining wall/Breast wall. Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government	22.79 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	17,093.00
4	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical isto twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709.1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	36.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	9,000.00
	Total					4,52,758.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of quantity checked &
approved for ₹ 452758/only

Executive Engineer,
Dehra Division,
HPPWD Dehra

256

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 4,45,137.00
Earnest Money :-Rs. 9,000.00
Time Limit :- Two Months.

Name of work:- Construction of road from Tutru (Dehra Bharwain road) via Bhagnoria, Choudhary & Harizan Basti upto GPS Bharwara Km 0/0 to 2/500 (SH:- Construction of Retaining wall at RD 1/425 to 1/450 & C/o U-Shape drain at RD 1/575 to 1/685 & V-Shape Drain 1/825 to 1/935).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation **in foundation for all types** of road structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown in the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification section 300 & 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	151.42 Cubic metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic metre	43,912.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size) for plain cement concrete and curing complete up to all heights/depth including the cost of form work in Parapets and the like etcetera as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	66.50 Cubic metre	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic metre	2,49,375.00
3	Providing 100mm (One Hundred millimeter) dia ***PVC pipe Weep Holes in brick*** masonry/ stone masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra, extending through the full width of the structure with slope of IV:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 & 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	20.00 Numbers	250.00	Rupees Two Hundred Fifty Only	Each	5,000.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	**Back filling with granular material behind abutment Retaining wall/Breast wall, Wing walls** and the like complete as per drawings and MORD technical specification section 1200 & 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	27.50 Cubic metre	750.00	Rupees Seven Hundred Fifty Only	Per Cubic metre	20,625.00
5	Providing and laying mechanically mixed and vibrated concrete for plain-cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) on ground or under water in drain including pumping or bailing out water/ dewatering removal of the slush as required at site which may arise at the time of laying concrete, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification section 800, 900 and 1200 or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, GST, toll tax or any other taxes imposed by the Government.	25.50 Cubic metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	1,26,225.00
	Total					**4,45,137.00**
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill is found to be checked & approved for Rs 445137/-

Executive Engineer,
Dehra Division,
HPPWD Dehra