Office of
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh Works Department Jaisinghpur 176095 Phone No. 01894-228030 Email ee-jaipwd-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **20.03.2025 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **19.03.2025** up to **4:00 PM** and the application for issue of tender from shall be received on **19.03.2025** up to **1:00 PM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75** days:-

Sr. No.	Name of Work	Estimated Cost in Rs.	EMD	Time limit	Cost of tender form
1	C/O Rajiv Gandhi Government Modal Day Boarding School at Solvanehr Distt. Kangra (HP) (SH:- Investigation soil bearing capacity Pil I & II)	90000.00	2000.00	Two Month	350/-
2	Upgradation, Improvement , and Strengthening of Dharamshala Dadh Palampur Holta Chadhiar Sandhole Road (Portion Baloo to Tinbar) Km 40/500-56/00 (Sh:- Preparation DPR of road under CRIF Km 50/00 to 56/00)	78000.00	2000.00	Two Month	350/-
3	Restoration of rain damages on various road under HP.PWD Sub- Division Panchrukhi (SH:- Hiring of JCB for removal of slips, Unlined drain & dressing of berms (Section Panchrukhi)	97900.00	2000.00	Two Month	350/-
4	Restoration of rain damages onPanchrukhi Lambagoan road Km 10/00 to 20/00 (SH:- C/O B/wall at RD 17/436 to 17/447)	96859.00	2000.00	Two Month	350/-
5	Restoration of rain damages on Bhawarna to Jhunga Devi road Km 15/500 to 26/250 (SH:- P/L GSB, G-II and G-III from RD 16/417.50 to 16/440)	97081.00	2000.00	Two Month	350/-
6	C/O link road to Village Alung Km 0/00 to 0/750 (SH:- C/O B/wall at RD 0/019.50 to 0/029) MNP	96515.00	2000.00	Two Month	350/-
7	C/O Link road Malli to Ward No-2 Draman Km 0/00 to 1/100 (SH:- F/C between Km 0/945 to 0/960) (SCDP)	98709.00	2000.00	Two month	350/-
8	A/A & M/O various roads in Jaisinghpur section under HP.PWD Sub- Division Jaisinghpur (SH:-Painting ,lettering of Kms Stones and sign boards etc.)	99727.00	2000.00	Three Month	350/-
9	C/O Dharamshala dadh Palampur Holta Chadhiar Sandhole road Km 0/00 to 90/00 (SH:- P/L Paver Block Km 54/987 to 54/996)	99500.00	2000.00	Two month	350/-
10	C/O Jeepable road Harsi Noula Dukhi Km 0/00 to 1/500 (SH:-C/O R/wall at RD 0/756 to 0/762) **MNP**	99767.00	2000.00	Two month	350/-
11	Restoration of rain damages on Various roads under Balakrupi Sub Division (SH:- Hiring of Hydraulic Excavator (JCB) for Removal of Slips and Boulder of various roads under Alampur Section)	99880.00	2000.00	Two Month	350/-
12	Restoration of rain damages on Link road from main road Kuhan to Village Gullana Km 0/00 to 0/720 (SH:-P/L GSB at RD 0/015 to 0/134.10 and 0/525 to 0/545)	99910.00	2000.00	Two Month	350/-
13	A/R & M/O C/O link road from Gandhigram (raina Bari) to Balh Bridge Km 1/599 to 3/099 (SH:- Maintenance of Graval road Km 2/00 to 2/300)	95888.00	2000.00	Two Month	350/-

14	C/O karori Kilhi Duhak road Km 0/00 to 5/00 (SH:- C/O breast Wall from RD 4/180 to 4/200)	9126.00	2000.00	Two Month	350/-
15	Restoration of rain damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:-C/O R/wall at RD 17/425 to 17/440)	9975.00	2000.00	Two Month	350/-
16	Restoration of rain damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:- Protection of old R/wall by providing 2 Nos. Pusta at RD 0/445)	99330.00	2000.00	Two Month	350/-

Certified that above works are of urgent nature and tenders are being called in exigency of works and in public interest.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.
(On behalf of Governor of Himachal Pradesh)

No.PWD/JSPR/CB/Tenders/2024-25- 13461-70 **Dated:** 12/03/2025

Copy to the following for information and necessary action:-

1. The Chief Engineer (K.Z.) HP.PWD., Dharamshala.
2. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
3. The Executive Engineer (IT) O/O E-in-C, HP.PWD., Shimla.
4-6. All the Assistant Engineer under this Division.
7-8. The Drawings / Accounts Branch in this office.
9. N.I.T. Register.
10. Notice Board.

Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

SCHEDULE OF QUANTITY

Name of work :-C/O Rajiv Gandhi Government Modal Day Boarding School at Solvanehr Distt. Kangra (HP) (SH:- Investigation soil bearing capacity Pil I & II)				**Estimated cost Rs.**		90000.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	**Description of Item**	**Quantity**	**Rate**		**Unit**	**Amount**
			In Figures	**In Word**		
1	Investigation of Bearing capacity of soil for C/O Rajiv Gandhi Government Modal Day Boarding School at Solvanehr Distt. Kangra (HP) Site at different locations of minimum 3.00 to 6.00 Mtr (three to six Meter) meter depth of each bore and submitted the test result complete in all respect .The rate is including GST, toll tax, Sale Tax or other taxes imposed by the Government.	12.00	7500.00	Rupees Seven Thousand Five Hundred Only	Per runing metre.	90000.00
	Total					90000.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Upgradation, Improvement , and Strengthening of Dharamshala Dadh Palampur Holta Chadhiar Sandhole Road (Portion Baloo to Tinbar) Km 40/500-56/00 (Sh:-Preparation DPR of road under CRIF Km 50/00 to 56/00)

Estimated cost Rs.	**78000.00**
Earnest Money Rs.	**2000.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Preparation of Detailed Project Report of road complete in all respect in manuscript form and submission of the same to higher office for approval. If any correction/amendment has desired by the head office the same may be corrected as desired and directed by the Engineer - Incharge . After approval the same should be submitted in fair form complete.The payment excludes any soil investigation and shall be made as per actual length of road. Preparation of survey plan showing all provision as per HPPWD Specification.The rate is inclusive of, toll tax, GST and all type of other taxes imposed by the Government	6.00	13000.00	Rupees Thirteen Thousand Only	Per Kilometre	78000.00
	Total					**78000.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP:PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on various road under HP.PWD Sub- Division Panchrukhi (SH:- Hiring of JCB for removal of slips, Unlined drain & dressing of berms (Section Panchrukhi)

					Estimated cost Rs.	**97900.00**
					Earnest Money Rs.	**2000.00**
					Time Limits	**Two Month**
S. N.	**Description of Item**	**Quantity**	**Rate**		**Unit**	**Amount**
			In Figures	**In Word**		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinary will be provided by the owner. The repair and spare watch and ward of machinary also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verfied by the Enginer-in-Charge.Note:- **The hire charges of plant machinery on per hour basis**	89.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	97900.00
	Total					**97900.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages onPanchrukhi Lambagoan road Km 10/00 to 20/00 (SH:- C/O B/wall at RD 17/436 to 17/447)				Estimated cost Rs.		96859.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	18.26	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	4109.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.20	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	90750.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	8.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	2000.00
	Total					**96859.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Bhawarna to Jhunga Devi road Km 15/500 to 26/250 (SH:- P/L GSB, G-II and G-III from RD 16/395 to 16/417.50)			Estimated cost Rs.			97081.00
			Earnest Money Rs.			2000.00
			Time Limits			Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	51.19	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	11518.00
2	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. for grading-I material and as per direction by the Engineer-in-Charge. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	29.25	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per cubic metre	39488.00

3	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	10.97	2050.00	Rupees Two Thousand Fifty Only	Per cubic Metre	22489.00
4	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) nominal size Grading-III to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.18 cum(zero point one eight cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads , lifts and other incidentals .The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the by the	10.97	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per cubic Metre	23586.00
	Total					**97081.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O link road to Village Alung Km 0/00 to 0/750 (SH:- C/O B/wall at RD 0/019.50 to 0/029) MNP	Estimated cost Rs.	96515.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	5.23	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	1177.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	24.89	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	Per Cubic Metre	93338.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	8.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	2000.00
	Total					**96515.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O Link road Malli to Ward No-2 Draman Km 0/00 to 1/100 (SH:- F/C between Km 0/945 to 0/960) (SCDP)

Estimated cost Rs.	**98709.00**
Earnest Money Rs.	**2000.00**
Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 9.80 (nine decimal eight zero) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	390.00	253.10	Rupees Two Hundred Fifty Three And Paise Ten Only	Per cubic metre	98709.00
	Total					**98709.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-A/A & M/O various roads in Jaisinghpur section under HP.PWD Sub- Division Jaisinghpur (SH:-Painting ,lettering of Kms Stones and sign boards etc.)

Estimated cost Rs.	**99727.00**
Earnest Money Rs.	**2000.00**
Time Limits	**Three month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint of Asian/ Nerolac brushing to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters with enamel paint of approval shade as per specifications, approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royality, malkana, GST and all type of other taxes imposed by the Government.	190.00	81.00	Rupees Eighty One Only	Per square metre	15390.00
2	Applying Painting two coats(excluding priming coat on new concrete masonry/plaster surfaces with readymixed paint brushing for use on floors to give an even shade including cleaning the surface of all dirt,dust and other foreign matter and sand papering as required. The rate includes octroi,royality,Malkana,Tol tax, sale tax, GST or any other taxes imposed by the Government.	190.00	86.00	Rupees Eighty Six Only	Per Square metre	16340.00
3	Writing letters of figures on any surface with synthetic enamel paint (other than white) (stop, comas, border, hyphens and like not to be measured and paid separately) in Indian letter/figure complete and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation with in all leads, lifts and other incidental The rate is including octroi, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	35050.00	1.94	Rupees One And Paise Ninety Four Only	Per letter per centimetre	67997.00
	Total					99727.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O Dharamshala dadh Palampur Holta Chadhiar Sandhole road Km 0/00 to 90/00 (SH:- P/L Paver Block Km 54/987 to 54/996)	**Estimated cost Rs.**	**99500.00**
	Earnest Money Rs.	**2000.00**
	Time Limits	**Two month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying **80 mm thick** Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness **80mm (Eighty millimetre)** as per drawings and Technical Specification Clause 1504 **(The execution of interlocking paver block shell be allowed after duly testing from the authorized labs)** and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	70.00	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per square metre	94500.00
2	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. *The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.*	0.80	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per Cubic Metre	5000.00
	Total					**99500.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP,PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O Jeepable road Harsi Noula Dukhi Km 0/00 to 1/500 (SH:-C/O R/wall at RD 0/756 to 0/762) MNP					Estimated cost Rs.	99767.00
					Earnest Money Rs.	2000.00
					Time Limits	Two Month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	8.10	225.00	Rupees Two Hundred Twenty Five Only	Per cubic Metre	1823.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	23.40	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	90090.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	15.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	3750.00
4	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section1200,1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax,GST or any other taxes imposed by the Government.	4.32	950.00	Rupees Nine Hundred Fifty Only	Per cubic Metre	4104.00
	Total					**99767.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP,PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Various roads under Balakrupi Sub Division (SH:- Hiring of Hydraulic Excavator (JCB) for Removal of Slips and Boulder of various roads under Alampur Section)

Estimated cost Rs.	**99880.00**
Earnest Money Rs.	**2000.00**
Time Limits	**Two Month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of Hydraulic Excavator of 1 cum bucket capacity @45 cum/hour for cutting/widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from road surface upto any leads and lifts up to any height and depth as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fuel and the operational staff for machinary will be provided by the owner. The repair and spare watch and ward of machinary also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verfied by the Enginer-in-Charge.Note:- **The hire charges of plant machinery on per hour basis**	90.80	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99880.00
	Total					**99880.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Link road from main road Kuhan to Village Gullana Km 0/00 to 0/720 (SH:-P/L GSB at RD 0/015 to 0/134.10 and 0/525 to 0/545)

Estimated cost Rs.	**99910.00**
Earnest Money Rs.	**2000.00**
Time Limits	**Two Month**

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401. for grading-I material and as per direction by the Engineer-in-Charge. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	65.73	1520.00	Rupees One Thousand Five Hundred Twenty Only	Per cubic metre	99910.00
	Total					***99910.00***
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-A/R & M/O C/O link road from Gandhigram (raina Bari) to Balh Bridge Km 1/599 to 3/099 (SH:- Maintenance of Graval road Km 2/00 to 2/300)					**Estimated cost Rs.**	**95888.00**
					Earnest Money Rs.	**2000.00**
					Time Limits	**Two month**
S. N.	**Description of Item**	**Quantity**	**Rate**		**Unit**	**Amount**
			In Figures	**In Word**		
1	Maintenance of gravel road including making up the loss of profile, rectifing corrugated surface, filling up of depressions, pot holes and erosion gullies by ading fresh material and compacting it with appropriate equipment or to strip excess of material from the road surface as per drawing and technical specification Clause 1905 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government	375.00	255.70	Rupees Two Hundred Fifty Five And Paise Seventy Only	Per square metre.	95888.00
	Total					**95888.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-C/O karori Kilhi Duhak road Km 0/00 to 5/00 (SH:- C/O breast Wall from RD 4/180 to 4/200)	Estimated cost Rs.	94260.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	26.40	250.00	Rupees Two Hundred Fifty Only	Per cubic Metre	6600.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	21.60	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Cubic Metre	83160.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	18.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	4500.00
	Total					**94260.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

15

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:-C/O R/wall at RD 17/425 to 17/440)

Estimated cost Rs.	99975.00
Earnest Money Rs.	2000.00
Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	18.00	200.00	Rupees Two Hundred Only	Per cubic Metre	3600.00
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	22.50	4200.00	Rupees Four Thousand Two Hundred Only	Per Cubic Metre	94500.00

	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.50	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	1875.00
						99975.00
	Total				%	
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)				
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:Protection of old R/wall by Providing 2 Nos Pusta at RD 0/445)	Estimated cost Rs.	99330.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	14.40	200.00	Rupees Two Hundred Only	Per cubic Metre	2880.00
2	Providing and laying cement concrete 1:4:8 (One cement: four sand: eight graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royality, malkana, toll tax, GST and all type of other taxes imposed by the Government.	22.40	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	95200.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section700,1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royality, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.00	250.00	Rupees Two Hundred Fifty Only	Per Running Metre	1250.00
	Total					**99330.00**
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur