

Himachal Pradesh
Public Works Department
HP.PWD Division Shahpur, Distt. Kangra (H.P)-176206
e-mail id: ee-shahpur-pwd@hp.gov.in
"SHORT TERM NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before **24-03-2025** up to 11:00 AM. and the same shall be opened on the same day at 11:30 AM. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **22-03-2025 up to 4:00 P.M** and the application for issue of tender form shall be received on **22-03-2025 up to 12:00 Noon**.

The earnest money in the shape of NSC/FDR/Saving account of the Post office/ Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1	Construction of Link Road Shahpur Gandhroop Kiari KM0/00 TO 2/400 (SH:- Construction of B/wall at Rd 0/185 to 0/195 and P/L G-II & G-II at rd 0/185 to 0/190).	99566.00	2000.00	Two Months	350/-
2	Improvement and widening of Rirlumar to Ghartarda road KM 0/000 TO 3/500 in Tehsil Shahpur Distt Kangra (H.P). (SH:- Providing and Laying Grading-II Km 2/405 to 2/750).	75250.00	1500.00	Two Months	350/-
3	C/o Pucca Path from Kishore Chand House to Deep Chand Land in Tehsil Shahpur Distt Kangra (H.P). (Deposit work.) (S.H:-Construction of Pucca path.).	99390.00	2000.00	Two Months	350/-
4	Constuction of link road Dodhamb Durgella , Batechh Via Tundu Km 0/00 to 6/450, in Tehsil Shahpur, Distt. Kangra (HP). (SH:- C/o R/Wall at RD 4/366 to 4/368.)	84767.00	1700.00	Two Months	350/-
5	Constuction of link road to Village Baldi Km 0/00 to 1/00 (Under MMSY). (SH:- Formation cutting at Rd 0/150 to 0/225.)	98947.00	2000.00	Two Months	350/-
6	Constuction of link road to Village Baldi Km 0/00 to 1/00 (Under MMSY). (SH:- Formation cutting at Rd 0/225 to 0/300.)	97537.00	2000.00	Two Months	350/-
7	Constuction of link road Dodhamb Durgella , Batechh Via Tundu Km 0/00 to 6/450, in Tehsil Shahpur, Distt. Kangra (HP). (SH:- C/o R/Wall at RD 4/370 to 4/372.)	84802.00	1700.00	Two Months	350/-
8	Annual Repair and Maintenance Dugiyari Kiyorian Daloh Baag Road Km 0/00 to 2/570. (SH:- Routine Maintenanc.)	80000.00	1600.00	One Months	350/-
9	Construction of Link Road from Garoh Dhiman Paniyari Basti to Order road Km 0/00 to 3/127.(SH:- Construction of Retaining wall Km 1/540 to 1/546.)	98094.00	2000.00	Two Months	350/-
10	Construction of Link Road from Garoh Dhiman Paniyari Basti to Order road Km 0/00 to 3/127. (SH:- Construction of Retaining wall Km 1/547 to 1/552.50.)	99650.00	2000.00	Two Months	350/-
11	Construction on Puhara Churtha Road Km 0/00 to 4/500 in Tehsil Shahpur Distt Kangra (H.P.) (S.H:-U-Shape drain at Rd 2/781 to 2/825.)	89458.00	1800.00	Two Months	350/-
12	Construction on Puhara Churtha Road Km 0/00 to 4/500 in Tehsil Shahpur Distt Kangra (H.P.) (S.H:-U-Shape drain at Rd 2/735 to 2/780.)	90390.00	1850.00	Two Months	350/-
13	Construction of Hamera Mohad Chattari road Km 0/00 to 9/100.(S.H:-Construction of Retaining wall Km 3/850 to 3/859.	94282.00	1900.00	Two Months	350/-
14	Construction of Hamera Mohad Chattari road Km 0/00 to 9/100.(S.H:-Construction of Retaining wall Km 3/863 to 3/870.10.	94499.00	1900.00	Two Months	350/-
15	Construction of 10.37 Mtr Span bridge over Bandla Nallah on Bandla Gehar road.(S.H:-Construction of approach road to bridge by Providing and laying Cement Concrete Pavement from RD.0/498.50 TO 0/520.50).	98956.00	2000.00	Two Months	350/-
16	Construction of 10.37 Mtr Span bridge over Bandla Nallah on Bandla Gehar road.(S.H:-Construction of approach road to bridge by Providing and laying Cement Concrete Pavement from RD.0/720.70 TO 0/734).	97838.00	2000.00	Two Months	350/-
17	Construction of 10.37 Mtr Span bridge over Bandla Nallah on Bandla Gehar road.(S.H:-Construction of approach road to bridge by Providing and laying Cement Concrete Pavement from RD.0/734 TO 0/742).	83524.00	1700.00	Two Months	350/-
18	Construction of road (Approximate 50.00 mtr.) from culvert main road to Bhim Roa Ambedkar Bhawan in Gramm Panchyat Thehar in Sub-Tehsil Harchakian, Distt. Kangra (HP). (Deposit Work).(S.H:-Providing and laying Cement Concrete Pavement between km 0/00 to 0/028).	83871.00	1700.00	Two Months	350/-
19	Construction of road (Approximate 50.00 mtr.) from culvert main road to Bhim Roa Ambedkar Bhawan in Gramm Panchyat Thehar in Sub-Tehsil Harchakian, Distt. Kangra (HP). (Deposit Work).(S.H:-Providing and laying Cement Concrete Pavement between km 0/029 to 0/050).	65944.00	1350.00	Two Months	350/-
20	Annual repair and maintenance of Charri Ghera road KM.0/00 TO 8/855 Under HP.PWD. Sub Division Gaggal.(S.H:-Painting and writing lettering, figures and kilometre stone etcetra.)	99310.00	2000.00	Two Months	350/-

21	Annual repair and maintenance of various roads under Under HP.PWD. Sub Division Gaggal.(S.H:-Painting and writing lettering, figures and kilometre stone etcetra.)	99273.00	2000.00	Two Months	350/-
22	Annual Repair and Maintance of PWD Rest House Shahpur in Tehsil Shahpur Distt Knagra (H.P.) (S:H:- Providing and laying panneling work in Rest House.(Fourth part).	87192.00	1750.00	Two Months	350/-
23	Annual Repair and Maintance of PWD Rest House Shahpur in Tehsil Shahpur Distt Knagra (H.P.) (S:H:- Providing and laying panneling work in Rest House.(Third part).	99000.00	2000.00	Two Months	350/-
24	Construction of additional accommodation for newly upgraded 100 bedded hospital building at Shahpur Distt Knagra (H.P.)(Deposit work).(S.H:-Repair of ramp connecting new block and old block and painting work.)	89975.00	1800.00	Two Months	350/-
25	Annual Repaire and Maintanance of Non-Residentail Building under HPPWD Division Shahpur in Tehsil Shahpur Distt Kangra (H.P.) (S.H:- Repair of National Highway Circle Office Building.(Ground and 1st floor).	78957.00	1600.00	Two Months	350/-
26	Annual Repaire and Maintanance of Non-Residentail Building under HPPWD Division Shahpur in Tehsil Shahpur Distt Kangra (H.P.) (S.H:- Repair of National Highway Circle Office Building (1st floor)	99286.00	2000.00	Two Months	350/-
27	Annual Repaire and Maintanance of Non-Residentail Building under HPPWD Division Shahpur in Tehsil Shahpur Distt Kangra (H.P.) (S.H:- Repair of National Highway Circle Office Building (Repair of Joinery work etc.at Ground and 1st floor.)	99367.00	2000.00	Two Months	350/-
28	Annual Repaire and Maintanance of Non-Residentail Building under HPPWD Division Shahpur in Tehsil Shahpur Distt Kangra (H.P.) (S.H:- Repair of National Highway Circle Office Building Ground floor.)	99554.00	2000.00	Two Months	350/-
29	C/O Junior Engineer Office Cum Residence at Darini in Tehsil Darini Distt Kangra (H.P.) (S.H:-Providing and Fixing Wood Plastic Composite (WPC) Wall Panelling. (Part-I).	86900.00	1750.00	Two Months	350/-
30	Construction of Link Road Shahpur Kiari Gandhroop road Km 0/00 to 2/400. (S.H:-Construction of Drain and P/L G-II & G-III at RD KM 0/190 to 0/195.)	96022.00	1950.00	Two Months	350/-
31	Annual Repaire and Maintanance of residential Building under HPPWD Shahpur in Tehsil Shahpur Distt Kangra (H.P.) (S.H: Providing and Laying paint work in rest house.	74235.00	1500.00	Two Months	350/-
32	A/R & M/O Various roads under Shahpur Sub Division (S.H:- Hiring of excavator cum loader on various roads under Harchakiyan section).	99000.00	2000.00	One Month	350/-
33	A/R & M/O Various roads under Shahpur Sub Division (S.H:- Hiring of excavator cum loader on various roads under Shahpur section).	99000.00	2000.00	One Month	350/-

Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions: -

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD. GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in-figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer,
Shahpur Division,
HP.PWD Shahpur.

(on behalf of Governor of Himachal Pradesh)
Dated:

No.PWD/SD/Tender/NIT/2024-25/-

Copy to following for information and necessary action:-

1. The Chief Engineer (KZ) HP,PWD Dharmshala.
2. The Superintending Engineer, 5th Circle HPPWD Palampur.
3. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
4. All the Assistant Engineer under this Division.
5. The Drawing/Accounts Branch in this office.
6. N.I.T Register.
7. Notice Board

Executive Engineer,
Shahpur Division,
HP.PWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99566.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Link Road Shahpur Kiari Gandhroop road Km 0/00 to 2/400.
SUB-HEAD :- Construction of B/Wall at Rd 0/185 to 0/195 and P/L G-II & G-III at Rd.0/185 to 0/190.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.95 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2783.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.95 Cubic metre	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	47633.00
3	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required densities as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	12.00 Cubic metre	2100.00	Rupees Two Thousand One Hundred Only		25200.00

4	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	10.25 Cubic metre	2200.00	Rupees Two Thousand Two Hundred Only	Per cubic metre	22550.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	1400.00
TOTAL :-						
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			
			99566.00			


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

Name of work :-Improvement & widening of Rirkumar to Ghartarda road km 0/000 to 3/500 in Tehsil Shahpur, District Kangra (H.P.)

(Sub Head:- Providing and Laying Grading-II km 2/405 to 2/750)

S. No.	Description of Item	Quantity	Rate In Figures	In Word Rupees Two Thousand One Hundred Fifty Only	Unit	Estimated cost Rs.	
						Earnest Money Rs.	Two Month
1	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	35.00	2150.00		Per cubic metre		75,250.00
	Total						75,250.00
	Quoted Rate(in Figures) Percentage	Excess (+)			%		
		Less (-)			%		
	G.Total in Figures						
	G.Total in Words						

Executive Engineer,
Shahpur Division,
H.P.W.D. Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99390.00
 EARNST MONEY :- ₹ 2000.00
 TIME LIMIT :- Two Months

NAME OF WORK :- C/o Pucca Path from Kishore Chand House to Deep Chand Land in Tehsil Shahpur Distt Kangra (H.P.) (Deposit work.)
 SUB-HEAD :- Construction of Pucca path.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock, chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	28.70	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	10045.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.70	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	89345.00
TOTAL :-						99390.00
(Amount to be quoted by the contractor in Figure)						
(Amount to be quoted by the contractor in words)						
Quoted Rate in Figure (%)						
Quoted Rate in Words (%)						


 Executive Engineer,
 Shahpur Division,
 H.P.W.D. Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 84767.00
 EARNEST MONEY :- ₹ 1700.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of link road Dodhamb Durgella, Batechh Via Tundu Km 0/00 to 6/450. in Tehsil Shahpur, Distt. Kangra (HP).

SUB-HEAD :- C/o R/Wall at RD 4/366 to 4/368.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.96 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1036.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.26 Cubic metres	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	79431.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	1750.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.00 Cubic metres	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2550.00
TOTAL :-						84767.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

Name of work :-Construction of link road to Village Baldi km 0/0 to 1/00. (under MMSY)
(SH:- Formation cutting at RD 0/150 to 0/225)

Executive Engineer,
Shahpur Division,
HP.PWD, Shahpur

SCHEDULE	
Name of work :-Construction of link road to Village Baldi	km 0/0 to 1/00.(under MMSY)

(SH:- Formation cutting at RD 0/225 to 0/300)

Executive Engineer,
Shabpur Division,
HR PWD Shabpur

Executive Engineer,
Shahpur Division,
HR PWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 84802.00
 EARNEST MONEY :- ₹ 1700.00
 TIME LIMIT : Two Months

NAME OF WORK :- Constuction of link road Dodhamb Durgella , Batechh Via Tundu Km 0/00 to 6/450. in Tehsil Shahpur, Distt. Kangra (HP).

SUB-HEAD :- C/o R/Wall at RD 4/370 to 4/372.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.06 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1071.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.26 Cubic metres	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	79431.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	1750.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.00 Cubic metres	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2550.00
TOTAL :-						84802.00
(Amount to be quoted by the contractor in Figure)						
(Amount to be quoted by the contractor in words)						
Quoted Rate in Figure (%)						
Quoted Rate in Words (%)						


 Executive Engineer,
 Shahpur Division,
 H.P. WD Shahpur

8

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 80000.00
 EARNEST MONEY :- ₹ 1600.00
 TIME LIMIT : One Month

NAME OF WORK Annual Repair and Maintenance Dugiyari Kiyorian Daloh Baag Road Km 0/00 to 2/570.

SUB-HEAD :- Routine Maintenance.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Restoration of rain cuts trimming of grass and weeds from the shoulder/berms and cutting of branches of trees, shrubs from road way and disposing off the same to suitable locations, cleaning the road side drain, culverts maintenance of kilometer stone, sign boards and providing white washing along the road complete (wherever is required) in all respect including entire carriage of materials within all leads, lifts and other incidentals and as per direction OF Engineer-in-Charge as per schedule. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	2.00 Kilometre	40000.00	Rupees Forty Thousand Only	Per Kilometre	80000.00
TOTAL :-						80000.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98094.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Link Road from Garoh Dhiman Paniyari Basti to Order road Km 0/00 to 3/127.
 SUB-HEAD :- Construction of Retaining wall Km 1/540 to 1/546.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.55 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2993.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	20.45 Cubic metre	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	88958.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	1400.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.58 Cubic metre	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4743.00
TOTAL :-						98094.00
Quated Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quated Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99650.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Link Road from Garoh Dhiman Paniyari Basti to Order road Km 0/00 to 3/127.
 SUB-HEAD :- Construction of Retaining wall Km 1/547 to 1/552.50.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.60 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3010.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	20.80 Cubic metre	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	90480.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	1400.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.60	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4760.00
TOTAL :- 99650.00						
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 H.P.W.D. Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 89458.00
 EARNEST MONEY :- ₹ 1800.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction on Puhara Churtha Road Km 0/00 to 4/500 in Tehsil Shahpur Distt Kangra (H.P.)
 SUB-HEAD :- U-Shape drain at Rd 2/781 to 2/825.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	27.00 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	9450.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	14.60 Cubic metre	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	80008.00
TOTAL :-						89458.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPWD Shahpur

12

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 90390.00
EARNEST MONEY :- ₹ 1850.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction on Puhara Churtha Road Km 0/00 to 4/500 in Tehsil Shahpur Distt Kangra (H.P.)
SUB-HEAD :- U-Shape drain at Rd 2/735 to 2/780.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2 Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3 27.00 Cubic metre	4 350.00	5 Rupees Three Hundred Fifty Only	6 Per cubic metre	7 9450.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	14.77 Cubic metre	5480.00	Rupees Five Thousand Four Hundred Eighty Only	Per cubic metre	80940.00
TOTAL :-						90390.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 94282.00
 EARNEST MONEY :- ₹ 1900.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Harnera Mohad Chattari road Km 0/00 to 9/100.

SUB-HEAD :- Construction of Retaining wall Km 3/850 to 3/859.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.46 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3661.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.45 Cubic metre	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	84608.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	2800.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.78	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	3213.00
TOTAL :-						94282.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 94499.00
 EARNEST MONEY :- ₹ 1900.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Harnera Mohad Chattari road Km 0/00 to 9/100.
 SUB-HEAD :- Construction of Retaining wall Km 3/863 to 3/870.10.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.56 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3346.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	19.67 Cubic metre	4350.00	Rupees Four Thousand Three Hundred Fifty Only	Per cubic metre	85565.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	2800.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.28	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2788.00
TOTAL :-						
94499.00						
(Amount to be quoted by the contractor in Figure)						
(Amount to be quoted by the contractor in words)						
Quoted Rate in Figure (%)						
Quoted Rate in Words (%)						

1351
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98956.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of 10.37 Mtr Span bridge over Bandla Nallah on Bandla Gehar road.

SUB-HEAD :- Construction of approach road to bridge by Providing and laying Cement Concrete Pavement from RD.0/498.50 TO 0/520.50

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Construction of plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement and any other equivalent type as per Clause 1501 using M25 (Grade), (design mix) concrete having coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	13.84 Cubic metres	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	98956.00
TOTAL :-						98956.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

13-7
 Executive Engineer,
 Shahpur Division,
 Haryana
 Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97838.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of 10.37 Mtr Span bridge over Bandla Nallah on Bandla Gehar road.

SUB-HEAD :- Construction of approach road to bridge by Providing and laying Cement Concrete Pavement from RD.0/720.70 TO 0/734

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregates of 90mm to 45mm (ninety millimetres to forty five millimetre) Grading-I, 10mm (one hundred millimetre) Compacted thickness to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (Eighty-hundred) kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density as per Technical Specification Clause 405 as per the entire satisfaction and directions of Engineer-in-Charge. including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.73 Cubic metres	2100.00	Rupees Two Thousand One Hundred Only	Per cubic metre	18333.00
2	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government. y, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	5.02 Cubic metres	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per cubic metre	10793.00

3	Construction of plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement and any other equivalent type as per Clause 1501 using M25 (Grade),(design mix) concrete having coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	9.61 Cubic metres	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	68712.00
Quoted Rate in Figure (%)						TOTAL :-
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in Figure)
						(Amount to be quoted by the contractor in words)
						97838.00


 Executive Engineer,
 Shahpur Division,
 HPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 83524.00
 EARNEST MONEY :- ₹ 1700.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of 10.37 Mtr Span bridge over Bandla Nallah on Bandla Gehar road.

SUB-HEAD :- Construction of approach road to bridge by Providing and laying Cement Concrete Pavement from RD.0/734 TO 0/742

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregates of 90mm to 45mm (ninety millimetres to forty five millimetre) Grading-I, 10mm (one hundred millimetre) Compacted thickness to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (Eighty-hundred) kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density as per Technical Specification Clause 405 as per the entire satisfaction and directions of Engineer-in-Charge. including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.56 Cubic metres	2100.00	Rupees Two Thousand One Hundred Only	Per cubic metre	15876.00
2	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government. γ, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	4.56 Cubic metres	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per cubic metre	9804.00

3	Construction of plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement and any other equivalent type as per Clause 1501 using M25 (Grade),(design mix) concrete having coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.09 Cubic metres	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	57844.00
TOTAL :-						83524.00
(Amount to be quoted by the contractor in Figure)						
(Amount to be quoted by the contractor in words)						
Quoted Rate in Figure (%)						
Quoted Rate in Words (%)						


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 83871.00
 EARNEST MONEY :- ₹ 1700.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of road (Approximate 50.00 mtr.) from culvert main road to Bhim Roa Ambedkar Bhawan in Gramm Panchyat Thehar in Sub-Tehsil Harchakian, Distt. Kangrta (HP). (Deposit Work).

SUB-HEAD :- Providing and laying Cement Concrete Pavement between km 0/00 to 0/028).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.35 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2223.00
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per drawing and technical specification. as per direction of Engineer-in-Charge including carriage of materials within all leads , lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	7.06 Cubic metres	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	6001.00

3	Construction of plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement and any other equivalent type as per Clause 1501 using M25 (Grade),(design mix) concrete having coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.58 Cubic metres	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	75647.00
Quoted Rate in Figure (%)						TOTAL :-
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in Figure)
						(Amount to be quoted by the contractor in words)
						83871.00


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 65944.00
 EARNEST MONEY :- ₹ 1350.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of road (Approximate 50.00 mtr.) from culvert main road to Bhim Roa Ambedkar Bhawan in Gramm Panchyat Thehar in Sub-Tehsil Harchakian, Distt. Kangra (HP). (Deposit Work).

SUB-HEAD :- Providing and laying Cement Concrete Pavement between km 0/029 to 0/050).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable. / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.99 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1747.00
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) as per drawing and technical specification. as per direction of Engineer-in-Charge including carriage of materials within all leads , lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax or any type of taxes imposed by the Government.	5.54 Cubic metres	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4709.00

3	Construction of plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement and any other equivalent type as per Clause 1501 using M25 (Grade),(design mix) concrete having coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.32 Cubic metres	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	59488.00
TOTAL :-						65944.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99310.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Annual repair and maintenance of Charri Ghera road KM.0/00 TO 8/855 Under HP.PWD. Sub Division Gaggal.
 SUB-HEAD :- Painting and writing lettering, figures and kilometre stone etcetra.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Painting two coats (excluding priming coat) on previously steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface to remove all dirt,dust and other foreign matter with enamel paint other than white including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	45.00 Squre metre	36.10	Rupees Thirty Six And Paise Ten Only	Per square metre	1625.00
2	Painting two or more coats of Nerolac/Asian paint/ Berger (excluding priming coat) on previously concrete based surface with enamel paint white to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering and stoping, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. Therate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	45.00 Squre metre	86.10	Rupees Eighty Six And Paise Ten Only	Per square metre	3875.00
3	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, comas, hyphens and the like not to be measured and paid separately ,Block letters, Indian letters / figures etc. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	35400.00 Per letter per centimetre hight	2.65	Rupees Two And Paise Sixty Five Only	Per letter per centimetre hight	93810.00
Quoted Rate in Figure (%)						TOTAL :- 99310.00
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in Figure)
						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shabgarh

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99273.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT: - Two Months

NAME OF WORK :- Annual repair and maintenance of various roads under Under HP.PWD. Sub Division Gaggal.
SUB-HEAD :- Painting and writing lettering, figures and kilometre stone etcetra.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Painting two coats (excluding priming coat) on previously steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface to remove all dirt,dust and other foreign matter with enamel paint other than white including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	3 44.00 Squire metre	36.10	5 Rupees Thirty Six And Paise Ten Only	6 Per square metre	7 1588.00
2	Painting two or more coats of Nerolac/Asian paint/ Berger (excluding priming coat) on previously concrete based surface with enamel paint white to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering and stoping , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	45.00 Squire metre	86.10		Per square metre	3875.00
3	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, comas, hyphens and the like not to be measured and paid separately ,Block letters, Indian letters / figures etc. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	35400.00 Per letter per centimetre hight	2.65		Per letter per centimetre hight	93810.00
Quoted Rate in Figure (%)						TOTAL :-
Quoted Rate in Words (%)						99273.00
(Amount to be quoted by the contractor in Figure)						
(Amount to be quoted by the contractor in words)						

Asst
 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 87192.00
EARNEST MONEY :- ₹ 1750.00
TIME LIMIT : Two Months

NAME OF WORK :- Annual Repaire and Maintanance of PWD Rest house Shahpur in Tehsil Shahpur Distt Kangra (H.P.)
SUB-HEAD :- Providing and laying panneling work in Rest house. (Fourth part).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and Fixing 12mm (Twelve millimetre) thick 2nd class Teak wood battens in skirting/linning in wall with butt jointing making grooves of required pattern including fixing of moulding at top and bottom base of 9mm thick century ply smooth surface of wooden battens complete in all respect as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.22	4500.00	Rupees Four Thousand Five Hundred Only	Per Square metre	45990.00
2	Polishing two coats with Melamine polish on new wood and wood based surface to give an even surface including cleaning the surface of all dirt, dust and sand papere smooth and including a coat of wood filler as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	43.37	950.00	Rupees Nine Hundred Fifty Only	Per Square metre	41202.00
Quated Rate in Figure (%)						TOTAL :-
Quated Rate in Words (%)						(Amount to be quoted by the contractor in Figure)
						(Amount to be quoted by the contractor in words)
						87192.00


Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Annual Repaire and Maintanance of PWD Rest house Shahpur in Tehsil Shahpur Distt Kangra (H.P.)

SUB-HEAD :- Providing and laying panneling work in Rest house. (Third part).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and Fixing 12mm (Twelve milimetre) thick 2nd class Teak wood battens in skirting/linning in wall with butt jointing making grooves of required pattern including fixing of moulding at top and bottom base of 9mm thick century ply smooth surface of wooden battens complete in all respect as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22.00	4500.00	Rupees Four Thousand Five Hundred Only	Per Square metre	99000.00
TOTAL :-						99000.00
Quated Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quated Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 89975.00
EARNEST MONEY :- ₹ 1800.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of additional accommodation for newly upgraded 100 bedded hospital building at Shahpur Distt Knagra (H.P.) (Deposit work).
SUB-HEAD :- Repair of ramp connecting new block and old block and painting work.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Painting with satin enamel of Asian/Nerolac Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	490.04	160.00	Rupees One Hundred Sixty Only	Per Square metre	78406.00
2	Providing and fixing glazing in door, window, ventilator shutters and partitions etcetra with EPDM rubber / neoprene gasket etcetra With Frosted glass of 4 mm (four millimetre) thickness weight not less than 10.00 kg/ sqm (ten point zero kilogram per square metre) of Modi Guard / Saint Gobain, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST and all type of other taxes imposed by the Government.	10.06	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Square metre	11569.00
TOTAL :-						89975.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

B37
Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 78957.00
 EARNEST MONEY :- ₹ 1600.00
 TIME LIMIT : Two Months

NAME OF WORK :- Annual Repaire and Maintanance of Non-Residential Building under HPPWD Division Shahpur in Tehsil Shahpur Distt Kangra (H.P.)
SUB-HEAD :- Repair of National Highway Circle Office Building. (Ground and 1st floor).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Finishing walls with Acrylic Smooth exterior paint of Asian / Dulux / Berger / Nerolac Suraksha shade New work (Two or more coat applied @ 1.67 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	310.00 Squre Metre	95.10	Rupees Ninety Five And Paise Ten Only	Per Squire metre	29481.00
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs: to scratches etc. complete: as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other Incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	310.00 Squre Metre	17.50	Rupees Seventeen And Paise Fifty Only	Per Squire metre	5425.00
3	Providing and fixing aluminium handle 75 mm (Seventy five millimetre) ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etcetra complete, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	11.00 Number	55.10	Rupees Fifty Five And Paise Ten Only	Each	606.00
4	Providing and fixing aluminium tower bolts, (100 x 10 mm) ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetra complete, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	20.00 Number	71.50	Rupees Seventy One And Paise Fifty Only	Each	1430.00

5	Providing and fixing hydraulic door closer tubular type aluminium section body transparent or dyed to required colour or shade, with necessary screws etcetra complete, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.00 Number	1100.00	Rupees One Thousand One Hundred Only	Each	1100.00
6	Providing and fixing 19 mm (Nineteen millimetre) thick phenol bonded (both Side) prelaminated BWP Grade particle board in matt finish flat pressed three layer or graded wood particle board conforming to IS: 12823 of Action Tesa / Greenlam / Merinolam / Kitlam / Vista approved shade Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etcetra complete as per architectural drawings and directions of Engineer- in-charge. Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side including carriage og material within all leads, lifts and other incidentals, as per approved drawing, design, specifications, specification and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	5.00 Squre Metre	2050.00	Rupees Two Thousand Fifty Only	Per Squre metre	10250.00
7	Providing and fixing Brass cupboard lock 6 levers of approved quality, 40 mm size necessary screws etcetra complete, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.00 Number	72.50	Rupees Seventy Two And Paise Fifty Only	Each	73.00
8	Providing and fixing magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete Double strip (horizontal type) including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	1.00 Number	45.10	Rupees Forty Five And Paise Ten Only	Each	45.00
9	Structural steel work of TATA/ SAIL riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	121.00 Killogram	112.00	Rupees One Hundred Twelve Only	Per Killograme	13552.00

10	Providing and fixing 0.60mm (Zero point six zero millimetre) thick pre-painted steel sheet roofing of TATA Durashine/ SAIL/ Reliance/ Jindal steel over steel trussed in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (six millimetre) dia metre with pre-painted limpet and rubber washers complete with all accessories as required, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST and all type of other taxes imposed by the Government.	8.24	1550.20	Rupees One Thousand Five Hundred Fifty And Paise Twenty Only	Per Square metre	12774.00
11	Finishing walls with Acrylic Smooth interiors paint of Asian / Dulux / Berger / Nerolac Suraksha paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	10.20	95.10	Rupees Ninety Five And Paise Ten Only	Per Square metre	970.00
12	Providing and fixing wash basin White Vitreous China Flat back wash basin Garnet no 10080 size 580x 430 mm (five hundred eighty into four hundred thirty) (Under counter Basin) Hindware , Cera Jaquar of star white / Snow white shade and as shown in the drawing / as per details with single 15 mm (Fifteen millimetres) C.P. brass pillar tap with C.I. brackets, 15 mm (fifteen millimetres) C.P. brass pillar taps, 32 mm (Thirty two millimetres) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	3250.50	Rupees Three Thousand Two Hundred Fifty And Paise Fifty Only	Each	3251.00
TOTAL :-						78957.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99286.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Annual Repair and Maintenance of Non-Residential Building under HPPWD Division Shahpur in Tehsil Shahpur Distt Kangra (H.P.)

SUB-HEAD :- Repair of National Highway Circle Office Building (1st floor)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Distemping (two coats) with acrylic oil bound washable distemper with Nerolac/ Asian paints of approved brand and manufacture and of required shade on ceiling/sloping roof surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge.	315.00 Squre Metre	72.50	Rupees Seventy Two And Paise Fifty Only	Per Square metre	22838.00
2	Wall painting with premium acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	980.10 Squre Metre	78.00	Rupees Seventy Eight Only	Per Square metre	76448.00
TOTAL :-						99286.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99637.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Annual Repaire and Maintanance of Non-Residential Building under HPPWD Division Shahpur in Tehsil Shahpur Distt Kangra (H.P.)
SUB-HEAD :- Repair of National Highway Circle Office Building (Repair of Joinery work etc.at Ground and 1st floor.)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing aluminium Frame work Jindal/ Hindalco for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (glazing, paneling and dash fasteners to be paid for separately Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15 (fifteen)) within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	82.00 Kilogramms	520.00	Rupees Five Hundred Twenty Only	Per Kilogram	42640.00
2	Providing and fixing aluminium work for shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15 (fifteen) within all leads, lifts of materials and other incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	40.00 Kilogramms	525.00	Rupees Five Hundred Twenty Five Only	Per Kilogram	21000.00
3	Painting with synthetic enamel paint Asian / Dulux / Berger / Nerolac Suraksha paints of approved brand and manufacture of required colour to give an even shade two or more coats on new wood work , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	423.00 Squire Metre	85.10	Rupees Eighty Five And Paise Ten Only	Per Squire metre	35997.00
TOTAL :-						99637.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)


Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99554.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Annual Repaire and Maintanance of Non-Residentail Building under HPPWD Division Shahpur in Tehsil Shahpur Distt Kangra (H.P.)
SUB-HEAD :- Repair of National Highway Circle Office Building. (Ground Floor).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Finishing walls with Acrylic Smooth exterior paint of Asian / Dulux / Berger / Nerolac Suraksha paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	310.05 Squre Metre	95.10	Rupees Ninety Five And Paise Ten Only	Per Squire metre	29486.00
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	310.00 Squire Metre	9.50	Rupees Nine And Paise Fifty Only	Per Squire metre	2945.00
3	Providing and laying 600x600mm (six hundred into six hundred millimetre) size double charge / ultra charge Vitrified tiles of Restile/ Nitco/ Rak/ Kajaria/ Orientbell/ Simpolo/ AGL/ Johnson/ Somany as per approved shade and design (thickness to be specified by manufacturer), with water absorption less than 0.08 % (zero decimal zero eight percent) and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm (twelve millimetre) thick bed of cement mortar 1:3 (one cement isto three coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three point three kilogramme per square metre) including grouting the joint with white cement & matching pigments etcetra complete, and carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications and as directed by Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	26.05 Squire Metre	1450.10	Rupees One Thousand Four Hundred Fifty And Paise Ten Only	Per Squire metre	37775.00

4	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	26.05 Cubic metres	950.00	Rupees Nine Hundred Fifty Only	Per Cubic metres	24748.00
5	Providing and fixing glazing in door, window, ventilator shutters and partitions etcetra with EPDM rubber / neoprene gasket etcetra With Frosted glass of 4 mm (four millimetre) thickness weight not less than 10.00 kg/ sqm (ten point zero kilogram per square metre) of Modi Guard / Saint Gobain, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	4.00 Squire Metre	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Squire metre	4600.00
TOTAL :-						99554.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 86900.00
 EARNEST MONEY :- ₹ 1750.00
 TIME LIMIT : Two Months

NAME OF WORK :- C/O Junior Engineer Office Cum Residence at Darini in Tehsil Darini Distt Kangra (H.P.)
 SUB-HEAD :- Providing and Fixing Wood Plastic Composite (WPC) Wall Panelling. (Part-I).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2 Providing & fixing 14mm (fourteen millimetre) (WPC(Wood Plastic Composites) Panelling/Lining(7.7" x 116"=2.95 x .20 Mtr. Make of approved side and brand of area 7.7" x 116" =2.95 x 0.20 Mtr. =0.590 Sqm for interior side including cutting and fixing in position. The WPC also not easy to deform, moisture proof, insect and fire resistance in all type of decorative colours of approved brands and as per the direction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3 43.45 Sqm metre	4 2000.00	5 Rupees Two Thousand Only	6 Per square metre	7 86900.00
TOTAL :-						86900.00
		(Amount to be quoted by the contractor in Figure)				
		(Amount to be quoted by the contractor in words)				
		Quoted Rate in Figure (%)				
		Quoted Rate in Words (%)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 96022.00
 EARNEST MONEY :- ₹ 1950.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Link Road Shahpur Kiari Gandhroop road Km 0/00 to 2/400.

SUB-HEAD :- Construction of Drain and P/L G-II & G-III at RD KM 0/190 to 0/195.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.85 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2748.00
2	Providing laying spreading and compacting by manual means of stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the Government.	12.03 Cubic metre	2100.00	Rupees Two Thousand One Hundred Only	Per cubic metre	25263.00

3	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	10.25 Cubic metre	2200.00	Rupees Two Thousand Two Hundred Only	Per cubic metre	22550.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	8.45 Cubic metre	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	45461.00
TOTAL :-						96022.00
(Amount to be quoted by the contractor in Figure)						
(Amount to be quoted by the contractor in words)						
Quoted Rate in Figure (%)						
Quoted Rate in Words (%)						



 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 74235.00
EARNEST MONEY :- ₹ 1500.00
TIME LIMIT : Two Months

NAME OF WORK :- Annual Repaire and Maintanance of residential Building under HPPWD Shahpur in Tehsil Shahpur Distt Kangra (H.P.)
SUB-HEAD :- Providing and Laying paint work in rest house.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Finishing walls with Acrylic Smooth exterior paint of Asian / Dulax / Berger / Nerolac Suraksha paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	499.01 Squre Metre	98.50	Rupees Ninety Eight And Paise Fifty Only	Per Square metre	49152.00
2	Finishing walls with Acrylic Smooth Interiors paint of Asian / Dulax / Berger / Nerolac Suraksha paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	263.75 Squre Metre	95.10	Rupees Ninety Five And Paise Ten Only	Per Square metre	25083.00
TOTAL :-						74235.00
Quated Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quated Rate in Words (%)						(Amount to be quoted by the contractor in words)


Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- A/R & M/O Various roads under Shahpur Sub Division.

SUB-HEAD :- Hiring of excavator cum loader on various roads under Harchakiyan Section.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of J.C.B./Excavator cum loader (J.C.B.) for removal of slips including trimming and edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil due to non availability of departmental machinery as per direction and entire satisfaction of engineering-in- Charge. The J.C.B./Excavator cum loader should work minimum 8.00 (eight) hours daily and excavated at least 30.00(thirty) cubic metre quantity per hour . Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fule and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. No deviation shall be allowed in any case.	90.00 Hours	1100.00	Rupees One Thousand One Hundred Only	Per hours	99000.00
Quoted Rate in Figure (%)						TOTAL :- 99000.00
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in Figure)
						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99000.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- A/R & M/O Various roads under Shahpur Sub Division.

SUB-HEAD :- Hiring of excavator cum loader on various roads under Shahpur Section.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Hiring of J.C.B./Excavator cum loader (J.C.B.) for removal of slips including trimming and edge cutting true to the required line, width and grade in all kind and classification of soil including rocky portion and saturated soil due to non availability of departmental machinery as per direction and entire satisfaction of engineering-in-Charge. The J.C.B./Excavator cum loader should work minimum 8.00 (eight) hours daily and excavated at least 30.00(thirty) cubic metre quantity per hour . Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the J.C.B./Excavator owner which shall have to be fully compensated by the contractor in all cases. The fule and operational staff for Excavator will be provided by the owner. The repair and spare, watch and ward of Excavator also be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. No deviation shall be allowed in any case.	90.00 Hours	1100.00	Rupees One Thousand One Hundred Only	Per hours	99000.00
TOTAL :-						99000.00
Quated Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quated Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur