



"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 20.06.2025 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 18.06.2025 up to 10.00 A.M. to 12:00 P.M. and tender form can be had from this office on 19.06.2025 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Development of ground, Mela Ghera Balh Mohal in GP Pihar Bedlu MP Lad Rajya Sabha Deposit (Sub Head:- Formation Cutting in Km 0/000 to 0/008) MPLADS :MPR/2022/43).	Rs. 84,628/-	Rs. 1,700/-	Rs. 350/-	Class "D"	Three months
2	Construction of road Mokshdham Siyun Banander in GP Maman (Sub Head:- Formation Cutting in km 0/000 to 0/120 under deposit MPLADS:MPR/2022/42).	Rs. 89,299/-	Rs. 1,800/-	Rs. 350/-	Class "D"	Three months
3	Construction of Old Samudayak Bhawan SC Basti Outpur G.P. Outpur Mohal under (MP Lad Deposit) (Sub Head:- Construction of Retaining wall at RD 0/00 to 0/004.90) MPLADS :MPR/2022/40).	Rs. 84,259/-	Rs. 1,700/-	Rs. 350/-	Class "D"	Two months
4	Development of Ground, Mela Ghera Balh Mohal in GP Pihar Bedlu under MP Lad Rajya Sabha Deposit (Sub Head:- Formation Cutting in Km 0/008 to 0/015) MPLADS:MPR/2022/43).	Rs. 48,932/-	Rs. 1,000/-	Rs. 350/-	Class "D"	Three months
5	Construction of road Mokshdham Siyun Banander in GP Maman (Sub Head:- Formation Cutting in km 0/120 to 0/165 under deposit MPLADS: MPR/2022/42).	Rs. 82,816/-	Rs. 1,700/-	Rs. 350/-	Class "D"	Three months
6	Construction of Old Samudayak Bhawan SC Basti Outpur G.P. Outpur Mohal under MP Lad Deposit (Sub Head:- Construction of Retaining wall at 0/009.80) MPLADS: MPR/2022/40).	Rs. 84,259/-	Rs. 1,700/-	Rs. 350/-	Class "D"	Two months
7	Construction & M/T of link road from Galu Bhatwari road to Village Badan & Chhanag Dhar Km. 0/0 to 3/0 in GP Ropa Padhar (SH:- Formation cutting in Km. 1/030 to 1/101) under deposit SID BSP/2024/803).	Rs. 99,656/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
8	Construction & M/T of link road from Galu Bhatwari road to Village Badan & Chhanag Dhar Km. 0/0 to 3/0 in GP Ropa Padhar (SH:- Formation cutting in Km. 1/120 to 1/177 to 0/932) under deposit SID BSP/2024/803).	Rs. 98,467/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
9	C/O link Road Machhyal to Dibh (BSP/2024/463) (deposit) (SH:- Hiring of Excavator cum loader for ROFD & F/C in between km. 0/0 to 1/100).	Rs. 41,275/-	Rs. 1,000/-	Rs. 350/-	Class "D"	One months

Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-VNIT/Press/2025-26-

3222 - 71

Dated:- 22/05/2025


1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

Job -1

SCHEDULE OF QUANTITY


Name of Work: Devolpoment of Ground, Mela Ghera Balh Mohal in GP Pihar Bedhlu (SH: Formation Cutting in km 0/000 to 0/008) M P L A P S : M P R / 2022/43. (Debris it)					Estimate Cost: Earnest Money: Time Limit :			84,628.00 1,700.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P			
				Figures	Words				
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 17.20 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	430.00	Per cubic metre						
Total									


Executive Engineer
B & R Division HP.PWD.
Joginder Nagar

Job-2

SCHEDULE OF QUANTITY

Name of Work: Construction of road Mokshdham Siyun Banander in GP Maman (SH: Formation Cutting in km 0/000 to 0/120) under deposit MPLADS: MPR/2022/42.				Estimate Cost: Earnest Money: Time Limit :			89,299.00 1,800.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Words	AMOUNT	
				Figures			Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 58.11 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	337.08	Per cubic metre					
Total								



Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job: 3

SCHEDULE OF QUANTITY

Name of Work : Construction of Old Samudayak Bhawan SC Basti Output Mohal under Deposit (SH: Construction of Retaining wall at RD 0/00 to 0/004.90) MPLADS: MPK/2022/40. MP Lead				Estimate Cost: Earnest Money: Time Limit :			84,259.00 1,700.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	Rs.	P
				Figures	Words			
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	7.28	Per cubic metre					
2.	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water .dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	15.53	Per cubic metre					
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	4.85	Per cubic metre					


4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes	4.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar

Job-4

SCHEDULE OF QUANTITY

Name of Work: Devolpoment of Ground, Mela Ghera Balh Mohal in GP Pihar Bedhlu Under m8 lad Rajya Sabha (SH: Formation Cutting in km 0/008 to 0/015) MPLADS : MPR/2022/43. (Deposit)				Estimate Cost: Earnest Money: Time Limit :		48,932.00 1,000.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 7.80 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	259.86	Per cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD,
Jalandhar Nagar

Name of Work: Construction of road Mokshdham Siyun Banander in GP Maman (SH: Formation Cutting in km 0/120 to 0/165) Under deposit MPLADS : MPR/2022/42.				Estimate Cost: 82,816.00 Earnest Money: 1,700.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 58.98 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	298.92	Per cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-6

SCHEDULE OF QUANTITY


Name of Work : Construction of Old Samudayak Bhawan SC Basti Output Mohal under Deposit (SH: Construction of Retaining wall at RD 0/004.90 to 0/009.80) MPLADS, MP 2022/40 M P Local				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate	AMOUNT	
				Figures	Words	Rs. P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D. technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levied by the government time to time excluding GST.	7.28	Per cubic metre			
2	Providing and laying cement concrete 1:5:10 (one cement: five sand: ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls, in or under water complete including, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900, 1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levied by the government time to time excluding GST.	15.53	Per cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levied by the government time to time excluding GST.	4.85	Per cubic metre			

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes	4.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD.
 Joginder Nagar


SCHEDULE OF QUANTITY

Name of Work: Construction & M/T of link road from Galu Bhatwari road to Village Badan & Chhanang Dhar km.0/0 to 3/0 in GP Ropa Padhar.(Sh:-Formation cutting in km.1/030 to 1/101) under deposit SID:BSP/2024/803				Estimate Cost: Earnest Money: Time Limit :		
				99,656.00 2,000.00 Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 37.99cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	404.12	Per cubic metre			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work: Construction & M/T of link road from Galu Bhatwari road to Village Badan & Chhanang Dhar km.0/0 to 3/0 in GP Ropa Padhar.(Sh:-Formation cutting in km.1/120 to 1/177) under deposit SID:BSP/2024/803				Estimate Cost: Earnest Money: Time Limit :			98,467.00 2,000.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate			AMOUNT	
				Figures	Words		Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 37.99cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	399.30	Per cubic metre					
		Total						



 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

Job (9)

620

SCHEDULE OF QUANTITY

Name of Work: Construction of link road Machyal to Dibh (BSP/2024/463) (Deposit) (Sub Head:-Hiring of excavator cum Loader for ROFD & F/C in between km 0/00 to 1/100				Estimate Cost: Earnest Money: Time Limit : One Month		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Hiring of hydraulic excavator cum loader of 1.00(one point Zero) cubic metre loader capacity for ROFD in narrow reaches of curves having out put not less than 40(Forty) cubic metre per hour i.e cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge.The rate is inclusive all taxes including GST levy by the government time to time.	32.50	Per working hour			
Total						


Executive Engineer
B & R Division HP.PWD.
Joginder Singh