Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2024-25/ 1674-78 Dated/ 23/5/25

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pardesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter No. PBW(B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

'NOTICE INVITING TENDERS'

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 04.06.2025 up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 03.06.2025 up to 4.00 P.M and the application for issue of tender form shall be received 02.06.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	Completion of road from Main road to Smt. Rajo Devi House Ward No. 5 (SW:- C/o CC Pavement RD 0/100 to 0/141.20 (Deposit)	Rs. 98,348.00	Rs. 2,000.00	Three Months
2	Jeepable road from Sh. Dhanu Ram S/o Sh. Giga Ram house to Govt. Agri Farm Ward No. 3 (Deposit) (SW:- C/o CC Pavement RD 0/000 to 0/035.50 (Deposit)	Rs. 99,059.00	Rs. 2,000.00	Three Months
3	C/o Jeepable road from main road to Capt. Jaiveer Choudhary house Ward No. 5 (SW:- P/L G-II and CC Pavement Km 0/00 to 0/020 (MPLAD)	Rs. 74,668.00	Rs. 1,500.00	Three Months
4	C/o Retaining wall for protection of the land of Sh. Mayank Sharma S/o Sh. Swaroop Chand Ghar (SW:- C/o Breast Wall (Deposit)	Rs. 74,020.00	Rs. 1,500.00	Three Months
5	C/o Pucca Path along with Pulli near Bhiral Khad Ward No 7 Nachir (SW:- P/L Cement Concrete Pucca path from RD 0/000 to 0/015 & C/o R/Wall from RD 0/050 to 0/054.35 (Deposit)	Rs. 73,780.00	Rs. 1,500.00	Three Months

6	C/o Pucca Path along with Pulli near Bhiral Khad Ward No 7 Nachir (SW:- C/o Approach from existing Pulli and P/L Cement concrete for Pucca path from RD 0/015 to 0/030 (Deposit)	Rs. 73,223.00	Rs 1,500.00	Three Months
7	C/o Jeepable road from main road to Mahasha Basti Ward No. 2 Balla (SW:- Providing and laying Interlocking Paver 60 MM and Side locking at RD 0/00 to 0/027 (VKVNY)	Rs. 98,415.00	Rs. 2,000.00	Two Months
8	C/o Jeepable road from main road to Mahasha Basti Ward No. 2 Balla (SW:- Providing and laying Interlocking Paver 60 MM and Side locking at RD 0/29 to 0/056 (VKVNY)	Rs. 98,415.00	Rs. 2,000.00	Two Months
9	C/o Jeepable road from Sh. Chamunda Mandir to Prakash Chand House Ward No. 5 Mahal Rakh (SH:- P/L Interlocking Tiles from RD 0/132 to 0/160 (VKVNY)	Rs. 98,476.00	Rs. 2,000.00	Two Months
10	C/o Jeepable road from Sh. Chamunda Mandir to Prakash Chand House Ward No. 5 Mahal Rakh (SH:- P/L Interlocking Tiles from RD 0/162 to 0/190 (VKVNY)	Rs. 98,476.00	Rs. 2,000.00	Two Months
11	C/o Cow Shed at Kudan Dehal PO Jia Tehsil Palampur Distt. Kangra (HP) (SH:- Providing and fixing of Doors and glass pans (Deposit)	Rs. 94,542.00	Rs. 1,900.00	Two Months
12	C/o Cow Shed at Kudan Dehal PO Jia Tehsil Palampur Distt. Kangra (HP) (SH:- Providing and laying of G.I Pipes & C/o Ramps for vehicle (Deposit)	Rs. 98,610.00	Rs. 2,000.00	Two Months
13	OFC damages from NH-154 near Veterinary College Palampur to Bharmat upper (SW:- P/L Interlocking Paver Block at Km 0/525 to 0/550)	Rs. 98,727.00	Rs. 2,000.00	Three Months
14	C/o Jeepable road from Main road to Mahasha Basti Ward No 2 Balla (SH:- C/o R/Wall at RD 0/00 to 0/015) (VKVNY)	Rs. 97,002.00	Rs. 2,000.00	Two Months
15	C/o Jeepable road from Main road to Mahasha Basti Ward No 2 Balla (SH:- P/L road filling, G-II & 1:4:8 at RD 0/00 to 0/045)) (VKVNY)	Rs. 99,965.00	Rs. 2,000.00	Two Months

16	C/o R/Wall to protect the land of Sh. Ashok Kumar S/o Sh. Bharu Ram Ward No. 5 (Deposit VKVNY)	Rs. 99,712.00	Rs. 2,000.00	Two Months
17	C/o Footpath from Yugal Kishore house towards main road via Sanjeev Sharma House Ward No. 2 GP Ghar (SW:- P/L Interlocking Paver Block) (Deposit)	Rs. 98,680.00	Rs. 2,000.00	Three Months
18	Repair of Path & Retaining Wall from Sh. Aman Kumar Shop towards Adhelti house Ward No. 5 GP Nachhir (SW:- Repair of Pucca Path & R/Wall (Deposit)	Rs. 74,847.00	Rs. 1,500.00	Three Months
19	C/o Footpath from Main road towards Sh. Sharvan Kumar S/o Sh. Makholi Ram Ward No. 3 GP Nachir Bandla (SW:- C/o Retaining wall & Footpath (Deposit)	Rs. 99,597.00	Rs. 2,000.00	Three Months
20	C/o Jeepable road from Mohan Lal House Ward No. 3 to Akshay Awasthi house Ward No 5 (SW:- C/o Retaining wall (Deposit)	Rs. 97,364.00	Rs. 2,000.00	Three Months
21	C/o Jeepable road from Mohan Lal House Ward No. 3 to Akshay Awasthi house Ward No 5 (SW:- C/o Retaining wall RD 0/120 to 0/133 (Deposit)	Rs. 99,920.00	Rs. 2,000.00	Three Months
22	OFC damages from NH-154 near Veterinary College Palampur to Bharmat upper (SW:- P/L Interlocking Paver Block at KM 0/500 to 0/525 (OFC)	Rs. 98,932.00	Rs. 2,000.00	Three Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand . Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Palampur Division
HPPWD Palampur

Schedule of Quantity

Work No. (1)

Name of Work : - Completion of road from main road to Smt. Rajo Devi house W. No. 5
(**S. W. :-** C/O CC pavement RD 0/100 to 0/141.20 (Deposit))

Estimated Cost :- 98,348/-
Earnest Money :- 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clasue 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads,lifts and other incidentals by Manual Means.The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.31	Cubic metres			Per Cubic-metre.	
2	Providing Concrete for plain/reinforced cement concrete1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical SpecificationsClause802,803,1202 &1203 including carriage of materials within all leads and lift and other incidentals.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	15.50	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work : - Jeepable road from Sh. Dhanu Ram S/O Sh. Giga Ram house to Govt. Agri farm W. No. 3 (Deposit)
(S. W. :- C/O CC pavement RD 0/000 to 0/035.50 Deposit

Work No. (2)

Estimated Cost :- 99,059/-
Earnest Money :-2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clasue 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads,lifts and other incidentals by Manual Means.The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	7.99	Cubic metres			Per Cubic-metre.	
2	Providing Concrete for plain/reinforced cement concrete1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical SpecificationsClause802,803,1202 &1203 including carriage of materials within all leads and lift and other incidentals.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	12.87	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work : -C/O Jeepable road from main road to Capt. Jaiveer Choudhary House Ward No. 5 (S. W. :- P/L G-II & CC Pavement Km. 0/000 to 0/020 (Deposit) MPLAD

Work No. (3)

Estimated Cost :- 74,668/-
Earnest Money :- 1500/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clasue 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads,lifts and other incidentals by Manual Means.The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	4.53	Cubic metres			Per Cubic-metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	7.55	Cubic metres			Per Cubic-metre.	
3	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clasue 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, GST or other taxes imposed by the Government..	2.00	Cubic metre			Per Cubic metre	
4	Steel work welded in built up sections/ framed work/tubler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames ,guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in-Charge.The rate includes octroi,royality,Malkana,Tol tax, GST or any other taxes imposed by the Government.	44.00	Kilogram me			Per Kilogram me	
5	Supplying,fitting and placing HYSD bar reinforcement in super structure complete as per drawing and technical specification clause 1002,1010 and 1202.as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals .The rate includes octroi,royality,Malkana,Tol tax, GST or any other taxes imposed by the Government.	37.00	kilogram me			Per kilogram me	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No. 4

Name of Work :- C/O Retaining wall for protection of the land of Sh. Mayank Sharma S/O Sh. Swaroop Chand Ghar
(S. W. :- C/O Breast wall (Deposit)

Estimated Cost :- 74,020/-
Earnest Money :- 1500/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arrise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	9.00	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	16.00	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick mansonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	10.00	Numbers			Each	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Work No. 5

Schedule of Quantity

Name of Work : - C/O Pucca Path along with Pulli near Bhiral Khad W. No. 7 G.P. Nachir
(S. W. :- P/L C.Conc. Pucca path from RD 0/000 to 0/015 & C/O R/wall from Rd 0/050 to 0/054.35 (Deposit)

Estimated Cost :- Rs. 73,780/-
Earnest Money :- Rs. 1500/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arrise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	4.44	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	10.98	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick mansonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the government.	5.00	Nos.			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, GST or other taxes imposed by the government.	3.94	Cubic metre			Per Cubic metre.	
5	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	3.38	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Work No.

Work No. (6)

Schedule of Quantity

Name of Work : - C/O Pucca Path along with Pulli near Bhiral Khad W. No. 7 G.P. Nachir
(S. W. :- C/O Approach from existing Pulli & P/L C.Conc. for Pucca path from RD 0/015 to 0/030 (Deposit)

Estimated Cost :- Rs. 73,223/-
Earnest Money :- Rs. 1500/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arrise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	4.39	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	10.86	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick mansonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	5.00	Nos.			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, GST or other taxes imposed by the Government.	3.90	Cubic metre			Per Cubic metre.	
5	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	3.38	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Jeepable road from main road to Mahasha Basti Ward No. 2 Balla. (SH:- Providing and Laying interlocking paver 60 mm and side locking at Rd 0/00 to 0/027). **VKVNY Deposit 4.00 Lacs**	Estimated cost Rs.	98415.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	72.90			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.81			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Jeepable road from main road to Mahasha Basti Ward No. 2 Balla. (SH:- Providing and Laying interlocking paver 60 mm and side locking at Rd 0/29 to 0/056). **VKVNY Deposit 4.00 Lacs**	Estimated cost Rs.	98415.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	72.90			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.81			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur.

(9)

SCHEDULE OF QUANTITY

Name of work:- C/o Jeepable road from Sh. Chamunda Mandir to Prakash Chand house ward No. 5 Mahal Rakh. (SH:-P/L interlocking tiles from Rd 0/132 to 0/160). **VKVNY Deposit 2.00 Lacs**	Estimated cost Rs.	98476.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	72.80			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.84			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

10

SCHEDULE OF QUANTITY

Name of work:- C/o Jeepable road from Sh. Chamunda Mandir to Prakash Chand house ward No. 5 Mahal Rakh. (SH:-P/L interlocking tiles from Rd 0/162 to 0/190). **VKVNY Deposit 2.00 Lacs**	Estimated cost Rs.	98476.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	72.80			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	0.84			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

(11)

SCHEDULE OF QUANTITY

Name of work:- C/o Cow shed at Kudan Dehal P.O Jia The. Palampur Distt. Kangra H.P. (SH:-Providing & Fixing of Doors & Glass Panes). **Deposit**

					Estimated cost Rs.	94542.00
					Earnest Money Rs.	1900.00
					Time Limits	Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using M.S. angels 40x40x6 mm for diagonal braces. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government. .	23.70			Per square metre	
2	Providing & fixing 5.5 mm thick glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government. .	10.08			Per Square Metre	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

12

SCHEDULE OF QUANTITY

Name of work:- C/o Cow shed at Kudan Dehal P.O Jia The. Palampur Distt. Kangra H.P. (SH:- Providing and Laying of G.I. pipes & C/o Ramps for vehicle). **Deposit**	Estimated cost Rs.	98610.00
	Earnest Money Rs.	2000.00
	Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, 1000 ltr capacity IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. The rate is inclusive of octroi, royality, malkana, GST and all type of other taxes imposed by the Government.	1000.00			Per litre	
2	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.15 mm dia nominal bore. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	130.00			Per Running Metre	
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering 1:2:4 (one cement : Two coarse sand : four graded stone aggregate 20 mm (Twenty Millimetre) nominal size) above plinth level including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government. .	10.26			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No. (13)

Name of Work :- OFC damages from NH-154 near Veterinary college Palampur to Bharmat upper (S. W. :- P/L interlocking Paver Block at Km. 0/525 to 0/550

Estimated Cost :- Rs. 98,727/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clasue 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	0.55	Cubic metres			Per Cubic-metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	73.78	Square Metre			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.48	Cubic metres			Per Cubic-metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Jeepable road from main road to Mahasha Basti Ward No. 2 Balla. (SH:- C/o R/wall at Rd 0/00 to 0/015).
VKVNY Deposit 4.00 Lacs

Estimated cost Rs.	97002.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.10			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	21.38			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	10.00			Each	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Jeepable road from main road to Mahasha Basti Ward No. 2 Balla. (SH:- P/L road filling, G-II & 1:4:8 at Rd 0/00 to 0/045). **VKVNY Deposit 4.00 Lacs**

Estimated cost Rs.	99965.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the government.	94.47			Per cubic metre	
2	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government.	11.81			Per cubic metre	
3	Providing and laying Cement concrete 1:4:8 (One Cement : Four Sand : Eight crushed stone aggregate) Nominal Mix P.C.C. grade for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clasue 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	13.95			Per cubic metre.	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o R/wall to Protect the land of Sh. Ashok Kumar S/o Sh. Bharu Ram Ward No. 5 . **(Deposit VKVNY 1.00 Lacs)**

Estimated cost Rs.	99712.00
Earnest Money Rs.	2000.00
Time Limits	Two Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royality, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	14.40			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the government.	21.60			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royality, GST, toll tax or other taxes imposed by the government.	10.00			Each	
	Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No. (17)

Name of Work : - C/O Footpath fromYugal Kishore house towards main road via Sanjeev Sharma house Ward No. 2 G.P. Ghar
(S. W. :- P/L interlocking Paver Block Deposit

Estimated Cost :- Rs. 98,680/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clasue 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	12.50	Cubic metres			Per Cubic-metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	50.40	Square Metre			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.86	Cubic metres			Per Cubic-metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work : -Repair of Path & Retaining wall from Sh. Amar Kumar Shop towards Adhelti house W. No. 5 G.P. Nachhir
(S. W. :- Repair of Pucca Path & R/Wall (Deposit)

Work No. 18

Estimated Cost :- 74,847/-
Earnest Money :- 1500/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arrise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	3.51	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	8.37	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick mansonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	3.00	Numbers			Each	
4	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clasue 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, GST or other taxes imposed by the Government..	7.69	Cubic metre			Per Cubic metre	
5	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up ,the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clasue 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	0.40	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No. 19

Name of Work :- C/O Footpath from main road towards Sh. Sharvan Kumar S/o Sh. Makholi Ram W. no. 3 G.P. Nachhir Bandla
(S. W. :- C/O Retaining wall & footpath Deposit

Estimated Cost :- Rs. 99,597-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1 with in all leads, lifts and other incidental. The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	4.50	Cubic metre			Per Cubic metre	
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arrise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	4.68	Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	11.16	Cubic metre.			Per Cubic metre	
4	Providing weep holes in brick mansonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	4.00	Nos.			Each	
5	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clasue 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, GST or other taxes imposed by the Government..	10.13	Cubic metre			Per Cubic metre	
6	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clasue 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	0.39	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No. 20

Name of Work :- C/O jeepable road from Mohan Lal house ward no.3 to Akshay Awasthi house ward no. 5
(S. W. :- C/O Retaining wall Deposit

Estimated Cost :- Rs. 97,364/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arrise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	10.42	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	19.80	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick mansonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	12.00	Nos.			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, GST or other taxes imposed by the Government.	8.92	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No. 21

Name of Work :- C/O Jeepable road from Mohan Lal house ward no.3 to Akshay Awasthi house ward no. 5
(S. W. :- C/O Retaining wall RD 0/120 to 0/133 Deposit

Estimated Cost :- Rs. 99,920/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arrise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	10.40	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specificationi section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equippments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, or other taxes imposed by the Government.	22.56	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No.

22

Name of Work : - OFC damages from NH-154 near Veterinary college Palampur to Bharmat upper
(S. W. :- P/L interlocking Paver Block at Km .0/500 to 0/525

Estimated Cost :- Rs. 98,932/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clasue 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	0.55	Cubic metres			Per Cubic-metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals.The rate including of octroi, royality, malkana, tolltax, sale tax or other taxes imposed by the Government.	73.94	Square Metre			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royality, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.48	Cubic metres			Per Cubic-metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur