

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed item/ percentage rate tender on form NO. 6&8 are hereby invited by the Executive Engineer, Bilaspur Division No. I, HP.PWD., Bilaspur on behalf of Governor of Himachal Pradesh from the approved and eligible contractors enlisted in PWD Department so as to reach in this office on or before **04/07/2025** up to 10.30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of the intending contractors or their authorized representatives who may like to be present. If it happens to be holiday on that day tenders will be opened on next working day. The application for obtaining the tender forms will be received up to **02/07/2025** up to 5.00 PM and the tender form can be had from this office on **03/07/2025** during the office hours.

The Earnest money in the shape of National Saving Certificate Time deposit Accounts/FDR of any Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, Division No. I, HP.PWD., Bilaspur must be accompanied with each application for obtaining the tenders. The tender application received without earnest money /cost of tender forms will similarly be rejected. The undersigned reserves the right to reject the tenders without assigning any reason.

Sr. No	Name of work	Estimated cost (In Rs.)	Earnest Money (In Rs.)	Cost of form (In Rs.)	Time limit
1	Construction of protection wall at Sh. Babu Ram house in G.P. Panchayat Nichali Bhater Tehsil Sadar Distt. Bilaspur (H.P.). (SH:- C/o R/wall at RD. 0/00 to 0/004.25).	94,918	2000	350	Two months
2	Restoration of rain damages on Gallu Jole Rohin road Km. 0/00 to 5/500. (SH:- C/o B/wall at RD. 4/270 to 4/276).	95,183	2000	350	One month
3	Restoration of rain damages on Panoh Harlog Samaila road Km. 0/00 to 22/615. (SH:- C/o R/wall at RD. 20/750 to 20/754.40).	95,787	2000	350	One month
4	A/R & M/O on all roads & paths under Sub-Division NO.II (Dholra Section). (SH:- Supply and stacking at site boulder stone and sand).	99,250	2000	350	One month
5	A/R & M/O non residential building Bilaspur. (SH:- Providing services of sweeper for sweeping/cleaning). (Period 01/06/2025 to 31/10/2025).	99,910	2000	350	One month
6.	A/R & M/O residential building in Changer Sector Bilaspur (H.P.). (SH:- White washing, painting, wood shutter, iron door, tile work qtr No. F-17 D/S).	96,034	2000	350	One month
7.	A/R & M/O residential type-II qtrs at Changer Sector Bilaspur. (SH:- White washing, wood work, tile work etc. at Qtr NO. F-17 D/S).	99,085	2000	350	One month
8.	A/R & M/O residential building at Changer Sector Bilaspur. (SH:- White washing & painting wood work, tile work etc. at Qtr NO. F-18 S/S).	98,933	2000	350	One month
9.	Special repair to DC office Bilaspur (H.P.) (SH:- P/F railing, curtain and repair of aluminium door etc.).	66,726	2000	350	One month
10.	Special repair to DC office Bilaspur (H.P.) (SH:- P/F aluminium door, white wash and painting work etc.).	83,993	2000	350	One month
11.	Restoration of rain damages on Kuthera Talwara Bara-daghat Km. 0/00 to 11/00. (SH:- C/o R/wall at RD. 0/070 to 3/074.60).	98,876	2000	350	One month

	A/R & M/O residential building in Changer sector Bilaspur. (SH:- Wire gauge wood shutter & tile work Qtr No. G-17 D/S)	91,560	2000	350	One month
13.	A/R & M/O residential type-III qtrs at Changer sector Bilaspur. (SH:- Rise the level of right side & front side existing boundary wall & P/F wire gauge whutter F-26 D/S).	89,598	2000	350	One month
14.	A/R & M/O residential building in Changer Sector Bilaspur. (SH:- P/F aluminium door, whutter for bath & vent; pre-painted sheet and cup board for kitchen cabnet in Qtr No. F-26 D/S).	96,201	2000	350	One month
15.	Restoration of rain damages on Shimla Mattour road NH-103 Km. 79/0 to 95/0. (SH:- Hiring of Excavator-cum-Loader/JCB for removal of slips and dressing of berms at various RD.).	93,500	2000	350	One month
16.	Restoration of rain damages on various road under Kuthera Sub-Division. (SH:- Hiring of Excavator-cum-loader/JCB for removal of slips and dressing of berms at various RD).	96,800	2000	350	One month

1. **Certified that the tenders for above said works are being called of emergent nature in exigency of public interest.**


TERMS & CONDITIONS: -

1. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
2. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactorily including adherence to quality future work will be awarded to him. All undertaking that he is not having more than two works in hand must be recorded in the application, failing which application of such contractor shall be rejected without any notice to him.
3. Earnest money should be accompanied with application. Application without earnest money will not be entertained.
4. The photo copy of Pan Number/renewal should be attached with the application otherwise tender form will not be issued.

NO.PW-BLP-I-CB-EA-I-Tender/ 2025- 4599-4640

Copy forwarded to the following for information please.

1. The Engineer-in-Chief, HP.PWD; Shimla-I.
2. The Chief Engineer (HZ) HP.PWD, Hamirpur.
3. The Superintending Engineer, 10th Circle, HP.PWD, Bilaspur.
4. The Executive Engineer (IT) O/o the Engineer-in-Chief, HP.PWD, Shimla through email:- cc-pwd-hp@nic.in alongwith copies of Schedule of quantities for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. All the contractors as per record of this office.
7. Accounts Branch/ Drawing Branch/Supdt. in this office.
8. Notice Board.


Executive Engineer,
Bilaspur, Division No.I
HP.PWD, Bilaspur.
Dated :- 26/06/2025


Executive Engineer,
Bilaspur, Division No.I,
HP.PWD, Bilaspur.

DRAFT SCHEDULE OF QUANTITY.

Estimated cost Rs. = 94,918/-only
Earnest Money Rs. = 2,000/- only.
Time Limit. = Two Month

Name of Work:- Construction of protection wall at Sh. Babu Ram house in G.P Panchayat Nichali Bhater The. Sadar Distt. Bilaspur (H.P).
(SH:- C/O R/Wall at RD. 0/00 to 0/004.25)

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2	6.65	Per Cubic metre	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms. lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	29.75	Square Metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.59	Per Cubic metre			

4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00	Each			
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.01	Per Cubic metre			
		TOTAL				


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

DRAFT SCHEDULE OF QUANTITY.			Estimated cost Rs. = 95,183/-only			
			Earnest Money Rs. = 2,000/- only.			
			Time Limit. = One Month			
Name of Work:- Restoration of rain damages on Galu Jole Rohin road Km. 0/00 to 5/500. (SH:- C/O R/Wall at RD. 4/270 to 4/276).						
Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure	In words	
1	2	18.12	4	5	6	8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (TenPer Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m,(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.		Per Cubic metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.90	Per Square Metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty milimetre) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.90	Per Cubic metre			-

4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.00	Each			
			TOTAL			


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Estimated cost Rs. = 95,787/-only
Earnest Money Rs. = 2,000/- only.
Time Limit. = One Month

DRAFT SCHEDULE OF QUANTITY.

Name of Work: Restoration of rain damages on Panoh Harlog Samaila road K.M. 0/00 to 22/615. (SH:- C/O R/Wall at RD. 20/750 to /754.40)		Qty.		Rates		Amount
Sr No	Description of items.	3	4	In Figure	In words	
				5	6	8
1	2					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.56	Per Cubic metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.40	Per Square Metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty milimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.26	Per Cubic metre			

	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00	Each			
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.50	Per Cubic metre			
		TOTAL				


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Draft Schedule of Quantity					Estimated cost Rs. = 99,250/-
					Earnest Money Rs. = 2000/-
					Time Limit. = One Month
Name of work :- A/R & M/O on all Roads & paths under Sub-Division No. II (Dholra Section) . (SH:- Supply and stacking at site boulder stone and sand) .					
Sr No.	Description of items.	Qty.	Unit	Rate In Figure In words	Amount
1	Supply and stacking at site boulder stone of approved quality as per HP.PWD specification along road side in proper stacks. The stacks should be on even ground, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	62.00	Per Cubic metre		
2	Supply and stacking at site of work clean sharp sand as per H.P. PWD, specification free from dirt, dust and other organic matter including stacking at road side clear of formation width uniformly distributed along road side in proper stacks. The stacks should be eve ground, including carriage of materials, within all leads and lifts as per direction of Engineer-in - Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.				
2.1	Clean coarse sharp sand.	23.00	Per Cubic metre		


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Draft Schedule of Quantity							Estimated cost Rs. = 99,910/- only	
							Earnest Money Rs. = 2,000/- only	
							Time Limit. = One month	
Name of Work:- A/R & M/O non residential building Bilaspur. (SH:- Providing services of sweeper for sweeping / cleaning). (Period 1.06.2025 to 31.10.2025).								
Sr No	Description	Qty.	Rates		Unit	Amount		
			In Figure	In words				
1	2	3	5	6	7	8		
1	Providing services of sweeper for sweeping / cleaning in Govt. Non residential buildings under Circuit house HP.PWD Bilaspur from 9 AM to 5 PM including Sunday and public holidays as per the satisfaction of Engineer-in-Charge	152.00			Days			
	TOTAL							


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Draft Schedule of Quantity

Estimated cost Rs. = 96,034/- only						
Earnest Money Rs. = 2,000/- only						
Time Limit. = One month						
Name of Work:- A/R & M/O residential building in Changer Sector Bilaspur (H.P). (SH:- White washing, painting, wood shutter, iron door, tile work qtr No. F-17 D/S).						
Sr No	Description	Qty.	Rates		Unit	Amount
			In Figure	In words		
1	2	3	5	6	7	8
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	128.52			Per Kilogram	
2	Removing dry oil bound distemper, water proofing cement paint and like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	264.16			Per Square Metre	
3	Applying Birla white putty wall care putty over plaster surfaces after thoroughly brushing the surface fire mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13.21			Per Square Meter	
4	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	264.16			Per Square Meter	

5	Painting one coat(excluding priming coat)on previously painted wood and wood based surfaces with enamel paint brushing to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	60.46			Per Square Metre
6	Repair to plaster of thickness 12mm to 20mm (Twelve to twenty milimetre) in patches of 2.50 (Two point fifty) Square meter and under and 10 (Ten) to 15mm (Fifteen milimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground upto 20m (twenty metre) lead with cement mortar 1:5 (One Cement : five approved Sand) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.42			Per Square Meter
7	Providing and fixing 40mm (Forty milimetre) thick panalled glazed or panalled and glazed shutter for doors windows and clorestary windows, including block enamelled iron built hinges with necessary screws in second class deodar wood. including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.25			Per Square Metre
		TOTAL			



Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Draft Schedule of quantity

Estimated cost Rs. 99,085/-only
Earnest Money Rs. 2,000/- only.
Time Limit. = One month

Name of work:- A/R & M/O residential type-II qtrs at Changer sector Bilaspur. (SH;- White washing , wood work, tile work etc. at Qtr No. F-17 D/S)

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	5	6	7	8
1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	85.96			Per Kilogramme	
2	Providing and fixing 40mm (Forty millimetre) thick panalised glazed or panalised and glazed shutter for doors windows and clostetory windows, including block enamelled iron built hinges with necessary screws in second class deodar wood. including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.80			Per Square Metre	
3	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm (One point four millimetre) in both directions with wire of dia 0.56 mm, (Zero point fifty six millimetre) for doors, windows and clerestory windows with hinges and necessary screws : 30 cm (Thirty centemetre) thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size Second class teak wood. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.25			Per Square Metre	
4	Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.03			Per Square Metre	
5	Painting with synthetic enamel paint of approved brand and manufacture togive an even shade Two or more coats on new work, Two or more coats on new work. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	48.94			Per Square Metre	

	Providing and fixing ISI marked bright finished brass sliding door bolts, (anodic coating not less than grade AC 10 (Ten) as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete 250x16mm (Two hundred fifty into sixteen millimetre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
7	Providing and fixing bright finished brass tower bolts, (barrel type) with necessary screws etc. complete : 100x10 mm. (One hundred into ten millimetre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00			Each	
8	Providing and fixing bright finished handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 100 mm.(One hundred millimetre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each	
9	Providing and fixing 10mm (Ten millimeter) thick anti skid water proof stain and impet resistant heavy duty vetrified tiles Nitco or equivalent 600x600mmx10mm (Six hundre into Six hundred into ten millimeter) manufactured of approved shade and colour in flooring, treads of 1:3 (One cement : Three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.25			Per Square Meter	
10	White glazed tiles 6 mm (Six millimeters) thick in skirting, risers of steps and Dado 12 mm (Twelve millimeter) thick cement mortar 1:3 (One cement and three sand) and jointed with cement slurry including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.66			Per Square Meter	
11	Providing and fixing C.P.brass bib tap with capstan head (superior and heavy type) 15mm (Fifteen millimetre) dia. including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	

	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes FINOLEX including fixing with approved adhesive etc. complete 75 mm (Seventy five millimetre) diameter. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00			Per Running Metre	
13	Providing and fixing PVC floor trap FINOLEX of self cleaning design including fixing with approved adhesive etc. complete. including cost of cutting making good in the walls and floors complete. 110x90 mm (One hundred ten into ninety millimetre). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
14	Providing and fixing Stainless Steel kitchen sink No. KCG 1011 with C.I. brackets and stainless steel plug 40 mm (Forty millimetre), including painting of fittings and brackets, cutting and making good the walls wherever required: 940x455 mm (Nine hundred forty into four hundred fifty five millimetre) bowl depth 178 mm (One hundred seventy eight millimetre). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
15	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 32 mm (Thirty two millimetre) dia including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
16	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required: W.C. pan with ISI marked white solid plastic seat and lid. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
17	Providing and fixing wash basin with C.I. brackets, 15 mm (Fifteen millimetre) C.P. brass pillar taps, 32 mm (Thirty two millimetre) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm (Six hundred thirty x four hundred fifty millimetre) with a pair of 15 mm (Fifteen millimetre) C.P. brass pillar taps including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	

	Providing and fixing uplasticeised PVC connection pipe with brass unions : 30 cm length 15 mm nominal bore. The rate including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
19	Providing and fixing C.P, brass stop / angle cock (concealed) of approved quality conforming to IS.8931 : 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
20	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete.including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	201.53			Per Square Meter	
21	Providing and applying Birla white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	50.38			Per Square Metre	
22	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	201.53			Per Square Metre	
	TOTAL					


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Draft Schedule of quantity

Estimated cost Rs. 98,933/-only

Earnest Money Rs. 2,000/- only.

Time Limit. = One month

Name of work:- A/R & M/O residential building at Chnager sector Bilaspur. (SH;- White washing & Painting wood work, tile work etc. at Qtr No. F-18 S/S).

Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	5	6	7	8
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	225.75			Per Square Meter	
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matt finish to the surface complete. As per HP PWD specification. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.58			Per Square Meter	
3	Distempering (two coat) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give and even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	225.75			Per Square Meter	
4	Painting one coat(excluding priming coat)on previously painted wood and wood based surfaces with enamel paint brushing to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	75.28			Per Square Metre	

5	Repairs to plaster in patches of 2.50 Sq.M (Two point fifty Per Square Metre). and under and 10 to 15mm (Ten to fifteen milimetre) thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 (Twenty) metres with Cement Mortar 1:5 (One Cement : five) Sand). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	2.26			Per Square Metre	
6	Providing and fixing 1st quality ceramic glazed floor tile conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm (Twelve milimetre) thick bed of cement Mortar 1:3 (One cement: Three coarse sand) and jointing with grey cement slurry @ 3.3kg (Three point three kilograme) per sqm including pointing in white cement mixed with pigment of matching shade complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.86			Per Square Metre	
7	Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade complete. 8 mm (Eight milimetre) thick. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.71			Per Square Metre	
8	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (Twenty milimetre) (average) thick base of cement mortar 1:4 (One cement : Four coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.26			Per Square Metre	
9	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. Granite work including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.2			Per Running Metre	

10	Providing and fixing 40mm (Forty millimeter) thick panelled glazed or panelled and glazed shutter for doors windows and clostetory windows, including block enamelled iron butt hinges with necessary screws in second class deodar wood, including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.44			Per Square Metre	
11	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm (One point four millimetre) in both directions with wire of dia 0.56 mm, (Zero point fifty six millimetre) for doors, windows and clerestory windows with hinges and necessary screws : 30 cm (Thirty centimetre) thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size Second class teak wood, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.36			Per Square Metre	
12	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Nos	
13	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 15 mm (Fifteen millimetre) dia nominal bore, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00			Per Running Metre	
14	Providing and fixing C.P. Brass shower rose 150 mm dia (Fifteen millimeter). including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
15	Providing and fixing C.P. Brass stop cock (concealed) of standard design and of approved make conforming to IS 8931. 15 mm nominal bore, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	

16	Providing and fixing PVC floor trap FINOLEX of self cleaning design including fixing with approved adhesive etc. complete . including cost of cutting making good in the walls and floors complete . 110x90 mm (One hundred ten into ninety millimetre) . including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
17	Providing and fixing 100 mm (one hundred millimeter) dia chromium plated grating of superior quality for floor, gully/Nahini trap. including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
18	Structural steel work in single section, fixed with or without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	53.00			Per Kilogramme	
19	Providing and fixing 5 layer 9mm ply wood for ceiling, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Per Square Metre	
	TOTAL					


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Estimated cost Rs. = 66,726/- only
Earnest Money Rs. = 2,000/- only
Time Limit. = One month

Draft Schedule of Quantity

Name of Work:- Special repair to DC office Bilaspur (H.P.). (SH;- P/F railig, curtain and repair of aluminium door etc.).

Sr No	Description	Qty.	Rates		Unit	Amount
			In Figure	In words		
		3	5	6	7	8
1	2	29.40			Per Running Metre	
1	Providing and fixing curtain including stitching and fixing in which curtain cloth and lining complete having size of 50 metre in width in all respect. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
2	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	381.24			Per Kilogramme	
3	Providing and fixing M.S sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : 300x16 mm. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
4	Taking out and refixing after repair of aluminium door at site. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
		TOTAL				


Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Draft Schedule of Quantity						
Name of Work:- Special repair to DC office Bilaspur (H.P). (SH;- P/F aluminium door, white wash and painting work etc.).						
Sr No	Description	Qty.	Rates		Unit	Amount
			In Figure	In words		
1	2	3	5	6	7	8
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	220.79			Per Square Metre	
2	Providing and applying Birla white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	66.24			Per Square Metre	
3	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) (One point six seven Litre / ten Per Square Metre) on existing cement paint surface. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	79.95			Per Square Meter	
4	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	140.84			Per Square Meter	

Estimated cost Rs. = 83,993/- only

Earnest Money Rs. = 2,000/- only

Time Limit = One month

Estimated cost Rs. = 98,876/-only
Earnest Money Rs. = 2,000/- only.
Time Limit. = One Month

DRAFT SCHEDULE OF QUANTITY.

Name of work:- Restoration of rain damages on Kuthera Talwara Bara-da-ghat Km. 0/00 to 11/00. (SH:- C/O R/Wall at RD. 3/070 to 3/076).

Sr No	Description of items.	Qty.		Rates		Amount
		3	4	In Figure 5	In words 6	
1	2					8
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (One point five metre) in width or 10 sqm (Ten Per Square Metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m.(One point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. (Fifty metre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.27	Per Cubic metre			
2	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.05	Square Metre			
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : Five fine sand : Ten graded stone aggregate 40 mm (Forty millimetre) nominal size) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.14	Per Cubic metre			

4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00	Each			
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification Clause 1204.3.8 of MORD Specification 1200 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.48	Per Cubic metre			



Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Draft Schedule of quantity

Draft Schedule of quantity						
Name of work:- A/R & M/O residential building in Changer sector Bilaspur. (SH;- Wire gauge wood shutter & tile work Qtr No. G-17 /S).						
Estimated cost Rs. 91,560/-only Earnest Money Rs. 2,000/- only. Time Limit. = One month						
Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
1	2	3	5	6	7	8
1	Providing and fixing wire gauge shutters for doors windows using galvanised M.S. wire gauge designation 85 (Eighty five) G with wire of dia 0.56 mm (Zero point fifty six) millimeter) 35 mm (Thirty millimeter) thick in 2nd class deodar wood including carriage of materials within all leads, lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.40			Per Square Metre	
2	Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	38.44			Per Square Metre	
3	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm (One point four millimetre) in both directions with wire of dia 0.63 mm (Zero point sixty three millimetre) all complete. With 2nd (Second) class teak wood beading 62X19 mm. (Sixty two into nineteen millimetre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.25			Per Square Metre	

	Providing and fixing anodised aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete 300x16 mm (Three hundred into sixteen milimetre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
5	Providing and fixing aluminium tower bolts with necessary screws etc. complete : 250x10 mm. including carriage of materials ,within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00			Each	
6	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete 100 mm (One hundred milimetre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.00			Each	
7	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in kirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 300x300 mm. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.49			Per Square Meter	

	Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade complete. 8 mm (Eight milimetre) thick, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	24.36			Per Square Metre
9	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 : 15 mm (Fifteen milimetre) nominal bore including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each
10	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes FINOLEX including fixing with approved adhesive etc. complete 110 mm (one hundred ten milimetre) diameter. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Per Running Metre
11	Providing and fixing PVC plain bend ISI marked i/c fixing with approved adhesive etc. complete 110 mm (One hundred ten milimetre). including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each
12	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. 15 mm (Fifteen milimetre)/dia nominal bore. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00			Per Running Metre

3	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931. 15 mm nominal bore. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
14	Providing and fixing C.P. Brass shower rose 150 mm dia (Fifteen millimeter) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
15	Providing and fixing PVC floor trap of self cleaning design including fixing with approved adhesive etc. complete . including cost of cutting making good in the walls and floors complete . 110x90 mm (One hundred ten into ninety millimetre) . including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
16	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
17	Providing and fixing unplasticised PVC connection pipe with brass unions : 30 cm length 15 mm nominal bore. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Per Running Metre	

18	Providing and fixing 100 mm (one hundred millimeter) dia chromium plated grating of superior quality for floor, gully/Nahini trap, including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
19	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm (Forty millimetre), including painting of fittings and brackets, cutting and making good the walls wherever required : 470x420 mm (Four hundred seventy into four hundred twenty millimetre) bowl depth 178 mm (One hundred seventy eight millimetre), including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
20	Providing and fixing wash basin with C.I. brackets, 15 mm (Fifteen millimetre) C.P. brass pillar taps, 32 mm (Thirty two millimetre) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever required: White Vitreous China Wash basin size 630x450 mm (Six hundred thirty x four hundred fifty millimetre) with a pair of 15 mm (Fifteen millimetre) C.P. brass pillar taps including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
21	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 32 mm (Thirty two millimetre) dia including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
TOTAL						

Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Draft Schedule of quantity

		Estimated cost Rs. 89,598/-only Earnest Money Rs. 2,000/- only. Time Limit. = One month				
Draft Schedule of quantity						
Name of work:- A/R & M/O residential type-III qtrs at Changer sector Bilaspur. (SH;- Rise the level of right side & front side existing boundary wall & P/F wire guage shutter F-26 D/S).						
Sr No	Description of items.	Qty.	Rates		Unit	Amount
			In Figure	In Word		
		3	5	6	7	8
1	2					
1	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven point five) in superstructure above plinth level up to floor V level. Cement mortar 1:4 (One cement :Four coarse sand), including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.13			Per Square Metre	
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand), including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.74			Per Cubic Metre	
3	15mm cement plaster in single coat on fair side of brick/concrete/stone walls for interior plastering upto all floor level in any height including arrises,internal rounded ngles,chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. Cement Mortar 1:4 (One cement : four Sand). as per HP.PWD Specification clause 17 & 4.4.1. including carriage of materials , within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	49.91			Per Square Meter	
4	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	49.91			Per Square Metre	

	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	49.91			Per Square Metre	
6	Providing and fixing wire guage shutters for doors windows using galvanised M.S. wire guage designation 85 (Eighty five) G with wire of dia 0.56 mm (Zero point fifty six) millimeter) 40 mm (Forty millimeter) thick in 2nd class deodar wood including carriage of materials within all leads, lifts and other incidentals. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.80			Per Square Meter	
7	Applying priming coat: With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.79			Square Metre	
8	Painting one coat(excluding priming coat)on previously painted wood and wood based surfaces with enamel paint brushing to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.79			Per Square Metre	
9	Providing and laying Cement concrete 1:2:4 (One cement : Two coarse sand : Four graded stone aggregate 40 mm (Forty milimetre) nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.85			Per Cubic Metre	
10	Fixing pieces of glass top of boundary wall in cement concrete. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Day	

	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 100x10 mm. (One hundred into ten milimetre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
12	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 (Ten) as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete 250x16mm (Two hundred-fifty into sixteen milimetre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
13	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 100 mm.(One hundred milimetre) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00			Each	
TOTAL						


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Draft Schedule of quantity

Draft Schedule of quantity							Estimated cost Rs. 96,201/-only
							Earnest Money Rs. 2,000/- only.
							Time Limit. = One month
Name of work:- A/R & M/O residential building in Changer sector Bilaspur. (SH;- P/F Aluminium door, shutter for bath & vent., pre-painted sheet and cup board for kitchen cabinet in qtr No. F-26 D/S).							
Sr No	Description of items.	Qty.	Rates		Unit	Amount	
			In Figure	In Word			
	2	3	5	6	7	8	
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	90.00			Per Kilogramme		
2	Providing and fixing 0.47mm (Zero point forty seven millimeter) thick pre-painted steel sheet of TATA / DURO SHINE in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) micron over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J opr L hooks, bolts and nuts , 6mm diameter with pre-painted limpet and rubber washers complete with all accessories. as per HP.PWD Specification , including carriage of materials , within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.79			Per Square Meter		
3	Providing and fixing 16.75mm (Sixteen point seventy five millimetre) thick HDMR board plain , pre-laminated board (decorative lamination on one side and other balancing lamination board flat pressed, 3 layer or graded medium density grade-1 . including carriage of materials in all leads and lifts as directed by the Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.47			Per Square Metre		

	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash asteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 (Fifty) micron), including carriage of materials within all leads and lifts as per direction of engineer-in-charge. The rate includes, octori, Malkhana, Toll tax, Good Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	30.30			Kilogramme
5	Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC15)	34.80			Kilogramme
6	Providing and fixing Backlite sheet 3mm (three millimetre) thick both side laminated as per direction of Engineer-in-charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.60			Per Square Metre
8	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.0 mm (Four millimetre) thickness (weight not less than 10 kg/ sqm (Ten kilogramme / Squaremetre). including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.80			Per Square Metre

	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 (Ten) as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete 250x16mm (Two hundred fifty into sixteen millimetre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Each	
10	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 100x10 mm. (One hundred into ten millimetre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.00			Each	
11	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 100 mm.(One hundred millimetre) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00			Each	
	TOTAL					


 Executive Engineer,
 Bilaspur Division No.1
 HP.PWD., Bilaspur

Draft Schedule of Quantity					Estimated cost Rs. = 93,500/-
					Earnest Money Rs. = 2000/-
					Time Limit. = One Month
Name of work :- Resoration of rain damages on Shimla Mattour road NH-103 Km. 79/0 to 95/0. (SH:- Hiring of Excavator-cum-loader/JCB for removal of slips and dressing of berms at various RD.).					
Sr No.	Description of items.	Qty.	Unit	Rate	
				In Figure	In words
1	Providing one number Excavator cum loader/JCB in good condition on hire bases site of work for removal of slip with in all leads and lifts as per direction of Engineer-in-Charge. The dumping site of material be arranged by the contractor at his own level and no dumping will be allowed along road side or in forest land failing which the contractor will be responsible for any kind of panel action as per rule of Hon'ble court.	85.00	Hours		



Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur

Draft Schedule of Quantity						Estimated cost Rs. = 96,800/-
						Earnest Money Rs. = 2000/-
						Time Limit. = One Month
Name of work :- Restoration of rain damages on various road under Kuther Sub Division. (SH:- Hiring of Excavator-cum-loader/JCB for removal of slips and dressing of berms at various RD.).						
Sr No.	Description of items.	Qty.	Unit	Rate		Amount
				In Figure	In words	
1	Providing one number Excavator cum loader/JCB in good condition on hire bases site of work for removal of slip with in all leads and lifts as per direction of Engineer-in-Charge. The dumping site of material be arranged by the contractor at his own level and no dumping will be allowed along road side or in forest land failing which the contractor will be responsible for any kind of panel action as per rule of Hon'ble court.	88.00	Hours			



Executive Engineer,
Bilaspur Division No.1
HP.PWD., Bilaspur