

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT.

No. PWD/JMD/CB/TENDER/2024-25- 1732-46
To


DATED: 21.06.2025

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :- Tender Notice.

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No. PBW(B)A(3)1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:-As above


Executive Engineer,
HPPWD Division,
Jawalamukhi.

Copy forwarded to the following:-

1. The FC-Cum Secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President MC Jawalamukhi.
9. The BDO Dehra /Pragpur/ Nagrota Surian/Surani.
10. Notice Board.
11. All the Head,of Branches.
12. All the Contractors working under Jawalamukhi Division.

/
Executive Engineer,
HP.PWD Division,
Jawalamukhi.

H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Jawalamukhi Division HPPWD., Jawalamukhi on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEDULE:

1. Date and time of receipt of application for tender form:
2. Date and time of issue of tender form:
3. Date and time of receipt of tenders:
4. Date and time of opening of tenders:


28.06.2025 upto 12.00 Noon
28.06.2025 12:00 PM to 5.00 PM
30.06.2025 upto 10.30AM
30.06.2025 at 11.00 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Jawalamukhi Division HPPWD Jawalamukhi must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
01	Restoration of Rain Damages on Nahallian Pihri Bhangolu-Da-Ghatta Road KM 0/0 to 10/00 (SH: P/L Cement Concrete Pavement at RD 0/820 to 0/839) SDF/2024/760	Rs. 99,817.00	Rs.2,000/-	One Month	Rs.350/-
02	Restoration of Rain Damages on Nahallian Pihri Bhangolu-Da-Ghatta Road KM 0/0 to 10/00 (SH: P/L Cement Concrete Pavement at RD 0/844 to 0/862.25) SDF/2024/761	Rs. 99,428.00	Rs.2,000/-	One Month	Rs.350/-
03	Construction of Drain Near the House of Harnam Singh in Village Lahru (SH: C/o C.C R/Wall at RD 0/010 to 0/018.30) VKV/2023/1027	Rs. 74,929.00	Rs.2,000/-	One Month	Rs.350/-
04	Construction of Main Road Punnu Ram Hosue to Lakshari Ram House in Village Dhanot KM 0/0 to 0/300 (SH: P/L Interlocking Concrete Paver Block Pavement at RD 0/233.80 to 0/251.90) Deposit Work	Rs. 99,800.00	Rs.2,000/-	One Month	Rs.350/-
05	Construction of Main Road Punnu Ram Hosue to Lakshari Ram House in Village Dhanot KM 0/0 to 0/300 (SH: P/L Interlocking Concrete Paver Block Pavement at RD 0/215.60 to 0/233.80) Deposit Work	Rs. 99,945.00	Rs.2,000/-	One Month	Rs.350/-
06	Construction of Main Road Punnu Ram Hosue to Lakshari Ram House in Village Dhanot KM 0/0 to 0/300 (SH: P/L Interlocking Concrete Block Pavement at RD 0/270.10 to 0/288.20) Deposit Work	Rs. 99,920.00	Rs.2,000/-	One Month	Rs.350/-
07	Construction of link road to House of Sh. Ashok Kumar in Village Tip Nallah (SH: Formation Cutting at RD 0/0 to 0/300) SDF/2024/542	Rs. 99,720.00	Rs.2,000/-	One Month	Rs.350/-
08	Restoration of Rain Damages on link road Kharmuhan to Dehru Mohal KM 0/0 to 1/00 (SH: ROFD at RD 0/270 to 0/510) SDF/2024/1316	Rs. 93,003.00	Rs.2,000/-	One Month	Rs.350/-
09	Restoration of Rain Damages on link road Dola to Sour Kalan Mohal KM 0/0 to 1/500 (SH: ROFD at RD 0/885 to 1/135) SDF/2024/1325	Rs. 99,057.00	Rs.2,000/-	One Month	Rs.350/-
10	Restoration of Rain Damages on link road Dodru Sour Khurd Kherian Mohal KM 0/0 to 3/00 (SH: ROFD at RD 0/705 to 0/960) SDF/2024/1324	Rs. 99,815.00	Rs.2,000/-	One Month	Rs.350/-
11	Restoration of Rain Damages on link road to Bari Khurd Mohal KM 0/0 to 1/00 (SH: ROFD at RD 0/075 to 0/330) SDF/2024/1314	Rs. 97,614.00	Rs.2,000/-	One Month	Rs.350/-
12	Construction of Main Road Punnu Ram House to Lakshari Ram House in Village Dhanot KM 0/0 to 0/300 (SH: P/L Interlocking Concrete Block Pavement at RD 0/251.90 to 0/270.10) Deposit Work	Rs. 99,920.00	Rs.2,000/-	One Month	Rs.350/-

	Periodic Renewal on Pihri Sihoti Road for the Year 2025-26 under Village Road (SH: P/L G-III for Surface Rectification in KM 0/0 to 1/00).	Rs. 69,138.00	Rs.2,000/-	Three Months	Rs.350/-
13	Periodic Renewal on Pihri Sihoti Road for the Year 2025-26 under Village Road (SH: P/L G-III for Surface Rectification in KM 1/00 to 2/00).	Rs. 69,720.00	Rs.2,000/-	Three Months	Rs.350/-
14	Periodic Renewal on Nahallian Pihri Bhangrolu-Da-Ghatta Road for the Year 2025-26 under Village Road (SH: P/L G-III for Surface Rectification in KM 1/00 to 4/500).	Rs. 70,018.00	Rs.2,000/-	Three Months	Rs.350/-
15	Periodic Renewal on Nahallian Pihri Bhangrolu-Da-Ghatta Road for the Year 2025-26 under Village Road (SH: P/L G-III for Surface Rectification in KM 4/500 to 5/00).	Rs. 70,805.00	Rs.2,000/-	Three Months	Rs.350/-
16	Restoration of Rain Damages on link road Sihoti Galoti to Lower Tikkar (SH: P/L Cement Concrete Pavement at RD 0/883 to 0/898.50) SDF/2024/1327	Rs. 83,128.00	Rs.2,000/-	One Month	Rs.350/-
17	Restoration of Rain Damages on link road to the House of Sh. Arjun Singh to Balahra (SH: P/L Cement Concrete Pavement at RD 0/0 to 0/027.50) SDF/2024/1149	Rs. 99,827.00	Rs.2,000/-	One Month	Rs.350/-
18	Restoration of Rain Damages on Sihoti Pihri Road KM 0/0 to 8/00 (SH: C/o PCC Drain at RD 0/800 to 0/810 & CCP at RD 0/833 to 0/845) SDF/2024/754	Rs. 99,579.00	Rs.2,000/-	One Month	Rs.350/-
19	Restoration of Rain Damages on Sihoti Pihri Road KM 0/0 to 8/00 (SH: P/L Cement Concrete Pavement at RD 0/833 to 0/845 & Drain at RD 0/800 to 0/810) SDF/2024/754	Rs. 99,843.00	Rs.2,000/-	One Month	Rs.350/-
20	Restoration of Rain Damages on Sihoti to Pihri Road KM 0/0 to 8/00 (SH: C/o PCC Drain at RD 0/800 to 0/810 and CCP at RD 0/833 to 0/845) SDF/2024/754	Rs. 99,532.00	Rs.2,000/-	One Month	Rs.350/-
21	Restoration of Rain Damages on link road Sihoti Galoti Road to Lower Tikkar (SH: P/L Cement Concrete Pavement at RD 0/847 to 0/862.50) SDF/2024/1327	Rs. 81,939.00	Rs.2,000/-	One Month	Rs.350/-
22	Restoration of Rain Damages on link road to the House of Sh. Arjun Singh to Balahra (SH: P/L Cement Concrete Pavement at RD 0/030 to 0/057.50) SDF/2024/1149	Rs. 99,743.00	Rs.2,000/-	One Month	Rs.350/-
23	Restoration of Rain Damages on link road Sihoti Galoti Road to Lower Tikkar (SH: P/L Cement Concrete Pavement at RD 0/865 to 0/881.50) SDF/2024/1327	Rs. 84,831.00	Rs.2,000/-	One Month	Rs.350/-
24	Restoration of Rain Damages on Bari Hari Galoti Mahadev Road KM 0/0 to 8/00 (SH: C/o Drain and Dressing of Berms at RD 0/0 to 1/018) SDF/2023/481	Rs. 99,764.00	Rs.2,000/-	One Month	Rs.350/-
25	Restoration of Rain Damages on Bari Hari Galoti Mahadev Road KM 0/0 to 8/00 (SH: C/o Drain and Dressing of Berms at RD 0/020 to 2/010) SDF/2023/481	Rs. 99,960.00	Rs.2,000/-	One Month	Rs.350/-
26	Restoration of Rain Damages on Bari Hari Galoti Mahadev Road KM 0/0 to 8/00 (SH: C/o Drain and Dressing of Berms at RD 0/0 to 1/015) SDF/2023/481	Rs. 99,470.00	Rs.2,000/-	One Month	Rs.350/-
27	Construction of link road upto Pankaj Kumar House in Village Galoti Mohal (SH: ROFD at RD 0/075 to 0/330) BSP/2024/73	Rs. 99,441.00	Rs.2,000/-	One Month	Rs.350/-
28	Restoration of Rain Damages on link road from Laharian to Bangal Mohal KM 0/0 to 1/00 (SH: ROFD at RD 0/675 to 0/930) BSP/2024/1310	Rs. 89,023.00	Rs.2,000/-	One Month	Rs.350/-
29	Restoration of Rain Damages on link road Della to Sour Kalah Mohal KM 0/0 to 1/500	Rs. 99,093.00	Rs.2,000/-	One Month	Rs.350/-

	(SH: ROFD at RD 0/300 to 0/600)SDF/2024/1326				
30	Construction of link road upto the house of Ramesh Chand Lower Tikkar Mohal (SH: ROFD at RD 0/045 to 0/360) BSP/2024/72	Rs. 96,505.00	Rs.2,000/-	One Month	Rs.350/-
31	Restoration of Rain Damages on link road upto the house of Rattan Chand Nalhoti Mohal KM 0/0 to 0/700 (SH: ROFD at RD 0/150 to 0/390) BSP/2024/70	Rs. 98,462.00	Rs.2,000/-	One Month	Rs.350/-
1	The contractors/firms should possess the following documents (Photocopy to be attached):				
(i)	Latest renewal of enlistment.				
(ii)	PAN (Permanent Account No.)				
(iii)	Registration under HP GST/ (TIN No.).				
(iv)	EPF (Employee Provident Fund Account No.)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	If any of the date mentioned above happened/to be Gazetted Holidays the same shall be processed on next working day.				
4	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
5	The next tender will be issued only after completion of previous works in hand.				
6	The offer of the tender shall remain valid upto 30 days after the opening.				



 Executive Engineer
 HPPWD Division Jawalamukhi
 Distt Kangra H.P
 on behalf of Governor of Himachal Pradesh

Exigency Certificate

It is certified that the tenders invited vide this office NIT
No. 1732-46 dated.. 21/06/25 are of emergent nature of work and in
public interest.

Place:

Dated:


Executive Engineer,
HPPWD Division,
Jawalanukhi.

PERCENTAGE BILL OF QUANTITY

Name of work:-

Restoration of rain damages on Nahlian Pihri Bhangolu da Ghatta Road Km. 0/0 to 10/00 (SH:-Providing and laying cement concrete pavement at RD. 0/820 to 0/839) SDF/2024/760

Estimate Cost :- Rs.99817.00
Earnest Money :-Rs. 2000.00
Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including cartage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	8.39 Cubic meter	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic meter	34,399.00
2	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement: one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including cartage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government	9.55 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	65,418.00
Total						
		% Above/below				
		Quoted Amount in Figures				99,817.00
		Quoted Amount in Words				

Bill of quantity checked and approved for Rd. 99817.00 only

Executive Engineer,
Jawalamulhi Division,
JPRWD Jawalamulhi

36

PERCENTAGE BILL OF QUANTITY

Name of work:-

Restoration of rain damages on Nahlian Pihri Bhangolu da Ghatta Road Km. 0/0 to 10/00 (SH.-Providing and laying cement concrete pavement at RD. 0/844 to 0/862.25) SDF/2024/761

Estimate Cost :- Rs.99428.00
Earnest Money :-Rs. 2000.00
Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	8.93 Cubic meter	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic meter	36,613.00
2	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST,sale tax or any other taxes imposed by the Government.	9.17 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	62,815.00
Total						
			% Above/below			
			Quoted Amount in Figures			99,428.00
			Quoted Amount in Words			

Bill of quantity checked and approved for Rs. 99,428.00 only

Executive Engineer,
Jawalamulhi Division,
PPWD Jawalamulhi

PERCENTAGE BILL OF QUANTITY

Name of work:-

Construction of Drain Near the House of Sh. Harnam Singh Lahru.(VKV/2023/1027).(S.H. :- C/o CC Rwall at RD 0/010 to 0/018.30)

Estimate Cost :- Rs 74929.00

Earnest Money :-Rs. 2000.00

Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	7.45 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	2,161.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	17.35 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	70,268.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1(V): 20H (One vertical is to twenty Horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614.709, 1204.3.7 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	10.00 Number	250.00	Rupees Two Hundred Fifty Only	Each	2,500.00
	Total					74,929.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

*Bill of quantity checked and approved
for Rs 74929/- only.*

[Signature]
Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.

64

PERCENTAGE BILL OF QUANTITY

JOB NO:- 2

Estimate Cost :- Rs.99,800.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

Name of work:- C/O Main road Punnu Ram house to Lakshari ram House Village dhanot in KM-0/000 to 0/300 (SH:- P/L Interlocking Concrete Block Pavement at RD. 0/233.80 to 0/251.90) (DEPOSIT WORK)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD Technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals . The rates including Royalty, Malkana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.34 Cubic meter	4050.00	Four Thousand and Fifty Rupees	Per Cubic meter	25678.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:2:4 (one cement isto Two sand isto four graded crushed stone aggregate 20mm (Twenty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD Technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals . The rates including Royalty, Malkana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1.09 Cubic meter	5800.00	Five Thousand and Eight Hundred Rupees	Per Cubic meter	6322.00
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	60.00 Square Metre	1130.00	One Thousand and One Hundred Thirty Rupees	Per Square Metre	67800.00
	Total					99800.00

Quoted Amount in Figures

DNIT No:-

Percentage Bill of Quantity checked & Approved for Rs.99,800/-

Executive Engineer,
Jawalamukhi Division,
APPPWD Jawalamukhi.

63

PERCENTAGE BILL OF QUANTITY

JOB NO:1

Estimate Cost :- Rs.99,945.00

Earnest Money :- Rs. 10,000.00

Time Limit :- One Month.

Name of work:- C/O Main road Punnu Ram house to Lakshari ram House Village dhanot in KM-0/000 to 0/300 (SH:- P/L Interlocking Concrete Block Pavement at RD-0/215.60 to 0/233.80) (DEPOSIT WORK)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete , in or under water in open foundation for all types of structures , including pumping or bailing out water / dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD Technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals . The rates including Royalty, Malkana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.37 Cubic meter	4050.00	Four Thousand Fifty Rupees	Per Cubic meter	25811.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:2:4 (one cement isto Two sand isto four graded crushed stone aggregate 20mm (Twenty millimeter) nominal size) for plain cement concrete , in or under water in open foundation for all types of structures , including pumping or bailing out water / dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD Technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals . The rates including Royalty, Malkana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1.09 Cubic meter	5800.00	Five Thousand Eight Hundred Rupees	Per Cubic meter	6334.00
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504 and as per the direction and the entire satisfaction of Engineer -in-Charge including carriage of material within all leads , lifts and other incidentals . The rates including Royalty, Malkana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	60.00 Square Metre	1130.00	One Thousand One Hundred Thirty	Per Square Metre	67800.00
Total						99945.00
Quoted Amount in Figures		Quantity	Rate in	Unit	Amount	
Quoted Amount in Words						

Quoted Amount in Figures
Quoted Amount in Words

DNIT No -

Percentage Bill of Quantity checked & approved
for Rs 99,945/-

Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.

Comm/F

DNT No - Percentage Bill of quantity checked & Approved by

Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.

67

PERCENTAGE BILL OF QUANTITY

JOB NO:-

Name of work:- Construction of Link Road to House of Sh Ashok Kumar Village Tipnala Mohal (SH:- Formation Cutting at RD 0/00 to 0/300
SDF/2024/542 (DEPOSIT WORK)

Estimate Cost :- Rs.99,720.00
Earnest Money :-Rs. 2,000.00
Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification clause 302.304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	332.40 Cubic meter	300.00	Three Hundred Rupees	Per Cubic meter	99,720.00
	Total					99,720.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

DNIT No- Percentage Bill of Quantity checked & approved for Rs 99,720/-

Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.

JOB NO:-

Estimate Cost :- Rs.93,003.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

PERCENTAGE BILL OF QUANTITY

Name of work:- Restoration of rain damages on Link road Kharmuhan to Dehru Mohal Km 0/0 to 1/00 (SH:- ROFD at RD 0/270 to 0/510)
SDF/2024/1316 (DEPOSIT WORK)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification clause 302.304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	320.70 Cubic meter	290.00	Two Hundred Ninety Rupees	Per Cubic meter	93,003.00
Total						93,003.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

DNIT No:- Percentage Bill of Quantity checked & approved for RD 0/270 to 0/510

Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.

69

PERCENTAGE BILL OF QUANTITY

JOB NO.:-

Estimate Cost :- Rs.99,057.00

Earnest Money :- Rs. 2,000.00

Time Limit :- One Month,

Name of work:- Restoration of rain damages on Link road Dola to Sour Kulan Mohal Km 0/0 to 1/500 (SH:- ROFD at RD 0/885 to 1/135 to)

SDF/2024/1325 (DEPOSIT WORK)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification clause 302.304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	341.58 Cubic meter	290.00	Two Hundred Ninety Rupees	Per Cubic meter	99,057.00
	Total				% Above/below	
					Quoted Amount in Figures	
					Quoted Amount in Words	

Percentage Bill of Quantity checked & Approved for
DNIT No -

Executive Engineer,
Jawaharlamukhi Division,
HPPWD Jawaharlamukhi.

70

PERCENTAGE BILL OF QUANTITY

JOB NO:-5

Estimate Cost :- Rs.99,815.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

Name of work:- Restoration of rain damages on Link road Dodru Sour Khurad Kherian Mohal Km 0/0 to 3/00 (SH:- ROFD at RD 0/705 to 0/960)
SDF/2024/1324 (DEPOSIT WORK)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification clause 302,304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss, to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	340.74 Cubic meter	290.00	Two Hundred Ninety Rupees	Per Cubic meter	98,815.00
Total						98,815.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

UNIT No - 1
Percentage Bill of Quantity checked & Approved
for Rs 98,815/-

Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.

71

PERCENTAGE BILL OF QUANTITY

JOB NO:-4

Name of work:- Restoration of rain damages on Link road to Bari Khurad Mohal Km 0/000 to 1/00 (SH:- ROFD at RD 0/075 to 0/330) SDF/2024/1314 (DEPOSIT WORK)

Estimate Cost :- Rs. 97,614.00
Earnest Money :- Rs. 2,000.00

Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in-Charge complete in conformity with the requirements of MORD Technical Specification clause 302.304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	336.60 Cubic meter	290.00	Two Hundred Ninety Rupees	Per Cubic meter	97,614.00
Total						97,614.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

DVI T No - Percentage Bill of Quantity Checked & Approved for 97,614/-

Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99,920.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

Name of work:- C/O Main road Punnu Ram house to Lakshari ram House Village dhannot In KM-0/000 to 0/300 (SH:- P/L Interlocking Concrete Block Pavement at RD-0/251.90 to 270.10) (DEPOSIT WORK)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete , in or under water in open foundation for all types of structures , including pumping or bailing out water / dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD Technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other Incidentals . The rates including Royalty, Malkana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.37 Cubic meter	4050.00	Four Thousand Fifty Rupees	Per Cubic meter	25798.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:2:4 (one cement isto Two sand isto four graded crushed stone aggregate 20mm (Twenty millimeter) nominal size) for plain cement concrete , in or under water in open foundation for all types of structures , including pumping or bailing out water / dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD Technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other Incidentals . The rates including Royalty, Malkana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1.09 Cubic meter	5800.00	Five Thousand Eight Hundred Rupees	Per Cubic meter	6322.00
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504 and as per the direction and the entire satisfaction of Engineer -in-Charge including carriage of material within all leads , lifts and other Incidentals . The rates including Royalty , Malkana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	60.00 Square Metre	1130.00	One Thousand One Hundred Thirty Rupees	Per Square meter	67800.00
Total						
			% Above/below			
			Quoted Amount in Figures			
			Quoted Amount in Words			

DN/T No. 2

Percentage Bill of Quantity checked & approved for Rs.99,920/-

Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.

61

PERCENTAGE BILL OF QUANTITY

Name of Work:- Periodic Renewal on Pihri Shohi road for the year 2025-26 under village Road (SH - Providing and laying G-III for surface rectification in Km. 0/00 to 1/000).

Estimate Cost :- Rs. 69738.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- Three Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing laying, spreading by mechanically means and compacting to 75mm (Seventy five millimeter) compacted thickness, stone aggregates of Grading-II, 53mm to 22.4mm (Fifty three to twenty two point four millimeter) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (Eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (Eleven point two millimeter) nominal size at the rate of 0.18cum (Zero point one eight cubic meter) per ten square meter to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical specification section 400 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, GST, toll tax or any other taxes imposed by the Government.	39.850 Cubic metre	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Per Cubic metre	69,738.00
	TOTAL					69738.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percent 1844942113-2102141890224
for Rs 69738/-

Executive Engineer,
 Jawalamukhi Division,
 HPPWD Jawalamukhi.

62

PERCENTAGE BILL OF QUANTITY

Name of Work:- Periodic Renewal on Pihni Shohi road for the year 2025-26 under village Road (SH:- Providing and laying G-III for surface rectification in Km. 1/00 to 2/000).

Estimate Cost :- Rs. 69720.00
 Earnest Money :- Rs. 2,000.00

Time Limit :- Three Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing laying, spreading by mechanically means and compacting to 75mm (Seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (Fifty three to twenty two point four millimeter) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (Eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (Eleven point two millimeter) nominal size at the rate of 0.18cum (Zero point one eight cubic meter) per ten square meter to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical specification section 400 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, GST, toll tax or any other taxes imposed by the Government.	39.840 Cubic metre	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Per Cubic metre	69,720.00
	TOTAL					69720.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Percentage Bill of Quantity checked & approved by E. C. 97201

Executive Engineer,
 Jawalamukhi Division,
 H.P.P.W.D. Jawalamukhi.

59

PERCENTAGE BILL OF QUANTITY

Compound
ALL FREE

Estimate Cost :- Rs. 70018.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Three Months.

Name of Work:- Periodic Renewal on Nahilian Pihri Bhagrolu Da Chatta road for the year 2025-26 under village Road (SH:- Providing and laying G-III for surface rectification in Km. 4/00 to 4/500).

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing laying, spreading by mechanically means and compacting to 75mm (Seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (Fifty three to twenty two point four millimeter) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (Eighty to hundred) KN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (Eleven point two millimeter) nominal size at the rate of 0.18cum (Zero point one eight cubic meter) per ten square meter to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical specification section 400 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, GST, toll tax or any other taxes imposed by the Government.	40.010 Cubic metre	1750.00	Rupess One Thousand Seven Hundred Fifty	Per Cubic metre	70,018.00
	TOTAL					70018.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Proceder Bill of quantity sheet is approved for Rs. 70018/-

Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.

60

PERCENTAGE BILL OF QUANTITY

Name of Work:- Periodic Renewal on Nahlihan Pihri Bhagrolu Da Ghatla road for the year 2025-26 under village Road (SH:- Providing and laying G-III for surface rectification in Km. 4/500 to 5/00).

Estimate Cost :- Rs. 70805.00
Earnest Money :- Rs. 2,000.00
Time Limit :- Three Months.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing laying, spreading by mechanically means and compacting to 75mm (Seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (Fifty three to twenty two point four millimeter) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (Eighty to hundred) KN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (Eleven point two millimeter) nominal size at the rate of 0.18cum (Zero point one eight cubic meter) per ten square meter to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical specification section 400 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, GST, toll tax or any other taxes imposed by the Government.	40.460 Cubic metre	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Per Cubic metre	70,805.00
	TOTAL					70805.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

percentage
Bill of quantity sheet 13
9/12/2024 Page 70805/-

Executive Engineer,
 Jawalamukhi Division,
 HPPWD Jawalamukhi.

78

PERCENTAGE BILL OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road Sihoti Galoti Road to Lower Tikker. (SH:-Providing and laying cement concrete pavement at RD 0/883 to 0/898.5) SDF/2024/1327.

Estimate Cost :- Rs.83128.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete. in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	7.26 Cubic meter	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic meter	29,766.00
2	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST,sale tax or any other taxes imposed by the Government	7.79 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	53,362.00
	Total					83,128.00
					% Above/below	
					Quoted Amount in Figures	
					Quoted Amount in Words	

Bill of quantity checked and approved for Rs 83128/- only

Executive Engineer,
 Jawalamulhi Division,
 R/PWD Jawalamulhi

81

PERCENTAGE BILL OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road to the house of Sh.Arjun Singh to Balahra. (SH:-Providing and laying cement concrete pavement at RD 0/00 to 0/027.50) SDF/2024/1149.

Estimate Cost :- Rs.99827.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Loosening original ground upto thirty centimetre below sub-grade level and compacting by rolling with Road roller 8-10kN static weight at OMC to achieve the required density as per Tables 300.1 and 300.2 of MORD Technical Specification section 300 and as per direction and the entire satisfaction of the Engineer in-Charge including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	32.76 Cubic meter	90.00	Rupees Ninety Only	Per Cubic meter	2,948.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification, 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	3.53 Cubic meter	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic meter	14,473.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST,sale tax or any other taxes imposed by the Government	12.03 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	82,406.00
	Total					99,827.00
						% Above/below
						Quoted Amount in Figures
						Quoted Amount in Words

Billed quantity checked and approved for Rs 99,82,471.00

Executive Engineer,
Jawaharini Division,
HPPWD Jawaharini

82 (1)

PERCENTAGE BILL OF QUANTITY

Name of work:- Restoration of rain Damages on Sihoti Pihri Road Km. 0/00 to 8/00. (S.H.: Construction of C/o PCC Drain at RD. 0/800 to 0/810 & CCP at RD. 0/833 to 0/845) SDF/2024/754.

Estimate Cost :- Rs 99579.00
Earnest Money :-Rs. 2000.00
Time Limit :- One Month.

Job No. Page :

Sr. No.	Description of Item	Quantity		Rate in		Unit	Amount
		Figures	Words	Words	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.65	Cubic meter	290 00	Rupees Two Hundred Ninty Only	Per Cubic meter	769 00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M.Ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like, Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depts, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.31	Cubic meter	4850 00	Rupees Four Thousand Eight Hundred Fity Only	Per Cubic meter	30608 00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3 (one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government	6.03 Cubic meter	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic meter	41306.00
4	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement : two sand : two stone) eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax GST or any other taxes imposed by the Government	6.56 Cubic meter	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic meter	26896.00
Total						99,579.00
		% Above/below		Quoted Amount in Figures		
				Quoted Amount in Words		

31.11.2019
for Rs 99,579/- only
and approved

Executive Engineer,
 J/Mukha Division,
 PWD J/Mukhi

77

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99843.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain Damages on Link road Sihoti Pihri Road Km. 0/00 to 8/00. (SH:-Providing and laying cement concrete pavement at RD 0/833 to 0/845 & Drain at Rd. 0/800 to 0/810) SDF/2024/754

Sr. No.	Description of Item	Quantity	Rate in	Unit	Amount
			Figures Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culvers, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	2.49 Cubic meter	290 00 Rupees Two Hundred Ninety Only	Per Cubic meter	722.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.56 Cubic meter	4100 00 Rupees Four Thousand One Hundred Only	Per Cubic meter	26,896.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.31	4550.00	Rupees Four Thousand Nine Hundred Only		30,915.00
4	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3 (one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	6.03 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	41,306.00
Total						99,843.00
			% Above/below			
			Quoted Amount in Figures			
			Quoted Amount in Words			

*6.03 of quantity checked and approved
for Rs 69,843/- only.*

Executive Engineer,
Jawalamulhi Division,
APPPWD Jawalamulhi

PERCENTAGE BILL OF QUANTITY

Name of work:- Restoration of rain Damages on Sihoti Pihri Road Km. 0/00 to 8/00, (S.H.:-Construction of C/o PCC Drain at RD. 0/800 to 0/810 & CCP at RD. 0/833 to 0/845) SDF/2024/754.

Estimate Cost :- Rs 99532.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.49 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	722.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, Grade M-10 (M-Ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation of all type of structure like, Drains, etcetera including pumping or bailing out water/dewatering (surface and sub soil water) removal of the slush which may arise at the time of laying under water, for all heights/depths, including cost of form work complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 or as per direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	6.31 Cubic meter	4850.00	Rupees Four Thousand Eight Hundred Fifty Only	Per Cubic meter	30,608.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3 (one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	6.03 Cubic meter	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic meter	41306.00
4	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement is to four sand is to eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.56 Cubic meter	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic meter	26896.00
Total						99,532.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Bill of materials checked and approved for Rs 99,532/- only.

Executive Engineer,
J/Mukh Division,
JMPWD J/Mukhi

84

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.81939.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain Damages on Link road Sihoti Galoti Road to Lower Tikker. (SH:-Providing and laying cement concrete pavement at RD 0/847 to 0/862.50) SDF/2024/1327.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete. in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.97 Cubic meter	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic meter	28,577.00
2	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST,sale tax or any other taxes imposed by the Government.	7.79 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	53,362.00
Total						81,939.00
			% Above/below			
			Quoted Amount in Figures			
			Quoted Amount in Words			

Bill of quantity checked and approved for Rs.81939.00

Executive Engineer,
 Jawalamulhi Division,
 JPPWD Jawalamulhi

807

PERCENTAGE BILL OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road to the house of Sh.Arjun Singh to Balahra. (SH:-Providing and laying cement concrete pavement at RD 0/030 to 0/057.50) SDF/2024/1149.

Estimate Cost :- Rs.99793.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Loosening original ground upto thirty centimetre below sub-grade level and compacting by rolling with Road roller 8-10kN static weight at OMC to achieve the required density as per Tables 300.1 and 300.2 of MORD Technical Specification section 300 and as per direction and the entire satisfaction of the Engineer in-Charge including carriage of materials up to all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	29.40 Cubic meter	90.00	Rupees Nine Only	Per Cubic meter	2,646.00
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction, and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	2.76 Cubic meter	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic meter	11,316.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5 Stone cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government	12.53 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	85,831.00
	Total					99,793.00
			% Above/below			
			Quoted Amount in Figures			
			Quoted Amount in Words			

*Bill of quantity checked and approved
for Rs 99,793/- on 24/08/23*

Executive Engineer,
Jawalamulhi Division,
G.P.W.D. Jawalamulhi

85

PERCENTAGE BILL OF QUANTITY

Name of work:- Restoration of Rain Damages on Link road Sinothi Galoti Road to Lower Tikker. (SH:-Providing and laying cement concrete pavement at RD 0/865 to 0/881.50) SDF/2024/1327.

Estimate Cost :- Rs.84831.00
Earnest Money :-Rs. 2000.00
Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete. in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	6.84 Cubic meter	4100.00	Rupees Four Thousand One Hundred Only	Per Cubic meter	28,044.00
2	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	8.29 Cubic metre	6850.00	Rupees Six Thousand Eight Hundred Fifty Only	Per Cubic metre	56,787.00
Total						84,831.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

*Billed quantity checked and approved
for Rs 84831.00 only*

Executive Engineer
Jawalamulhi Division,
HPWD Jawalamulhi

86

PERCENTAGE BILL OF QUANTITY

Name of work : **Reconstruction of Drain Penangues on East Hill Estate Mahabudw Road Km. 0/00 to 8/000 (SH) Construction of drains and directing of waters at EC**
 0/00 to 1/018) SDF/2023/481

Estimate Cost :- Rs. 99764.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sl. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government	1018.00 Square metre	50.00	Rupees Sixty Only	Per Square metre	51080.00
2	Construction of running surface drains of average cross-section of 100 to 140 sqm in soil to specified lines grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307, and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government	1018.00 Running metre	30.00	Rupees Thirty Eight Only	Per Running metre	30564.00
Total				% Above/below		99,764.00
				Quoted Amount in Figures		
				Quoted Amount in Words		

Bill of quantity checked and approved for Rs 99764/- only

Executive Engineer,
 Jawaharpuri Division,
 APPWD Jawalamulhi

87

PERCENTAGE BILL OF QUANTITY

Name of work:- Restoration of Rain Damages on Bari Hari Galoti Mahadev Road Km. 0/00 to 8/000. (SH:-Construction of drain and dressing of berms at RD.
1/020 to 2/040) SDF/2023/481

Estimate Cost :-Rs.99960.00
Earnest Money :-Rs. 2000.00
Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty Malkhana Octroi Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1020.00 Square metre	60.00	Rupees Sixty Only	Per Square metre	61,200.00
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307, and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	1020.00 Running metre	38.00	Rupees Thirty Eight Only	Per Running metre	38,760.00
Total				% Above/below		99,960.00
				Quoted Amount in Figures		
				Quoted Amount in Words		

Bill of Quantity checked and approved for Rs 99,960/- only.

Executive Engineer,
Jawalamulhi Division,
GPPWD Jawalamulhi

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99470.00
 Earnest Money :-Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain Damages on Beri Hari Galoti Mahadev Road Km. 0/00 to 8/000. (SH:-Construction of drain and dressing of berms at RD.
 0/00 to 1/015) SDF/2023/481

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	1015.00 Square metre	60.00	Rupees Sixty Only	Per Square metre	60,900.00
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307, and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	1015.00 Running metre	36.00	Rupees Thirty Eight Only	Per Running metre	36,570.00
Total				% Above/below		
				Quoted Amount in Figures		
				Quoted Amount in Words		

*Bill of quantity checked and approved
 per Rs 99470-00*

Executive Engineer,
 Jawalamulhi Division,
 PHRDWD Jawalamulhi

72

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99,441.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

Name of work:- Construction of Link road upto Pankaj Kumar House Village Galoti Mohal (SH:- ROFD at RD 0/075 to 0/330) BSP/2024/73

(DEPOSIT WORK)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiselling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in-charge complete in conformity with the requirements of MORD Technical Specification clause 302.304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	342.90 Cubic meter	290.00	Two Hundred Ninety Rupees	Per Cubic meter	99,441.00
	Total					99,441.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

DONIT NO-

Percentage Bill of Quantity checked & approved for Rs 99,441/-

Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.

73

PERCENTAGE BILL OF QUANTITY

JOB NO:-3

Name of work:- Restoration of rain damages on Link road from Lahrian to Bangal Mohal Km 0/000 to 1/000 (SH:- ROFD at RD 0/675 to 0/930) BSP/2024/1310 (DEPOSIT WORK)

Estimate Cost :- Rs.89,023.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification clause 302.304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	306.98 Cubic meter	290.00	Two Hundred Ninety Rupees	Per Cubic meter	89,023.00
Total						89,023.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

DN/T No - Percentage Bill of Quantity checked & Approved for Rs 89023/-

Executive Engineer
Jawalamukhi Division,
HPPWD Jawalamukhi.

74

PERCENTAGE BILL OF QUANTITY

JOB NO:-

Estimate Cost :- Rs.99,093.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

Name of work:- Restoration of rain damages on Link road Dola to Sour Kalan Mohal Km 0/0 to 1/500 (SH:- ROFD at RD 0/300 to 0/600 to)
SDF/2024/1326 (DEPOSIT WORK)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in-Charge complete in conformity with the requirements of MORD Technical Specification clause 302.304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	341.70 Cubic meter	290.00	Two Hundred Ninety Rupees	Per Cubic meter	99,093.00
Total						99,093.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

DNIT No- Percentage Bill of Quantity checked & approved for Rs 99,093/-

Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.

JOB NO. 4

JOB NO. 4

45 to 0/360) BSP/2024/72

Description of Item

Executive Engineer,
Jawalamukhi Division,
MPPWD Jawalamukhi.

76

PERCENTAGE BILL OF QUANTITY

JOB NO:-2

Name of work:- Restoration of rain damages on Link road upto house of Rattan Chand Nalhoi Mohal Km 0/000 to 0/700 (SH:- ROFD at RD 0/150 to 0/390) BSP/2024/70 (DEPOSIT WORK)

Estimate Cost :- Rs.98,462.00
Earnest Money :-Rs. 2,000.00
Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation for road way in hilly areas in all heights and depths and in all kinds of soil by manual/ mechanical means, including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling or wedging out of rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines grades, cutting and trimming of side slopes, camber, super elevation and levels shown as per the drawings and as directed by the Engineer-in Charge complete in conformity with the requirements of MORD Technical Specification clause 302.304 and 1603 and sorting out and stacking of useful materials with in all leads and lifts of material in acquired road width and transporting of un-useful materials for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to required width of road or on approved dumping sites through all modes of transportation including head load or animal transport or by mechanical means including leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals, necessary to complete the work by mechanical means and labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him to the extent of damage occurred in all cases. The rate including Royalty, Malkana, Octroi, toll tax, sales tax or GST any other taxes imposed by the Government.	339.53 Cubic meter	290.00	Two Hundred Ninety Rupees	Per Cubic meter	98,462.00
Total						98,462.00
Quoted Amount in Figures						
Quoted Amount in Words						

Percentage Bill of Quantity checked & approved for as 98,462/-

Executive Engineer,
Jawalamukhi Division,
HPPWD Jawalamukhi.