

Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2024-25/ 3864-68

Dated/ 28-6-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2,
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter No. PBW(B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

- 1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
- 3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **10.07.2025** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on **09.07.2025** up to 4.00 P.M and the application for issue of tender form shall be received **08.07.2025** up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	C/o Jeepable road from Sh. Desh Raj House to Sh. Ashok Kumar House S/o late Sh. Nathu Ram house village Rathan Ward No. 2 Mohal (SH:- P/L CC Pavement road Km 0/033 to 0/064.80)	Rs. 99,532.00	Rs. 2,000.00	Three Months
2	C/o Jeepable road from Smt. Rattani Devi House towards Rajinder Chauha. (SW:- P/L CC Pavement & C/O R/Wall (Deposit)	Rs. 99,943.00	Rs. 2,000.00	Three Months
3	C/o Jeepable road from Smt. Rattani Devi House towards Rajinder Chauha. (SW:- P/L CC Pavement & C/O R/Wall (Deposit)	Rs. 49,499.00	Rs. 1,000.00	Three Months
4	C/o Pucca Path alongwith Retaining wall & Pulli near the house of Karam Chand (SH:- C/o Pulli and Edge wall (Deposit)	Rs. 85,689.00	Rs. 1,800.00	Two Months
5	C/o Pucca Path alongwith Retaining wall & Pulli near the house of Karam Chand (SH:- P/L Interlocking Paver Block (Deposit)	Rs. 63,175.00	Rs. 1,300.00	Two Months
6	C/o Miyaat Play Ground Gram Panchayat Kandi Drognu (SH:- C/o R/Wall (Deposit)	Rs. 99,337.00	Rs. 2,000.00	Two Months
7	C/o link road from Palampur Thakurdwara Chowki to Har via Nagarkot Colony Joginder ADO House (SW:- C/O 1.00 Mtrs Span Culvert & U-Shape drain at RD 1/700 to 1/730)	Rs. 99,995.00	Rs. 2,000.00	Three Months
8	Restoration of damages due to laying of OFC on link road Tanda Pantehar Molichak Banuri road Km 4/450 to 5/00 (SW:- P/L Paver Block at RD 4/952 to 4/974)	Rs. 99,639.00	Rs. 2,000.00	Three Months
9	R/Wall on Path and Kuhal to Protect the land of Sh. Lekh Raj Sharma VPO Ghar (SW:- C/o R/Wall (Deposit)	Rs. 99,787.00	Rs. 2,000.00	Three Months
10	C/o link road from Tanda Pantehar to Patial Basti Km 0/000 to 0/900 (SH:- Providing and laying Cement Concrete Paver Block at RD 0/060 to 0/084 (OFC Deposit)	Rs. 99,297.00	Rs. 2,000.00	Three Months
11	C/o link road from Tanda Pantehar to Patial Basti Km 0/000 to 0/900 (SH:- Providing and laying Cement Concrete Paver Block at RD 0/090 to 0/114 (OFC Deposit)	Rs. 99,694.00	Rs. 2,000.00	Three Months

12	C/o jeepable road from Mohan Lal house ward No. 3 to Akshay Awasthi house Ward No. 5 (SW:- C/o 1.00 mtrs Span Culvert at RD 0/135 (Deposit)	Rs. 98,868.00	Rs. 2,000.00	Three Months
13	C/o Special repair of Spedu to Satchali Bridle path KM 0/00 to 34/00 (SW:- Cutting work & Chiseling work and RR Dry Masonary (Deposit)	Rs. 96,211.00	Rs. 2,000.00	Three Months
14	C/o Special repair of Spedu to Satchali Bridle path KM 0/00 to 34/00 (SW:- Cutting work & Chiseling work and RR Dry Masonary (Deposit)	Rs. 99,982.00	Rs. 2,000.00	Three Months
15	Restoration of OFC Damage on link road Tanda Pantehar Molichak Banuri road Km 0/000 to 5/00 (SW:- Providing and laying Interlocking Concrete Block Pavement at RD 4/935 to 4/957) (OFC Deposit)	Rs. 97,710.00	Rs. 2,000.00	Two Months
16	Restoration of OFC damages on link road Tanda Pantehar Molichak Banuri road Km 0/00 to 5/00 (SW:- P/L Interlocking Concrete Block Pavement at RD 4/910 to 4/932.50 (OFC Deposit)	Rs. 99,756.00	Rs. 2,000.00	Two Months
17	Balance work of Jeepable road from Kumharta towards Newa Plantation (SH:- P/L CC Pavement at RD 0/170 to 0/205 (VKVNY (Deposit)	Rs. 99,225.00	Rs. 2,000.00	Two Months
18	Restoration of Parour Lahla Gopalpur Rakh Ghamrota Jiyen Sukeri Kandi Bandla road Km 0/00 to 33/00 (SW:- Hiring of JCB for removal of slip and Clearance of drain (DC Deposit)	Rs. 98,900.00	Rs. 2,000.00	Two Months
19	Restoration of damages due to laying of OFC on link road Tanda Pantehar Molichak Banuri road Km 4/450 to 5/00 (SW:- P/L Paver block at RD 4/910 to 4/931)	Rs. 99,870.00	Rs. 2,000.00	Three Months
20	Restoration of damages due to laying of OFC on link road Tanda Pantehar Molichak Banuri road Km 4/450 to 5/00 (SW:- P/L Paver block at RD 4/931 to 4/952)	Rs. 99,870.00	Rs. 2,000.00	Three Months
21	C/o Pulli near the house of Sh. Ashok Kumar S/o Sh. Minak Ram GP Kand GwalTikkar (SW:- C/o 2.00 mtr Span Culvert)	Rs. 97,704.00	Rs. 2,000.00	Three Months
22	R/Wall to protect land in village Sunehar W. No. 9 Mohal Padhiyarkhar (SW:- C/o R/Wall (VKVNY Deposit)	Rs. 74,708.00	Rs. 1,500.00	Three Months
23	R/o Speru to Goarth road Km 0/00 to 2/00 (SW:- Hiring of JCB Breaker for breaking of stones at various reaches (DC Deposit)	Rs. 98,000.00	Rs. 2,000.00	Two Months
24	R/o Speru to Goarth road Km 0/00 to 2/00 (SW:- Hiring of JCB for removal of slips and clearing of drains in Km 0/00 to 2/00 (DC Deposit)	Rs. 98,000.00	Rs. 2,000.00	Two Months
25	Restoration of rain damages due to digging of road trenches for laying of water supply pipe line from Palampur Neugal Park to Lohna (SW:- C/o 1.00 mtrs span culvert at RD 1/920 to 1/922)	Rs. 74,054.00	Rs. 1,500.00	Three Months
26	Restoration of rain damages due to digging of road trenches for laying of water supply pipe line from Palampur Neugal Park to Lohna (SW:- C/o Retaining wall from RD 5/730 to 5/731.50(JSV Deposit)	Rs. 99,485.00	Rs. 2,000.00	Three Months
27	C/o link road from National Highway towards Joshi Basti in GP Padiarkhar (SW:- Providing and laying Cement concrete Pavement RD 0/000 to 0/019 (VKVNY Deposit)	Rs. 99,428.00	Rs. 2,000.00	Three Months

28	C/o link road from National Highway towards Joshi Basti in GP Padiarkhar (SW:- Providing and laying Cement concrete Pavement RD 0/019 to 0/046 (VKVNY Deposit)	Rs. 49,896.00	Rs. 1,000.00	Three Months
29	Restoration of OFC Damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road Km 33/000 to 40/500 (SW:- Providing and laying Interlocking Paver Block at RD 37/700 to 37/70805)	Rs. 94,171.00	Rs. 1,900.00	Three Months
30	Ambulance road from Sh. Raj Kumar House to Sh.Pritam Chand house Ward No. 5 Village Chornali (SW:- P/L Cement Concrete RD 0/030 to 0/071.80 (VKVNY Deposit)	Rs. 99,896.00	Rs. 2,000.00	Three Months
31	C/o Jeepable road Sh. Ajay Sharma house to Sarvjeet house Ward No. 5 Chandpur (SW:- C/o R/Wall from RD 0/010 to 0/014 & P/L Cement Concrete from RD 0/000 to 0/025.20 (VKVNY Deposit)	Rs. 99,831.00	Rs. 2,000.00	Three Months
32	Additional Accommodation Govt. Senior Secondary School Kandwari (SW:- Painting, Distempering and lettering work (Deposit)	Rs. 98,250.00	Rs. 2,000.00	Three Months
33	Kulani Chandpur Bharmat Colony Kamakhya Mandir N.H. Holta Simblu Patti road (SW:- Painting and writing letters in kilometer stones etc (Under Nabard)	Rs. 99,614.00	Rs. 2,000.00	Three Months
34	A/R & M/O various roads under Palampur Division Distt. Kangra (HP) (SW:- Providing and supplying Form No. 8 for preparing various Agreements)	Rs. 99,000.00	Rs. 2,000.00	Three Months
35	A/R & M/O various Residential Buildings of PWD under Palampur Division HP.PWD Palampur (SW:- Providing and supplying of printing agreements, file cover and plain file cover for various works)	Rs. 73,000.00	Rs. 1,500.00	Three Months

Terms & Conditions-

Following documents should accompany the application for tender

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years
8. The Contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand . Next tender will be issued only after completion of previous works in hand.

Executive Engineer
Palampur Division
HPPWD Palampur

Work No.

Estimated Cost :- Rs. 99,532/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months

Schedule of Quantity

Name of Work :- C/O Jeepable road from Sh. Desh Raj house to Sh. Ashok Kumar house S/O Late Sh. Nathu Ram house village

Rathan Ward No. 2 Mohal
(S. W. :- P/L CC Pavement road km 0/033 to 0/064.80

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	6.68			Per Cubic metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix.P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	13.36			Per Cubic metre.	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Name of Work :- C/O Jeepable road from Smt. Rattani Devi house towards Rajinder Chauha
(S. W. :- P/L CC Pavement & C/O R/Wall Deposit)

Schedule of Quantity

Work No. 2

Estimated Cost :- Rupees 99,943/-

Earnest Money :- Rupees 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing concrete for plain/ reinforced concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	11.20	Cubic metres			Per Cubic metre.	
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1. including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	3.43	Cubic metre			Per Cubic metre	
3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	6.61	Cubic metre			Per Cubic metre	
Total :-							

Executive Engineer
Palampur Division
HP.PWD Palampur

Name of Work :- C/O Jeepable road from Smt. Rattiani Devi house towards Rajinder Chauha
 (S. W. :- C/O R/Wall *Deposit*)

Work No. **3**

Estimated Cost :- Rupees 49,499/-
 Earnest Money :- Rupees 1000/-
 Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any Charge including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	6.47			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth), as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement; five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	11.09			Per Cubic metre	
Total :-						

Executive Engineer
 Palampur Division
 HP.PWD Palampur

4

SCHEDULE OF QUANTITY

Name of work:- C/o Pucca Path alongwith Retaining wall & Pulli Near the house of Karam Chand. (SH:- C/o Pulli & edge wall)
). (Deposit 1.50 Lacs)

Estimated cost Rs. 85689.00

Earnest Money Rs. 1800.00

Time Limits Two Months

Sr. No	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	10.24			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	14.67			Per cubic metre	
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc, as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government	147.10			Per Kilogram	
	Total					

Executive Engineer,
 Palampur Division
 HP.PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o Pucca Path alongwith Retaining wall & Pulli Near the house of Karam Chand. (SH:- P/L interlocking paver block). (Deposit 1.50 Lacs)		Estimated cost Rs.		63175.00		
		Earnest Money Rs.		1300.00		
		Time Limits		Two Months		
Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arrisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	1.05			Per cubic metre.	
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	45.50			Per square metre	
	Total					

Executive Engineer
Palampur Division
HP.PWD Palampur

6

SCHEDULE OF QUANTITY						
Name of work:- C/o Miyaat Play Ground Gram Panchyat Kandi Drogna. (SH:- C/o R/wall). Deposit 1.00 Lacs						
Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
				Estimated cost Rs.		99337.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	8.64			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.60			Per cubic metre	
3	Back filling with granular material behind abutment, wing wall and return wall to the full height compacted to a firm condition complete or as directed by the Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The work should be done as per MORTH technical specification clauses 710.1.4 of IRC: 78 & 2200. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	2.88			Per cubic metre	
4	Providing weep holes in brick masonry/stone masonry/plain of reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00			Each	
	Total					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

of Work :- C/O link road From Palampur Thakurdwara Chowki to Har via Nagarkot Colony Joginder ADO house
 W. :- C/O 1.00 mter Span Culvert at RD #700 at Rd 1780 and V-shape drain 1700 to 1730

Work No. **7**

Estimated Cost : Rs. 99,995/-

Earnest Money : 2000/-

Time limit : Three Months

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. including the cost of form work and curing, complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.60	Cubic metres			Per Cubic metre.	
2	Providing concrete for plain/reinforced concrete in open foundations 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate (20 mm nominal size) R.C.C. grade M- 25 (M-Twenty Five) complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals .The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	3.84	Cubic metres			Per Cubic metre	
3	Supplying,fitting and placing HYSD bar reinforcement in super structure complete as per drawing and technical specification clause 1002,1010 and 1202.as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals .The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	408.00	kilogram me			Per kilogram me	
4	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	11.55	Cubic metre			Per Cubic metre	
5	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	6.83	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

17-6-25

Work No. 8

Schedule of Quantity

Estimated Cost :- Rupees 99,639/-
Earnest Money :- Rupees 2000/-
Time limit : Three Months.

Name of Work :- Restoration of damages due to laying of OFC on link road Tanda Pantehar Molichak Banuri road Km. 4/450 to 5/00
(S. W. :- P/L Paver block at RD 4/952 to 4/974

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	3.00			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	67.58			Per square metre	
3	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	0.99			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- R/Wall on path and Kuhl to protect the land of Sh. Lekh raj sharma V.P.O. Ghar
(S. W. :- C/O R/Wall CBE Post)

Work No. 9

Estimated Cost :- Rupees 99,787/-
Earnest Money :- Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Mailkama,Toll tax, GST or any other taxes imposed by the Government.	9.77			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specifications section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	22.57			Per Cubic metre	
					Total :-	


Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- C/O link road from Tanda Pantehar to Patial Basti Km. 0/000 to 0/900
(S. W. :- P/L Cement concrete Paver Block at RD 0/060 to 0/084 (MNP)

Work No. **10**

Estimated Cost :- Rs. 99,297/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the intersices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	0.28			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	74.71			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203, includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.48			Per Cubic metre.	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- C/O link road from Tanda Panthehar to Patial Basti Km. 0/000 to 0/900
 (S. W. :- P/L Cement concrete Paver Block at RD 0/090 to 0/114 (MNP)

Work No. 11

Estimated Cost :- Rs. 99,694/-
 Earnest Money :- Rs. 2000/-
 Time limit : Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	0.28			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	75.02			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.48			Per Cubic metre.	
					Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Drafts Schedule of Quantity
 Name of Work :- C/O Jeepable road from Mohan Lal house ward no.3 to Akshay Awasthi house ward no. 5
 (S. W. :- C/O 1.00 mtr. Span culvert at RD 0/135) Deposit

Estimated Cost :- Rs. 98,868/-
 Earnest Money :- Rs. 2000/-
 Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	7.20	Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	2.32	Cubic metre			Per Cubic metre	
3	Providing and laying cement concrete for plain / reinforced concrete in sub structure complete as per drawing and technical specifications clause 802,804,805,806,807,1202 and 1204 for height upto 5.0m. PCC grade M-15 (Nominal Mix 1:2.5:5) and curing complete including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	5.70	Cubic metre			Per cubic metre	
4	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 & 1203 including carriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.05	Cubic metre			Per Cubic metre	
5	P&L Plain / reinforced cement concrete in super structure complete as per Drawing and technical specifications Clauses 800,1205.4 and 1205.5 for height upto 5.00m RCC Grade M-25 nominal mix (1:1.5:3) as in Deck Slab etc. including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	1.15	Cubic metres			Per Cubic metre	
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bars with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	160.00	Kilogram me			Per Kilogram me	
7	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5	232.50	Cubic metres			Per Cubic metre	
						Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

Name of Work :- C/O special repair of Spedu to Satchali bridle path Km. 0/000 to 34/000
(S. W. :- Cutting work & Chiseling work and RR dry Masonry) *Deposit work*

Work No. **13**

Estimated Cost :- Rupees 96,211/-
Earnest Money :- Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Cutting in earth work and disposal of excavated earth upto a lead of 20 metres:-Chiselling/wedging out of rock where blasting is prohibited in Hard rock including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	148.50			Per Cubic metre	
2	C/o Dry rubble masonry in breast wall and retaining walls revetment walls and parapets & Foot Path Steps etc. including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	4.72			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Name of Work :- C/O special repair of Spedu to Satchali bridle path Km. 0/000 to 34/000
 (S. W. :- Cutting work & Chiseling work and RR dry Masonry) *Deposit Work*

Work No. **14**

Estimated Cost :- Rupees 99,982/-
 Earnest Money :- Rupees 2000/-
 Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	182.25			Per Cubic metre	
2	Cutting in earth work and disposal of excavated earth upto a lead of 20 metres:-Chiselling/wedging out of rock where blasting is prohibited in Hard rock including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	74.25			Per Cubic metre	
3	C/o Dry rubble masonry in breast wall and retaining walls revetment walls and parapets & Foot Path Steps etc. including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	4.05			Per Cubic metre	
					Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur


SCHEDULE OF QUANTITY

Name of work:- Restoration of OFC Damage on link road Tanda Pantchar Molichak Banuri road Km 0/00 to 5/00. (SH:- P/L interlocking concrete block pavement at Rd 4/935 to 4/957). OFC Deposit		Estimated cost Rs.		97710.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two Months		
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	66.00			Per square metre	
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	2.10			Per cubic metre.	
Total						

Executive Engineer
Palampur Division
HP.PWD Palampur

16

SCHEDULE OF QUANTITY						
Name of work:- Restoration of OFC Damage on link road Tanda Pantehar Molichak Banuri road Km 0/00 to 5/00. (SH:- P/L interlocking concrete block pavement at Rd 4/910 to 4/932.50). OFC Deposit						
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification. Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	67.50			Per square metre	99756.00
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	2.12			Per cubic metre.	2000.00
Total						


 Executive Engineer,
 Palampur Division
 HP, PWD Palampur


SCHEDULE OF QUANTITY

Name of work:- Balance work of Jeepable road from Kumharta towards Neva Plantation. (SH:- P/L C.C. Pavement at Rd 0/170 to 0/205). VKVNY Deposit 5.00 Lacs					
Sr No.	Description of Item	Quantity	Rate		Unit
			In Figures	In Word	
1	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix. P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.75			Per cubic metre.
Total					
			Estimated cost Rs.		99225.00
			Earnest Money Rs.		2000.00
			Time Limits		Two Months
					Amount

Executive Engineer,
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- R/o road on Parour Lahla Goplapur Rakh Ghamrota Jiyuen Sukeri Kandi Bandla road Km 0/00 to 33/00 . (SH:- Hiring of JCB for removal of slip & clearance of drain). D.C. Deposit 164656/-		Estimated cost Rs. 98900.00				
		Earnest Money Rs. 2000.00				
		Time Limits Two Months				
Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of JCB (Excavator-Cum-Loader) including P.O.L. charges shifting charges and other ancillary equipments as per required at site of work for removal of slips. The disposal of this un-serviceable material has to be done in the required width of the road to avoid damages to the properties of the people or in case any damage mttook place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	86.00			Per Hour	
					Total	


 Executive Engineer,
 Palampur Division
 HP.PWD Palampur.

5/20/2018 dt 17-6-25

Schedule of Quantity

Name of Work : - Restoration of damages due to laying of OFC on link road Tanda Pantehar Molichak Banuri road Km. 4/450 to 5/00
(S. W. :- P/L Paver block at RD 4/910 to 4/931

Work No. (19)

Estimated Cost :- Rupees 99,870/-
Earnest Money :- Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty thee to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	4.00			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge includingcarriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	65.52			Per square metre	
3	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical SpecificationsClause802,803,1202 &1203 including carriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.08			Per Cubic metre	
Total :-						

Executive Engineer
Palampur Division
HP.PWD Palampur

T/S No 2817 dt 17-6-25
 20

Name of Work :- Restoration of damages due to laying of OFC on link road Tanda Pantehar Molichak Banuri road Km. 4/450 to 5/00
 (S. W. :- P/L Paver block at RD 4/931 to 4/952)

Schedule of Quantity

Work No.
 Estimated Cost :- Rupees 99,870/-
 Earnest Money :- Rupees 2000/-
 Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	4.00			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	65.52			Per square metre	
3	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix ,P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 &1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.08			Per Cubic metre	
					Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

Name of Work :- C/O Pulli near house of Sh. Ashok kumar S/O Late Sh. Minak Ram G.P. kand Gwalitkker
(S. W. :- C/O 2.00 mtr. Span culvert

Work No. 21

Estimated Cost :- Rupees 97,704/-
Earnest Money :- Rupees 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructum of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	4.80	Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	3.12	Cubic metre			Per Cubic metre	
3	Providing plain/ reinforced Cement concrete in Sub Structure 1:2.5:5 (One Cement : two and half sand : five crushed stone aggregate) Nominal Mix P.C.C. grade M-15 (M-fifteen) complete as per drawings and technical specifications Claus 802,804,805,806,807,1202 and 1204 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	12.30	Cubic metre			Per cubic metre	
4	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix.P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203, including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.72	Cubic metres			Per Cubic metre.	
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bars with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana,Tol tax, GST or any other taxes imposed by the Government.	90.00	Kilogram me			Per Kilogram me	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Work No. **22**

Name of Work :- R/Wall to protect land in village Sunehar W. No. 9 Mohal Padhiyarkhar
(S. W. :- C/O R/Wall (VKNY Deposit))

Estimated Cost :- Rupees 74,708/-
Earnest Money :- Rupees 1500/-
Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	7.68	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	16.56	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	5.00	Nos.			Each	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

23

SCHEDULE OF QUANTITY

Sr. No.		Description of Item	Quantity	Rate		Unit	Amount
				In Figures	In Word		
Name of work:- R/O of Speru to Goarth road Km 0/00 to 2/00 . (SH:- Hiring of JCB Breaker for Breaking of stones at Various reaches). D.C. Deposit							
				Estimated cost Rs.		98000.00	
				Earnest Money Rs.		2000.00	
				Time Limits		Two Months	
1		Hiring of JCB (Breaker) including P.O.L. charges shifting charges and other ancillary equipments as per required at site of work for breaking of rocks. The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damage took place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	49.00			Per hour	
Total							

Executive Engineer,
Palampur Division
HP.PWD Palampur.

24

SCHEDULE OF QUANTITY

Name of work:- R/O of Speru to Goarth road Km 0/00 to 2/00 .(SH:- Hiring of JCB for removal of slip & clearing of drain in Km 0/00 to 2/00). D.C. Deposit

Sr. No.	Description of Item	Quantity	Rate		Unit	Two Months Amount
			In Figures	In Word		
			Time Limits			
						Estimated cost Rs. 98900.00
						Earnest Money Rs. 2000.00
1	Hiring of JCB (Excavator-Cum-Loader) including P.O.L. charges shifting charges and other ancillary equipments as per required at site of work for removal of slips. The disposal of this un-serviceable material has to be done in the required width of the road to avoid damages to the properties of the people or in case any damage mtook place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	86.00			Per Hour	
Total						

Executive Engineer,
Palampur Division
HP, PWD Palampur.

25

Schedule of Quantity

Name of Work :- Restoration of Rain damages due to digging of road trenches for laying of water supply pipe line from Palampur Neugal Park to Lohna
(S. W. :- C/O 1.00 mtr. Span Culvert at RD 1/920 to 1/922

Work No. Estimated Cost :- Rs. 74,054/-
Earnest Money :- Rs. 1500/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	15.39 Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	0.52 Cubic metre			Per Cubic metre	
3	Providing plain/ reinforced Cement concrete in Sub Structure 1:2.5:5 (1 Cement : 2.5 sand : 5 crushed stone aggregate) Nominal Mix P.C.C. grade M-15 (M-fifteen) complete as per drawings and technical specifications Claus 802,804,805,806,807,1202 and 1204 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	8.11 Cubic metre			Per cubic metre	
4	Providing and laying Reinforced cement concrete in 1:1.5:3 (one cement : one point five coarse sand : three graded crushed stone aggregate) 20 mm nominal size so as to obtain minimum crushing strength of R.C.C. grade M-25 (M-Twenty Five) and curing complete excluding cost of reinforcement for reinforced concrete work in foundations and plinth as per drawings and technical specifications Clauses 802,803,1202 and 1203 as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals .The rate includes octroi,royalty,Malkana.Tol tax, GST or any other taxes imposed by the Government.	1.25 Cubic metres			Per Cubic metre	
5	Providing Concrete for plain/reinforced cement concrete)1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix up to all height R.C.C grade M 20 (M-Twenty) in sub structure as per drawing and Technical Specifications Clause 802,804, 805,806,807,1202 &1204 including carriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	0.31 Cubic metre			Per Cubic metre	
6	Supplying,fitting and placing HYSD bar reinforcement in super structure complete as per drawing and technical specification clause 1002,1010 and 1202.as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals .The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	118.83 Kilogram			Per Kilogram	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur



Work No.

Estimate Cost :-Rs. 99,485/-

Earnest Money :-Rs.2000/-

Time Limit :- Three Months

Schedule of Quantity

Name of Work :- Restoration of Rain damages due to digging of road trenches for laying of water supply pipe line from Palampur Neugal Park to Lohna

Sub Work :- C/O Retaining wall From RD 5/730 to 5/731.50 (JSV Deposit)

S. No	Description of Item	Quantity	Rate		Unit	Amount Rupees
			In figure	In Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	6.52			Per Cubic metre	
2	Providing and Laying concrete for plain/reinforced concrete in open foundations 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete including the cost of form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; within all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	21.39			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	8.00			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	5.18			Per Cubic metre	
Total :-						

Executive Engineer,
Palampur Division,
HPPWD Palampur

27

Work No.

Estimated Cost :- Rs. 99,428/-

Earnest Money :- Rs. 2000/-


Time limit : Three Months

Schedule of Quantity

Name of Work :- C/O link road from National highway towards Joshi Basti in GP Padiarkhar

(S. W. :- P/L Cement concrete Pavement Rd 0/000 to 0/019) VKVNY Deposit

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads,lifts and other incidentals by Manual Means.The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	9.33			Per Cubic metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203, including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	12.45			Per Cubic metre.	
Total :-						


 Executive Engineer
 Palampur Division
 HP.PWD Palampur

Work No. 28

Estimated Cost :- Rs. 49,896/-
 Earnest Money :- Rs. 1000/-
 Time limit : Three Months

Schedule of Quantity

Name of Work :- C/O link road from National highway towards Joshi Basti in GP Padiarkhar
 (S. W. :- P/L Cement concrete Pavement Rd 0/019 to 0/046) VKVNY Deposit

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	7.92			Per Cubic metre.	
					Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Work No. 29

Estimated Cost :- Rs. 94,171/-
 Earnest Money :- Rs. 1900/-
 Time limit : Three Months.

Schedule of Quantity
 Name of Work :- Restoration of OFC damages on Dharamshala Yol Dadh Hoifa Chadhiyar Sandhole road km. 33/000 to 40/500
 (S. W. :- Providing and Laying interlocking Paver Block at RD 37/700 to 37/708.5

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	4.65			Per Cubic metre.	
2	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	62.05			Per square metre	
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	0.68			Per Cubic metre.	
					Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

Name of Work :- Ambulance road from Sh. Raj Kumar house to Sh. Pritham chand house Ward No. 5 village Chornali
 (S. W. :- P/L Cement concrete Rd 0/030 to 0/071.80) VKVNY Deposit

Work No. **30**

Estimated Cost :- Rs. 99,896/-
 Earnest Money :- Rs. 2000/-

Time limit : Three Months

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads,lifts and other incidentals by Manual Means.The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government	7.83			Per Cubic metre.	
2	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	13.06			Per Cubic metre.	
					Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Estimated Cost :- Rs. 99,831/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

Schedule of Quantity
Name of Work :- C/O Jeepleable road Sh. Ajay Sharma house to Sarveet house ward no.5 Chandpur
(S. W. :- C/O R/wall from RD 0/010 to 0/014 & P/L cement concrete from Rd 0/000 to 0/025.20) VKVNY Deposit

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	2.24	Cubic metre			Per Cubic metre	
2	Providing and Laying concrete for plain/reinforced concrete in open foundations 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete including the cost of form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; within all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	7.44	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the government.	6.00	Nos.			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	1.80	Cubic metre			Per Cubic metre	
5	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer -in -charge i/c carriage of materials within all leads, lifts and other incidentals by Manual Means.The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	6.04	Cubic metres			Per Cubic metre.	
6	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203, includingthe cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	8.06	Cubic metres			Per Cubic metre.	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

Schedule of Quantity

Estimated Cost : Rupees 99,909/-
 Earnest Money : Rupees 2000/-
 Time limit : Three Months.

Work :- Additional Accomodation Govt. Senior Secondary School Kandwari

Work :- Painting, Distempring and lettering work **Deposit**

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications. Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two ornore coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidental. The rate include octroi, royalty, ,Malkana, Tol tax, GST or any other taxes imposed by the Government.	81.72	Square metre			Per Square metre	
2	Writing letters or figures on any surface with black japan paint of approved brand and manufacture (stops,comas,hyphens and the like not to be measured and paid separately).The rate include octroi, royalty, ,Malkana, Tol tax, GST or any other taxes imposed by the Government. The rate include octroi, royalty, ,Malkana, Tol tax, GST or any other taxes imposed by the Government.	33650.00	per letter per cm. height			Per Square metre	
3	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives.New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	150.00	Square metre			Per Cubic metre	
Total:-							

Executive Engineer
 Palampur Division
 H.P.PWD Palampur

33

Schedule of Quantity

Estimated Cost : Rupees 99,614/-
 Earnest Money : Rupees 2000/-
 Time limit : Three Months.

Name of Work :- Kulani Chandpur Bharmat Colony Kamakhya Mandir N.H. Holta Simblu Patti Road
 Sub Work :- Painting & writing letters in Kilometre Stones etc. Under Nakad

S. No.	Description of Item	Quantity		Rate		Amount
		In figure	In words	In figure	In words	
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications. Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two ornate coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidental. The rate include octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	84.60	Square metre		Per Square metre	
2	Writing letters or figures on any surface with black japan paint of approved brand and manufacture (stops,comas,hyphens and the like not to be measured and paid separately).The rate include octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government. The rate include octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	30000.00	per letter per cm. height		Per Square metre	
3	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives.New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi,royalty,Malkana, Tol tax, GST or any other taxes imposed by the Government.	200.00	Square metre		Per Cubic metre	

Executive Engineer
 Palampur Division
 H.P.PWD Palampur


31

Schedule of Quantity

Estimated Cost :- Rupees 99,000/-
Earnest Money :- Rupees 2000/-
Time limit : Three Months.

Name of Work :- A/R & M/O various roads under Palampur Division Distt. Kangra (H.P.)
Sub Head :- Providing and supplying Form No. 8 for preparing various agreements

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and supplying of Form no. 8 (eight) comprising 112 (one hundred twelve) pages printed with black ink as per the norms of CPWD manual complete in all respect. The rates shall be including all taxes, GST, levy by the Government time to time and carriage of material with in all leads, lifts and as per the Direction of Engineer -in -charge.	550.00			Each	
					Total:-	


Executive Engineer
Palampur Division
H.P.PWD Palampur

35

Schedule of Quantity
 Name of Work :- A/R & M/O various residential buildings of PWD under Palampur Division HPPWD Palampur
 Sub Head :- Providing and supplying of Printing agreement, file cover & plain File cover for various works

Estimated Cost : Rupees 73,000/-
 Earnest Money : Rupees 1500/-
 Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and supplying of Printing agreement File cover Superior quality in all respect. The rates shall be included all taxes, GST, levy by the Government time to time and carriage of material with in all leads, lifts and as per the Direction of Engineer -in -charge.	1000.00			Each	
	Providing and supplying of plain File cover Superior quality for various works complete in all respect. The rates shall be included all taxes, GST, levy by the Government time to time and carriage of material with in all leads, lifts and as per the Direction of Engineer -in -charge.	1000.00			Each	
	Total:-					

~~Executive Engineer~~
 Palampur Division
 H.P.PWD Palampur