

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Scaled item rate / percentage rate tender are hereby invited on Form No. 6 & 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Government of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 04-08-2025 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 04-08-2025 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender:- 05-08-2025 at 10.30 AM.
4. Date of opening of Tender:- 05-08-2025 at 11.30 AM.

Sr. No	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	C/O link road from Panjarda to Deyog Janglian road Km 0/00 to 1/00 (SH:- C/O ROFD at RD 0/105 to 0/230) (Under SDP 2024-213)	4,98,016/-	10000/-	Two Months	Rs. 350/-	Class-D
2	C/O link road Panjarda to Deog Janglian (SH:- C/O R/wall at RD 0/310 to 0/323.70) (Under SDP 2024-213)	2,17,515/-	5000/-	Two Months	Rs. 350/-	Class-D
3	C/O link road to village Jol Km 0/00 to 0/600 (SH:- P/L filling in Km 0/00 to 0/065 , Cement concrete pavement at RD 0/00 to 0/070 & R/wall at RD 0/050 to 0/060 (Under SDP/ 2024/212)	4,99,427/-	10000/-	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, list of which any be attached with their applications (The proof of ownership of machinery/ leg up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

- (i) No Violation of social distancing.
- (ii) Mandatorily wearing of face cover by everyone.
- (iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

For and on behalf of Governor of HP.

No:-PW/BHD/TA/NIT/2024- 5271-5300

Dated:- 28-07-2025

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj.
12. Various Contractors/ Firms.

Executive Engineer,
Bhoranj Division,
HPPWD, Bhoranj.

SCHEDULE OF QUANTITY

OF WORK:- C/O link road Panjarda to Deog Janglian . (SH:- C/O R/Wall at RD 0/310 to 0/323.70.) (Under S.D.P, 2024-213)

Estimated Cost
Earnest Money
Time

Rs 217515/-
Rs. 5000/-
2 month

No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.09	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	44.40	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	23.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	15.62	Per Cubic Meter			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- C/o of link road from Panjarda to Deyog Janqlan road Km 0/0 to 1/00 (SH:- C/O ROFD at RD. 0/105 to 0/230.) ~~(Under SCDP)~~

(Under SDP, 2624-213)

Estimated Cost
Earnest Money
Time

Rs 4,98,016/-
Rs. 10000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Excavation in earth work in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side. Water pollution, etc and to protect soil stability of hill side rock shall be excavated with chiseling and wedging our rock (where blasting is prohibited) All earth work in cutting/excavation including rock excavation shall be carried out true to line, grades, slopes, width, camber, super elevation and level as shown on the drawing as per direction of Engineer in Charge in conformity with the requirement of technical specification for rural roads august 2004 clause 16.2 of general conditions of contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and stage, disposal of unsuitable cut material in specified manner, trimming/filling of unevenness blindage and finishing of the road to specified dimensions or as directed by Engineer in charge for smooth riding. The recovery of useful stones shall be made from the contractor and recovery of 189.47 cubic meter useful stones shall be made @ 300/-per cubic meter on prorata basis in each running bill. Any loss to the public and private property during the course of excavation shall be resorted by the contractor what so ever the nature of the same may be. The servicable material will be stacked out specified /dimension in all leads and lifts as per the direction of Engineer in Charge.	1291.87	Per Cubic Meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HR PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- C/O Link road to Village Jol Km. 0/00 to 0/600 (SH:- P/L filling in km 0/00 to 0/065 , cement concrete pavement at RD. 0/00 to 0/070 & R/wall at RD 0/050 to 0/060). (Deposit work) ~~2024/212~~ **8DP/2024/212**

Estimated Cost
Earnest Money
Time

Rs 4,99,427/-
Rs. 10000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Excavation, Supplying filling of local earth (i/c royalty) by mechanical means up to all leads and lifts also including ramming, dewatering of earth layers up to all heights in trenches earth side of foundation etc. complete and as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	211.50	Per Cubic Meter			
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	31.50	Per Cubic Meter			
3	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10 (M-ten) nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm (forty millimeters) nominal size including centering and shuttering in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.00	Per Cubic Meter			
4	Providing and laying mechanically mixed cement concrete (M-20) (M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm (twenty millimeters) for plain / reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.00	Per Cubic Meter			
5	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	34.84	Per Cubic Meter			

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HR PWD Bhoranj