

OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS
DEPARTMENT BANGANA

No:- PW-BGN-CB/T-1/2025-26-
To

- 3371-80

Dated:- 25.07
2025

The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.
cc-pwd-hp@nic.in.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD, Una.
4. The Assistant Engineer, Sub Division, HPPWD Bangana and Basal.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.

A. S. Chaudhary
Executive Engineer
Bangana Division
HPPWD Bangana.

Executive Engineer
Bangana Division
HPPWD Bangana.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BGN/CB/T-1/20245-26-

3371-80 dated 25/7/2025

A. S. Ch
Executive Engineer
Bangana Division
HPPWD Bangana.

**OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS
DEPARTMENT BANGANA**


NOTICE INVITING TENDER.

Sealed percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Bangana Division HPPWD Bangana on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **01-08-2025 up to 10.30 A.M** and same will be opened on the same day at 11.00 AM in presence of the interested contractors or their authorized representative. The application will be received in this office on at **31-07-2025 upto 11.30 PM**. The tender form can be had from the office of Executive Engineer Bangana Division HPPWD Bangana on cash payment (Non-refundable) on **31-07-2025** during office Hours **2.00 PM to 4.30 PM**. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Bangana Division HPPWD Bangana cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period	Eligible of Class
1	Construction of Various Road Under HPPWD Sub Division Bangana. (SH:- Construction of Inauguration/Foundation Pedestal Made of Moulder Bricks, P/F Granite Plates)	99497.00	2000.00	Two Month	D
2	Stock Storage at HPPWD Sub Division Bangana. (Sub Head:- Supply & Stacking First Class Machine Made Modular Bricks)	99900.00	2000.00	Two Months	D
3	Construction of Various Roads Under HPPWD Sub Division Bangana. (Sub Head:- Construction of Foundation/Inauguration Padestal Made of Modular Bricks, P/F Granite Plates)	99497.00	2000.00	Two Months	D
4	Restoration of Rain Damages on TMBD Road Km. 0/000 to 28/675. (Sub Head:- Construction of R/Wall at RD. 18/805 to 18/809.20)	98524.00	2000.00	Two Months	D
5	Restoration of Rain Damages on TMBD Road Km. 0/000 to 28/675. (Sub Head:- Construction of R/Wall at RD. 18/809.20 to 18/813.40)	98092.00	2000.00	Two Months	D
6	Restoration of Rain Damages on TMBD Road Km. 0/000 to 28/675. (Sub Head:- Construction of R/Wall at RD. 18/813.40 to 18/817.60)	98338.00	2000.00	Two Months	D
7	Restoration of Rain Damages on TMBD Road Km. 0/000 to 28/675. (Sub Head:- Back Filling Behind Wire Crate R/Wall in Km. 27/840 to 27/512 & 27/850 to 27/875)	99697.00	2000.00	Two Months	D
8	Restoration of Rain Damages on Various Roads Under Bangana Sub Division. (Sub Head:- Hiring of Tipper Under Bangana Section in Various Roads)	99125.00	2000.00	Two Months	D
9	A/R & M/O PWD Rest House Bangana Tehsil Bangana Distt. Una HP. (Sub Head:- P/F Flooring Room No. 01 & 03 etc)	99585.00	2000.00	Two Months	D
10	A/R & M/O PWD Rest House Bangana Tehsil Bangana District Una HP. (Sub Head:- P/F Curtain for Door & Window, Door Mat, Inauguration Board etc)	99443.00	2000.00	Two Months	D
11	Restoration of Rain Damages on Link Road Bangana to Thathoon to Bandu Brahmana Km. 0/000 to 0/500. (Sub Head:- Construction of R/Wall from RD. 0/480 to 0/487.50)	98038.00	2000.00	Two Months	D
12	Restoration of Rain Damages on Link Road Bangana to Thathoon to Bandu Brahmana Km. 0/000 to 0/500. (Sub Head:- Construction of R/Wall from RD. 0/488 to 0/495.50)	98284.00	2000.00	Two Months	D

13	Restoration of Rain Damages on Talai Lidkot Road Km. 0/000 to 10/000. (Sub Head:- Removal of Slips at Various RD's in Km. 2/000 to 6/000)	99385.00	2000.00	Two Months	D
14	Restoration of Rain Damages on Talai Lidkot Road Km. 0/000 to 10/000. (Sub Head:- Removal of Slips at Various RD's in Km. 6/000 to 10/000)	99291.00	2000.00	Two Months	D
15	Restoration of Rain Damages on Lathiani to Kohdra Road Km. 0/000 to 8/420. (Sub Head:- Construction of 600mm Dia Hume Pipe Culvert at RD. 2/435)	91568.00	1900.00	Two Months	D
16	Restoration of Rain Damages on Various Roads Under Bangana Sub Division. (Sub Head:- Hiring of JCB under Bangana Section-I)	98900.00	2000.00	Two Months	D
17	Restoration of Rain Damages on Various Roads Under Bangana Sub Division. (Sub Head:- Hiring of JCB Under Bangana Section-II)	99475.00	2000.00	Two Months	D
18	Stock Storage at HPPWD Sub Division Bangana. (Sub Head:- Supply & Stacking of Wet Mix Macadam for Bangana Section-I)	99556.00	2000.00	Two Months	D
19	Stock Storage at HPPWD Sub Division Bangana. (Sub Head:- Supply & Stacking of Wet Mix Macadam for Bangana Section-II)	99993.00	2000.00	Two Months	D
20	Stock Storage at HPPWD Sub Division Bangana. (Sub Head:- Supply & Stacking RCC Hume Pipe 450mm Dia)	99225.00	2000.00	Two Months	D
21	Stock Storage at HPPWD Sub Division Bangana. (Sub Head:- Printing & Supplying of PWD Tender Form No. 6, 7, 8 & Agreement File Cover for HPPWD Division Bangana.	99710.00	2000.00	Two Months	D
22	Stock Storage at HPPWD Sub Division Bangana. (Sub Head:- Supply & Stacking Road Bond Ready Mix Pot Seal at Section Bangana-I)	99900.00	2000.00	Two Months	D
23	Stock Storage at HPPWD Sub Division Bangana. (Sub Head:- Supply & Stacking Road Bond Ready Mix Pot Seal at Section Bangana-II)	99225.00	2000.00	Two Months	D
24	Restoration of Rain Damages on Various Roads under Bangana Sub Division. (Sub Head:- Hiring of Tipper Under Chaproh & Bhiru Section in Various Roads)	97600.00	2000.00	Two Months	D
25	Construction of Link Road to Village Dadiyar (Sub Head:- Construction of R/Wall in Km. 0/300 to 0/307) (Under SCDP)	99165.00	2000.00	Two Months	D
26	Construction of Link Road to Village Dadiyar (Sub Head:- Construction of R/Wall in Km. 0/314 to 0/321) (Under SCDP)	99254.00	2000.00	Two Months	D
27	Construction of Link Road to Village Dadiyar (Sub Head:- Construction of R/Wall in Km. 0/307 to 0/314) (Under SCDP)	99254.00	2000.00	Two Months	D
28	Repair & Maintenance of Office Building of Executive Engineer HPPWD Bangana District Una HP (Sub Head:- Providing & Fixing Split type Air Conditioner in Correspondence Branch)	69980.00	1400.00	Seven Days	D

HIM SUCHANA AVAM JAN SAMPARK.


 Executive Engineer
 Bangana Division
 HPPWD Bangana.
 On behalf of Governor of Himachal Pradesh.

Percentage BoQ.

Name of Work:- SC/O various road under HPPWD Sub Division at Bangana Sub Division (Sh:- C/O Innaguation / foundation Padestal made of Moulder Bricks , P/F Granite Plates)

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder name and values only

Sr. No.	Description of work	Estimated Cost	Quantity	Earnest Money	2000.00	Time Limit	Two Month
				Unit	Estimated Rate in Words	Total amount without Taxes	AMOUNT Rs. P
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.		0.97	Per Cubic meter	246.80	240.00	Rupees Two Hundred & Forty Six - Paise Eighty Only
2.00	Providing and laying cement concrete 1:4:8 (One cement : four coarse sand : eight graded crushed stone aggregate 40mm (forty millimetre) nominal size)mechanically mixed and curing complete excluding cost of form work upto all work plinth level including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , labour cess or other taxes imposed by the Government		3.75	Per Cubic metre.	4200.00	15750.00	Rupees Four Thousand Two Hundred Only

(4) 8

3.00	Brick work with common burnt clay F.P.S. modular bricks of class designation 7.5 in super structure in cement mortar 1:3 (One cement: three coarse sand) in all heights and depth as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.40	Per Square Meter	16033.60	38481.00	Rupees Sixty Thousand & Thirty Three Paise Sixty Only
4.00	Pointing on brick work with cement mortar 1:4 (1 cement 4 sand) including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	23.78	Per Square Meter	104.00	2473.00	Rupees One Hundred & Four Only
5.00	Providing and Fixing Imagination / foundation plate writing grooving and painting properly as per drawing and technically specification and as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	3.00	Nos.	7500.00	22500.00	Rupees Seven Thousand Five Hundred Only
6.00	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications of ICI (Dulux Gloss) (Luxol High Gloss) Asian Paint (Premium Apcolite Gloss) Shalimar make two or more coats applied on walls @ 1.25 ltr/10 sqm (one point twenty five liter per ten square meter) over and including one coat of Special primer applied @ 0.75 ltr /10 sqm (zero point seventy five per ten square meter) complete upto all floor level as per the direction by the Engineer in charge in all floor level/height including entire carriage of materials with in all leads and lifts and other incidentals. The	190.98	Per Square Meter	105.00	20053.00	Rupees One Hundred & Five Only
Total Rs.						Rupees Ninety Nine Thousand Four Hundred & Ninety
Quoted Rate in Figures			Excess(+)			
			Less(-)			


Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

9

Name of work:- Stock Storage at HP PWD Sub Div : _____
_____ PW Division Bangana

Estimated Cost	99900.00
Rs	

Earnest Money	2000.00
Rs	

Time Limit:	Two Month
-------------	-----------

Time Limit:	Two Month
-------------	-----------

Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

(3)

Tender Inviving Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- C/O various roads under HPPWD Sub Division at Bangana (SH:- C/O Foundation /inauguration Padestal made of Modular Bricks , P/F Granite Plates)

Name of Bidder/ Bidding Firm/ Company :-


Estimated Cost	Rs	99497.00
Earnest Money	Rs	2000.00
Time Limit:	Two Month	

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	0.972	Per cubic metre	246.80	240.00	Ruppes Two Hundred Forty Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	3.75	Per Cubic metre	4200.00	15750.00	Ruppes Fifteen Thousand Seven Hundred & Fifty Only
3.00	Brick work with common burnt clay F.P.S. (machine made modular) bricks super structure in cement mortar 1:3(One cement: three coarse sand) in all heights and depth as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	2.40	Per Cubic metre.	16033.60	38481.00	Ruppes Thirty Eight Thousand Four Hundred Eighty One Only
4.00	Flush/ Ruled/ Struck or weathered Pointing on tile brick work with cement mortar 1:4 (cement : four fine sand) as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	23.78	Per Square meter	104.00	2473.00	Ruppes Two Thousand Four Hundred & Seventy Three Only

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. p.	Total Amount without Taxes in Rs. p.	Total Amount in Words
5.00	Providing and laying /Inauguration plate writing, grooving and painting properly as per drawing HP.PWD specification size (0.90x0.75 cm) as per the direction by the Engineer-in-charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	3.00	Each	7500.00	22500.00	Rupees Twenty Two Thousand Five Hundred Only
6.00	Finishing wall with weather proof exterior grade emulsion of approved design Asian Paint ICI, Dulux gloss Nerolac Burger (Luxol high gloss) premium Apcolite glos and Shalimar Paint (Apexultima) or its equivalent on undecorated wall surfaces (Two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete upto all floor level including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	190.98	Per Square metre.	105.00	20053.00	Rupees Twenty Thousand & Fifty Three Only
Total in Figures					99497.00	Rupees Ninety Nine Thousand Four Hundred
Quoted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on TMBD ROAD KM 0/00 to 28/6/75(SH:- C/O R/wall at RD 18/805 to 18/809.20)

Estimated Cost Rs 98524.00

Earnest Money 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: Two Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	17.11	Per cubic metre	280.00	4791.00	Rupess Four Thousand Seven Hundred & Ninety One Only
2.00	Providing and laying cement concrete 1:5:10(one cement : five sand : ten graded stone aggregate 40mm/forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD, technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	24.59	Per Cubic metre	3626.00	89163.00	Rupess Eighty Nine Thousand One Hundred & Sixty Three Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 Kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.00	Each	246.00	2214.00	Rupess Two Thousand Two Hundred & Fourteen Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MOR.D 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.02	Per Cubic metre	780.00	2356.00	Rupess Two Thousand Three Hundred & Fifty Six Only
Total in Figures					98524.00	Rupess Ninety Eight Thousand Five Hundred &
Quoted Rate in Figures					Excess (+) Less (-)	

Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HP.PWD Division Bangana

Name of work:- Restoration of Rain Damages on TMBD ROAD KM 0/00 to 28/6/75(SH:- C/O R/wall at RD 18/809.20 to 18/813.40)

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only.)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	17.11	Per cubic metre	280.00	4791.00	Rupees Four Thousand Seven Hundred & Ninety One Only
2.00	Providing and laying cement concrete 1:5:10(One cement :five sand: ten graded stone aggregate 40mm(forty millimeter)/nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD, technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	24.59	Per Cubic metre	3626.00	89163.00	Rupees Eighty Nine Thousand One Hundred & Sixty Three Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.00	Each	246.00	1722.00	Rupees One Thousand Seven Hundred & Twenty Two Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.02	Per Cubic metre	800.00	2416.00	Rupees Two Thousand Four Hundred & Sixteen Only
Total in Figures					98092.00	Rupees Ninety Eight Thousand & Ninety Two Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Asst Engr
Executive Engineer
Bangana Division
HP.PWD. Bangana

Percentage BOQ

6

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on TMBD ROAD KM 0/00 to 28/675(SH:- C/O R/wall at RD 18/813.40 to 18/817.60)

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost	Rs 98338.00
Earliest Money	Rs 2000.00
Time Limit	Two Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	17.11	Per cubic metre	280.00	4791.00	Rupees Four Thousand Seven Hundred & Ninety One Only
2.00	Providing and laying cement concrete 1:5:10(one cement : five sand : ten graded stone aggregate 40mm/forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD, technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	24.59	Per Cubic metre	3626.00	89163.00	Rupees Eighty Nine Thousand One Hundred & Sixty Three Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.00	Each	246.00	1968.00	Rupees One Thousand Nine Hundred & Sixty Eight Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.02	Per Cubic metre	800.00	2416.00	Rupees Two Thousand Four Hundred & Sixteen Only
Total in Figures				98338.00		Rupees Ninety Eight Thousand Three Hundred & Thirty Eight Only
Quoted Rate in Figures				Excess (+) Less (-)		

Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

7

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on TMBD ROAD KM 0/00 to 28/675(SH:- Back filling behind wire crate R/wall in Km 27/480 to 27/512 & 27/850 to 27/875)

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	93.02	Per Cubic metre	650.00	60463.00	Rupees Sixty Thousand Four Hundred & Sixty Three Only
2.00	Construction of embankment with approved material obtained at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300.1 and 300.2 with in all leads and lifts as per Technical Specification MORD 2014 Clause 301.5 The rate shall include carriage of machineries, equipment, tools and materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	347.20	Per Cubic metre	113.00	39234.00	Rupees Thirty Nine Thousand Two Hundred & Thirty Four Only
Total in Figures					99697.00	Rupees Ninety Nine Thousand Six Hundred & Ninety Seven Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Amit Kumar
Executive Engineer
Bangana Division
HP.PWD. Bangana

Percentage BOQ

8

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Various roads under Bangana Sub-Division (SH: Hiring of Tipper under Bangana Section in various roads)

Estimated Cost
Rs 99125.00

Earnest Money
Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: Two Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work eith in all leads and lifts to the entire satisfaction of the Engineer In-charge. The tipper should work minimum 8.00(Eight hours) from 19.00 A.M. to 5.00P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in charge.. The rate includes octroi, royalty,malkhana, toll tax,GST,labour cess or other taxes imposed by the Government.	32.50	Per Day	3050.00	99125.00	Rupees Ninety Nine Thousand One Hundred & Twenty Five Only
Total in Figures					99125.00	Rupees Ninety Nine Thousand One Hundred Twenty Five Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Asst Enr
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- A/R & M/O PWD Rest House Bangana Tehsil Bangana Distt. Una. (HP) (SH: P/F Flooring room No.01 & 03 etc.)

Estimated Cost
Rs 99585.00

Earnest Money
Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit:

Two Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Providing and Fixing hard density (HDF) AC-4 in flooring preeliminated one side decorative 8mm thick and other side plain having density 800/1000/cum with necessary fixing arrangement and screws in all respect completed as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	44.26	Per Square meter	2250.00	99585.00	Rupees Ninety Nine Thousand Five Hundred & Eighty Five Only
Total in Figures					99585.00	Rupees Ninety Nine Thousand Five Hundred & Eighty Five Only
Quoted Rate in Figures		Excess (+) Less (-)				

As per
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

10

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- A/R & M/O PWD Rest House Bangana Tehsil Bangana Dist. Una. (HP) (SH: P/F Curtain for Door & Window, Door Mat, Inauguration Board etc.)

Estimated Cost	Rs	99443.00
Earnest Money	Rs	2000.00
Time Limit:	Two Month	

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bids in the following format)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Providing and fixing curtain including stitching and fixing in which curtain cloth & lining complete having size of 2.60x1.10 metre in width complete as per HP.PWD specification, as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	37.00	Each	1900.00	70300.00	Rupees Seventy Thousand Three Hundred
2.00	Providing and fixing stainless steel rod 25mm dia i/c bracket and final complete as per HP.PWD specification, as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	19.65	Per Running meter	450.00	8843.00	Rupees Eight Thousand Eight Hundred & Forty Three Only
3.00	Supplying of Door foot mat green colour PVC carpet as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.00	Each	800.00	2400.00	Rupees Two Thousand Hundred Only
4.00	Providing and fixing sofa cover set and final complete as per HP.PWD specification, as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	2.00	Set	2500.00	5000.00	Rupees Five Thousand
5.00	Providing and fixing Inauguration Board 8mm thick of size 12'x12' along within frame work completed as per HP.PWD specification, as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	1.00	Each	9900.00	9900.00	Rupees Nine Thousand Hundred Only
6.00	Supplying of Randal Plastic Swing Lid Garbage Waste Dustbin Wei & Dry for Home, Office, Factory (25 Ltr) Plastic Dustbin (Blue colour) & ISI approved , as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	5.00	Each	600.00	3000.00	Rupees Three Thousand Only
Total in Figures					99443.00	Rupees Ninety Nine Thousand Four Hundred Fourty Three Only
Quoted Rate in Figures					Excess (+) Less (-)	

Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on link road Bangana to Thathoon to Bandu Brhmma Km 0/000 to 0/500 (SH: C/o R/wall from RD 0/480 to 0/487.50)

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the B Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in W
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	5.22	Per cubic metre	250.00	1305.00	Rupees One Thousand Hundred & Five C
2.00	Providing and laying cement concrete 1:5:10(one cement : five sand : ten graded stone aggregate 40mm(forty millimeter)nominal size and curing complete including cost of form work with MS plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.PWD, technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	24.97	Per Cubic metre	3626.00	90541.00	Rupees Ninety Thon Five Hundred & Four Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.00	Each	246.00	2952.00	Rupees Two Thousand Hundred & Fifty Two
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	5.40	Per Cubic metre	600.00	3240.00	Rupees Three Thousand Hundred & Four
Total in Figures					98038.00	Rupees Ninety E Thousand & Thirty Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Executive Engineer
Bangana Division
HP.PWD, Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on link road Bangana to Thathoon to Bandu Brhmana Km 0/000 to 0/500 (SH: C/o R/wall from RD 0/488 to 0/495.50)

Estimated Cost
Rs 98284.00

Earnest Money
Rs 2000.00

Time Limit:
Two Month

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bid Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of sumps and other deteriorous material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	5.22	Per cubic metre	250.00	1305.00	Rupees One Thousand Hundred & Five O
2.00	Providing and laying cement concrete 1:5:10(One cement :five sand: ten graded stone aggregate 40mm/forty millimeter)nominal size and curing complete including cost of form work with M5 plates plain concrete on ground or under water and curing complete including pumping bailing out water dewatering removal of slush or required at site which may arise at the time of laying under water complete for all heights and depths in retaining wall /breast wall as per drawing and HP.P.W.D., technical specification direction of Engineer-in-charge including carriage of materials within all leads and lifts . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	24.97	Per Cubic metre	3626.00	90541.00	Rupees Ninety Thou Five Hundred & Four Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in-charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.00	Each	246.00	3198.00	Rupees Three Thousand Hundred & Ninety E Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	5.40	Per Cubic metre	600.00	3240.00	Rupees Three Thousand Hundred & Four Only
Total in Figures					98284.00	Rupees Ninety Eight Thousand Two Hundred Eighty Four On
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Executive Engineer
Bangana Division
HP.P.W.D. Bangana

5

Estimated Cost	99385.00
Rs	

Earnest Money	2000.00
Rs	

Time Limit:	Two Month
-------------	-----------

1. *Chlorophyll a* and *b* were determined by the method of Arar and Collins (1971).

Executive Engineer
Bangana Division
P.P.W.D. Bangana

Percentage BOQ

(14)

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Talai Lidkot road Km 0/000 to 10/000 (SH:

Removal of Slip at verious RD's in km 6/000 to 10/000)

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns; else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. p.	Total Amount without Taxes in Rs. p.	Total Amount in Words
1.00	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials with in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkhana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	794.33	Per cubic metre	125.00	99291.00	Rupees Ninety Nine Thousand Two Hundred & Ninety One Only
Total in Figures					99291.00	Rupees Ninety Nine Thousand Two Hundred & Ninety One Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Amol Kumar
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Lathiani to Kodra road Km 0/000 to 8/420 (SH: C/o 600mm dia Hume pipe Culvert at RD 2/435)

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks) where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	13.80	Per cubic metre	280.00	3864.00	Rupees Three Thousand Eight Hundred & Sixty Four Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.27	Per cubic metre	4695.00	10658.00	Rupees Ten Thousand Six Hundred & Fifty Eight Only
3.00	Providing and laying cement concrete work 1:2:5:5 (one cement: two decimal five sand:five graded stone aggregate) 40mm (forty millimetre) nominal size in substructure mechanically mixed and vibrated including curing complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 and as per the direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.99	Per cubic metre	4958.00	39614.00	Rupees Thirty Nine Thousand Six Hundred & Fourteen Only
4.00	Providing and laying 600mm(six hundred millimetre) dia reinforced cement concrete pipe NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2(one cement:two sand) but excluding excavation protection work,back filling,concrete and masonry work in head walls and parapets as per technical specifications clause -1106 including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	7.50	Per running meter	3200.00	24000.00	Rupees Twenty Four Thousand Only
5.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	2.56	Per cubic metre	5247.00	13432.00	Rupees Thirteen Thousand Four Hundred & Thirty Two Only
Total in Figures					91568.00	Rupees Ninety One Thousand Five Hundred & Sixty Eight Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Executive Engineer
Bangana Division
H.P.P.W.D. Bangana

Ambar

Percentage BOQ

(18)

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Various roads under Bangana Sub-Division (SH: Hiring of JCB under Bangana-I Section)

Estimated Cost	98900.00
Rs	
Earliest Money	2000.00
Rs	
Time Limit:	Two Month

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviceable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred Only
Total in Figures					98900.00	Rupees Ninety Eight Thousand Nine Hundred Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Amol Chav
Executive Engineer
Bangana Division
HP, PWD, Bangana

Percentage BOQ

(19)

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Various roads under Bangana Sub-Division (SH: Hiring of JCB under Bangana-II Section)

Estimated Cost
Rs 99475.00

Earnest Money
Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviceable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	86.50	Per Hours	1150.00	99475.00	Ruppes Ninety Nine Thousand Four Hundred & Seventy Five Only
Total in Figures					99475.00	Ruppes Ninety Nine Thousand Four Hundred & Seventy Five Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Anand Chav
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

26

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Stock Storage at HP.PWD Sub-Division Bangana (SH: Supply and stacking of wet mix macadam for Bangana-I Section)

Estimated Cost	Rs	99556.00
Earnest Money	Rs	2000.00

Time Limit:	Two Month
-------------	-----------

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Supply and Stacking grading-3 wet mix macadam as per technical specification clouse 406 by Mechanical means, including loading & unloading and stacking properly at site, as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	86.57	Per Cubic meter	1150.00	99556.00	Rupees Ninety Nine Thousand Five Hundred & Fifty Six Only
Total in Figures					99556.00	Rupees Ninety Nine Thousand Five Hundred & Fifty Six Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Amol
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

91

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Stock Storage at HP.PWD Sub-Division Bangana (SH: Supply and stacking of wet mix macadam for Bangana-II Section)

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Supply and Stacking grading-3 wet mix macadam as per technical specification clause 406 by Mechanical means, including loading & unloading and stacking properly at site, as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	86.95	Per Cubic meter	1150.00	99993.00	Ruppes Ninety Nine Thousand Nine Hundred & Ninety Three Only
Total in Figures					99993.00	Ruppes Ninety Nine Thousand Nine Hundred & Ninety Three Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Ameear
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

52

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Stock Storage at HP.PWD Sub-Division Bangana(SH: Supply and stacking RCC Hume pipes 450mm dia)

Estimated Cost	99225.00
Rs	
Earnest Money	2000.00
Rs	
Time Limit:	Two Month

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Supply and Stacking RCC 450mm dia Hume pipes (2.50 mtr length each pipe) i/c collar approved brand/ISI marked including loading & unloading and stacking properly at site, including carriage of materials within all leads and lifts and including all incidentals and as per drawings and technical specification as per the direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	21.00	Each	4725.00	99225.00	Rupees Ninety Nine Thousand Two Hundred Fifty Only
Total in Figures					99225.00	Rupees Ninety Nine Thousand Two Hundred & Twenty Five Only
			Excess (+)			
			Less (-)			
Quoted Rate in Figures						

And Car
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

25

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Stock Storage at HP.PWD Sub-Division Bangana (SH:- Printing and supplying of PWD Tender Form No.6,7,8 and agreement file cover for HP.PWD Division Bangana)

Estimated Cost	Rs	99710.00
Earnest Money	Rs	2000.00
Time Limit:	Two Month	

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Printing and supplying of PWD Tender Form No.6 for HP.PWD Division Bangana as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	390.00	Each	10.00	3900.00	Rupees Three Thousand Nine Hundred Only
2.00	Printing and supplying of PWD Tender Form No.8 & 7 for HP.PWD Division Bangana as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	390.00	Each	207.00	80730.00	Rupees Eighty Thousand Seven Hundred & Thirty Only
3.00	Providing and Supplying Agreement file cover (printed) including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	580.00	Each	26.00	15080.00	Rupees Fifteen Thousand & Eighty Only
Total in Figures					99710.00	Rupees Ninety Nine Thousand Seven Hundred & Ten Only
Quoted Rate in Figures					Excess (+) Less (-)	

Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

24

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Stock Storage at HP.PWD Sub-Division Bangana (SH: Supply and stacking road Bond ready mix pot seal at Section Bangana-I)

Estimated Cost Rs 99900.00
Earnest Money Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: Two Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Supply and Stacking patch work material (Ready mix Pot seal) Packing of 25.00 kg (Twenty five) Kilogramme per bags as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	148.00	Per Bag	675.00	99900.00	Rupees Ninety Nine Thousand Nine Hundred Only
Total in Figures					99900.00	Rupees Ninety Nine Thousand Nine Hundred Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Executive Engineer
Bangana Division
HP.PWD.Bangana

Amal Ch

Percentage BOQ

25

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Stock Storage at HP.PWD Sub-Division Bangana (SH: Supply and stacking road Bond ready mix pot seal at Section Bangana-I)

Estimated Cost	99225.00
Rs	
Earnest Money	2000.00
Rs	

Name of Bidder/ Bidding Firm/ Company :-

Time Limit:	Two Month
-------------	-----------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Supply and Stacking patch work material (Ready mix Pot seal) Packing of 25.00 kg (Twenty five) Kilogramme per bags as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	147.00	Per Bag	675.00	99225.00	Rupees Ninety Nine Thousand Two Hundred & Twenty Five Only
Total in Figures					99225.00	Rupees Ninety Nine Thousand Two Hundred & Twenty Five Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Executive Engineer
Bangana Division
HP.PWD, Bangana

Percentage BOQ

26

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Restoration of Rain Damages on Various roads under Bangana Sub-Division (SH: Hiring of Tipper under Chaproh & Bihru Section in various roads)

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost	Rs	97600.00
Earnest Money	Rs	2000.00
Time Limit:	Two Month	

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Hiring of Tipper 5.5 cum capacity having lift system for carriage of meterial to different site of work eith in all leads and lifts to the entire satisfaction of the Engineer In-charge. The tipper should work minimum 8.00(Eight hours) from 19.00 A.M. to 5.00P.M. dally. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be bome by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in charge.. The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	32.00	Per Day	3050.00	97600.00	Rupees Ninety Seven Thousand Six Hundred Only
Total in Figures					97600.00	Rupees Ninety Seven Thousand Six Hundred Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				

Amal Kumar
Executive Engineer
Bangana Division
HP.PWD,Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- C/O link road to Village Dadiyar (SH:- C/O R/wall in Km 0/300 to 0/307) Under SCDP

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	9.66	Per cubic metre	312.00	3014.00	Rupees Three Thousand & Fourteen Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	22.05	Per Cubic metre	3946.00	87009.00	Rupees Eighty Seven Thousand & Nine Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.00	Each	302.00	6342.00	Rupees Six Thousand Three Hundred & Fourty Two Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MORD 2014 technical specification clause 1604,7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.50	Per Cubic metre	800.00	2800.00	Rupees Two Thousand Eight Hundred Only
Total in Figures					99165.00	Rupees Ninety Nine Thousand One Hundred & Sixty Five Only
Quoted Rate in Figures					Excess (+) Less (-)	

Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- C/O link road to Village Dadiyar (SH:- C/O R/wall in Km 0/307 to 0/314) Under SCDP

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost Rs	99254.00
Earnest Money Rs	2000.00
Time Limit:	Two Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks/ where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	9.66	Per cubic metre	312.00	3014.00	Rupees Three Thousand & Fourteen Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or hauling out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within in all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, GST, labour cess or other taxes imposed by the Government.	22.05	Per Cubic metre	3950.00	87098.00	Rupees Eighty Seven Thousand & Ninety Eight Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.00	Each	302.00	6342.00	Rupees Six Thousand Three Hundred & Fourty Two Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MOR.D 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.50	Per Cubic metre	800.00	2800.00	Rupees Two Thousand Eight Hundred Only
Total in Figures					99254.00	Rupees Ninety Nine Thousand Two Hundred & Fifty Four Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD, Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- C/o link road to Village Dadiyar (SH:- C/O R/wall in Km 0/314 to 0/321) Under SCDP

Estimated Cost
Rs 99254.00

Earnest Money
Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: Two Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	9.66	Per cubic metre	312.00	3014.00	Rupees Three Thousand & Fourteen Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	22.05	Per Cubic metre	3950.00	87098.00	Rupees Eighty Seven Thousand & Ninety Eight Only
3.00	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 110mm (one hundred ten millimeter) diameters, PVC pipe of finolex/ D-Plast make having working pressure 4.00 kg per square millimeter extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.00	Each	302.00	6342.00	Rupees Six Thousand Three Hundred & Forty Two Only
4.00	Back filling with granular material behind abutment, wing wall and return wall complete as per drawing, direction of Engineer in charge and MOR.D 2014 technical specification clause 1604.7.8 including carriage of materials/machinery required to execute the work with in all leads and lifts including other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	3.50	Per Cubic metre	800.00	2800.00	Rupees Two Thousand Eight Hundred Only
Total in Figures					99254.00	Rupees Ninety Nine Thousand Two Hundred & Fifty Four Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- Repair & Maintenance Office Building of Executive Engineer HPPWD Division Bangana Distt. Una (HP) (SH: Providing & Fixing Split type Air Conditioner in Correspondence Branch)

Name of Bidder/ Bidding Firm/ Company :-


Estimated Cost	69980.00
Earnest Money	1400.00
Rs	

Time Limit:	Seven Days
--------------------	------------

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount without Taxes in Rs. P.	Total Amount in Words
1.00	Supply, installation, testing and commissioning of SPLIT type Air-Conditioner 1.5 Tonne capacity two in one (Cold & Hot) conforming to ISI-1391 Part-1992 with ammentent No.1 (except power consumption Norms) fitted with Hermetically shielded 1.5 Tonne capacity split type Air-Conditioner make VOLTAS as required complete in all respect including, as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.00	Each	64500.00	64500.00	Rupees Sixty Four Thousand Five Hundred Only
2.00	Supplying and fixing wall mounting Voltage Stabilizer 4KVA Automatic type with output 150X 240 volts with voltage regulator range from 170 volts and Auto cut off beyond and time delay operation for the surges and fluctuations suitable for 1.5 TR Capacity Split Air Conditioner making connections etc. Automatic Voltage Stabilizer 4 KVA Make (Whirpool), as required complete in all respect including, as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals,as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.00	Each	3900.00	3900.00	Rupees Three Thousand Nine Hundred Only
3.00	Providing and fixing on M.S. Outdoor heavy duty stand powder coated suitable to hang 1.5 lit. Split type AC with six Nos. Anchor bolts as required complete in all respect and as per direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.00	Each	950.00	950.00	Rupees Nine Hundred & Fifty Only
4.00	Providing and fixing PVC Drain Pipe 25mm with accessories for waste water of AC as per direction of Engineer in Charge including carriage of materials within all leads, lifts and other incidentals. The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.00	Per Running meter	105.00	630.00	Rupees Six Hundred & Thirty Only
Total in Figures					69980.00	Rupees Sixty Nine Thousand Nine Hundred & Eighty Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Bangana Division
 HP.PWD,Bangana